

*ANATOMY OF*

---

# **DOMESTIC ANIMALS**

**SYSTEMIC & REGIONAL APPROACH**

**PASQUINI & SPURGEON**

***5th***

**Sudz Pub 1989**

Happy New Year & Special Thanks To My Best Friends :  
Dr Stator , Vetaqua , Animal , Adem ,Chocolate Chips,  
Dr Vet Tox, Fabio13 , Macko , new vet, Peruk ,  
Peymanbi, Vet Sam , Skoorooch  
& All ELIB4Vet Member's Tomajwwii 2010/12





Pasquini & Spurgeon

# Anatomy of Domestic Animals

*Systemic and regional approach*



5th edition



# Table of Contents

## Regional

### GENERAL

Descriptive Terms.....	16
Bones.....	22
Joints.....	104
Muscles.....	134
Fascia.....	221
Body Cavities.....	224
Respiratory System .....	302
Circulatory System.....	383
Veins - Body.....	438
Lymphocenters - Body.....	440
Nervous System.....	444
Autonomic Nervous System.....	522
Common Integument.....	530

### HEAD

Skull Bones.....	32
Joints of Skull.....	127
Muscles of Head .....	204
Arteries - Head .....	412
Brain & Cranial Nerves .....	452
Ventricles & Meninges .....	473
Oral Cavity .....	234
Nose .....	302
Horn - Eye - Ear .....	545

### NECK & BACK

Vertebrae.....	60
Joints - Back.....	128
Muscles - Neck.....	210
Muscles - Back.....	218
Arteries - Neck .....	411
Spinal Cord.....	470
Spinal Meninges.....	476



## THORAX

## Table of Contents - Regional

Bony Thorax.....	70
Muscles - Thorax.....	216
Thoracic Cavity & Lungs.....	318
Heart.....	383
Arteries - Thorax.....	414
Nerves - Thorax.....	479

## THORACIC LIMB

Bones - Thoracic Limb.....	72
Foot.....	536
Joints - Thoracic Limb.....	110
Muscles - Thoracic Limb.....	142
Stay Apparatus.....	196
Arteries - Thoracic Limb.....	416
Nerves - Thoracic Limb.....	480

## ABDOMEN

Muscles - Abdomen.....	200
Nerves - Abdomen.....	498
Stomach.....	268
Arteries - Abdomen.....	422
Intestines.....	274
Arteries - Intestines.....	426
Serous Membranes - Abdomen.....	282
Kidneys.....	328
Spleen.....	442

## PELVIS

Muscles - Perineum.....	220
Female Reproductive System.....	340
Mammary Gland.....	533
Male Reproductive System.....	356
Arteries - Pelvis.....	428
Nerves - Pelvis.....	520

## PELVIC LIMB

Bones - Pelvic Limb.....	90
Joints - Pelvic Limb.....	118
Muscles - Pelvic Limb.....	168
Stay Apparatus - Pelvic Limb.....	198
Arteries - Pelvic Limb.....	432
Nerves - Pelvic Limb.....	500



---

# Note to the Student

## Regional headings

---

Thoracic limb-88

Thoracic limb-**536**

**117**-Thoracic limb-143

Regional headings are located in the upper right hand corner of each page, followed by the next page which to turn. In most cases, the next page is the following one, indicated by a normally printed page number (e.g., Thoracic limb-88). When the next page is somewhere else in the text, the page number is bold print (e.g., Thoracic limb-**536**). When a page follows another part of the text, the regional heading is preceded by this page number in bold type (e.g., **117**-Thoracic limb-143).

## LEGENDS

---

- |   |                                      |
|---|--------------------------------------|
| a. Crest of ilium                                       | g. Pubic tubercle                    |
| b. Tuber sacrale (II-157)                               | h. Gluteal surface of ilium (II-157) |
| c. Articulate surface (II-156)<br>(sacropelvic surface) | i. Greater ischiatic notch           |
| d. Body of ilium  | j. Ischiatic spine                   |
| e. Arcuate line   | k. Lesser ischiatic notch            |
| f. Iliopubic eminence                                   | l. Ischiatic table (II-159)          |
|   | m. Ischiatic arch                    |

Legends, like the above from pg. 95, refer to a number of drawings on 2 facing pages (e.g., pages 94-95). The first structure in each legend refers to the first drawing unless followed by a figure number (e.g., a). When a structure is found on another figure, it is followed by the new figure's number (e.g., b. Tuber sacrale (II-157)). All structures not followed by a figure change are found in the last figure indicated (e.g., c.-g. in fig. II-156).

## Index

---

Petioles, 309a

Peyer's patches, 440

Phalangeal joints, 114

Entries are followed by one of three types of page numbers. A bold page number indicates the structure is found in the text and in an illustration (Phalangeal joints, 114). A normal page number indicates the structure is found only in the text (Peyer's patches, 440). A normal page number followed by a letter indicates the term is only found in an illustration labeled with that letter (Petiolus, 309a).

WWW.ELIB-VET.COM



# Table of Contents

---

## Systemic

<b>LIST OF ABBREVIATIONS.....</b>	<b>13</b>
<b>CHAPTER I. DESCRIPTIVE TERMS.....</b>	<b>15</b>
Descriptive Terms.....	16
<b>CHAPTER II. BONES.....</b>	<b>21</b>
Shapes of bones.....	22
Bone Processes.....	24
Divisions of the Skeleton.....	26
Skull Bones.....	32
Paranasal Sinuses.....	56
Hyoid Apparatus.....	58
Vertebrae.....	60
Thorax.....	70
Bones - Thoracic Limb.....	72
Bones - Pelvic Limb.....	90
<b>CHAPTER III. JOINTS.....</b>	<b>103</b>
Articulations.....	104
Synovial Joints.....	106
Joints of the Thoracic Limb.....	110
Joints of the Pelvic Limb.....	118
Joints of the Skull & Hyoid Apparatus.....	127
Joints of the Vertebral Column.....	128
<b>CHAPTER IV. MUSCLES.....</b>	<b>133</b>
Superficial Muscles of the Body.....	134
Muscle, general.....	140
Muscles - Thoracic Limb.....	142
Muscles - Pelvic Limb.....	168
Stay Apparatus.....	196
Abdominal Muscles.....	200
Facial Muscles.....	204
Muscles of the Neck.....	210
Thoracic Muscles & Muscles of the Vertebral Column.....	216

## Table of Contents - Systemic

Muscles - Perineum.....	220
Cutaneous Muscles & Fascia.....	221
<b>CHAPTER V. DIGESTIVE SYSTEM.....</b>	<b>223</b>
Body Cavities.....	224
Oral Cavity.....	234
Teeth.....	238
Aging by Teeth.....	248
Salivary Glands.....	258
Pharynx.....	262
Stomach.....	268
Intestines.....	274
Serous Membranes.....	282
Liver.....	292
Pancreas.....	298
<b>CHAPTER VI. RESPIRATORY SYSTEM.....</b>	<b>301</b>
Nose.....	303
Nasal Cavity.....	304
Larynx.....	308
Thoracic Cavity.....	318
Lungs.....	320
<b>CHAPTER VII. URINARY SYSTEM.....</b>	<b>327</b>
Kidneys.....	328
Arteries.....	335
Nephron.....	336
Urinary Bladder.....	338
<b>CHAPTER VIII. REPRODUCTIVE SYSTEM.....</b>	<b>339</b>
Ovaries.....	340
Uterus.....	342
Vagina, Vulva & Vestibule.....	346
Broad Ligament.....	348
Embryonic membranes.....	352
Placenta.....	353
Ovaries & Estrus.....	354
Testis.....	356
Spermatic Cord.....	362
Accessory Sex Glands.....	364
Penis.....	366
Scrotum.....	376
<b>CHAPTER IX. CIRCULATORY SYSTEM.....</b>	<b>381</b>
Arteries & Veins of the Body.....	382
Pericardium.....	383
Heart.....	384
Fetal Circulation.....	386
Development of the Heart.....	388
Heart Exterior and Interior.....	394
Valves of the Heart.....	403
Coronary Arteries.....	406

## Table of Contents - Systemic

Aortic Arch.....	408
Arteries of the Head.....	412
Arteries of the Thorax.....	414
Arteries of the Thoracic Limb.....	416
Abdominal Aorta.....	422
Arteries of the Pelvis.....	428
Arteries of the Pelvic Limb.....	432
Veins of the Body.....	438
Lymphocenters.....	440
Spleen.....	442
<b>CHAPTER X. NERVOUS SYSTEM.....</b>	<b>443</b>
Neurons.....	446
Neuroglia.....	448
Synapse.....	449
Reflex arc.....	450
Brain.....	452
Cranial Nerves.....	460
Spinal Cord.....	470
Spinal Nerves.....	472
Ventricles.....	473
Meninges.....	474
Spinal plexuses.....	477
Thorax - Nerves.....	479
Thoracic Limb Nerves.....	480
Lumbosacral Plexus.....	498
Pelvic Limb Nerves.....	500
Pelvis - Nerves.....	520
Autonomic Nervous System.....	522
<b>CHAPTER XI. COMMON INTEGUMENT - EYE - EAR.....</b>	<b>529</b>
Skin.....	530
Mammary Gland.....	533
Foot.....	536
Horn.....	545
Eye.....	546
Ear.....	551
Lacrimal apparatus.....	558
<b>APPENDIX .....</b>	<b>559</b>
Types of Nerves .....	560
Neuroanatomy .....	562
Nerve/Joint Blocks - Equine limbs .....	584
Radiology .....	603
Ox - Exploratory Laparotomy .....	632
Ox - Flank Anesthesia .....	640
<b>INDEX .....</b>	<b>643</b>

# Introduction

## Introduction to Fifth Edition

The last two and a half years of teaching Canine Anatomy, Comparative Anatomy, and Applied Anatomy at Ross University have stimulated this fifth edition. *The Anatomy of Domestic Animals* was originally made for an undergraduate veterinary anatomy class. Interest in it by Veterinary students has stimulated additional editions. The goal was to add information for the Veterinary student and still make it manageable for the undergraduate and veterinary technicians. This is still the goal for this edition. This book is still for the undergraduate and the future practising veterinarian, not for future PhDs in anatomy. Added Applied and Clinical Anatomy have been placed in shaded boxes to increase interest in anatomy. The Appendix has been increased with applied anatomy topics that have been difficult for many students here to learn - Nerve Blocks in the horse, Neuroanatomy, and Abdominal Exploration of the ox. These are probably too advanced for the undergraduate, but may stimulate their interest. The radiology section in the appendix should help both the veterinary student and the undergraduate.

Susan Pasquini has since the first edition been responsible for getting this book put together. She has typed, edited and pasted up the pages. While taking Canine and Comparative anatomy at Ross University (soon to be a DVM) she has edited and suggested things for this edition. Without her this and all previous editions would not have been possible.

Mike Smith, from Colorado State University, came down to the Caribbean to take over my class and edited the text while I worked on this edition. Many anatomy discussions were held overlooking the Caribbean sipping a "cold one".

Dr. Charles Hutchison, the Head and other half of the Anatomy Department, through his encyclopedic knowledge and great lectures was a constant stimulus to me and my text. The Neuroanatomy in the appendix evolved from taking notes of his lectures and then editing them from other sources. Dr. Hutchison then edited the final draft.

The radiology section was started by taking notes of Dr. Charles Peugh's lectures when he was here. This was used in Dr. Bruhl-Day's radiology class and in Canine Anatomy and modified over the semesters. Dr. Barbee from Washington State edited and changed it to come up with the final product.

Lynn Lankes a second semester student at Ross edited the text as she learned anatomy, and was invaluable.

Dr. Rudolfo Bruhl-Day and Dr. Sandra Mattoni are in the process of translating this book into Spanish.

I would also like to thank all the anatomists who did the work in anatomy and wrote texts on the subject. Their work and my teaching veterinary students have resulted in this text that hopes to simplify, not define anatomy.



---

# Note to the Student

## **Illustrations**

---

Illustrations are on the same page as the related text or on the facing page..

## **Labels**

---

**1,2,3 or I,I,II** - Arabic numerals or Roman numerals preceding structures in the text refer to numbers in the illustrations on the same or facing pages. These are structures to be learned. Arabic numerals, followed by structure names on the illustrations (usually the dog) allow identification without consulting the text. These are followed closely by illustrations (usually the horse or ox) that have numbers only, allowing you to test yourself.

**A,B,C** - Capital letter labels of the illustrations are important structures learned on another page (where they usually were Arabic numerals).

**a,b,c** - Small letter labels in the illustrations are less important structures not needed to be learned by the undergraduate student. In some illustrations, they are important structures (to be learned on another page) that help orient the drawing.

## **Phonetic (FOH-net-ik) spelling**

---

Phonetic spellings follow commonly mispronounced words.

## **Etymology**

---

The etymology appears in brackets following some terms. The term's language, root word and its meaning are given. The language is indicated by abbreviations (e.g. L. = Latin, G. = Greek, Fr. = French).

## **Text organization**




---

The text is organized into general information, species differences, and clinical information. The general information comes first and is true for all the species considered. Species differences follow, and then clinical applications to help give "life" to the facts.

WWW.ELIB-VET.COM

# ANATOMY OF DOMESTIC ANIMALS:

- Comparative systemic approach to the domestic animals, including horse, ox, sheep, pig, dog, cat, goat and llama
- Outline of essential anatomical structures
- Species differences
- Clinically significant anatomy



WWW.ELIB-VET.COM

Please send the book(s) I have checked:

- ☒ Anatomy of Domestic Animals..... \$ 44.95
- ☐ Atlas of Equine Anatomy..... \$ 39.95
- ☐ Atlas of Bovine Anatomy ..... \$ 39.95
- ☐ Senior Veterinary Student Guide  
to Small Animal Clinics..... \$19.95

\$2.50 Shipping & Handling for single orders

Amount Enclosed..... \$

Name

Address

City State Zip

**SUDZ**  
**PUBLISHING**  
1222 S. HWY. 377  
P.O. Box 1199  
Pilot Point, TX 76258  
Phone (817) 686-9208

[WWW.ELIB4VET.COM](http://WWW.ELIB4VET.COM)

# List of Abbreviations

## LIST OF ABBREVIATIONS

The plural of an abbreviation is indicated by the last letter being duplicated. (E.g., plural for ligaments is ligg.)

a.	= artery	lt.	= left
antebr.	= antebrachial	m.	= muscle
caud.	= caudal	med.	= medial
cran.	= cranial	n.	= nerve
cutan.	= cutaneous	palm.	= palmar
dist.	= distal	pl.	= plural
dors.	= dorsal	plant.	= plantar
ext.	= external	prox.	= proximal
for.	= foramen	rostr.	= rostral
gl.	= gland	rt.	= right
int.	= internal	sin.	= singular
lat.	= lateral	supf.	= superficial
lg.	= large	v.	= vein
lig.	= ligament	ventr.	= ventral
ln.	= lymph node		

## COMMON SINGULARS AND PLURALS

	singular	plural
Greek nouns		
	-is	-es
e.g.	testis	testes
	-on	-a
e.g.	spermatozoon	spermatozoa

## Latin nouns

	-a	-ae
e.g.	vertebra	vertebrae
	-us	-i
e.g.	humerus	humeri
	-um	-a
e.g.	septum	septa
	-os	-ossa

## PRONUNCIATIONS

Phonetic pronunciations appear in parentheses following commonly mispronounced terms.

The most strongly accented syllable is capitalized (e.g., foh-RAY-men).

Secondary accents are given a single quote mark (') (e.g., tyoo'be-ROS-i-tee).

ay as in make  
ee as in be  
y as in eye  
oh as in pole  
yoo as in cute  
e as in bet

l as in sip  
o as in not  
u as in bud  
a as in above  
oo as in sue  
oy as in oil

## Singular and plural are the same

e.g.	ductus	ductus
	manus	manus
	sinus	sinus


WWW.ELIBVET.COM



[WWW.ELIB4VET.COM](http://WWW.ELIB4VET.COM)


# Chapter I

## Descriptive Terms



# DESCRIPTIVE TERMS - PLANES - SECTIONS

General-17



**DESCRIPTIVE TERMS:** precise descriptive terms are used to describe the position of structures and relationships between structures in quadrupeds (four-footed animals). For such terms to have meaning, the quadruped must be in the anatomical position, standing on its four limbs. The anatomical position for humans is standing with the arms at the side and the palms pointing forward. Some human terminology is acceptable for use in certain structures of the animal head.

**1. Dorsal (dors.):** away from the ground. Also, the surfaces below the proximal (see below) ends of the carpus (wrist in humans) and tarsus (ankle in humans) opposite the palmar and plantar surfaces (see below). (The vertebrae are dorsal to the heart).

**2. Ventral (ventr.):** toward the ground (The tongue is ventral to the nasal cavity).

**3. Cranial (cran.):** towards the head. (The neck is cranial to the tail.) Anterior is substituted for cranial in the eye.

**4. Caudal (caud.)** (*L. cauda*, tail): towards the tail. (The hindlimb is caudal to the forelimb.) Posterior is substituted for caudal in the eye.

**5. Rostral (rostr.):** (*L. rostrum*, beak): a part on the head closer to

the nose (corresponds to cranial for the rest of the body). (The nose is rostral to the ears). A part behind another part on the head is called caudal as in the rest of the body.

**6. Palmar (palm.):** the surface below the proximal ends of the carpus directed caudally or towards the ground, thus replacing caudal for this part of the limb. (The dew claw of the ox is on the palmar surface of the forelimb). The opposite, cranially facing side is the dorsal side.

**7. Plantar (plant.):** the surface below the proximal end of the tarsus directed caudally or toward the ground. As in the forelimb, the opposite side is the dorsal side.

**8. Medial (med.):** towards the median plane (pg. 18). (The chest is medial to the thoracic limbs).

**9. Lateral (lat.):** farther from the median plane. (The shoulder is lateral to the ribs).

**10. Proximal (prox.)** (*L. proximus*, next): nearest the trunk or point of origin of a limb, vessel, nerve or organ. (The elbow is proximal to the digit).

**11. Distal (dist.)** (*L. distans*, distant): farther from the trunk or

point of origin of a limb, vessel, nerve or organ. (The carpus is distal to the elbow).

**12. Superficial** (supf.): nearer the surface. (The biceps brachii muscle is superficial to the humerus).

**13. Deep:** farther from the surface. (The femur is deep to the thigh muscles).

**Peripheral** (per-IF-er-al): distant from its point of origin; near the surface of the body. (nerves are peripheral to the central nervous system [brain and spinal cord]).

**Axial and abaxial:** indicate relative position to the longitudinal axis of the limb. These terms are restricted to the digits where the axis is considered to pass between the third and fourth digits.

- **Axial:** closer to the longitudinal axis. (The inside of a digit is the axial side).

- **Abaxial:** further from the longitudinal axis of a limb. (The outside of a digit is the abaxial side)

**External** (ext.): closer to the outer surface of a structure. (The capsule is external to the kidney).

**Internal** (int.): closer to the center of a structure. (The medulla is internal to the cortex).

**Supra** (L. "above"): a prefix signifying above or over (supraspinatus, supraorbital).

**Infra** (IN-frah)(L. *infra* beneath): a prefix signifying below or beneath (infraspinatus, infratrochlear).


**Human terms:**

- **Anterior:** toward the front. This corresponds to ventral and cranial on the limbs of animals, and rostral in head (Anterior chamber, anterior cruciate).


- **Posterior:** toward the back. Posterior corresponds to dorsal and caudal aspect of the limbs or animals and to caudal in the head (posterior chamber, caudal cruciate).

- **Superior:** higher. Sometimes replaces dorsal for head structures (levator labii superioris muscle).

- **Inferior:** lower. Sometimes replaces ventral for structures of the head (inferior palpebra).








**PLANES:** an imaginary or real surface on which any two points can be connected by a straight line.

1. Median (mid-sagittal) plane (on midline): the plane dividing the body into equal right and left portions.

2. Sagittal (paramedian or parasagittal) plane (SAJ-i-tal) (off midline): a plane dividing the body into unequal right and left portions. It is parallel to the median plane.

3. Transverse plane: a plane perpendicular to the median plane, dividing the body into cranial and caudal parts. A transverse plane also crosses an organ or limb at a right angle to its long axis.

4. Frontal (dorsal) plane: a plane perpendicular to both median and transverse planes, dividing body into dorsal and ventral portions.



**SECTIONS:** cuts through various planes of the body to display internal structures. Therefore, sections through these different planes have the same name (e.g., median section is through the median plane).

**Longitudinal section** (*L. longitudo*, length): a cut parallel to the


long axis of an organ or limb. Longitudinal sections may be cut in the median, sagittal or frontal planes.

**Transverse section or cross section:** a cut through the transverse plane of a structure.


WWW.ELIB4VET.COM

## Chapter II


# Bones








**Fig. II-1 - Short bone**



**Fig. II-2 - Flat bone**



**Fig. II-3 - Irregular bone**

**BONES or OSSEOUS TISSUE** (G. *osteon* bone): the hard, semi-rigid, calcified connective tissue forming the skeleton. Bones are classified as short, flat, irregular, sesamoid and long bones by their shape.

**Osteology** (G. *osteon* bone + *logos* study) is the study of bones.

**Short bone:** a cube-shaped bone (e.g., carpal and small tarsal bones).

**Flat bone:** two plates of compact bone, separated by cancellous bone (e.g., some bones of skull and ribs).

**Irregular bone:** a complex and irregularly-shaped bone (e.g., vertebrae and certain facial bones).

**Sesamoid** (SES-ah-moid) bone: a small bone embedded in a tendon; resembling a sesame seed (e.g., patella, proximal and distal sesamoid bones).

**Long bone:** a bone longer than wide, consisting of a diaphysis (body) and two epiphyses (extremities) with their articular cartilage (e.g., humerus, radius, femur, tibia, metacarpals and metatarsals).

- 1. **Diaphysis** (dy-AF-i-sis): the long shaft (body) of a long bone.
- 2. **Epiphysis** (e-PIF-i-sis)(pl. = epiphyses [e-PIF-i-seez]): the two enlarged ends (proximal and distal extremities) of a long bone.

- 3. **Metaphysis** (me-TAF-i-sis): the joining point of the diaphysis and the epiphysis in a mature bone.

- 4 **Periosteum** (per'ee-OS-tee-um): the fibrous covering around the bone that is not covered by articular cartilage. This layer is necessary for bone growth, repair, nutrition and attachment for ligaments and tendons.

- 5. **Articular surface:** the smooth layer of hyaline cartilage covering the epiphysis where one bone forms a joint with another bone.

- 6. **Medullary** (MED-yoo-lar'ee) cavity: the space in the diaphysis containing the marrow.

- 7. **Endosteum** (en-DOS-tee-um): the fibrous tissue lining the medullary cavity of a bone.

- 8. **Apophysis** (Gr. "an offshoot"): any outgrowth of a bone - a process.

- 9. **Cortex:** compact bone surrounding the medullary cavity.

- 10. **Epiphyseal cartilage, growth plate:** the plate of cartilage between the diaphysis and epiphyses of immature long bones. This is where lengthening of long bones takes place. Synonyms are - epiphyseal plate, physis, metaphyseal plate, growth plate and growth cartilage.




Fig. II-4 - Long bone

• **Physis:** (FY-sis)(Gr. *phyein* to grow); term commonly used by radiologists for the epiphyseal growth plate.

**Endochondral ossification:** the formation of long bones in the fetus by transforming a cartilaginous model into bone. Bone replacement takes place in three primary ossification centers - the diaphysis and the two epiphyses. This results in a bone capped with articular cartilage and two cartilage discs (growth plates) between the diaphysis and the two epiphyses. Lengthening of bone occurs at the outer side of the growth plate (side next to the epiphysis). Lengthening stops when the growth plates are completely replaced by bone. During growth, radiographically, the epiphyseal cartilage appears as a radiolucent line (dark line) separating the diaphysis from the two epiphyses. The growth in diameter is the result of bone deposited beneath the periosteum (subperiosteal intramembranous ossification).

**Intramembranous ossification:** forms the flat bones of the head and doesn't use a cartilaginous model.

**11. Compact bone:** gross term for the part of bone that looks solid.

**12. Cancellous bone:** gross term for bone with visible spaces in it. It has a trabecular structure of strands of bone separated by spaces and is located at the epiphyseal ends of the marrow cavity.

**Woven bone:** histological name for immature bone that has been laid down but not organized by secondary remodeling, this can be compact or cancellous bone.

**Haversian bone:** histological term for adult bone that has been remodeled. This also can be compact or cancellous bone.

## CLINICAL

**Physis:** in growing bones is easily fractured.

Cancellous bone can be harvested surgically and moved to a fracture site to aid in repair. Sources of cancellous bone:

- Tibial tuberosity
- Greater tubercle of the humerus
- Greater trochanter of the femur
- Wing of the ilium




Fig. II-5 - Femur & Humerus




Fig. II-6 - Radius & Ulna

**MARKINGS ON BONES:** the bumps, holes and depressions on a bone's surface. These markings can be either articular or nonarticular. The following list is in alphabetical order.

**Canal:** a tunnel through one or more bones (e.g., vertebral canal).

**1. Condyle (KON-dyl) (G. knuckle):** a large articular prominence (e.g., occipital condyles of the skull and the condyles of the humerus, femur and tibia).

**2. Cotyloid (KOT-i-lold) cavity:** a deep articular depression (e.g., acetabulum of the hip joint).

**3. Crest:** a prominent border or ridge (e.g., crest of the hipbone).


**4. Epicondyle (G. *epi*, upon):** a prominence just proximal to a condyle (e.g., lateral epicondyle of the humerus or femur).

**5. Facet (F. little faces):** a smooth, flat surface (e.g., articular facet of a thoracic vertebra for attachment to a rib). Articular facets are covered with hyaline cartilage.


**Fissure (FISH-ur) (Fig. II-33,h):** a narrow, cleft-like opening between adjacent bones.

**6. Foramen (foh-RAY-men) (L. an aperture):** an opening through a bone (e.g., infraorbital foramen, obturator foramen, foramen magnum).





**Fig. II-7 - Os coxae, sacrum  
& caudal vertebrae**



**Fig. II-8 - Horse - 7th Cervical vertebra  
- caud. view**

**7. Fossa (FOS-a) (L. pit) (pl. fossae):** a small hollow (e.g., mandibular fossa, olecranon and radial fossae of the humerus).

**8. Fovea (FOH-vee-a) (L. a pit):** a shallow, nonarticular depression (e.g., fovea capitis on the head of the femur).

**9. Groove (L. *sulcus* furrow):** a long, narrow furrow accommodating a vessel, nerve or tendon (e.g., grooves on the distal end of the radius).

**10. Head:** a rounded articular process (e.g., head of the femur or humerus).

[WWW.ELIB4VET.COM](http://WWW.ELIB4VET.COM)

**Line (Fig. 11-108,c):** a ridge less prominent than a crest.

**Meatus (mee-AY-tus) (L. a passage) (pl. meati or meatuses) (Fig. 11-27,7):** a tube-like canal through a bone (e.g., external auditory meatus).

**11. Notch:** a depression at the edge of a bone (e.g., semilunar

notch of the ulna, popliteal notch of the tibia).

**15 (1,3,4,5,10,12,13,14). Process:** any prominent, roughened projection from a bone (e.g., crest, spine, trochanter, tubercle, tuberosity, etc.).

**12. Spine (L. *spina* thorn):** a sharp, slender process (e.g., spine of a vertebra, spine of the scapula).

**13. Trochanter (troh-KAN-ter):** a large, blunt process found only on the femur (e.g., greater trochanter of the femur).

**Trochlea (TROHK-lee-a) (pg. 96,#7):** a pulley shaped structure (e.g., trochlea of the femur).

**14. Tubercle:** a small, rounded process (e.g., greater tubercle of the humerus).

**15. Tuberosity or tuber:** a large, usually roughened process (e.g., ischial tuberosity).

# DIVISIONS OF THE SKELETON

General-27

**THE SKELETON (G. dried):** the skeleton is divided into the axial skeleton, the appendicular skeleton and the visceral skeleton. The subdivisions of the axial and appendicular divisions are listed below with the bones that make them up.

**AXIAL SKELETON:** the bones and cartilages protecting the soft structures of the head, neck and trunk; consisting of the skull, hyoid apparatus, vertebral column and thorax.

1. **Skull:** the bones of the face and the cranium. These can be further subdivided into bones of the cranium and bones of the face.

2. **Hyoid apparatus:** the bones holding the larynx in place and serving as a major attachment for the tongue.

3, 14. **Vertebral column or backbone:** the variable number of irregular bones (vertebrae) joined by cartilaginous intervertebral discs. It helps maintain posture and participates in body movements. It houses and protects the spinal cord. The vertebrae are grouped into cervical, thoracic, and lumbar vertebrae, the sacrum (fused sacral vertebrae) (14) and caudal vertebrae. The column forms the central axis of the body and makes up the skeleton of the tail.

4, 5. **Thoracic:** the ribs (4) and sternum (5) protecting the thoracic organs.

**APPENDICULAR SKELETON:** the bones of the limbs and the bones connecting the limbs to the axial skeleton (limb girdles).

6-13. **Thoracic limb or pectoral limb (PEK-toh-ral) ("forelimb"):** the scapula, humerus, radius, ulna, carpal bones, metacarpal bones, phalanges and their sesamoid bones.

6. **Thoracic girdle or shoulder girdle:** the two scapulae (6) in domestic animals. In man the clavicle is included and provides a strut to hold the shoulder laterally. In the domestic animals, which need their limbs under them, it is at best vestigial, with no functional significance. The girdle connects the bones of the arm to the axial skeleton by muscular attachments (syssarcosis), not by a conventional articulation.

7. **Arm or brachium:** the humerus (7).

8, 9. **Forearm or antebrachium:** the radius (8) and ulna (9).

10-13. **Manus:** the carpus, metacarpus and digits. In the carnivores, it is also called the forepaw.

10. **Carpus:** the carpal bones (10).

11. **Metacarpus:** the metacarpal bones (11).

12, 13. **Digits:** the phalanges (12) and associated sesamoid bones (13).

15-21, 12, 13. **Pelvic limb ("hindlimb"):** the os coxae, femur,

patella, tibia, fibula, tarsal bones, metatarsal bones, phalanges and their sesamoid bones.

15. **Pelvic girdle:** the two hip bones (ossa coxarum) (15) attached to each other ventrally and to the sacrum (14) dorsally. They connect the pelvic limbs to the axial skeleton. With the sacrum, they form the bony pelvis surrounding and protecting the pelvic organs.

16. **Thigh:** the femur (16).

16, 17, 18 & 19. **Stifle:** the joint between the thigh and crus, along with its menisci and the patella (17).

18, 19. **Leg or crus (L. leg):** the tibia (18) and fibula (19).

20, 21, 12, & 13. **Pes (L. foot):** the tarsus, metatarsus and digits. It is also called the hindpaw in carnivores.

20. **Tarsus or hock:** the tarsal bones (20).

21. **Metatarsus:** the metatarsal bones (21).

12, 13. **Digits:** the same as the thoracic limb, consisting of the phalanges (12) and associated sesamoid bones (13).

**VISCERAL or SPLANCHNIC SKELETON:** consists of bones that develop in the viscera or soft structures such as the os penis (22) in carnivores and the ossa cordis in the ox and sheep.

WWW.ELIB4VET.COM






Fig. II-9 - Dog Skeleton - lat. view




Fig. II-10 - Horse - Skeleton - lat. view




Fig. II-11 - Ox - Skeleton - lat. view

1. Skull
2. Hyoid apparatus (not shown)
3. Vertebral column
4. Ribs
5. Sternum

6. Scapula
7. Humerus
8. Radius
9. Ulna
10. Carpal bones
11. Metacarpal bones

12. Phalanges
13. Sesamoid bones
14. Sacrum (part of vertebral column)
15. Os coxae
16. Femur

17. Patella
18. Tibia
19. Fibula
20. Tarsal bones
21. Metatarsal bones





Fig. II-12 - Pig - Skeleton - lat. view

Fig. II-13 - Cat - Skeleton - lat. view



1. Skull
2. Hyoid apparatus  
(not shown in pig)
3. Vertebral column
4. Ribs
5. Sternum

6. Scapula
7. Humerus
8. Radius
9. Ulna
10. Carpal bones
11. Metacarpal bones

12. Phalanges
13. Sesamoid bones
14. Sacrum (part of  
vertebral column)
15. Os coxae
16. Femur

17. Patella
18. Tibia
19. Fibula
20. Tarsal bones
21. Metatarsal bones






Fig. II-14 - Sheep - Skeleton - lat. view




Fig. II-15 - Llama - lat. view

1. Skull
2. Hyoid apparatus (not shown)
3. Vertebral column
4. Ribs
5. Sternum
6. Scapula
7. Humerus
8. Radius
9. Ulna
10. Carpal bones
11. Metacarpal bones
12. Phalanges
13. Sesamoid bones
14. Sacrum (part of vertebral column)
15. Os coxae
16. Femur
17. Patella
18. Tibia
19. Fibula
20. Tarsal bones
21. Metatarsal bones



**CRANIUM** (KRAY-nee-um): the bones surrounding the brain, forming the cranial cavity.

**Roof of the cranium:** the paired frontal and parietal bones in most domestic species.

**Occipital region:** the caudal aspect of the skull formed by the occipital bone.

**Temporal region:** the lateral walls of the cranium formed by the temporal bones.

**The floor of the cranium:** the ventral aspect of the cranium formed primarily by the unpaired sphenoid bone.

**The rostral wall of the cranium:** the rostral aspect of the cranium formed by the unpaired ethmoid bone.

1. **Occipital** (ok-sip-i-tal) bone: the caudal aspect of both the cranial cavity and the skull as a whole.

2. **Temporal bone:** the caudolateral wall of the cranial cavity.

3. **Parietal** (pa-RY-i-tal) bone (L. *paries* wall): together with the frontal bone forms the roof of the cranial cavity in all domestic animals, except the ox and pig.

4. **Frontal bone** (L. *frons* forehead): the rostral part of the roof of the cranial cavity in most domestic species. In the ox and pig, it forms the entire roof.

5. **Ethmoid bone:** the unpaired bone forming the rostral wall of the cranial cavity.

6. **Sphenoid** (SFEE-noyd) bone (G. *sphen* wedge): the unpaired bone forming the floor of the cranial cavity.

**FACIAL PART OF THE SKULL:** the part enclosing the nasal and oral cavities. Among the species, this part can show variations in length (e.g., horse vs. cat). The dog shows great variation within the species whereas, it is fairly uniform in the other domestic species. The facial region is divided into oral, nasal and orbital regions.

**Oral region:** the incisive, maxillary, and palatine bones and the mandible surrounding the oral cavity.

**Nasal region:** the nasal, maxillary, palatine, and incisive bones surrounding the nasal cavity.

**Orbital region:** the bony socket holding the eye, formed by portions of the frontal, lacrimal, palatine, sphenoid, and zygomatic bones.

7. **Nasal bones:** along with the cranial part of the frontal bone form the osseous roof of the nasal cavity.

8. **Maxillary bone** (MAK-sil-ler'-ee) or maxilla: the lateral part

of the face and the part of the hard palate holding the upper cheek teeth.

9. **Incisive bone:** the rostral bone holding the upper incisors (front teeth).

10. **Palatine** (PAL-a-ty-n) bone: forms the hard palate, along with the maxillary and incisive bones.

11. **Zygomatic bone** or malar bone (L. *mala* cheeks): the cranial part of the zygomatic arch.

12. **Lacrimal** (LAK-ri-mal) bone (*lacrima* tear): the medial surface of the orbit.

13. **Ventral nasal concha** (KONG-kah): a scroll of bone located in the nasal cavity.

14. **Pterygoid** (TER-i-goid) bones: the small, paired bones in the caudal part of the nasopharynx.

15. **Vomer** (plowshare): the unpaired bone forming part of the osseous nasal septum.

16. **Mandible** (L. *mandere* to masticate): the large bone articulating with the skull that supports all the lower teeth.

WWW.ELIBAVET.COM

## SPECIES DIFFERENCES

**Interparietal bone** (Fig. II-20,a): the bone found only in the horse and cat, between the two parietal bones, rostral to the occipital bone. In other species, it is present in the fetus but then fuses with surrounding bones before birth.

**Frontal bone:** forms the entire roof of the cranium in the ox and pig.

**Rostral bone:** unique bone found in the nose of the pig.

**Dog:** there are three types of skulls in dogs relative to the proportions of the facial bones and the cranial vault.

- **Mesaticephalic:** the average conformation (i.e., beagle)

- **Dolichcephalic** (dal-i-hoh-se-FAL-ik): has a larger facial component (i.e., collie)

- **Brachiocephalic:** has a shorter facial component (i.e., Boston Terrier).

# SKULL BONES - DOG

Fig. II-16 - Dog - Skull  
- dors. view





Fig. II-17 - Dog - Skull  
- lat. view




Fig. II-18 - Dog - Skull  
- ventr. view




Fig. II-19 - Dog- Skull - sagittal section



# SKULL BONES - HORSE

Head-35

Fig. II-20 - Horse - Skull  
- dors. view




Fig. II-21 - Horse - Skull - ventr. view





Fig. II-22 - Horse - Skull - lat. view

- |              |  |
|--------------|--|
| 1. Incisive  | 10. Occipital                                    |
| 2. Maxillary | 11. Sphenoid                                     |
| 3. Lacrimal  | 12. Vomer  |
| 4. Pterygoid | 13. Palatine                                     |
| 5. Temporal  | 14. Ethmoid (not shown - horse)                  |
| 6. Parietal  | 15. Ventr. nasal concha                          |
| 7. Zygomatic | 16. Mandible                                     |
| 8. Frontal   | 17. Interparietal (separate only in horse & cat) |
| 9. Nasal     |  |

Fig. II-23 - Ox - Skull - lat. view





Fig. II-24 - Ox - Skull  
- ventr. view

Fig. II-25 - Ox - Skull  
- dors. view





Fig. II-26 - Ox - Skull - sagittal section



**SPECIES DIFFERENCES**


Frontal bone: forms the entire roof of the cranium in the ox and pig



# SKULL - LATERAL VIEW

Head-37

Fig. II-27 - Dog - Skull



A. Incisive bone  
B. Maxillary bone  
C. Lacrimal bone  
D. Zygomatic bone  
E. Frontal bone  
F. Parietal bone  
G. Temporal bone

H. Nuchal crest  
(not shown in ox)  
L. Occipital bone  
J. Tympanic bulla  
K. Mandible  
L. Coronoid process  
M. Mental foramen

a. Zygomatic process  
b. Frontal process  
c. Ramus of mandible  
d. Cheek teeth  
e. Canine tooth  
f. Incisor tooth  
g. Articular process

h. Retroarticular process  
i. Angular process (carnivores)  
j. Angle of mandible (horse & ox)  
k. Pterygopalatine fossa

**1. Zygomatic arch:** the bony arch forming the lateral wall of the orbit. It consists of the zygomatic bone and the zygomatic processes of the temporal bone.

**2. Orbit (F. circle):** the bony socket holding the eye.

**3. Lacrimal fossa:** the depression in the medial margins of the orbit. It collects tears and sends them through the lacrimal canal which opens into the nasal cavity.

**4. Infraorbital foramen:** the rostral opening of the infraorbital canal, located in the maxillary bone.

**5. Occipital condyles:** the paired structures lateral to the foramen magnum that articulate with the first cervical vertebra (atlas).

**6. Paracondylar (jugular) process:** the ventral projection near the occipital condyles.

**7. External acoustic meatus:** the large opening caudal to the

zygomatic arch where the external ear attaches. In life it is covered by the ear drum (tympanic membrane) which separates the external and middle ear.

**8. Mastoid process:** located caudal to the external acoustic meatus. It is an attachment site for muscles.

**9 External occipital protuberance:** the caudal process of the occipital bone.

## SPECIES DIFFERENCES

**Bony orbit:** complete in the horse and ruminants, is incomplete in the carnivores but is completed by the orbital ligament.

**Facial crest:** in horses, the ridge on the lateral surface of the face

**Facial tuberosity:** in ruminants, the process on the lateral surface of the face.








Fig. II-30 - Dog - Skull



## DORSAL SURFACE OF THE SKULL



1. Nuchal crest (NOO-kal): the transverse ridge at the transition from the dorsal to the caudal (nuchal) surfaces of the skull.
2. Temporal fossa: the depression formed by the temporal and parietal bones.
3. Nasal aperture: the rostral bony opening into the nasal cavity.
4. Median sagittal crest: extends rostrally from the external occipital protuberance on the midline (absent ruminants).

## SPECIES DIFFERENCES

6. Cornual process: the process of the frontal bone of horned ruminants that is enclosed by the horn.

Temporal fossa (2): in ruminants has been pushed to the lateral side of the skull by the frontal bone.

WWW.ELIBAVET.COM








Fig. II-33 - Dog - Skull

## VENTRAL SURFACE OF THE SKULL

**1. Foramen magnum:** the large opening into the cranial cavity for continuity of the spinal cord and brain.

**2. Tympanic bulla (tim-PAN-ik):** the smooth bulbous enlargement on the ventral side of the temporal bone housing the middle ear.

**3. Mandibular fossa:** the area on the zygomatic arch for articulation with the articular process (condyle) of the mandible.

**4. Optic canal:** the passageway for the optic nerve from the eyeball to the brain. It is rostral to many other foramina that allow passage of other cranial nerves.

**5. Choanae (koh-AY-nee) (sin.= choana) or caudal nares:** the two bony openings, at the caudal end of the hard palate, leading from the nasal cavity into the pharynx.

**6. Hard palate:** the horizontal parts of the incisive, palatine and maxillary bones, separating the nasal and oral cavities.

### SPECIES DIFFERENCES

**Foramen orbitotundum:** found in ruminants and pigs, is the joining of the round and orbital foramina of other species.




Fig. II-34 - Ox - Skull

- A. Occipital condyle
- B. Jugular process
- C. Zygomatic arch
- D. Vomer bone
- E. Palatine bone
- F. Maxillary bone
- a. Hypoglossal canal
- b. Stylomastoid foramen
- c. Ext. acoustic meatus
- d. Foramen lacerum
- e. Pterygoid canal
- f. Hamulus of pterygoid bone
- g. Major palatine foramen
- h. Palatine fissure
- i. Orbital fissure
- j. Rostr. alar foramen
- k. Caud. alar foramen
- l. Oval foramen
- m. Retroarticular process
- n. Condylod fossa
- o. Tympano-occipital fissure (carnivores)




Fig. II-35 - Horse - Skull




# SKULL - SAGITTAL SECTION

Head-43

WWW.ELIB4VET.COM

Fig. II-36 - Dog - Skull



A. Foramen magnum  
B. Tympanic bulla  
(not shown in horse)  
C. Pterygoid bone  
D. Frontal bone  
E. Optic canal  
F. Occipital bone  
G. Vomer (not  
shown in dog)

a. Tentorium osseum  
(absent in ox)  
b. Transverse canal  
(absent in ox)  
c. Hypoglossal canal  
d. Jugular foramen  
e. Int. acoustic meatus  
f. Entrance to maxillary  
recess (canine)

g. Palatine sinus (ox)  
h. Sphenopalatine sinus  
(horse)  
i. Mandibular foramen (not  
shown in dog)  
j. Sphenoid sinus (ox & carnivores)  
(not shown in dog)

## SAGITTAL SECTION OF THE SKULL

**1. Cranial cavity:** the space in the cranium containing the brain, its meninges and blood vessels.

**2. Hypophyseal fossa** (hy'poh-FIZ-ee-al): the depression in the floor of the cranial cavity (sphenoid bone) holding the pituitary gland (hypophysis).

**3. Cribriform plate** (L. *cribum* sieve): the rostral part of the wall of the cranial cavity. Many holes in this part of the ethmoid bone allow the passage of the olfactory nerve (CN I).

**4. Nasal cavity:** the hollow space behind the nose, surrounded by the facial bones. It is divided in half longitudinally by the nasal septum and is filled by the ventral nasal conchae and ethmoturbinate

bones.

**5. Ventral nasal concha** (KONG-ka): a scroll of bone filling the rostral part of the nasal cavity.

**6. Dorsal nasal concha:** the largest nasal turbinate of the ethmoid bone.

**7. Ethmoid bone:** the bone in the caudal nasal cavity. It has many bony scrolls called ethmoturbinates and its cribriform plate forms the rostral wall of the cranial cavity.

**8. Frontal sinus:** the cavity (paranasal sinus) within the frontal bone.




Fig. II-37 - Horse - Skull





Fig. II-38 - Ox - Skull

Fig. II-39 - Dog - Mandible - med. view



- |                         |                                 |
|-------------------------|---------------------------------|
| a. Mandibular notch     | f. Cheek teeth                  |
| b. Coronoid process     | g. Angular process (carnivores) |
| c. Mandibular symphysis | h. Angle of jaw                 |
| d. Incisor teeth        | i. Masseteric fossa             |
| e. Canine tooth         | (not shown-dog)                 |

WWW.ELIB4VET.COM

**MANDIBLE** (L. *mandere* to masticate) or lower jaw bone: the largest and only mobile bone of the mammalian skull. It holds the lower teeth and consists of a right and left half united at the mandibular symphysis (c).

**1. Body:** the horizontal part bearing the lower incisor, canine, premolar and molar teeth.

**2. Mental foramen** (L. *mentum chin*): the rostral opening of the mandibular canal. (Not visible in the dog illustration)

**3. Ramus:** the vertical part of the mandible bearing no teeth.

**4. Articular (condylar) process** (KON-di-lar): the smooth process which articulates with the mandibular fossa of the temporal bone to form the temporomandibular joint.

**5. Mandibular foramen:** the opening on the medial side of the ramus leading into the mandibular canal.






Fig. II-40 - Ox - mandible  
- dor. view





Fig. II-41 - Horse - Mandible - craniolat. view



Fig. II-42 - Dog  
Floor of cranium




1. Cribriform plate
2. Optic canal
3. Orbital fissure
4. Round foramen
5. Oval foramen

6. Foramen lacerum
7. Int. acoustic meatus
8. Jugular foramen
9. Hypoglossal canal
10. Foramen magnum


- a. Palatine fissure
- b. Sulcus chiasmatis
- c. Rostr. clinoid process
- d. Caud. clinoid process
- e. Dorsum sellae

- f. Petrosal crest
- g. Canal for trigeminal n.
- h. Canal for transverse sinus
- i. Condyloid canal

**Fig. II-43 - Horse**  
-Floor of cranium



**Fig. II-44 - Ox - Floor**  
of cranium






Fig. II-45 - Dog -ventr. view of caud. skull

1. Foramen magnum
2. Hypoglossal canal
3. Tympano-occipital fissure (carnivores)
4. Stylomastoid foramen
5. Ext. acoustic meatus
6. Foramen lacerum

7. Oval foramen
8. Orbital fissure
9. Optic canal
10. Choanae (caudal nares)
11. Jugular foramen (#3 ext. opening in carnivores)

- a. Caud. alar foramen
- b. Major palatine foramen
- c. Supraorbital canal (II-47)
- d. Canal for facial n. (II-45)
- e. Cochlear window

- f. Malleus
- g. Stapes
- h. Incus
- i. Promontory
- j. Rostr. alar foramen
- k. Hamate process of pterygoid bone



Fig. II-46 - Horse - Ventr. view of caud. skull





Fig. II-47 - Ox - Ventr. view of caud skull



# FORAMINA

Head-51

OPENINGS	STRUCTURES PASSING THROUGH	FACTS
Infraorbital foramen	Infraorbital n. (derived from CN* V2)	Cran. opening of infraorbital canal
Fossa for the lacrimal sac		Leads to lacrimal foramen & canal
Maxillary foramen	Infraorbital n. (CN V3)	Caud. opening of infraorbital canal
Cribriform foramina	Olfactory n. (CN I)	Openings in cribriform plate of ethmoid bone
Optic canal	Optic n. (CN II)	
Orbital fissure (carnivores & horse)	CN III, IV, Ophthalmic div. of CN V & VI	
Round foramen	Maxillary division (CN V2)	Ventral to orbital fissure in horse
Foramen orbitorotundum (ruminant & pig)	CN III, IV, V1, VI & Maxillary division (CN V2)	Combined orbital & round foramen in ruminant & pig
Oval foramen (horse & pig)	Mandibular division (CN V3)	Part of foramen lacerum in horse & pig
Foramen lacerum	Int. carotid a. (mandibular division [CN V3] - horse & pig)	
Int. acoustic meatus	CN VIII (vestibulocochlear n.)	
Jugular foramen	CN IX, X & XI	
Tympano-occipital fissure (carnivores)	CN IX, X & XI	Ext. opening of jugular foramen in carnivores
Stylomastoid foramen	CN VII (Facial n.)	
Mandibular foramen	Mandibular alveolar n. (CN V3)	Prox. opening of mandibular canal
Mental foramen	Mandibular alveolar n. (CN V3)	Dist. opening of mandibular canal

\*CN = Cranial Nerve




Fig. II-49 - Horse - Cranial & orbital regions of skull - lat. view




Fig. II-50 - Ox - Skull (cranial & orbital regions) - lat. view




Fig. II-51 - Pig - Skull - dors. view






Fig. II-52 - Pig - Skull - lat. view










Fig. II-55 - Goat - Skull - dors. view




Fig. II-56 - Goat - Skull - lat. view

# SKULL - SHEEP

Head-56




Fig. II-57 - Sheep - Skull - dors. view




Fig. II-58 - Sheep - Skull - lat. view



# 

Head-57




Fig. II-59 - Horse - Paranasal sinuses  
- lat. view




Fig. II-60 - Horse - Paranasal sinuses  
- dors. view

- a. Dors. conchal sinus (horse)
- b. Lacrimal canal
- c. Sphenopalatine sinus (horse)
- d. Infraorbital canal
- e. Nasomaxillary opening (horse)
- f. Palatine sinus (ruminants)

**PARANASAL SINUSES** (par'a-NAY-zal SY-nus-seez): the air-filled cavities within some bones of the skull. They are lined by a mucous membrane and communicate with the nasal cavity. The frontal and maxillary sinuses are the best known, but several others may be present, including the sphenoid, palatine, lacrimal and conchal sinuses.

**1. FRONTAL SINUS:** the paranasal sinus found in the frontal bones of all domestic species.

**2. MAXILLARY SINUS:** the paranasal sinus in the maxillary bone. It opens into the nasal cavity through the nasomaxillary opening (e).

### 

**Frontal sinus:** in the dorsal part of the skull, between the orbits in the horse, small ruminants and carnivores. In the ox and pig the frontal sinus extends to the back of the skull. In the ruminant it has a number of diverticula besides the cornual diverticulum.

**Conchofrontal sinus:** in horses, the joined frontal and dorsal conchal sinus.

**3. Frontomaxillary opening:** in the horse, the large opening between the caudal maxillary sinus and the frontal sinus.

**4. Cornual diverticulum:** the direct continuation of the frontal sinus into the cornual process in horned ruminants.

**Dog:** has a maxillary "recess" (Fig II-36,f) between bones in the area of the maxillary bone, not inside the maxillary bone.

**Horse:** has two maxillary sinuses separated by a bony septum, the rostral maxillary sinus (2') and the caudal maxillary sinus (2'').

**Pig and ruminants:** have a single maxillary sinus.

**Lacrimal bulla:** paper thin caudal extent of the maxillary sinus in the ruminants.

Fig. II-61 - Ox - Paranasal sinuses  
 - dors. view





Fig. II-62 - Ox - Paranasal sinuses  
 - lat. view



**CLINICAL:**

**Trephination** (tree-FYN-ay-shun): the drilling of holes (trephine holes) into the paranasal sinuses.

**Horse:** all but the last upper cheek teeth can be removed (expelled) through trephined holes in the maxillary sinuses. The last cheek tooth is reached by trephining the conchofrontal sinus (1/2 inch off midline between the medial canthi of the eyes), then use a curved punch through the frontomaxillary opening. Care must be taken to avoid the infraorbital canal (d) and the lacrimal canal (b).

**Boundaries for trephination of the maxillary sinus in the horse:**

- Dorsal - line from medial canthus to infraorbital foramen.
- Ventral - Facial crest.

**Cornual diverticulum** (4) of the frontal sinuses is often opened in dehorning and thus a possible entrance for inflammation (sinusitis).

**Ox - Trephination of the four compartment frontal sinus:**

- Rostral compartment - between the eyes 1 inch from the midline.
- Postorbital diverticulum - 1 - 1 1/2 inches caudal to lateral canthus of eye.
- Nuchal diverticulum - caudally, halfway between midline and base of the horn.

**Sinusitis:** inflammation of the paranasal sinuses. Trephination may be used to drain such infections.







Fig. II-63 - Dog - hyoid apparatus  
-craniolat. view



A. Thyroid cartilage  
B. Epiglottic cartilage  
C. Cricoid cartilage  
D. Trachea

a. Tympanohyoid cartilage  
b. Stylohyoid bone  
c. Epihyoid bone  
d. Ceratohyoid bone  
e. Thyrohyoid bone  
f. Basihyoid bone

Fig. II-64 - Dog - Hyoid apparatus  
- lat. view

**HYOID APPARATUS (HY-oid)** (*G. hyoedes* u-shaped): a number of connected bones suspending the larynx and tongue from the skull. The hyoid apparatus consists of the basihyoid, thyrohyoid, ceratohyoid, epihyoid, and stylohyoid bones and tympanohyoid cartilage.


**Basihyoid bone:** unpaired hyoid bone crossing the midline where it can be palpated.

**Memory aid:** to the order of the hyoid bones in relationship to each other – Sick Elephants Can Be Treated.


## SPECIES DIFFERENCES

1. **Lingual process:** the rostral projection of the basihyoid bone into the tongue. Carnivores lack such a process, but the horse has a long one and the ox a short one.

**Fig. II-65 -Ox - Hyoid apparatus  
-craniolat. view**



**Fig. II-66 - Horse - Hyoid apparatus  
- craniolat. view**



# VERTEBRAE

Beginning-Neck & Back-61

**VERTEBRAL COLUMN**, spine or backbone: protects the spinal cord, supports the head and serves as attachment for the muscles effecting body movements. It extends from the skull through the tail and consists of irregular bones - vertebrae. The vertebrae are firmly joined by slightly moveable joints. All the vertebral joints together allow a great amount of movement.

**VERTEBRAE** (VER-te-bree) (sin. = vertebra): the irregularly-shaped bones making up the spinal column. They are grouped by location into cervical (neck), thoracic (cranial back), lumbar (loin), sacral (croup) and caudal (tail) vertebrae. Each group is represented by its first letter followed by the number representing how many are in each section. C7 T13 L7 S3 Ca n is the vertebral formula of the dog. The number of each type of vertebrae is constant except the caudal ones. Twenty can be used as a rough estimate of the caudal vertebrae with some dogs having more and some less. Common features of a typical vertebra are the body, vertebral arch, vertebral foramen and processes.

1. **Intervertebral foramen**: the opening between vertebrae formed by caudal and cranial notches of adjacent vertebrae. These openings allow passage of the spinal nerves.

2. **Intervertebral discs**: the fibrocartilages connecting the bodies of adjacent vertebrae.

3. **Vertebral arch** (VER-tee-bral): the dorsal part of a vertebra that arises from the body. It consists of two upright pedicles forming the walls of the vertebral foramen. From the pedicles two lamina project to the midline and form the roof of the vertebral foramen.

4. **Vertebral foramen**: the space formed by the vertebral arch and the body. The vertebral foramina of all the vertebrae form the vertebral canal, housing the spinal cord.

**Vertebral canal**: formed in the live animal by all the vertebral foramina.

5. **Body**: the thick, spool-shaped ventral portion of the vertebra. It is convex cranially and concave caudally to articulate with adjacent vertebrae.

**The 7 processes of the vertebral arch**: the spine and the two transverse processes provide sites for muscle attachment. The four articular processes form synovial joints with adjacent vertebrae.

6. **Spinous process or spine**: the dorsal projection of the vertebral arch.

7. **Transverse process**: the lateral extension of the vertebral arch. They divide the muscles of the back into dorsal (epaxial) and ventral (hypaxial) groups.

8. **Articular processes**: the four articular processes, two cranial and two caudal (8' and 8''), articulate respectively with the caudal and cranial articular processes of adjacent vertebrae. These form synovial joints.

## VERTEBRAL FORMULA:

	C7	T13	L7	S3	Ca20-24
Carnivore	7	11-15	6-7	4	20-23
Pig	7	18	6	5	15-21
Horse	7	13	6	5	18-20
Sheep	7	13	6-7	4	16-18




Fig. II-67 - Ox - Cervical vertebrae - lat. view




Fig. II-68 - Dog - Cervical vertebra




Fig. II-69 - Thoracic vertebrae - Dog  
- cran. view




Fig. II-70 - Lumbar vertebra - Dog  
- dors. view



# CERVICAL VERTEBRAE

Neck & Back-63

Fig. II-71 - Dog - Atlas - cran. view





Fig. II-72 - Dog - Axis - cran. view




Fig. II-73 Dog - Cervical vertebra - craniolat. view

- A. Body
- B. Vertebral arch
- C. Vertebral foramen
- D. Spine
- E. Transverse process
- F. Cran. articular process
- G. Caud. articular process

- a. Alar notch or foramen
- b. Dors. arch of atlas
- c. Ventr. tubercle of atlas
- d. Lat. vertebral foramen (not shown in dog)

**CERVICAL VERTEBRAE** (*cervix* neck): the seven vertebrae of the neck in all mammals, characterized by a transverse foramen (except C7). The 1st (atlas) and 2nd (axis) cervical vertebrae are atypical.

**1. Transverse foramen:** the hole through the transverse process of C1-C6, together forming the transverse canal. This differentiates the cervical vertebrae from C7 and the remaining vertebrae.

**Transverse process:** of the cervical vertebrae are divided into ventral and dorsal tubercles.

**Sixth cervical vertebra's transverse processes:** large ventral projections which on a radiograph are used as landmarks and often called the "sleds".

**Seventh cervical vertebra:** has a higher spinous process, an articular facet on the caudal end of its body for the head of the first rib, and no transverse foramen.

**ATLAS (C1):** the first cervical vertebra, named for its support of the head. It has a synovial articulation with the occipital condyles to form the atlanto-occipital joint which allows flexion and




Fig. II-74 - Horse - Atlas - dors. view




Fig. II-67 - Horse - Axis - lat. view




Fig. II-76 - Ox - Atlas - caudodors. view




Fig. II-77 - Ox - Axis - craniolat. view

...ion (the "yes" joint). The atlas is atypical because it lacks a body and a spinous process.

**2. Ventral arch:** the portion of the atlas replacing the body of other vertebrae.

**3. Wings:** the large lateral masses that are modified transverse

processes.

**AXIS (C2):** the long second cervical vertebra. It has a large ridge-like spinous process and the dens.

**4. Dens:** the peg-like cranial process forming a pivot articulation with the atlas, allowing pivotal motion (the "no" joint).

## THORACIC VERTEBRAE

Neck & Back-65

**THORACIC VERTEBRAE:** the vertebrae of the thorax, characterized by articular facets for the pair of ribs they bear.

**Anticlinal vertebra:** the thoracic vertebra with the most vertically oriented spine, usually the eleventh (T11) in the dog. All spines cranial to this vertebra are inclined caudally, all spines caudal to it incline cranially. This is often used as a landmark in reading radiographs of the thorax or back.

1. **Costal facets:** the two plane surfaces that articulate with a rib's head, located on the caudal and cranial end of the vertebral bodies of most of the thoracic vertebrae.

2. **Transverse costal facet:** the plane surface on the transverse process that articulates with the tubercle of the same numbered rib.

### SPECIES DIFFERENCES

Species	# of thoracic vertebrae	Anticlinal vertebra
Carnivores	13	11
Horse	18	16
Ox	13	13
Sheep	13	13
Pig	14-15	10
Chicken	7	-

Fig. II-79 - Dog - 7th thoracic vertebra  
- craniolat. view

Fig. II-78 - Dog - 10th thoracic vertebra  
- lat. view






Fig. II-80 - Horse - 1st thoracic vertebra  
- craniolat. view



3. Transverse costal facet

1. Cran. costal facet

2. Caud. costal facet

Fig. II-81 - Horse - 5th thoracic  
vertebra - lat. view




Fig. II-82 - Ox - 3rd thoracic  
vertebra - craniolat.  
view




Fig. II-83 - Ox - Anticlinal  
(T<sub>13</sub>) vertebra -  
lat. view

- A. Body
- B. Vertebral arch
- C. Vertebral foramen
- D. Spine
- E. Transverse process
- F. Cran. articular process
- G. Caud. articular process

- a. Mammillary process
- b. Lat. vertebral foramen (ox)



## LUMBAR VERTEBRAE

Neck & Back-67

**LUMBAR VERTEBRAE** (Fr. *lumbus* loin): the vertebrae of the lumbar (lower back, loin) region, characterized by their large size and long plate-like transverse processes (1). They can be distinguished from the last thoracic vertebrae by their lack of costal facets.

Accessory processes (d): are found from the midthoracic to the lumbar vertebrae. These can be seen through the intervertebral foramen in radiographs and shouldn't be confused with a ruptured intervertebral disc.

### SPECIES DIFFERENCES

Species	# of lumbar vertebrae
Carnivores	7
Horse	6 (5 in some Arabians)
Ox	6
Sheep	6-7
Pig	6-7
Chicken	14 (lumbrosacral)




Fig. II-84 - Dog - 1st lumbar vertebra  
- caud. view

1. Transverse process (E)







Fig. II-85 - Dog - 6th lumbar vertebra  
- caudolat. view

**Fig. II-86 - Horse - 3rd lumbar vertebra - caud. view**



**1. Transverse process (E)**

**Fig. II-87 - Horse - 6th lumbar vertebra - caudolat. view**



**Fig. II-88 - Ox - 4th lumbar vertebra - craniolat. view**

- A. Body
- B. Vertebral arch
- C. Vertebral foramen
- D. Spine
- E. Transverse process
- F. Cran. articular process
- G. Caud. articular process

- a. Mammillary process
- b. Articular surface for wing of sacrum (horse)
- c. Articular surface for 5th lumbar vertebrae (horse)

# SACRUM

Neck & Back-69

**SACRUM:** the bone formed by the fusion of the sacral vertebrae. It articulates with the hip bones forming the sacroiliac joint. The portion of the vertebral canal through the sacrum is called the sacral canal.

1. Dorsal and 2. ventral sacral foramina: the openings on the dorsal and ventral surfaces of the bone for passage of spinal nerves.

3. Wings: the lateral parts of the sacrum articulating with the hip bones to form the sacroiliac joint.

## SPECIES DIFFERENCES:

4. Spinous processes: the unfused processes in the horse and carnivores.

5. Median sacral crest: the fused sacral spinal processes in the ruminants.

Species Differences	
Species	Fused vertebrae
Carnivores	3
Horse	5
Ox	5
Sheep	4
Pig	4

**CAUDAL (coccygeal) VERTEBRAE:** the vertebrae of the tail varying in number between the species and within the species. They become progressively smaller distally.





Fig. II-90 - Dog - Sacrum - lat. view

Fig. II-89 - Dog - Sacrum - dorsocran. view



2. Ventr. sacral foramen






Fig. II-91 - Dog - Sacrum - ventr. view




## SACRUM

**Fig. II-92 - Horse - Sacrum  
- dorsolat. view**



**Fig. II-93 - Ox - Sacrum - lat. view**



**Fig. II-94 - Ox - Sacrum - dors. view**

- A. Body
  - B. Vertebral arch
  - C. Vertebral (sacral) canal
  - D. Spine
  - E. Transverse process
  - F. Cran. articular process
  - G. Caud. articular process
- a. Articular (auricular) surface for ilium
  - b. Lat. sacral crest
  - c. Promontory
  - d. Surface for articulating with transverse process of last lumbar vertebra (horse)




Fig. II-95 - Dog - Thorax - lat. view

**THORAX:** the bony cavity formed by the sternum, the ribs, the costal cartilages, and the bodies of the thoracic vertebrae. The thorax encloses and protects the thoracic organs.

**1. RIBS** (*L. costae*): the long, curved bones forming the lateral wall of the thorax.

- **True ribs** (a) (sternal ribs): articulate by their costal cartilage with the sternum.

- **False ribs** (b) (asternal ribs): their costal cartilages unite to form the costal arch, indirectly joining them to the sternum.

- **Floating ribs** (c): found in the dog and man, end in costal cartilages that do not join to the sternum or other costal cartilage.

**2. Head of the rib:** articulates with caudal and cranial costal facets

of adjacent thoracic vertebrae and the intervening intervertebral disc.

**3. Tubercle of the rib:** articulates with the articular facet on the transverse process of the same numbered vertebra.

**4. Intercostal space:** the space between two adjacent ribs.

**5. COSTAL CARTILAGE** (*L. costa, rib*): the bars of hyaline cartilage either connecting the bony rib to the sternum or to the costal arch or ending freely.

**6. Costal arch:** the curved structure formed by the costal cartilages of the false ribs.

**7. STERNUM** or breastbone: the unpaired bones (*sternebrae*) forming the floor of the thorax.




Fig. II-96 - Horse - Rib

Fig. II-97 - Horse - Thorax - lat. view

Fig. II-98 - Ox - Thorax - lat. view

**I. Manubrium** (ma-NOO-bri-um) (L. handle): the expanded first sternebra.

**II. Xiphoid process** (ZY-foyd) (G. *xiphos*, sword): the last sternebra which is a thin, horizontal bone capped by the xiphoid cartilage.

**III. "THORACIC INLET"** or cranial thoracic opening: formed by the last cervical vertebra, first pair of ribs and the sternum.

**IV. "THORACIC OUTLET"** or caudal thoracic opening: sealed by the diaphragm.

## SPECIES DIFFERENCES

**Floating ribs:** last pair in dogs only.

**Number of sternebrae:** carnivores - 8, pig, horse and man - 6, ruminants - 7.







Fig. II-99 - Dog - Thoracic limb skeleton - med. view

- A. Shoulder joint
- B. Elbow joint
- C. "Carpal" articulations
- D. Metacarpophalangeal articulations
- E. Prox. interphalangeal articulations
- F. Dist. interphalangeal articulations



A. Shoulder joint  
B. Elbow joint  
C. "Carpal" articulation ("knee")

D. Metacarpophalangeal articulation (fetlock joint)

E. Prox. interphalangeal articulation (pastern joint)  
F. Dist. interphalangeal articulation (coffin joint)




Fig. II-103 - Ox - Thoracic limb skeleton  
- lat. view

Fig. II-104 - Ox - Thoracic limb skeleton  
- med. view



Fig. II-105 - Pig - Thoracic limb skeleton  
- lat. view




Fig. II-106 - Pig - Thoracic limb  
skeleton - med. view

A. Shoulder joint  
B. Elbow joint  
C. "Carpal" joints

D. Metacarpophalangeal joint  
E. Prox. interphalangeal joint  
F. Dist. interphalangeal joint

Converging arrows  
indicate angle of  
flexion of joint

Fig. II-107 - Dog - Lt. scapula - lat. view




Fig. II-108 - Dog - Lt. scapula - med. view




Fig. II-109 - Cat - Clavicle




Fig. II-110 - Cat - Lt. scapula - ventr. view

- a. Scapular notch
- b. Neck
- c. Supraglenoid tubercle
- d. Dors. border
- e. Facies serrata
- f. Infraglenoid tubercle
- g. Coracoid process
- h. Nutrient foramen (Fig. II-111)
- i. Cran. angle
- j. Ventr. angle

**CLAVICLE** (KLAV-i-kul) (L. little key) (collar bone): the bone articulating with the shoulder and the sternum in man to maintain the shoulder in a lateral position. The domestic animals need their thoracic limb under their bodies, so the clavicle is absent or rudimentary.

**SCAPULA** (SCAP-yoo-la) ("shoulder blade"): the flat, triangular bone of the shoulder. The two scapulae make up the thoracic girdle.

**1. Spine of the scapula:** the long projection dividing the scapula's lateral surface and ending as the acromion.

**2. Acromion** (a-KROH-mee-on): the expanded distal end of the spine of the scapula.

**3. Supraspinous fossa** (soo'-pra-SPY-nus): the area cranial to the spine providing attachment for the supraspinatus muscle.

**4. Infraspinous fossa:** the area caudal to the spine providing attachment for the infraspinatus muscle.

**5. Subscapular fossa:** most of the medial (costal) surface of the scapula providing attachment for the subscapular muscle. The dorsal part of the costal surface is the serrated surface (e) for the attachment of the serratus ventralis muscle.

**6. Glenoid cavity:** the shallow cavity articulating with the head of the humerus to form the shoulder joint.

**7. Scapular cartilage:** the cartilaginous structure on the dorsal border of the scapula.




Fig. II-111 - Horse - Rt. scapula - lat. view




Fig. II-107 - Ox - Rt. scapula - ventr. view


**Supraglenoid tubercle:** the process near the cranial aspect of the glenoid cavity, providing attachment for the biceps brachii muscle.

**Coracoid process (KOR-ah koid) (Gr. crowlike)(g):** the small process on the medial side of the supraglenoid tubercle for the attachment of the coracobrachialis muscle.

**8. Suprahamate process:** the caudal projection of the acromion found only in the cat. The distal end of the spine can be called the acromion or hamate (L. hooked) process.

WWW.ELIB4VET.COM

Fig. II-112 - OX -Scapula - med. view



## SPECIES DIFFERENCES:

**Clavicle:** Cat - a separate, non-articulating bone, seen radiographically. Dog - a rudimentary structure embedded in the brachiocephalic muscle, rarely seen radiographically. Horse and Ox - absent.

**Acromion (2):** absent in the horse and pig.

**9. Spinal tuber:** a bony enlargement of the scapular spine found in the horse and pig (poorly developed in the cat and ox).

**Scapular cartilage (7):** a narrow band in the dog, while in the horse, ruminants and pig it is a broad, thin structure.

## CLINICAL

**Secondary ossification centers:** - supraglenoid tubercle in the carnivores fuses by eight months of age. Supraglenoid tubercle and cranial glenoid cavity (fuse one year) and dorsal border of the scapula (fuses at three years).

**Clavicle:** in the cat can be mistaken for a bone in the esophagus on lateral radiographs.



# HUMERUS

Thoracic limb-79




Fig. II-114 - Dog - Lt. Humerus  
-- cran. view



Fig. II-115 - Dog  
- Lt. humerus  
- caud. view




Fig. II-116 - Cat - Lt. humerus  
- caud. view

- a. Tricipital line
- b. Brachial groove
- c. Lat. epicondylar crest
- d. Trochlea
- e. Capitulum
- f. Neck
- g. Insertion of infraspinous tendon (II-118)

**HUMERUS** (HYOO-mer-us) (arm or brachial bone): the largest bone of the thoracic limb. It articulates proximally with the scapula, forming the shoulder joint; and distally with the radius and ulna, forming the elbow joint.

**1. Head:** the rounded process articulating with the scapula's glenoid cavity to form the shoulder joint.

**2. Intertubercular (bicipital) groove:** the sulcus between the greater and lesser tubercles through which the tendon of the biceps brachii muscle runs.

**3. Greater (lateral, major) tubercle:** the large process cranio-lateral to the head to which many muscles attach. The point of the shoulder is a surface feature formed by the greater tubercle.

**4. Lesser (medial, minor) tubercle:** the process on the medial side of the head.

**5. Body (shaft, diaphysis):** the cylindrical part connecting the two ends (epiphyses) of the bone.

**6. Deltoid tuberosity:** the large tuberosity on the lateral side of the humerus.


**7. Humeral condyle:** the entire distal extremity of the humerus, including the two articular areas (humeral capitulum and humeral trochlea), the two fossae (three fossae in the cat) and the lateral and medial epicondyles.

**8. Lateral epicondyle:** the lateral side of the humeral condyle, giving rise to the extensors of the forearm. Functionally it is

# HUMERUS

Thoracic limb-80

Fig. II-117 - Ox - Lt. humerus  
- caud. view



10. Olecranon fossa

Fig. II-118 - Ox  
- Lt. humerus  
- cran. view




Fig. II-119 - Horse -lt. humerus  
- cran. view





Fig. II-120 - Horse - Lt. humerus  
- lat. view

known as the extensor epicondyle.

**9. Medial epicondyle:** the medial-most point of the humeral condyle, functionally known as the **flexor epicondyle** because it provides attachment for the flexor muscles of the forearm.

**10. Olecranon fossa (oh-LEK-ra-non):** the caudal excavation receiving the proximal end of the ulna on extension of the elbow.

**11. Radial fossa:** the excavation opposite the olecranon fossa receiving the proximal end of the radius on flexion of the elbow. The cat has a small coronoid fossa medial to the radial fossa for the medial coronoid process of the ulna on flexion of the elbow.

## SPECIES DIFFERENCES

**12. Supratrochlear foramen:** the hole between the olecranon and the radial fossa found in the dog and sometimes the pig. Nothing passes through it.

**13. Supracondylar foramen:** the opening in the medial epicondyle present only in the cat. To remember which side it is on, the median nerve and brachial vessels pass through it.

**14. Intermediate tubercle:** a prominence in the horse's intertubercular groove.

**15. Greater tubercle:** is divided into cranial and caudal parts in the ungulates.

# ULNA & RADIUS

7. Anconeal process

6. Trochlear notch

2. Head

1. Radius

4. Ulna

9. Interosseous space

WWW.ELIB4VET.COM


3. Carpal articular surface

Fig. II-121 - Dog - Lt. ulna & radius - lat. view

Fig. II-122 - Dog - Lt. ulna & radius - caud. view

- a. Articular fovea of radius (II-122)
- b. Neck of radius
- c. Groove for common digital extensor tendon (II-121)
- d. Styloid process of radius
- e. Radial tuberosity
- f. Coronoid process (II-122)
- g. Radial notch (not shown - lg. animals)
- h. Body of radius
- i. Body of ulna
- j. Olecranon process (tuberosity)

Thoracic limb-81



**1. RADIUS** (L. spoke of a wheel): the main weight-bearing bone of the forearm, articulating with the humerus and ulna forming the elbow joint and with the carpal bones and ulna forming the antebrachio-carpal joint. Three distal grooves on its cranial surface accommodate tendons.

**2. Head:** the proximal part of the radius which articulates (fovea capitis, a) with the humerus (capitulum) and ulna.

**3. Carpal articular surface:** the articular surface on the distal end of the radius (trochlea) which articulates with the carpal bones.

**Styloid process of radius (d):** distal end of the radius.

**4. ULNA** (L. elbow): the long, thin bone serving mainly for muscle attachment and formation of the elbow joint. Proximally it articulates with the humerus and radius, distally with the radius and the carpal bones.

**5. Olecranon** (Oh-LEK-ra-non): the proximal part of the ulna

providing a lever arm for the extensor muscles of the elbow. It forms the point of the elbow.

**6. Trochlear notch** (TROHK-lee-ar) (semilunar notch): the depression for articulation with the humerus and ending in the anconeal process.

**7. Anconeal process:** the proximal end of the trochlear notch which fits in the olecranon fossa of the humerus when the elbow is extended.

**Medial coronoid process (f):** the large distal end of the trochlear notch.

**8. Styloid process of the ulna:** the pointed, distal end of the ulna.

**9. Interosseous space:** the space between the ulna and radius, readily seen in the carnivores and pig. The horse has a proximal interosseous space and the ox has proximal and distal ones.



# ULNA & RADIUS

Thoracic limb-82




Fig. II-123 - Horse - Rt. ulna & radius - cran. view




Fig. II-125 - Ox - Rt. ulna & radius - cran. view

Fig. II-124 - Horse - Rt. ulna & radius - med. view

## SPECIES DIFFERENCES

**Ulna:** fuses with the radius in the horse and ruminant; therefore, these animals cannot supinate or pronate their forearm. It is not fused in the carnivores and pig, allowing pronation and supination.

**Styloid process of ulna:** the distal epiphysis of the horse's ulna is fused with the radius, and in essence becomes a part of the radius.

## CLINICAL

**Capped elbow, olecranon bursitis:** an inflammation causing the formation of a subcutaneous bursa over the olecranon tuberosity. In horses this is caused by repeated trauma of the elbow hitting the hoof while lying and is called "shoe boil".

**Ununited anconeal process:** failure of the secondary ossification of the anconeal process to unite with the ulna after five

months of age.

**Fragmented medial coronoid process (f):** can cause degenerative joint disease of the elbow.

**Premature closure of the epiphyseal growth plate (epiphyseal cartilage, physis):** can occur in the distal radius or ulna. The other bone will continue growing causing deformities of the bones distal to the carpus and joint problems in the elbow.

**Angular limb deformities in foals:** can be caused by opposite sides of the distal growth plate of the radius growing at different rates. If caught early it may be surgically corrected. A staple may be driven on either side of the physis to slow its growth and allow the other side to catch up. This must be removed when the limb straightens or the limb will deviate the opposite way. Periosteal stripping is the cutting of the periosteum on the side of the physis that is growing slowly. This will speed up its growth to catch up with the other side.




Fig. II-127 - Dog - Lt. carpus  
- dors. view




Fig. II-128 - Dog - Lt. carpus - lat. view

**MANUS:** the distal part of the thoracic limb, consisting of the carpus, metacarpus, phalanges and their associated sesamoid bones. It is also called the forepaw in the carnivores.

**CARPUS (KAR-pus) (L. wrist):** the carpal bones; also the compound joint formed by these bones, or the region between the forearm and metacarpus.

**CARPAL BONES:** the two rows of bones forming the carpus. The number of carpal bones varies between species due to fusion between bones or absence of one or more bones. The pig has the generalized pattern of eight bones. The proximal row consists of the radial carpal, intermediate carpal, ulnar carpal and accessory carpal bones. The distal row, from medial to lateral, consists of carpal bones 1-4.

## Proximal row:

- **Cr. Radial:** the largest carpal bone, medially located.
- **Ci. Intermediate:** between the radial and ulnar carpal bones.
- **Cu. Ulnar:** laterally located bone in the proximal row.
- **Ca. Accessory:** projects behind (palmar) the carpus, articulating with the ulnar carpal. (It is the only carpal bone to which muscles attach - flexor carpi ulnaris and extensor carpi ulnaris).

**Distal row:** consists of the 1st, 2nd, 3rd and 4th carpal bones ( $C_1$ ,  $C_2$ ,  $C_3$  &  $C_4$ ) in the generalized pattern.

- |  |                   |
|--|-------------------|
| Cr Radial carpal bone                        | a. Radius         |
| Ci Intermediate carpal bone                  | b. Ulna           |
| Cu Ulnar carpal bone                         | c. Metacarpal II  |
| Ca Accessory carpal bone                     | d. Metacarpal III |
| $C_1$ First carpal                           | e. Metacarpal IV  |
| $C_2$ Second carpal                          | f. Metacarpal V   |
| $C_3$ Third carpal                           |                   |
| $C_4$ Fourth carpal                          |                   |
| $C_{2+3}$ fused 2nd & 3rd carpal (ruminants) |                   |

## SPECIES DIFFERENCES

**Pig (Fig. II-143-144):** has the "generalized" carpus of eight bones.

**Horse:** conforms to the generalized pattern of eight bones unless the 1st carpal bone is missing, or rarely if a fifth one is present.

**Dog and cat:** have seven carpal bones due to fusion of the radial and intermediate carpal bones to form the dog's "radial" carpal bone.

**Ruminant:** has six carpal bones. The 1st carpal bone is missing and the 2nd and 3rd carpal bones are fused forming the "fused 2nd and 3rd" carpal bone.



Fig. II-129 - Horse - Lt. carpus - dors. view





Fig. II-130 - Horse - Lt. carpus - palm. view




Fig. II-131 - Ox - Lt. carpus - dors. view




Fig. II-132 - Ox - Lt. carpus - lat. view

## CLINICAL

Sesamoid bone of the oblique carpal extensor (extensor pollicis longus) tendon: is located on the medial side of the carpus and shouldn't be mistaken for a chip fracture.

Valgus and varus: terms for deviation of the bones distal to a joint. These can be caused by premature closure of the distal

growth plates of the ulna or radius in carnivores or by differential growth rates of the distal physis of the radius in foals.

Carpus valgus: lateral deviation of the bones distal to the carpus. (Memory aid - "L" in vaLgus for lateral deviation.)

Carpus varus: medial deviation of the bones distal to the carpus.






Fig. II-133 - Dog - Lt. metacarpal bones - dors. view




Fig. II-134 - Dog - Lt. metacarpal bones - palm. view

- |       |                |                             |
|-------|----------------|-----------------------------|
| McI   | Metacarpal I   | a. Base                     |
| McII  | Metacarpal II  | b. Carpal articular surface |
| McIII | Metacarpal III | c. Metacarpal tuberosity    |
| McIV  | Metacarpal IV  | d. Body                     |
| McV   | Metacarpal V   | e. Head                     |
|       |                | f. Sagittal ridge           |
|       |                | g. Condyles (med. & lat.)   |

**METACARPUS:** the region of the manus located between the carpus and digits.

**METACARPAL BONES:** the generalized metacarpus has five bones numbered I-V from medial to lateral. The species differ due to absence or fusion of bones. Each bone is composed of a base articulating with the carpus, a head articulating with the proximal phalanx of a digit, and a shaft connecting the two extremities. At least one sesamoid bone is associated with each metacarpal bone.

**CARNIVORE METACARPAL BONES:** the generalized pattern of five metacarpal bones. Metacarpal I (McI) is much reduced and bears no weight, it is part of the dew claw.

# METACARPAL BONES

**FIG METACARPAL BONES** (Fig. II-143 & 144): has four metacarpal bones. The 1st metacarpal bone (McI) is missing. Metacarpal bones II and V (McII and McV) are greatly reduced and don't bear weight. The weight is borne by metacarpals III and IV (McIII and McIV).

**HORSE METACARPAL BONES:** has three metacarpal bones. The 1st and 5th are missing.

**Splint bones:** the common name for the greatly reduced metacarpals II and IV (McII and McIV). The splints usually end distally in small swellings that are called the "buttons of the splints".

**Cannon bone:** the common name for the large metacarpal III (McIII). It is the only metacarpal to articulate with the digit.




Fig. II-135

Horse - Lt. Metacarpal bone  
- dors. view

Fig. II-136

Horse - Lt. Metacarpal bone  
- palm. view




Fig. II-137

Ox - Lt. metacarpal bones  
- dors. view

Fig. II-138

Ox - Lt. metacarpal bones  
- palm. view

## RUMINANT DIFFERENCES

- |                              |                              |
|------------------------------|------------------------------|
| h. Dors. longitudinal groove | k. Intertrochlear incisure   |
| i. Prox. metacarpal canal    | l. Palm. longitudinal groove |
| j. Dist. metacarpal canal    |                              |

**RUMINANT METACARPAL BONES:** two metacarpal bones. The 1st and 2nd (McI and McII) are missing and the 3rd and 4th are fused.

**Large metacarpal bone (cannon bone):** the common name for fused metacarpals III & IV.

**Small metacarpal bone:** the common name for the greatly reduced metacarpal V (McV).

## CLINICAL - HORSE METACARPUS

**"Bucked shins":** the inflammation (periostitis) of the dorsal surface of the horse's cannon bone affecting horses mostly under three years of age.

**"Splints":** an inflammation of the horse's interosseous ligament between the splint bones and the cannon bone (not to be confused with the splint bones).

**"Fractured splint":** a fracture of a splint bone.






Fig. II-139 - Dog - Lt. digits - dors. view

**DIGITS:** the bones corresponding to the fingers and toes of man. There are five digits in the generalized digital pattern, numbered from medial to lateral (I-V). Species differences are due to reduction in the number of digits. The digits generally consist of three phalanges and a number of sesamoid bones.

**Dew claw or paradigit:** a digit not bearing weight.

**CARNIVORE - DIGITS:** four main weight-bearing digits (II-V).

**Dew claw (i):** the 1st digit and the 1st metacarpal bone. The 1st digit is reduced in size having only two phalanges, the proximal and distal, and one proximal sesamoid bone. Some dog breeds have double dew claws.

**1. Proximal phalanx (FAY-lanks):** the first phalanx divided into the base, body, and head.

**2. Middle phalanx:** the second phalanx with the same structure as the proximal phalanx, but shorter. It is not present in the first




Fig. II-140 - Dog - Lt. manus - palm. view

digit.

**3. Distal phalanx:** the third phalanx carries the horny claw. The flexor process (f) on the palmar side provides insertion for the deep digital flexor tendon. The extensor process (e) located on the dorsal proximal part of the four main digits provides insertion for the tendons of the common digital extensor muscle (long digital extensor muscle in the hindlimb).


**4. Ungual process:** the tapered, cone-shaped process covered by the horny claw.

**Horny claw (h):** the fingernail-like structure covering the ungual process.

**5. Palmar sesamoid bones:** the nine small bones at the metacarpophalangeal joint; two for each of the four main digits and one for the 1st digit.

**Distal sesamoid bones:** are represented by cartilage in the carnivores and rarely ossify.





- a. Base
- b. Body
- c. Trochlea
- d. Ungual crest (carnivores)
- e. Extensor process

- f. Flexor process
- g. Dors. sesamoid bone (dog)
- h. Horny claw (carnivores)
- i. Dew claw (carnivores, pig & ox)

**OX - DIGITS:** four digits, two weight-bearing and two non-weight-bearing. The 1st digit is missing. The second and fifth digits are vestiges (improbable to find) externally manifested as horny dew claws behind the fetlock.

**Third and fourth digits:** fully developed weight-bearing digits consisting of three phalanges and three sesamoid bones each. They are numbered medially to laterally.

1. Proximal phalanx: the long pastern as in the horse.

2. Middle phalanx: the short pastern.

3. Distal phalanx: the coffin bone.

**Sesamoid bones:** two proximal (5) at the metacarpophalangeal joint and one distal (6) at the distal interphalangeal joint for each digit.

**FIG - DIGITS:** four digits, the 1st is missing. The second and fifth are reduced and do not bear weight and are called dew claws. They are fully formed except that they lack a distal sesamoid bone. The main digits (3rd and 4th) consist of three phalanges, two proximal sesamoids and one distal sesamoid.

Fig. II-143 - Pig - Lt. manus  
- dors. view





Fig. II-144 - Pig  
- Lt. manus  
- Palm. view



Cr Radial carpal bone  
Ci Intermediate carpal bone  
Cu Ulnar carpal bone  
Ca Accessory carpal bone  
C3, C4, C5 3rd, 4th, and 5th carpal bones

R Radius  
U Ulna  
McII-V Metacarpal bones

**HORSE - DIGITS:** one digit per limb supporting Mc III.

1. Proximal phalanx: the long pastern.

2. Middle phalanx: the short pastern.

3. Distal phalanx: the coffin bone. It fits into the hoof and has an extensor process for the insertion of the digital extensor tendon.

- Parietal surface (a): surface next to the hoof wall.
- Sole surface (b): surface facing the ground.
- Medial and lateral solar foramina (h): entrances to the solar canal for the continuations of the digital arteries.
- Solar canal: the canal between the solar foramina for the terminal arch of the arteries.
- Palmar processes, "angles" or "wings" (c): of the coffin bone.
- Parietal grooves: sulci on the parietal surface.

Ungual cartilage (Fig. III-23): the medial and lateral cartilages of the hoof attached to the coronary border (e) of the distal phalanx.

4. Proximal sesamoid bones or "sesamoids": the two small bones on the palmar side of the metacarpophalangeal (fetlock) joint. The lateral one is taller radiographically than the medial one. This bone is situated between the suspensory ligament and the distal sesamoidean ligaments. Together these make up the suspensory apparatus of the fetlock joint.

5. "Navicular bone" (L. little ship) or distal sesamoid bone: unlike other sesamoid bones it is not embedded in a tendon but is between the deep digital flexor tendon and the middle and distal phalanges. It has articular and flexor surfaces and proximal and distal borders.

## CLINICAL - HORSE

Quittor: an inflammation of the ungual cartilages.

Sidebone: the mineralization of the ungual cartilages with age. This usually has no clinical significance.

Ringbone: periosteal bone deposition on the phalanges, occurring near the pastern joint (proximal interphalangeal joint) is a high ringbone; near the coffin joint (distal interphalangeal joint) is a low ringbone.

Osselets: ringbone around the metacarpal/metatarsal phalangeal joint (fetlock).


Buttress foot (pyramidal disease): bone deposition at the extensor process of the coffin bone, caused by a fracture of the extensor process or it may be a form of low ring bone.

Rotation of the coffin bone: the rotation of the toe of the distal phalanx towards the sole of the hoof, resulting from chronic laminitis.

"Navicular" disease: a lameness blamed on problems with the distal sesamoid bone and/or the deep digital tendon passing over this bone.




**Fig. II-145 - Horse**  
- Lt. digit  
- dors. view



**Fig. II-146 - Horse - Lt. digit**  
- lat. view

**5. Navicular bone**  
(dist. sesamoid bone)



**Fig. II-147 - Horse - Lt. manus - palm. view**



Fig. II -148 - Dog - Lt. pelvic limb skeleton  
- lat. view




Fig. II-149 - Dog - Lt. pelvic limb skeleton  
- med. view

# HORSE - SKELETON - PELVIC LIMB

Pelvic limb-92

Fig. I-150 - Horse - Lt. pelvic limb skeleton  
- lat. view





Fig. II-151 - Horse  
Lt. pelvic limb  
skeleton - med. view



A. Hip joint (coxal articulation)  
B. Stifle joint (genual articulation)  
C. Hock (tarsal) joint

D. Metatarsophalangeal joints  
E. Prox. interphalangeal joint  
F. Dist. interphalangeal joint

Converging arrows  
indicate angle of  
flexion of joint

Fig. II-152 - Ox - Lt. pelvic limb skeleton  
- lat. view




Fig. II-153 - Ox - Lt. pelvic limb  
skeleton - med. view

A. Hip joint (coxal articulation)  
B. Stifle joint (genual articulation)  
C. Hock (tarsal) joint


D. Metatarsophalangeal joints  
E. Prox. interphalangeal joint  
F. Dist. interphalangeal joint



# **PIG - SKELETON - PELVIC LIMB**

Pelvic limb-94



**Fig. II-154 - Pig - Lt. pelvic limb skeleton  
- lat. view**



**Fig. II-155 - Pig - Lt. pelvic limb skeleton  
- med. view**

# **PELVIC GIRDLE**

**Fig. II-156 - Dog - Pelvic girdle - cran. view**



**Fig. II-157 - Horse - Lt. os coxae - lat. view**

**PELVIC GIRDLE** or bony pelvis: consists of the joining of the two hip bones (ossa coxarum), sacrum and first few caudal vertebrae. It encloses the pelvic cavity. The "pelvic inlet" is the cranial opening into the pelvic cavity. The "pelvic outlet" is the caudal opening out of the pelvic cavity. The widest horizontal distance of the pelvic cavity is the transverse diameter. The vertical diameter from the pelvic symphysis to the sacrum (promontory).


**HIP BONE** or os coxae: the fused ilium, ischium, pubic and acetabular bones. The acetabular bone is in the center of the acetabulum and fuses early leaving no visible indication of its presence.

**Hip bones** or ossa coxarum: the two hip bones. They are joined at the pelvic symphysis.

**1. ILIUM:** the largest and most cranial part of the os coxae. It consists of a wing and a body. It forms the cranial part of the acetabulum and articulates with the sacrum. The ischiatic spine (j) separates the greater (i) and lesser (k) ischiatic notches.

**2. Wing:** the lateral masses of the ilium that articulate with the sacrum. The gluteal surface (h) is the lateral aspect of the wing where the middle gluteal muscle arises. The auricular surface (c) articulates with the sacrum forming the sacroiliac joint. The iliac crest (a) is the cranial edge of the wing.






**Fig. II-158 - Horse - Ossa coxarum**  
- ventr. view

- |                                      |                             |
|--------------------------------------|-----------------------------|
| a. Crest of ilium                    | i. Greater ischiatic notch  |
| b. Tuber sacrale (11-157)            | j. Ischiatic spine          |
| c. Auricular surface (11-156)        | k. Lesser ischiatic notch   |
| (sacropelvic surface)                | l. Ischiatic table (11-159) |
| d. Body of ilium                     | m. Ischiatic arch           |
| e. Arcuate line                      | n. Sacrum                   |
| f. Iliopubic eminence                | o. Sacroiliac joint         |
| g. Pubic tubercle                    | p. Lunate surface           |
| h. Gluteal surface of ilium (11-157) | q. Acetabular notch         |

**Fig. II-159 - Ox - Ossa coxarum**  
- dors. view



**3. Tuber coxae:** the palpable prominence on the lateral wing. In the ox it is called the "hook".

**Tuber sacrale (b):** the medial process of the wing next to the sacrum.

**4. ISCHIUM** (G. hip): the caudal-most part of the os coxae. The ischiatic table (l) is the horizontal part caudal to the obturator foramen.

**5. Ischiatic tuberosity** ("pin bone" in the ox): the thick, caudal part of the ischium providing attachment for the caudal thigh muscles.

**Ischiatic arch (m):** the caudal indentation between the ischiatic tuberosities.

**6. PUBIS:** the cranioventral part of the os coxae. The pubis consists of a central body and two branches (rami). The cranial

ramus forms part of the acetabulum and the caudal ramus is medial to the obturator foramen. The pecten is the cranial border of the two pubic bones (pubes). The pectineus muscle attaches to the iliopubic eminence (f).

**7. ACETABULUM** (as'e-TAB-yoo-lum) (L. vinegar cup): the concavity articulating with the femoral head. It is formed by the fusion of the ilium, ischium, pubic and acetabular bones. The ligament of the femoral head attaches to the fossa in the acetabulum. The lunate surface (p) articulates with the head of the femur.

**8. OBTURATOR FORAMEN** (OB-too-ray'ter): large opening in the floor of the os coxae.

**9. PELVIC SYMPHYSIS:** the junction of the right and left os coxae between the two pubic and two ischial bones.

**CLINICAL:** Fractures of the bony pelvis are common in the dog.



# FEMUR

Pelvic limb-97

**FEMUR** (thigh bone): the heaviest bone in the body articulating proximally with the hip bone (forming the hip joint) and distally with the tibia and patella (forming the stifle joint).

**1. Head:** the smooth process articulating with the acetabulum of the os coxae, forming the hip joint. It has a depression (fovea) (h) for the round ligament of the femur. The neck (a) joins the head to the body of the femur.

**2. Greater (major, lateral) trochanter** (troh-KAN-ter): the large prominence lateral to the head.

**3. Lesser (minor, medial) trochanter:** the prominence distal to the head.

**Trochanteric fossa (j):** depression on the caudal aspect of the femur between the trochanters.

**4. Third trochanter:** the prominence on the lateral side, distal to the greater trochanter.

**5. Medial and 6. lateral condyles** (G. knuckles): the two large prominences articulating with the tibia and the menisci (fibrocartilage discs between femur and tibia).

**Extensor fossa (e):** depression on the lateral condyle for the attachment of the long digital extensor muscle.

**7. Patellar surface or femoral trochlea** (L. pulley): the groove articulating with the patella, bounded by two ridges, the medial one being the thicker in all species.

**8. PATELLA** (pa-TEL-a) (L. little plate) (knee cap): the largest sesamoid bone of the body, articulating with the patellar surface of the femur.

## SPECIES DIFFERENCES

**9. Trochlear tubercle:** the large prominence on medial ridge of the patellar surface in the horse. The patella locks over this structure when the stay apparatus is in use (pg. 198).

**4. Third trochanter (4):** absent in the ruminants.

**10. Fabellae** (L. bean): the two small sesamoid bones embedded in the heads of the gastrocnemius muscle of the carnivore.

1. Head

2. Greater trochanter

Fig. II-160 - Dog - Lt. femur - cran. view

4. Third trochanter

WWW.EBIB4VET.COM

3. Lesser trochanter

8. Patella

7. Patellar surface

Fig. II-161 - Dog - Lt. femur - caud. view

10. Fabella

a. Neck of femur

b. Body of femur

c. Med. epicondyle

d. Lat. epicondyle

e. Extensor fossa

f. Base of patella

g. Apex of patella

h. Fovea of femoral head

i. Intertrochanteric crest

j. Trochanteric fossa

k. Med. & lat. supracondylar tuberosities

l. Popliteal surface

m. Intercondyloid fossa

n. Nutrient foramen

o. Supracondyloid fossa

p. Articular surface of patella (II-163)


6. Lat. condyle

5. Med. condyle

# FEMUR


Pelvic limb-98

Fig. II-162 - Horse  
- Lt. femur - caud. view




2. Greater trochanter

Fig. II-164 - Ox - Rt. femur  
- cran. view




WWW.ELIB4VET.COM

Fig. II-165 - Ox - Rt. femur  
- caud. view



8. Patella

Fig. II-163 - Horse - Rt. Patella  
- cran. view - caud. view



Sesamoid bone of the popliteal tendon in carnivores: shouldn't be mistaken for a chip fracture in radiographs.

Patellar fibrocartilage: in the horse and ox attaches the medial patellar ligament with the patella.

## CLINICAL

Mid shaft fractures in carnivores: result in the caudal displacement of the distal fragment due to the pull of the gastrocnemius muscle.

# TIBIA & FIBULA

Pelvic limb-99





Fig. II-166 - Dog - Rt. tibia & fibula - cran. view

Fig. II-167 - Dog - Rt. tibia & fibula - caud. view



**LEG SKELETON (L. crus):** the tibia and fibula.

**1. INTEROSSEOUS SPACE:** separates the tibia and fibula.

**2. TIBIA** ("shin bone"): the medially located long bone.

**3. Lateral and 4. medial condyles** (G. knuckles): the two processes articulating with the corresponding femoral condyles and fibrocartilage discs (menisci).

**5. Tibial tuberosity:** the large proximal cranial process where muscles and the patellar ligament(s) attach.

**6. Distal articular surface or cochlea:** the two grooves, separated by a ridge, articulating with the trochlea of the tibial tarsal bone.

**7. FIBULA** (L. pin or skewer) ("calf bone"): the long, thin bone bearing little weight, serving mainly for muscle attachments. It articulates distally with the tibia and the fibular tarsal bone. It is the more lateral of the two bones of the leg

**8. Lateral malleolus** (mal-LEE-oh-lus): the distal end of the fibula.



# TIBIA & FIBULA

Pelvic limb-100

Fig. II-168 - Horse - Lt. tibia & fibula  
- cran. view




Fig. II-169 - Horse - Lt. tibia  
& fibula - caud. view

- |                                      |   |
|--------------------------------------|---|
| a. Intercondylar eminence            | f. Head of fibula                       |
| b. Cran. intercondylar area          | g. Body of fibula                       |
| c. Cran. border                      | h. Body of tibia                        |
| d. Muscular groove (extensor sulcus) | i. Groove of lat. malleolus             |
| e. Med. malleolus                    | j. Popliteal notch (II-167)             |
|                                      | k. Popliteal sesamoid bone (carnivores) |

Fig. II-170 - Ox - tibia & fibula  
- cran. view





Fig. II-171 - Ox - tibia  
& fibula - lat. view

## SPECIES DIFFERENCES

**Carnivores and pig:** the tibia and fibula are not fused.

**Ruminants:** the head of the fibula fuses to the tibia. Most of the body of the fibula fails to develop, therefore the proximal and distal fibula are not connected and there is no interosseous space. The distal end of the fibula (lateral malleolus) remains separate from the tibia.

**Horse:** the fibula is a reduced bone that reaches only half way down the tibia. The true distal end of the fibula (lateral malleolus) is fused with the tibia.

## CLINICAL

Growth plates in the dog: unite by one year of age. The one for the tibial tuberosity can be mistaken for a fracture in all species.




Fig. II-172 - Dog - Lt. tarsus - dors. view




Fig. II-173 - Dog - Lt. tarsus - med. view

**TARSUS** (G. *tarsos* flat) or "hock": the two (or two and a half) rows of bones between the crus and the metatarsal region. The proximal row consists of the talus (tibial) and calcaneus (fibular) tarsal bones. In the generalized pattern seen in the carnivores and pig, the distal row consists of central, 1st, 2nd, 3rd, and 4th tarsal bones. The central tarsal bone is actually between the proximal row and the numbered tarsal bones. It doesn't span the whole tarsus because of the "two story" fourth tarsal bone.

**1. Talus (L. ankle bone) or tibial tarsal bone**: the largest bone of the tarsus, located on its dorsomedial side. It articulates by its trochlea (b) with the tibia (the tibia and fibula in the dog).

**2. Calcaneus (kal-KAY-nee-us) (L. heel) or fibular tarsal bone**: the second bone of the proximal row, lateral to the tibial tarsal bone.

**3. Calcanean tuberosity**: the large process of the fibular tarsal bone serving as a lever arm for the common calcanean tendon.

**Sustentaculum tali (a)**: the medial "shelf" of the calcaneus. The tendon of the lateral head of the deep digital flexor tendon crosses it.

## SPECIES DIFFERENCES

**Carnivores and pigs**: have seven tarsal bones.

**Ruminants**: have five tarsal bones due to fusion of four bones to form two bones - centroquartal bone (fused central and fourth) and fused second and third.

**Horse**: has six tarsal bones due to fusion of two bones - fused 1st and 2nd.

**Ruminant and pig**: have two trochlea to their talus.


## CLINICAL

**Capped hock**: a bursitis (inflammation) of a subcutaneous bursa that forms due to trauma over the calcanean tuberosity. It may be seen in cattle and horses.




**Fig. II-174 - Horse - Rt. tarsus - med. view**

**Fig. II-175 - Horse - Rt. tarsus - plant. view**



**Fig. II-176 - Ox - Rt. tarsus - dors. view**



**Fig. II-177 - Ox - Rt. tarsus - lat. view**

a. Sustentaculum tali  
b. Trochlea  
c. Central tarsal bone  
d. Groove for flexor tendons

I - IV. Numbered tarsal & metatarsal bones  
I & II. Fused 1st & 2nd tarsal bones (horse)  
IV & c. Centroquartal bone (fused central & 4th tarsal bone) (ox)  
II & III. Fused 2nd & 3rd tarsal bones (ox)



# METATARSAL BONES

Pelvic limb-118




Fig. II-178 - Horse - Metatarsal bone - plant. view

## BOVINE METATARSAL BONES

- a. Base
- b. Tarsal articular surface
- c. Prox. metatarsal canal
- d. Dist. metatarsal canal
- e. Head
- f. Intertrochlear incisor
- g. Plant. longitudinal groove
- h. Body




Fig. II-179 - Ox - Metatarsal bone - plant. view


**METATARSAL BONES and DIGITS** (met'a-TAR-sul): their pattern is the same as in the thoracic limb of the horse and pig.

## SPECIES DIFFERENCES

**Carnivores:** the first metatarsal bone is even more reduced than in the front limb and the first digit (dew claw) is often absent.

**Ruminants:** the fifth metatarsal bone is absent. A metatarsal sesamoid bone is present and is often called the "small metatarsal" or metatarsal II.

Fig. II-180 - Pig - Lt. pes -dors. view Fig. II-181 - Pig - Lt. -plant view




## PORCINE METATARSALS

- A Calcanean tuberosity
- Tt Tibial tarsal bone
- Tf Fibular tarsal bone
- Tc Central tarsal bone
- T 1-4 Tarsal bones 1-4
- Mt 2-5 Metatarsal bones 2-5
- Ph 1-3 Prox., middle & dist. phalanges

## Chapter III

# Joints

---



**ARTICULATION** (ar-tik'-yoo-LAY-shun) or **JOINT**: union or junction between two or more bones of the skeleton.

**Arthrology** (G. *arthros*, joints + *logos*, study): the study of joints.

**JOINT CLASSIFICATION**: Joints can be classified by several criteria.

**SIMPLE OR COMPOUND JOINTS**: classified by the number of bones articulating with each other.

- **Simple joints**: articulations with two articulating bones.
- **Compound joints**: articulations with more than two bones articulating (e.g., stifle).

**STRUCTURAL CLASSIFICATION**: classified by their uniting medium into fibrous, cartilaginous and synovial joints.

- **Fibrous joint**: articulation united by fibrous tissue, allowing little or no movement, as in a suture or syndesmosis. These are often temporary joints that later ossify (synostosis).

- **Cartilaginous joint**: articulation united by fibrocartilage, hyaline cartilage, or both, as in a synchondrosis or a symphysis. These also can be slightly movable or immovable.

- **Synovial joint**: an articulation united by a synovial joint capsule. These are freely movable.

**FUNCTIONAL CLASSIFICATION OF JOINTS**: indicates the degree of motion possible.

- **Immovable joint or synarthrosis** (sin'-ar-THROH-sis) (pl.= synarthroses) (synarthroidal joint) (*syn*, together; *arthro*, joint): the fixed tight union allowing little or no movement and having great strength (e.g., suture between two facial bones).

– **Suture** (SOO-chur): a **fibrous joint** between the skull bones. They may ossify with age.

– **"Hyaline cartilage joint"** or synchondrosis (sin'kon-DROH-sis): an immovable, temporary joint of **hyaline cartilage**, e.g., the cartilaginous epiphyseal plate uniting the diaphyses and epiphyses (pg. 22 of immature bones). The epiphyseal plate allows growth of the bone and then ossifies with age. This process eliminates the joint by forming a synostosis (ossified joint). A few synchondroses persist through life, such as the costochondral junctions (pg. 131).

- **Slightly movable joint or amphiarthrosis** (am-fee-ar-THROH-sis) (amphiarthroidal joint): a joint connected by either connective tissue or fibrocartilage (e. g., between the vertebral bodies). *Amphi*, as in amphibian, implies both immovable and movable (which it is), allowing only slight motion.

– **"Ligamentous joint"** or syndesmosis (sin'-dez-MOH-sis)

(G. *syndesmos*, ligament): a **fibrous joint** uniting two bones by a sheet of fibrous connective tissue (e.g., attachments between the costal cartilages in the costal arch [pg. 71] and the interosseous ligament [pg. 111, e] between the radius and ulna in carnivores).

– **Symphysis** (SIM-fi-sis): the **fibrocartilaginous** (or possibly hyaline cartilaginous) joints that occur on the midline of the body. Although they may or may not ossify with age, they always limit the motion of the joint. Examples are the pelvic symphysis (pg. 118) and joints between sternbrae (pg. 131,1) and vertebral bodies (pg. 130). Fibrocartilage, a strong form of cartilage, is found where bones need to be strongly bound together and still allow some movement.

- **Freely movable joint or diarthrosis** (dy'ar-THROH-sis) (diarthroidal joint): synovial joints. The uniting medium may be considered the joint capsule.

- **Synovial joint**: discussed on pg. 106.

**GOMPHOSIS** (gom-FOH-sis): the name for the fibrous implantation of the teeth into the alveoli of the jaw bone. This is not a true joint because the teeth are not part of the skeleton. This peg-and-socket joint is held together by fibrous connective tissue, the **periodontal ligament**, that attaches each tooth in its socket.

*Authors note:* The proper terms for the different classification of joints (synarthrosis, synchondrosis, syndesmosis, synostosis, amphiarthrosis, etc.) are confusing, easily forgotten, and probably won't make you a better veterinarian.






Fig. III-1 - Fibrous & cartilaginous joints

**SYNOVIAL** (sin-OH-vee-al) (diarthroidal) **JOINT** (movable joint): characterized by its mobility, joint cavity, articular cartilage, synovial membrane and fibrous capsule. This is the most common type of joint. Functionally it is freely movable.

**1. Joint capsule:** the two-layered structure surrounding the joint, made of an outer fibrous layer and an inner synovial membrane.

**2. Fibrous layer (capsular ligament):** the white and yellow elastic fibrous part of the joint capsule. It attaches to the periosteum on or near the margin of the articular cartilage. Its thickness varies from joint to joint and within each joint.

**3. Synovial membrane:** the inner lining of the fibrous layer. It is highly vascular, nerve rich, and produces synovial fluid. The membrane may extend outside the fibrous layer to communicate with a synovial sheath or to form a bursa under a tendon or ligament.

**Synovial fluid:** the viscous liquid produced by the synovial membrane to lubricate the joint, supply nutrients, and remove waste from the hyaline articular cartilage. It has the consistency of raw egg white.

**4. Articular cartilage** (ar-TIK-yoo-lar KAR-u-tij): the translucent, bluish-tinged cartilage, usually hyaline, covering the articular ends of bones. It reduces the effects of concussion and friction by its compressibility, elasticity and smoothness. Varying in thickness between and within joints, the cartilage is thickest in areas of highest pressure and friction. Having no vascular or nerve supply, articular cartilage depends on synovial fluid to supply nutrients and remove waste products.

**Ligaments (5-6):** strong bands of white fibrous connective tissue uniting bones. They function to keep joint surfaces in apposition and still allow movement. They are usually inelastic and may be intracapsular or extracapsular.

**5. Intracapsular ligaments:** ligaments located within the joint capsule. They are not within the joint space because the synovial membrane reflects over them (e.g., cruciate ligaments of the stifle).

**6. Extracapsular ligaments:** ligaments developing outside of or as part of the joint capsule (e.g., the collateral ligaments on the sides of all hinge joints).

**7. Joint cavity:** a unique feature of a synovial joint. It is little more than a potential space containing a trace of synovial fluid.

**8. Meniscus or disc:** a plate of fibrocartilage partially or completely dividing a joint cavity. It functions to allow a greater variety of motion and alleviate concussion. Discs are found only in the stifle (pg. 120) and temporomandibular joints (pg. 127). The intervertebral discs do not divide a joint space.

**9. BURSA** (BUR-sa) (synovial): a sac-like structure between

different tissue that reduces friction between these tissues. Resembling a synovial joint capsule, its walls consist of a fibrous layer lined by a synovial membrane. Bursae are located between skin and bones, tendons and bones, muscles and bones, and ligaments and bones.

**10. SYNOVIAL SHEATH:** a structure similar to a bursa that wraps completely around a tendon. It reduces friction between the tendon and underlying bones.

## CLINICAL

**False joints:** a joint formed in an unreduced (unhealed) fracture, having all the structures of a synovial joint.

**Excess synovial fluid:** since synovial fluid in the healthy animal is minimal, the amount of fluid present indicates the state of health of the joint.

**Luxations or dislocations:** an articular separation, usually due to injury or degenerative changes, but may also have predisposing genetic factors (e.g., patellar dislocation in toy poodles).

**Bursitis** (bur-SY-tis): inflammation of a bursa.

Fig. III-3 - Horse - Stifle  
- caud. view




Fig. III-2 - Ox - Digit & dist. part of  
metacarpus - sagittal section




Fig. III-4 - Ox - Digits, synovial sheaths & bursae



**CLASSIFICATION of SYNOVIAL JOINTS:** Synovial joints are freely movable joints classified in several ways - by the number of articular surfaces, by the shape of the articular surfaces, or by the particular function of the joint.

**NUMBER of ARTICULAR SURFACES:** a joint is either simple or compound.


- **Simple joint:** two articular surfaces enclosed in a joint capsule (e.g., shoulder joint).
- **Compound joint:** more than two articular surfaces enclosed within the same joint capsule (e.g., stifle).

**CLASSIFICATION BY MOVEMENT:** the contraction of muscles crossing a joint and the shape of the joint produce its characteristic movements.


- **Plane (arthrodial) joint (ar-THROH-dee-al):** multiarticular articulations having flat articular surfaces allowing a simple gliding or sliding motion (e.g., carpal, small tarsal bones, cranial and caudal articulation between vertebrae).
- **Ball-and-socket (spheroidal) joint:** a multiarticular articulation consisting of a spheroidal head fitting into a pit or socket allowing universal movement - flexion-extension, abduction-adduction, medial and lateral rotation, and circumduction (e.g., shoulder and hip joints).
- **Hinge (ginglymus) joint (JIN-gli-mus):** a uniaxial joint allowing movement at right angles to the bones involved (flexion and extension) (e.g., elbow joint).
- **Pivot (trochoid) joint (TROH-koyd):** a uniaxial joint allowing rotation around a longitudinal axis of a bone (e.g., atlanto-axial joint).
- **Condylar joint:** a uniaxial joint formed by two condyles of one bone fitting into concavities of another bone. Flexion and extension and a little rotation are permitted by such a joint (e.g. femorotibial joint, the temporomandibular joints [both together form a condylar joint]).
- **Ellipsoidal joint:** a biaxial joint formed by an ellipsoidal, convex surface fitting into a concavity. Movement in two planes is allowed (flexion-extension; abduction-adduction) with a small amount of rotation (e.g. radiocarpal joint).
- **Saddle joint:** a biaxial joint with the articular surface of the two bones concave in one direction and convex in the other. These surfaces fit together like two saddles, one rotated 90 degrees. A saddle joint allows the same motions as the ellipsoid (flexion-extension; abduction-adduction) and some rotation (e.g., distal interphalangeal joints).

**MOVEMENT OF SYNOVIAL JOINTS:** Synovial joints may show one or more of the following movements, depending on their shape and where the muscles cross them.



- **Flexion (FLEK-shun):** decreasing the angle between two bones.
- **Extension (ek-STEN-shun):** increasing the angle between two bones.
- **Dorsal and ventral flexion:** bending the spinal column dorsally or ventrally.
- **A-B-duction (ab-DUK-shun):** moving a part away from the median plane, or a digit away from the axis of the limb.
- **A-D-duction (ad-DUK-shun):** moving a part toward the median plane or a digit toward the axis of the limb.
- **Circumduction:** movement circumscribing a cone shape, accomplished by combining flexion, abduction, extension and adduction in order.
- **Rotation:** movement around the long axis of a part (e.g., radio-ulnar joints in carnivores).
- **Universal:** all the above movements (e.g., shoulder joint).




Plane Joints



Hinge Joint



Ball & Socket Joints




Pivot Joint


Fig. III-5 - Synovial joints - Ox

Fig. III-7 - Ox - Shoulder joint  
- cran. view

Fig. III-6 - Horse - Shoulder joint



- a. Scapula
- b. Humerus
- c. Biceps brachii tendon
- d. Fibrous band
- e. Intertuberal bursa
- f. Infraspinatus bursa (inconstant)
- g. Coracobrachialis m.
- h. Synovial bursa
- i. Infraspinatus tendon



Shoulder joint capsule




Fig. III-8 - Ox - Shoulder joint  
- med. view

**SHOULDER JOINT**, glenohumeral or scapulohumeral joint: a ball-and-socket (spheroid) type synovial joint between the glenoid cavity and the humeral head. It has a loose joint capsule with no true collateral ligaments. The muscles crossing this joint provide enough support so shoulder luxation is rare in the dog. It is functionally a freely movable (diarthrodial) joint.

**Movement:** capable of universal motion, but chiefly flexion and extension in the domestic animals.

**Synovial sheath of biceps brachii tendon:** an extension of the joint capsule around the tendon of the biceps brachii muscle as it passes in the bicipital (intertubercular) groove of the humerus.

**Bicipital bursa:** located in the bicipital (intertubercular) groove of horses under the bicipital tendon. Unlike the synovial sheath in dogs, it doesn't communicate with the shoulder joint capsule.

**Infraspinatus bursa:** located between the tendon of insertion of the infraspinatus muscle and the greater tubercle.

**Transverse humeral ligament:** attaches to the greater and lesser tubercles and holds the biceps tendon in the intertubercular (bicipital) groove.

## CLINICAL

**Joint blocks:** in the horse the bicipital bursa and the shoulder must be blocked separately because they don't communicate.

**Osteochondrosis:** a failure of cartilage maturation. Pressure on such a defective cartilage will cause it to crack and may cause a piece ("joint mouse") to be separated and float in the synovial space (osteochondrosis dissecans). This is most common on the head of the humerus in dogs.



## 2. Med. collateral lig.





Fig. III-9 - Horse - Elbow joint - craniolat. view

- a. Humerus
- b. Olecranon
- c. Radius
- d. Biceps brachii tendon
- e. Interosseous lig.
- f. Triceps brachii (olecranon) bursa

Fig. III-10 - Ox - Elbow joint - lat. view



## 2. Med. collateral lig.




Fig. III-11 - Ox - Elbow joint - med. view

## 1. Elbow joint capsule

**ELBOW JOINT** (cubital articulation or humeroradioulnar): a hinge (ginglymus) type of synovial joint allowing flexion and extension. It is also a compound joint formed between the humerus, the radius and the ulna.

**Joint capsule:** the sac enclosing all three articular parts.

**Ligaments:** the medial (2) and lateral (3) collateral ligaments located on the sides of the joint.

**The proximal radioulnar joint:** the joint between the proximal radius and proximal ulna. This joint is fused in the horse and ruminants. Along with the distal radioulnar joint, it allows 90° rotation of the paw.

**Interosseous ligament of the radius of the carnivores:** a thin band of connective tissue passing transversely around the head of the radius and attaching at both ends to the ulna. With the ulna it forms a ring in which the radius can turn when the forearm is rotated.

## CLINICAL

**Elbow luxation:** uncommon in the dog due to the anconeal process projecting into the olecranon fossa. It is more common laterally than medially because of the large medial epicondyle. To reduce a lateral luxation the joint should be maximally flexed so the anconeal process can be negotiated back into the olecranon fossa.

**Ununited anconeal process, fragmented medial coronoid process and osteochondrosis of the humeral trochlea:** can all cause lameness of the elbow.

**Olecranon bursitis or capped elbow:** a false subcutaneous bursa between the skin and the olecranon due to repeated trauma. This is called "shoe boil" in horses due to the repeated contact between the hoof or shoes with the elbow when the animal is laying down.



# JOINT - CARPUS

Thoracic limb-113





Fig. III-13 - Ox - Carpus, capsule removed - cran. view

2. Lat. collateral lig.


Fig. III-12 - Ox - Lt. carpus - cran. view

- a. Radius
- b. Radial carpal bone
- c. Ulnar carpal bone
- d. Metacarpal bone
- e. Intercarpal lig.
- f. Radiocarpal synovial sac
- g. Middle carpal synovial sac
- h. Carpometacarpal synovial sac
- i. Intercarpal joint
- j. Accessory carpal bone



1. Joint capsule

Fig. III-14 - Horse - Lt. carpus - caudomed. view



3. Med. collateral lig.

**DISTAL RADIOULNAR JOINT:** between the distal radius and ulna. It is part of the antebrachicarpal joint with which it shares a joint capsule. With the proximal radioulnar joint it is responsible for the rotation allowed in the forearm of the carnivores and pigs. It is fused in the horse and ruminants.

**CARPAL JOINTS:** a hinge (ginglymus) type of synovial joint, allowing flexion and extension with some lateral movement. It consists of three main joints - antebrachicarpal, middle carpal and carpometacarpal.

**Antebrachicarpal joint:** between the distal radius and ulna and the proximal row of carpal bones. There is a lot of movement in this joint.

**Middle carpal joint:** between the two rows of carpal bones. It communicates with the carpometacarpal joint. Although less than the antebrachicarpal joint, it also has a lot of movement.

**Carpometacarpal joint:** between the distal row of carpal bones and the metacarpal bones. It communicates with the middle carpal joint. There is very little movement in this joint.

**Intercarpal joints:** plane joints between the individual carpal bones.

**INTERMETACARPAL JOINTS:** articulations between the proximal ends of the metacarpal bones.

**Ligaments:** consist of two collateral ligaments (2, 3) and many intercarpal ligaments between individual carpal bones. The collateral ligaments don't completely cross all three joints of the carpus.

**Palmar carpal ligament or fibrocartilage:** covers the palmar side of the carpus providing a smooth surface to the carpal canal.

**Flexor retinaculum:** thickening of the deep fascia that connects to the medial side of the carpus and the accessory carpal bone. With the carpal bones it forms the carpal canal.

**Carpal canal:** formed by the accessory carpal bone laterally, the other carpal bones dorsally and the flexor retinaculum on the palmar side.

**Structures passing through the carpal canal:** • Tendons and synovial sheaths of the superficial and deep digital flexors • Ulnar and median nerve • Arteries and veins.






Fig. III-15 - Synovial sheaths of carpus - craniolat. view




Fig. III-16 - Ox - Synovial sheaths of carpus - med. view

- |                                   |                                    |
|-----------------------------------|------------------------------------|
| a. Extensor carpi radialis        | h. Lat. ulnar m. (III-15)          |
| b. Oblique carpal extensor        | i. Flexor carpi ulnaris (III-16)   |
| c. Common digital extensor        | j. Accessory carpal bone           |
| d. Lat. digital extensor          | k. Fused metacarpal bones III & IV |
| e. Flexor carpi radialis (III-16) | l. Metacarpal bone V               |
| f. Deep digital flexor            | m. Radius                          |
| g. Supf. digital flexor           |                                    |

### SPECIES DIFFERENCES

"Knee": a popular term for the horse's carpus.

"Radiocarpal joint": popular, though erroneous, term for the entire antebrachiocarpal joint

### CLINICAL

Carpitis or "popped knees": traumatic arthritis of the carpus in horses.

Valgus: lateral deviation of the bones distal to the joint in question. *Memory aid:* the L in valgus indicates lateral deviation distal to the joint.

Varus: medial deviation of the bones distal to the joint in question (No L, so medial).

Knocked knees or carpal valgus: lateral deviation of the joints distal to the carpus.


Bow legged or carpal varus: medial deviation of the bones distal to the carpus.

Carpal hygroma: subcutaneous bursa on the dorsal surface of the carpus, caused by trauma.

Carpal joint blocks (see pg. 132)

"Splints": inflammation of the horse's metacarpal interosseous ligament between the splint bones and the cannon bone.





**1. METACARPOPHALANGEAL (MP) JOINTS:** the articulations between the metacarpal bones and the proximal phalanges, including the palmar sesamoid bones. It is a modified hinge (ginglymus) joint allowing extension and flexion.

## PHALANGEAL JOINTS

**2. Proximal interphalangeal (IP) joints:** a saddle type of synovial joint between the proximal and middle phalanges.

**3. Distal interphalangeal (IP) joints:** the saddle type of synovial joint between the middle and distal phalanges.

**4. LIGAMENTS:** medial and lateral collateral ligaments stabilize the sides of all metacarpophalangeal and phalangeal joints. Many ligaments attach to the sesamoid bones. These sesamoid ligaments are important in the horse's stay apparatus (pg. 196).

abnormal separation of the two digits. When removing one claw it is wise to leave the proximal interdigital ligament to give support to the remaining digit.

**"Fetlock joint" (1):** popular term used for the metacarpophalangeal (front limb) and metatarsophalangeal (hind limb) joints in the horse, and occasionally in ruminants.

**"Pastern joint" (2):** popular term used for the proximal interphalangeal joint in the horse and often in ruminants.

**"Coffin joint" (3):** popular name used for the distal interphalangeal joint in the horse and often in ruminants.

**Suspensory apparatus:** in the horse consists of the suspensory ligament, the palmar sesamoid bone and the distal sesamoidean ligaments. They act as a unit to support the fetlock joint. Disruption in any one of the three components will result in the fetlock sinking.

## SPECIES DIFFERENCES

**Dorsal ligaments:** paired ligaments found in carnivores. They are responsible for keeping the claw retracted in the cat. Flexion of the distal interphalangeal joint by the deep digital flexor is responsible for protrusion of the claw.

**Declawing or onychectomy (Gr. *onyx* nail):** removal of the distal phalanges through the distal interphalangeal joint in cats.

**Proximal and distal interdigital ligaments in the ox:** prevent

**Distal sesamoidean ligaments, X, Y, V ligaments - horse:** an unofficial term referring to the straight (Y), oblique (V) and cruciate (X) ligaments that anchor the sesamoid bones distally to P1 and P2. They counteract the pull of the suspensory ligament.

**Navicular (podotrochlear) bursa:** located between the navicular bone and the deep digital flexor tendon in the horse. Its inflammation is associated with navicular disease which is more prevalent in the forelimbs. The pain causing lameness may be eliminated by digital neurectomies (cutting the digital nerves).





Fig. III-18 - Ox - Ligg. of digits - lat. view

## 6. Synovial sheath



## 5. Bursa

Fig. III-20 - Ox - Synovial sheaths & bursae - palm. view




Fig. III-21 - Ox - Joint capsules - dors. view

Fig. III-19 - Ox - Ligg. of digits, one digit removed - med. view




Fig. III-22 - Ox - Digits - sagittal section

- |   |  |   |
|---|--|---|
| a. Palm. anular lig. (III-22)                             | i. Deep (cruciate) dist. sesamoidean lig.    | o. Dist. sesamoidean impar (navicular) lig. (III-19,22)           |
| b. Prox. digital anular lig.                              | j. Suspensory lig.                           | p. Suspensory navicular lig. (III-19)                             |
| c. Dist. digital anular lig.                              | k. Extensor br. of suspensory lig. (III-18)  | q. Middle br. of suspensory lig. (absent in horse)                |
| d. Dist. phalanx  | l. Common digital extensor (tendon) (III-22) | r. Dist. interdigital cruciate lig. (III-20) (absent in horse)    |
| e. Collateral sesamoidean lig. (III-18)                   | m. Supf. digital flexor (tendon)             | s. Prox. interdigital cruciate lig. (III-20,21) (absent in horse) |
| f. Intersesamoidean lig. (III-19)                         | n. Deep digital flexor (tendon)              |   |
| g. Supf. (straight) dist. sesamoidean lig. (absent in ox) |  |   |
| h. Middle (oblique) dist. sesamoidean lig. (III-19)       |  |   |



JOINTS - DIGIT

Thoracic limb-117




Fig. III-23 - Horse - Digit - lat. view




Fig. III-24 - Horse - Digit - palm. view




Fig. III-25 - Horse - Digit, supf. & deep digital flexor tendons removed - palm. view




Fig. III-26 - Horse - Fetlock joint - palm. view




Fig. III-27 - Horse - Digit - lat. view






Fig. III-28 - Horse - Digit  
- parasagittal section

A. Suspensory lig.  
B. Extensor br. of  
suspensory lig.  
C. Common digital extensor  
(tendon)  
D. Supf. digital flexor  
(tendon)  
E. Deep digital flexor  
(tendon)  
F. Lat.(ungual)cartilages  
G. Hoof (III-24)  
H. Digital cushion


a. Palm. annular lig.  
b. Prox. digital annular lig.  
c. Dist. digital annular lig.  
d. Dist. phalanx  
e. Intersesamoidean lig.(III-25)  
f. Supf. (straight) dist.  
sesamoidean lig. (absent  
in ox)  
g. Middle (oblique) dist.  
sesamoidean lig.  
h. Suspensory navicular lig.  
i. Dist. Sesamoidean impar  
(navicular) lig.

j. Dist. sesamoidean (navicular) bone  
k. Deep (cruciate) dist.  
sesamoidean lig. (III-26)  
l. Collateral sesamoidean lig. (III-27)  
m. Dors. pouch of fetlock joint (III-28)  
n. Palm. pouch of fetlock joint  
o. Digital sheath  
p. Dors. pouch of pastern joint  
q. Palm. pouch of pastern joint  
r. Dors. pouch of coffin joint  
s. Palm. pouch of coffin joint  
t. Connective tissue bridge


# JOINTS OF PELVIS

102-Pelvic limb-119

**Fig. III-29 - Dog - Ligg. of the pelvic girdle - lat. view**



**Fig. III-31 - Horse - Ligg. of the hip joint - ventr. view**



**1. SACROILIAC JOINT (Fig. III-33):** the relatively immovable articulation between the wings of the sacrum and ilium. This is a combined cartilaginous and synovial joint. Fibrocartilage unites the surfaces of the wings of the sacrum and ilium, forming a sacroiliac synchondrosis. There is a tight joint capsule along the margin of the joint reinforced by dorsal and ventral sacroiliac ligaments.

**2. SACROTUBEROUS LIGAMENT:** the connective tissue extending from the sacrum and first caudal vertebrae to the ischiatic tuberosity.

**3. PELVIC SYMPHYSIS:** the symphyseal, slightly movable (fibrocartilaginous) joint between the two hip bones (os coxae). The bones are united by cartilage in the young animal; in the adult, the cartilage is gradually replaced by bone. The front part is formed by the pubic symphysis between the pubic bones. The caudal part is formed by the ischial symphysis between the ischii bones.

**HIP JOINT, coxal (KOK-sal) or coxofemoral articulation:** the ball-and-socket (spheroidal) type synovial joint between the head of the femur and the acetabulum of the hip bone. It has no collateral ligaments. Its integrity depends on the round ligament of the femur, its strong roomy joint capsule and the muscle mass surrounding it. Functionally, it is a freely movable (diarthrodial)

joint allowing universal movement (flexion-extension, abduction-adduction, medial and lateral rotation and circumduction). As in any joint, what is gained in freedom of movement is offset by loss of stability.

**4. Ligament of the head of the femur:** formerly the round ligament of the femur, it is the short intracapsular ligament extending from the acetabular cavity to the notch on the head of the femur (fovea capitis).

**Acetabular lip:** the band of fibrocartilage around the rim of the acetabulum increasing the depth of the acetabulum.

**Acetabular notch:** normal defect in the ventromedial aspect of the acetabulum.

**Transverse acetabular ligament:** crosses the acetabular notch completing the acetabular cavity.


## SPECIES DIFFERENCES

**Sacrospinous ligament:** Dog - a band of connective tissue (2). Absent in the cat.

**5. Broad sacrotuberous ligament of the horse and ox: ("sacro-sciatic ligament"):** a sheet of connective tissue attaching to the



Fig. III-32 - Ox - Ligg. of the pelvic girdle - lat. view



- |   |   |
|---|---|
| a. Dorsal sacroiliac ligament (111-30)              | h. 1st caudal. vertebra                 |
| b. Greater ischiatic foramen (absent in carnivores) | i. Acetabulum (111-30)                  |
| c. Lesser ischiatic foramen (absent in carnivores)  | j. Ischiatic tuberosity                 |
| d. Cranial pubic ligament (111-18)                  | k. Sacral tuberosity                    |
| e. Acetabular margin (lip) (cotyloid ligament)      | l. Head of femur- (111-31)              |
| f. Os coxae   | m. Fovea capitis                        |
| g. Sacrum (111-29)                                  | n. Transverse acetabular ligament       |
|   | o. Ventral sacroiliac ligament (111-33) |
|   | p. Joint capsule (hip)                  |

1. Sacroiliac joint




Fig. III-33 - Ox - Ligg. of the pelvic girdle - cran. view

ilium, ischiatic spine, and the ischiatic tuberosity, thereby completing the lateral pelvic wall. Between the broad sacrotuberous ligament and the greater and lesser ischiatic notches (Pg. 95, i,k) of the hip bone are two openings: the greater and lesser ischiatic foramina (b,c).

**6. Accessory ligament of the head of the femur:** the ligament found only in the horse. It extends from the prepubic ligament through the acetabular notch under the transverse acetabular ligament. It attaches with the round ligament of the femur to the fovea capitis of the head of the femur. It stabilizes the hip and also makes it harder for a horse to kick to the side (cow kick), but doesn't prevent it.

**Trochanteric bursae in the horse:** between the insertions of the medial and the superficial gluteal and the greater trochanter and the third trochanter respectively.

## CLINICAL

**Hip dysplasia:** malformed hip joint resulting in a progressive degenerative disease, having a high incidence in some breeds. It is evaluated radiographically. This condition causes pain and is treated many ways; cutting the pectineus muscle (pectineal tenotomy), cutting the neck and head of the femur off (head and neck osteotomy), or remodelling the acetabulum by cutting up

the hip bones and repositioning them.

**Hip luxation:** more common in cattle than horses. The ox has a weaker round ligament, no accessory ligament, and a more shallow acetabulum.

**Craniodorsal hip luxation:** is the most common direction a hip luxates in all species. To evaluate hip luxation of the dog place your thumb in the space between the greater trochanter and the ischiatic tuberosity. Then rotate the limb outward (laterally). If the hip joint is intact the thumb will be forced out. If the thumb remains, the joint is luxated or the neck of the femur is broken.

**Knock down hip:** incorrect term for a fractured greater trochanter in large animals.

**Unilateral trochanteric bursitis:** inflammation of either or both trochanteric bursae causing a horse to favor the injured side by cocking the hip towards the good side. This configuration during movement is called "dog trotting".

**Compression test - horse:** have a kick board in place, stand behind the horse and palpate the third trochanter on both sides for heat, pain and evidence of swelling associated with bursitis. Press maximally with palms over both the greater trochanters and both third trochanters.






Fig. III-35 - Dog - Rt. stifle opened, dist. end of femur & prox. end of tibia

**STIFLE JOINT** or genual articulation (L. *genu*, knee): the compound joint between the femur and patella and the femur and tibia. It is a condylar joint which acts like a hinge joint with a little rotation.

**Femoropatellar joint:** the articulation between the patella and trochlea of the femur. It has a spacious joint capsule.

**1. Patellar ligament(s):** the part of the tendon of insertion of the quadriceps muscle between the patella and the tibial tuberosity. (The patella is a sesamoid bone within the tendon of the quadriceps muscle.)

**Femorotibial joint:** the articulation between the femoral condyles and tibia (and the interposed menisci).

**2,3. Medial and lateral menisci** (G. crescents) or semilunar cartilages: the crescentic fibrocartilaginous discs between the tibial and femoral articulating condyles which compensate for incongruence of the articulating bones and act as shock absorbers.

**4, 5. Medial (tibial) and lateral (fibular) collateral ligaments:** strong stabilizing bands on the medial and lateral sides of the stifle.

**4. Medial (tibial) collateral ligament:** strong stabilizing band on the medial side of the stifle. It fuses with the joint capsule and the medial meniscus.

**5. Lateral (fibular) collateral ligament:** the strong band connecting the lateral epicondyle to the head of the fibula. It is separated from the lateral meniscus by the tendon of the popliteus muscle.

**6,7. Cranial and caudal cruciate** (L. resembling a cross) ligaments: two intra-articular ligaments named for their tibial attachment.

**6. Cranial cruciate ligament:** inserts cranially on the tibia. It arises from the caudolateral femur. It prevents cranial movement of the tibia in relationship to the femur.

**7. Caudal cruciate ligament:** inserts caudally on the tibia. It arises from the craniomedial distal femur. It prevents caudal movement of the tibia in relationship to the femur.

**LAMP: memory aid** for which side the cranial (anterior) and caudal (posterior) cruciate ligaments are on - lateral and medial respectively.

**Femoral ligament of the lateral meniscus or meniscofemoral ligament (d):** connects the caudal part of the lateral meniscus to the femur. It is the only ligament connecting the menisci to the femur.

**Femoropatellar ligaments, medial and lateral (m):** extend from the epicondyles to the patella.



Fig. III-36 - Ox - Rt. stifle  
- med. view




Fig. III-37 - Ox - Rt. stifle  
& joint capsule - lat. view





Fig. III-38 - Ox - Rt. stifle  
- caud. view

- A. Patella
- B. Trochlea of femur
- C. Tibia
- a. Femoral condyles
- b. Tibial tuberosity
- c. Tibial condyles
- d. Meniscofemoral lig.
- e. Transverse lig. (carnivores)
- f. Tendon of popliteal m.
- g. Long digital extensor m.
- h. Medial patellar lig. (III-36)
- i. Middle patellar lig.
- j. Lat. patellar lig. (III-37)
- k. Joint capsule
- l. Bursa

## SPECIES DIFFERENCES

Carnivores, pigs and small ruminants: have one patellar ligament.

Horse and ox: have three patellar ligaments - lateral, middle (intermediate) and medial (h-j).

**Medial ridge (trochlear tubercle) of the femoral trochlea** (Fig. III-41): the enlarged process in the horse that is consciously forced between the medial and middle patellar ligaments to cause the "patellar lock" of the stay apparatus (pg. 196).

**Parapatellar fibrocartilage:** the hook of fibrocartilage attached to the medial side of the patella. The medial patellar ligament attaches to it. It hooks over the medial patellar ridge when the stay apparatus is engaged.

## CLINICAL

**"Upward fixation of the patella":** the involuntary (pathological) "catching" of the patella on the medial ridge of the femoral trochlea. Surgical cutting of the medial patellar ligament eliminates this problem, at least temporarily.

**Cranial ("anterior") drawer sign:** the pathological movement of the tibia cranial to the femur due to rupture of the cranial cruciate ligament. This happens commonly in small animals due to trauma from the lateral side (HBC, hit by car). This tends to also tear the medial collateral ligament, and the medial meniscus since it is attached to the medial collateral ligament.

**Horse:** The synovial joint cavity of the stifle is divided into three sacs - the medial and lateral femorotibial sacs and the femoropatellar sac. The femoropatellar sac usually communicates with the medial femorotibial sac and sometimes communicates with the lateral femorotibial sac. The lateral and medial femorotibial pouches never communicate. This is clinically important because if one sac is infected, the other two may be also. When anesthetizing these joints in lameness diagnosis all three joints have to be injected.

**Patellar luxation:** the displacement of the patella medially or laterally out of the femoral patellar surface (trochlea). Medial luxation is more common in small breeds and lateral luxation more common in large breeds.

**Gonitis:** inflammation to the stifle. This can be due to soft tissue or bony lesions.






Fig. III-39 - Horse - Lt. stifle  
- cran. view




Fig. III-40 - Horse - Lt. stifle - lat. view




Fig. III-41 - Horse - Lt. stifle  
- med. view




Fig. III-42 - Horse - Lt. stifle  
- caud. view

A. Patella  
B. Trochlea  
of femur  
C. Tibia

a. Femoral condyles (III-40)  
b. Tibial tuberosity  
c. Tibial condyles  
d. Meniscofemoral lig. (III-42)

e. Tendon of insertion of  
quadriceps mm. (III-39)  
f. Tendon of popliteus m. (III-40,  
removed in III-39)

g. Long digital extensor m.  
h. Med. patellar lig. (III-39)  
i. Middle patellar lig.  
j. Lat. patellar lig.






Fig. IV-43 - Ox - Tarsus - sagittal section

**TIBIOFIBULAR JOINT:** between the lateral condyle of the tibia and the head of the fibula. They differ between the species due to variations in fibular development. Its joint capsule is an extension of the lateral sac of the femorotibial sac of the stifle joint.

**TARSAL JOINT** or "hock" (TAR-sul) (G. *tarsos*, flat): a compound hinge (ginglymus) type of synovial joint. It is a composite, uniaxial joint articulation like the carpal joint, allowing flexion and extension.

**Tibiotarsal ("tibiotarsal") joint:** articulation between the proximal row of tarsal bones (talus and calcaneus) and the tibia and fibula. The trochlear ridges of the talus fit into the cochlea of the tibia. The ridges and grooves are off the sagittal plane so that the hindpaw passes lateral to the forepaw in a gallop. This is the most movable of the tarsal joints. Its synovial sac communicates with the proximal intertarsal sac and the synovial sheath around the tendon of the lateral digital flexor.

**Proximal intertarsal joint:** articulation between the proximal row (talus and calcaneus) and the central and fourth tarsal bones. It communicates with the talocrural sac.

**Distal intertarsal joint:** articulation between the central tarsal and tarsal bones I, II and III. The distal intertarsal joint doesn't cross the whole tarsus because the fourth tarsal bone crosses it on the lateral side.

**Tarsometatarsal joint:** articulation between the distal row of tarsal bones and the metatarsal bones I to V.

**Intertarsal joint:** the plane articulations between the individual tarsal bones, as apposed to the proximal and distal intertarsal joints which are between the rows of tarsal bones.

**Tarsal joint capsule:** as in all synovial joints, consists of fibrous and synovial parts. The fibrous part extends from the distal end of the tibia and fibula to the proximal end of the metatarsal bones. Its plantar surface is thickened to smooth the deep wall of the tarsal canal. The synovial part encloses the individual tarsal joints and these are called synovial sacs - talocrural sac, proximal intertarsal sac, distal intertarsal sac and tarsometatarsal sac. The intercommunication between the different joints of the tarsus is important clinically in horses for intra-articular injections in lameness diagnosis (see appendix).



**1,2. Medial and lateral collateral ligaments:** the strong bands on either side of the tarsus. Both have long and short parts.

**Intertarsal ligaments:** numerous connective tissue bands holding the tarsal bones together.

**Proximal extensor retinaculum:** the transverse ligament across the distal end of the tibia holding down the tendons of the long digital extensor and cranial tibial muscles.

**Distal extensor retinaculum:** the transverse loop that holds the tendon of the long digital extensor muscle.

**3. Long plantar ligament:** the well developed ligament on the plantar side of the fibular tarsal bone (calcaneus) connecting the fibular tarsal bone to the metatarsus.

**Tarsal canal:** passage formed by the tarsal bones and the flexor retinaculum. It contains:

- Tendon and sheath of long digital extensor
- Plantar branch of saphenous artery and vein
- Medial and lateral plantar nerves

**INTERMETATARSAL, METATARSOPHALANGEAL AND INTERPHALANGEAL JOINTS:** resemble the analogous joints of the thoracic limb.




Fig. III-45 - Ox - Rt. tarsus - lat. view

## SPECIES DIFFERENCES

### Proximal tibiofibular joint:

- **Carnivore, horse and pig:** the head of the fibula articulates with the tibia by a plane type of synovial joint.
- **Ruminant:** the head of the fibula is fused to the tibia.

### Distal tibiofibular joint:

- **Carnivore, ruminant and pig:** the distal fibula (lateral malleolus) forms a synovial joint with the distal tibia. Its joint capsule is a continuation of the talocrural joint.
- **Horse:** the distal fibula (lateral malleolus) fuses with and becomes a part of the tibia.

- A. Tibia
- B. Tibial tarsal bone (III-45)
- C. Fibular tarsal bone
- D. Sustentaculum tali (III-46)
- E. Calcaneal tuberosity
- F. Central tarsal bone
- G. Metatarsal bone

- a. Intertarsal lig. (III-45)
- b. Short lat. collateral lig.
- c. Long lat. collateral lig.
- d. Joint capsule (III-44)
- e. Tibiotarsal synovial sac (III-45)
- f. Prox. intertarsal synovial sac
- g. Dist. intertarsal synovial sac
- h. Tarsometatarsal synovial sac
- i. Tendon of third fibular m. (III-45)
- j. Tendon of cran. tibial m.
- k. Tendon of supf. digital flexor m.
- l. Tendon of deep digital flexor m.
- m. Tendon of long digital extensor m. (III-47)
- n. Tendon of long fibular m.

## CLINICAL

**"Curb":** an enlargement of the horse's long plantar ligament.

**Horse's tarsal pouches:** the part of the joint capsule not tied down by bones or ligaments. The horse has three pouches of the talocrural joint named for their locations - dorsomedial pouch, medioplantar pouch and lateroplantar pouch.

**Arthrocentesis** (ar'throh-sen-TEE-sis): the puncture and aspiration of a joint (see appendix).

**Spavin:** the common term for problems of the tarsus. This is a common clinical entity that may become progressively worse.

**Bog spavin:** the distension of the tarsal synovial pouches with excess synovial fluid.

**Bone spavin, true spavin or jack spavin:** osteoarthritis and periostitis of the hock. The distal intertarsal, tarsometatarsal and sometimes the proximal intertarsal joints are involved. The disease usually begins on the dorsomedial aspect of these joints. Periosteal reactions result in bone formation that can bridge and even fuse the joint (ankylosis). Ankylosis may cure the lameness. **Early lesions of osteoarthritis of the hock** are on the dorsomedial hock in the area of the cunean tendon. The radiographs will show lesions of the lips or edges of the third and central tarsal bones or the third metatarsal bones. When viewed from the rear there is an asymmetrical gluteal rise. The horse raises the sound limb's hip, thus, lowering the other so the affected hock flexes less. This is called "hiking". **"Jack spavin"** is an especially large form of bone spavin.

**"High spavin":** bone spavin of the proximal tarsus.






Fig. III-46 - Ox - Tarsus & synovial sheaths - med. view




Fig. III-47 - Ox - Tarsus & synovial sheaths - lat. view

**Blind (occult) spavin:** a lameness of the tarsus with no palpable or radiological changes.

**Blind spavin:** an enlargement of the medial saphenous vein over the tarsus.

**Spavin test:** the procedure to test for lameness due to problems in the tarsus. Lift the leg and flex the hock for one minute. Set the leg down and immediately trot the animal. This will exacerbate a spavin for several steps. A strong positive reaction (horse lame) indicates lameness in the hock, but doesn't diagnose spavin. Radiographs will isolate problem further. Mild positive reactions to a spavin test may be due to gonitis or arthritis, so view these with suspicion.

**Cunean bursitis - horse:** inflammation of the cunean bursa. The bursa is located over the common site of bone spavin, so bursitis must be differentiated from bone spavin.

**Cunean tenotomy - horse:** cutting the medial branch of the cranial tibial muscle (cunean tendon) (Fig. III-51). This is often done to relieve the clinical signs of bone spavin or cunean bursitis. This doesn't cure the animal or prevent further problems if stress is continued. Untreated cunean bursitis will

eventually advance to osteoarthritis of the hock.

**Tarsal conformation:** the correct orientation of the horse's tarsus should be vertical. Deviation from this orientation results in conformational defects.

**"Sickle-hocked" or "curby":** a conformational defect where the tarsus is angled (flexed).

**"Cow-hocked":** a conformational defect where the two tarsi deviate medially towards each other. The tarsi should be straight and parallel when viewed from behind.

**Exostosis (ek'sos-TOH-sis):** bone proliferation. A painful joint will try to commit suicide. The joint tries to fuse (ankylose) itself because it won't hurt if it can't move.

**Ankylosis (ang'ki-LOH-sis):** immobility and consolidation of a joint due to disease, injury, or surgical procedure.

**Arthrodesis (ar'throh-DEE-sis) of the joint:** causing the joint to fuse surgically. This speeds up nature's attempts to fuse the joint. The distal intertarsal and tarsometatarsal articular cartilage is destroyed by a drill bit, allowing the joint to quickly fuse.



# TARSUS - HORSE

Pelvic limb-168




Fig. III-48 - Horse - Lt. tarsus  
- med. view




Fig. III-49 - Horse - Lt. tarsus  
- cran. view




Fig. III-50 - Horse - Lt. tarsus - lat. view

- A. Tibia
- B. Tibial tarsal bone (talus)
- C. Fibular tarsal bone (calcaneus)
- D. Sustentaculum tali
- E. Calcanean tuberosity
- F. Central tarsal bone (III-49)
- G. Metatarsal bone

- a. Intertarsal lig. (III-48)
- b. Tendon of third fibular (peroneus tertius) m. (III-51)
- c. Lat. tendon of cran. tibial m.
- d. Short lat. collateral lig. (III-50)
- e. Long lat. collateral lig.
- f. Cranial tibial m. (III-51)




Fig. III-51 - Horse - Tendons  
- dorsal view

# 1. Temporomandibular joint

# 2. Suture





Fig. III-52 - Ox - Skull  
- lat. view

# 3. Symphysis of mandible


Fig. III-53 - Ox - Hyoid  
apparatus &  
laryngeal cartilages



# 4. Joints of the Hyoid Apparatus

- |                           |                      |
|---------------------------|----------------------|
| a. Skull                  | f. Ceratohyoid bone  |
| b. Mandible               | g. Basihyoid bone    |
| c. Tympanohyoid cartilage | h. Thyrohyoid bone   |
| d. Stylohyoid bone        | i. Thyroid cartilage |
| e. Epiphyoid bone         |                      |

Fig. III-54 - Ox - Mandible - dors. view



**1. TEMPOROMANDIBULAR JOINT:** a condylar joint between the condyles of the mandible and the mandibular fossae of the temporal bones. It has a loose joint capsule whose lateral side is strengthened to form a lateral ligament.

**Articular disc:** a thin meniscus lying between the two articular surfaces of the joint.

**2. SUTURES OF THE SKULL:** the immovable, fibrous joints between the skull bones.

**3. SYMPHYSIS OF THE MANDIBLE:** the cartilaginous joint joining the right and left mandibular bodies.

**JOINTS OF THE AUDITORY OSSICLES:** the ear bones articulate with each other via synovial joints. The stapes articulates with the vestibular window by a fibrous joint (syndesmosis). The auditory ossicles are held in place by a number of ligaments (See Ch. VIII).

**4. JOINTS OF THE HYOID APPARATUS:** the synovial articulations between the bones of the hyoid apparatus and between the thyrohyoid bone and the cranial cornu of the thyroid cartilage. The tympanohyoid cartilage forms a fibrous (syndesmosis) articulation with the skull.






Fig. III-55 - Ox - Cran. cervical region - dors. view




Fig. III-56 - Dog - Cervical region - lat. view

**JOINTS of the VERTEBRAL COLUMN:** typical intervertebral articulations consist of two types of joints - cartilaginous and synovial. Symphyseal (cartilaginous) joints are formed by intervertebral discs joining adjacent vertebral bodies. Synovial joints are formed by caudal and cranial articular processes of adjacent vertebrae. The atlanto-occipital and atlanto-axial joints are atypical intervertebral articulations.

**1. ATLANTO-OCCIPITAL JOINT** (the "yes" joint): the condylar joint acting as a modified hinge type of synovial joint between the occipital condyles and the cranial articular surfaces of the atlas. It has a spacious joint capsule strengthened by three membranes (dorsal, ventral, and lateral atlanto-occipital).

**2. ATLANTO-AXIAL JOINT** (the "no" joint): the pivot type of synovial joint between the dens and cranial articular surface of the atlas and axis. It has a loose joint capsule. The apical ligament of the dens connects the apex of the dens to the occipital bone. The transverse atlantal ligament connects to the two arches of the atlas, crosses over the dens of the axis, thus holding the dens against the ventral arch of the atlas.

**3. Joints of the vertebral articular processes:** the synovial articulations between the caudal and cranial articular processes of adjacent vertebrae.

**4. Nuchal ligament** (lig. nuchae, ligament of the nape): the

yellow-elastic connective tissue connecting the upper cervical vertebrae or skull with the spinous processes of the thoracic vertebrae. It helps support the head.

**5. Supraspinous ligament:** the heavy band of connective tissue running over the tops of the spinous processes from the first thoracic vertebra to the caudal vertebrae. It prevents abnormal separation of the vertebral spines during flexion of the vertebral column. It is the direct continuation of the funicular part of the nuchal ligament.

## SPECIES DIFFERENCES

**Nuchal ligament:** in the dog, a paired band of connective tissue extending from the spinous process of the axis to the spinous process of the 1st thoracic vertebra. It is absent in the cat. In the horse, ox and pig it consists of two paired parts. The funicular (cord) part resembles that of the dog, but is paired and arises from the skull and inserts on spines of the thoracic vertebrae of the withers. The lamellar (sheet) part (b) consists of two sheets of connective tissue arising from the second and third thoracic spines and the funicular part, and inserting on cervical spines C2-C6.

**Bursas of the nuchal ligament in horses:** positioned between bony processes and the funicular part. The atlantal bursae






Fig. III-57 - Horse - Cervical region - lat. view




Fig. III-58 - Ox - Cervical region - lat. view

A. Skull  
B. Atlas  
C. Axis  
D. 2nd thoracic  
vertebra

a. Funicular part of  
the nuchal lig.  
b. Lamellar part of  
the nuchal lig.

1. Atlanto-occipital joint  
2. Atlanto-axial joint  
3. Joints of Vertebral processes  
4. Nuchal lig.  
5. Supraspinous lig.

(cranial nuchal bursa) is constantly found over the atlas. An inconstant bursa (caudal nuchal bursa) is sometimes found over the axis. A constant supraspinous bursa is over the most prominent spines of the withers.


**Dorsal scapular ligament:** the thickening of the thoracolumbar fascia in the withers region. It interdigitates with the origin of the serratus ventralis muscle on the deep surface of the scapula.

## CLINICAL


**"Poll-evil":** inflammation of the atlantal bursa.

**"Fistulous withers":** inflammation of the supraspinous bursa. Special care should be taken because *Brucella spp.*, which is transmissible to humans (zoonosis), have been isolated. Rupture of this inflamed bursa may migrate down the dorsal scapular ligament and be trapped deep to the scapula.





**Fig. III-59 - Horse - 3rd & 4th thoracic vertebrae - craniolat. view**



**Fig. III-60 - Ox - Floor of thorax - dors. view**

- |                              |                          |
|------------------------------|--------------------------|
| 1-5. pg. 129                 | 9. Interspinous lig.     |
| 6. Ventral longitudinal lig. | 10. Costovertebral joint |
| 7. Dorsal longitudinal lig.  | 11. Sternocostal joints  |
| 8. Intervertebral discs      | 12. Costochondral joints |

## OTHER JOINTS and LIGAMENTS of the VERTEBRAL COLUMN:

**6. Ventral longitudinal ligament:** the tendinous band lying on the ventral surfaces of the vertebrae from the axis to the sacrum. It prevents over-extension of the spine.

**7. Dorsal longitudinal ligament:** the tendinous band on the floor of the vertebral canal from the axis to the sacrum. It prevents hyperflexion of the spine.

**8. Intervertebral discs:** the layers of fibrocartilage between the bodies of adjacent vertebrae, each consisting of an outer fibrous ring and an inner pulpy nucleus.

• **Anulus fibrosus (fibrous ring):** consists of bands of parallel fibers connecting adjacent vertebral bodies. It is thin dorsally and thick ventrally.

• **Nucleus pulposus (pulpy nucleus):** the semi-fluid remnant of the notochord surrounded by the fibrous ring. It serves to absorb shock.

**9. Interspinous ligament:** the fibers connecting the spines of adjacent vertebrae along the entire length of the vertebral column.

**Interarcuate ligaments or yellow ligaments (Fig. III-62):** the elastic ligaments filling the dorsal spaces between the arches of adjacent vertebrae.

**10. Costovertebral joints:** the two distinct articulations between most ribs and the vertebral column. The head of each rib forms a ball-and-socket type of synovial joint with the caudal and cranial costal facets of adjacent vertebrae. The tubercle of each rib forms a plane type of synovial joint with the transverse process of the corresponding vertebra. Each articulation has a joint capsule and corresponding ligaments (radiate ligament of the head, intercapital






Fig. III-61 - Ox - 8th & 9th costovertebral articulation - craniolat. view




Fig. III-62 - Ox - 1st & 2nd lumbar vertebrae - dors. view

- |                                |                                  |
|--------------------------------|----------------------------------|
| a. Costotransverse lig.        | g. Transverse process            |
| b. Radiate lig. of head of rib | h. Vertebral canal               |
| c. Intercapital lig.           | i. Spine                         |
| d. Rib                         | j. Joint capsule (III-61)        |
| e. Head of rib                 | k. Intertransverse lig. (III-62) |
| f. Tubercle of rib             | l. Symphysis (III-60)            |

ligament, costotransverse ligament, and ligament of the neck).

**Intercapital ligament:** connects the heads of a pair of opposite ribs. It crosses through the intervertebral foramen and over the dorsal part of the vertebral disc. They are not present between the first pair and last two pairs of ribs.

**11. Sternocostal joints:** the pivot type of synovial articulations between the first eight costal cartilages and the sternum. Each has a joint capsule and ligaments (dorsal and ventral sternocostal ligaments, costoxiphoid ligaments and sternal ligament).

**Intercostal joint of the asternal ribs of the costal arch** is a slightly movable fibrous joint (synchondrosis). Intercostal joints between the sternbrae are immovable cartilaginous joints (synchondrosis).

**12. Costochondral junction or joints:** the fibrous (syndesmosis) joints between the ribs and the costal cartilages. They have no synovial cavities since they are not synovial joints.

#### CLINICAL:

**Rupture of an intervertebral disc:** the rupture or degeneration of the fibrous ring allowing the pulpy nucleus to bulge or "explode" out of the disc. Because the annulus fibrosus is thinnest dorsally, the rupture usually happens dorsally or dorsolaterally into the vertebral canal. This can put pressure on the spinal cord, causing pain or paralysis. This is most common at the thoracolumbar junction (T11 - L2) or the neck region. Rarely does it happen in the thoracic region because of the intercapital ligaments, which reinforce the disc dorsally.

**Hemilaminectomies:** the removal of the right or left dorsal vertebral arch to relieve pressure in the spinal canal.

**Disc fenestration:** the removal of the remaining nucleus pulposus from a ruptured disc.


**"Wobbler":** a horse with cervical vertebral instability which impinges on the spinal cord, resulting in different degrees of ataxia.






## Chapter IV

# Muscles





**Fig. IV-1 - Dog - Muscles (cutaneous mm. removed) - lat view**








Fig. IV-2 - Horse - Muscles (cutaneous mm. removed) - lat. view



**Fig. IV-3 - Ox - Muscles (cutaneous mm. removed) - lat. view**







**Fig. IV-4 - Pig - Muscles (cutaneous mm. removed) - lat. view**



# SUPERFICIAL MUSCLES - BODY - CAT & SHEEP

General-139

Fig. IV-5 - Cat - Muscles (cutaneous mm. removed) - lat. view



1. Masseter
2. Brachiocephalicus
3. Trapezius
4. Sternoccephalicus
5. Supf. pectoral (not shown in sheep)
6. Deep pectoral
7. Infraspinatus
8. Deltoid
9. Triceps brachii
10. Brachialis
11. Extensor carpi radialis
12. Common digital extensor
13. Lat. digital extensor
14. Lat. ulnar
15. Oblique carpal extensor
16. Flexor carpi radialis (not shown in sheep)
17. Flexor carpi ulnaris (not shown in sheep)
18. Latissimus dorsi
19. Serratus ventralis
20. Int. abdominal oblique
21. Ext. abdominal oblique
22. Middle gluteal

23. Supf. gluteal (absent in ruminants)
24. Tensor fasciae latae
25. Vastus lateralis
26. Biceps femoris

Fig. IV - Sheep - Muscles, Cutaneous mm. removed - lat. view

27. Semitendinosus
28. Gastrocnemius
29. Third fibular (absent in carnivores)
30. Cran. tibial m.

31. Long digital extensor
32. Deep digital flexor
33. Supf. digital flexor (tendon)






Fig IV-7 - Llama - Supf. muscles



# MUSCLE

General-141

**MUSCLES:** the contractile organs responsible for movement in an animal. The two varieties of muscle are **striated** (striped), which includes skeletal and cardiac muscle, and **unstriated** or smooth muscle. Muscles are either **involuntary** or **voluntary**. Involuntary smooth and cardiac muscles are responsible for breathing, heart beat, peristaltic movements of the intestines, constriction of blood vessels and many other vital functions. Voluntary or skeletal muscles are of primary concern in this section. They allow movement from one place to another (location), movement of one part of the body in relation to another, and the maintenance of body posture.

**ORIGIN and INSERTION:** the attachments of a muscle, usually to bones.

1. **Origin (OR-i-jin):** the less movable of the two attachments. In the limbs this is usually the more proximal attachment.

2. **Insertion:** the more movable of the two attachments. In the limbs this is usually the more distal attachment.

## MUSCLE ATTACHMENTS:

**Fleshy attachments:** the apparent direct attachment of muscles to bone, e.g., scapular muscles. In reality, they attach to the periosteum of the bone by very short tendons.

**Tendinous attachments:** the dense connective tissue connecting spindle-shaped or pennate muscles to bone.

**Aponeurotic attachments:** the flat, tendinous sheets associated with flat muscles such as those of the abdominal wall.

**MUSCLE CONTRACTION:** shortening of a muscle, causing a change in the alignments of bones around a joint.

**Muscle function:** the movement of parts of the body. For each movement a number of muscles contract to produce a smooth controlled movement. Muscles are grouped into prime movers, antagonists, synergists, or fixators. The same muscle may be any of the above, depending on the movement produced.

3. **Prime mover or agonist (AG-o-nist)** (G. *agon*, a contest): produces the characteristic movement at a joint. The biceps brachii muscle is the prime mover for flexion of the elbow joint.

4. **Antagonist:** opposes the movement of a prime mover. It aids the prime mover by slowly relaxing so the movement produced is smooth and controlled. The triceps brachii muscle, the prime mover for extension of the elbow joint, is the antagonist to the biceps brachii muscle during flexion of the elbow.

**Synergist** (G. *syn*, together + *ergon*, work): a muscle that indirectly aids the action of a prime mover.

**Fixator:** a muscle that stabilizes the proximal end of a limb while the distal end moves.

**MUSCLE ACTIONS:** depend on how they cross a joint, number of joints crossed and the shape of the joints. The resulting movements (muscle actions) are extension, flexion, rotation, abduction, adduction and circumduction. When visualizing a muscle, imagine what happens to the bones of the joint when the muscle contracts (shortens). For most joints (hinge) there is a flexor side and an extensor side. Note the side of the joint the muscle crosses. Those crossing the flexor surface will cause flexion of the joint upon contraction.

5. **Extension:** an increase in the angle between bones (moves bones further apart).

6. **Flexion:** a decrease in the angle between bones (brings bones closer together).

7. **Adduction** (spelled with a "d", it "adds" to the body): the movement of a limb or structure toward the median plane (toward the body) or, in the digits, toward the limb's axis.

8. **Abduction** (spelled with a "b"): the movement of a limb away from the body (or median plane), or in the digits, away from the axis of the limb.

9. **Rotation:** the movement of a part around its long axis.

10. **Circumduction:** the movement of an extremity that describes the surface of a cone. This is produced by successive flexion, abduction, extension, and adduction.

**Supination:** the movement of the forearm so the palmar side is rotated upward or forward (as when a cat laps milk from its paw).

**Pronation:** the movement of the palmar side of the paw or foot downward or backward.

**MUSCULAR ARRANGEMENTS:** the muscle fibers (cells) are grouped together into fascicles (bundles) that in turn are grouped together to form the muscle.

**Parallel muscle:** the muscle bundles (fascicles) run parallel to each other the entire length of the muscle (e.g., sartorius and abdominal muscles). This allows greatest shortening of the muscle, but less strength of contraction.


**Pennate muscle** (penna, feather): the muscle bundles converge on a tendon at an angle. This arrangement allows more bundles, thus, stronger contractions, but less shortening because of the shorter length of the muscle bundles (e.g., gastrocnemius muscle).

• **Unipennate muscle:** a pennate muscle whose tendon runs along one side.


• **Bipennate muscle:** a pennate muscle whose muscle bundles converge on a tendon from two directions.



Fig. VI-8 - Dog - Muscle functions and attachments - thoracic limb



7. Flexion




6. Extension



8. Abduction

9. Adduction



10. Rotation

11. Circumduction

Fig. IV-9 - Cartoons of muscle actions  
- inked by Barrett Pasquini

**Multipennate muscle:** a pennate muscle whose tendons branch inside the muscle.

**Sphincter (SFINK-ter):** a muscle whose fibers encircle an opening. Contraction of its fibers close the opening. This type of muscle is found at the entrance and exit of a passageway (e.g., urinary and digestive systems).

**EXTRINSIC MUSCLES of the THORACIC LIMB** (thoracic girdle muscles): the muscles that attach to the thoracic limb and some other part of the body, i.e., to the head, neck, or trunk. The brachiocephalicus (5), trapezius (2), omotransversarius (a), latissimus dorsi (9) and superficial pectoral (11) muscles form the **superficial layer** of the extrinsic muscles. The rhomboid (4), serratus ventralis (8) and deep pectoral (13) muscles form the **deep layer**.

**Synsarcosis** (sis'sar-KOH-sis): the muscle connection, as opposed to a bone to bone joint, between the thoracic limb and the body.

**INTRINSIC MUSCLES:** the muscles having both attachments (origin and insertion) on the thoracic limb bones.

**INTRINSIC MUSCLES OF THE SHOULDER:** act primarily on the shoulder - the deltoid (7), supraspinatus (1), infraspinatus (3), teres major (c), teres minor (b), subscapularis (6) coracobrachialis (d) and biceps brachii (14) muscles.

**INTRINSIC MUSCLES OF THE ARM:** act primarily on the elbow joint, and are divided into flexor and extensor groups. The flexor group consists of the biceps brachii (14) and brachialis (12) muscles. They are located cranially and innervated by the musculocutaneous nerve. The extensor group, triceps brachii (10), tensor fasciae antebrachii (e) and anconeus (f) muscles, are all located caudally and innervated by the radial nerve.

**CRANIO-LATERAL FOREARM (ANTEBRACHIAL) MUSCLES:** extend the digits and carpus, and supinate the paw - extensor carpi radialis (15), common digital extensor (16), lateral digital extensor (17), lateral ulnar (18) (actually a flexor), oblique carpal extensor (19), and supinator (pg. 160 [#20]) muscles. Most arise directly or indirectly from the lateral (extensor) epicondyle of the humerus and are innervated by the radial nerve.

**CAUDAL ANTEBRACHIAL MUSCLES:** the flexors of the carpus and digits and pronators of the forearm. Most of them originate on or around the medial (flexor) epicondyle of the humerus and are innervated by the median and ulnar nerves. They include the flexor carpi radialis (22), flexor carpi ulnaris (20), superficial digital flexor (23), and deep digital flexor (25) muscles. The pronators include the pronator teres (21) and pronator quadratus muscles in carnivores. Supination and pronation occur in carnivores and pigs, but not other domestic species due to fusion of the ulna and radius and loss of the pronator muscles.

**INTRINSIC MUSCLES OF THE MANUS:** except for the interosseous muscle (24) which supports the metacarpophalangeal joint, the rest are relatively insignificant.

## EXTRINSIC MUSCLES of the THORACIC LIMB

### Superficial layer

- Brachiocephalicus (5)
- Trapezius (2)
- Omotransversarius (a)
- Latissimus dorsi (9)
- Superficial pectoral (11)

### Deep layer

- Rhomboid (4)
- Serratus ventralis (8)
- Deep pectoral (13)

## INTRINSIC MUSCLES:

### Intrinsic muscles of the shoulder:

- Deltoid (7)
- Supraspinatus (1)
- Infraspinatus (3)
- Teres major (c)
- Teres minor (b)
- Subscapularis (6)
- Coracobrachialis (d)
- Biceps brachii (14)
- Triceps brachii, long head

### Intrinsic muscles of the arm: flexors and extensors of the elbow

#### Flexor group - musculocutaneous nerve

- Biceps brachii (14)
- Brachialis (12)

#### Extensor group - radial nerve

- Triceps brachii (10)
- Tensor fasciae antebrachii (e)
- Anconeus (f)

### Craniolateral forearm muscles - extend the digits and carpus and supinate the paw - radial nerve - lateral (extensor) epicondyle

- Extensor carpi radialis (15)
- Common digital extensor (16)
- Lateral digital extensor (17)
- Lateral ulnar (18) (actually a flexor)
- Oblique carpal extensor (19)
- Supinator (pg. 160 [#20])


### Caudal forearm muscles: flexors of the carpus & digits & pronators of the forearm - median & ulnar nerves - medial (flexor) epicondyle

- Flexor carpi radialis (22)
- Flexor carpi ulnaris (20)
- Superficial digital flexor (23)
- Deep digital flexor (25)
- Pronator teres (21)
- Pronator quadratus

### Intrinsic muscles of the manus:

- Interosseous muscle (24)







# MUSCLES - THORACIC LIMB - HORSE

Thoracic limb-145




Fig. IV-12 - Horse - thoracic limb  
- lat. view




Fig. IV-13 - Horse - thoracic limb  
- med. view

1. Supraspinatus
2. Trapezius
3. Infraspinatus
4. Rhomboideus (IV-13)
5. Brachiocephalicus (IV-12)
6. Subscapularis (IV-13)
7. Deltoid (IV-12)
8. Serratus ventralis
9. Latissimus dorsi
10. Triceps brachii
  - 10a. Long head
  - 10b. Lat. head
  - 10c. Med. head (IV-13)
11. Supf. pectoral

12. Brachialis (IV-12)
13. Deep pectoral (IV-13)
14. Biceps brachii
15. Extensor carpi radialis
16. Common digital extensor (IV-12)
17. Lat. digital extensor
18. Lat. ulnar
19. Oblique carpal extensor
20. Flexor carpi ulnaris (IV-13)
21. Pronator teres (absent - horse)
22. Flexor carpi radialis

23. Supf. digital flexor
24. Interosseous
25. Deep digital flexor
- a. Omotransversarius (not shown in horse)
- b. Teres minor
- c. Teres major (IV-13)
- d. Coracobrachialis
- e. Tensor fasciae antebrachii
- f. Subclavius




Fig. IV-14 - Ox - thoracic limb  
- lat. view




Fig. IV-15 - Ox - thoracic limb  
- med. view



# EXTRINSIC MUSCLES - SHOULDER

Thoracic limb-147

**EXTRINSIC MUSCLES:** connect the thoracic limb to the body (head, neck, and trunk).

1. **Trapezius** (G. *trapezion*, an irregular, four-sided figure): the triangular muscle extending from the dorsomedial neck and thorax to the spine of the scapula. It elevates the scapula, thus, the forelimb. It has two heads – the cervical part (trapezius cervicis) and the thoracic part (trapezius thoracis).

2. **Latissimus dorsi** (L. widest of the back): the broad, flat, fan-shaped muscle extending from the dorsal thoracolumbar region to the medial side of the humerus. It flexes the shoulder.

3. **Brachiocephalicus** (brak'ee-oh-se-FAL-ik-us): the wide muscle extending from the head and neck to the arm. The **clavicular intersection** divides this muscle into the cleidocephalicus (b) and the cleidobrachialis (c) muscle. The cleidocephalicus is further divided in all species, except the horse, where it is called the cleidomastoideus. The brachiocephalicus acts to advance the limb or draw the head laterally.

**Clavicular** (klah-VIK-yoo-lar) (tendon) **intersection** (d): the fibrous remnant of the clavicle located cranial to the shoulder, transversing the brachiocephalicus muscle.

**Omotransversarius** (a): extends from the shoulder region to the cervical vertebrae. In the horse it is fused with the brachiocephalicus and doesn't attach to the scapular spine, possibly because there is no acromion.

## SPECIES DIFFERENCES

**Brachiocephalicus:** all its heads are named for their attachments. The value of memorizing the species differences is doubtful.

- Cleidobrachialis and cleidocephalicus are present in all species.

- Cleidocephalicus is further divided in all, but the horse.

Species	Cleidobrachialis	Cleidocephalicus
Ruminant & pig	Cleidobrachialis	Cleidocephalicus Cleidomastoideus Cleidocervicalis
Carnivores	Cleidobrachialis	Cleidocephalicus Cleidomastoideus Cleidocervicalis
Horse	Cleidobrachialis	Cleidocephalicus Cleidomastoideus

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
<b>Trapezius</b>		Spine of scapula	Elevate shoulder & draw it forward or backward	Accessory
Cervical fibrous	Median fibrous raphe of neck			
Thoracic part	Spines of vertebrae T <sub>3-8</sub> or 9			
<b>Omotransversarius</b>	Wing of atlas	Dist. scapular spine	Draw limb forward	Accessory & cervical
<b>Latissimus dorsi</b>	Thoracolumbar fascia	Humerus (teres major tubercle)	Flex shoulder or advance body	Thoraco-dorsal
<b>Brachiocephalicus</b>	Clavicular intersection		Pull limb forward or flex neck laterally	Accessory & axillary
Cleidocephalicus		Skull (neck & skull/mastoid process in carnivores)		
Cleidobrachialis		Humerus		






Fig. IV-16 - Dog - Lt. shoulder - extrinsic mm. - lat. view



# EXTRINSIC MUSCLES - SHOULDER

Thoracic limb-149

4. **Rhomboid (ROM-boid) or rhomboideus:** the extrinsic muscle lying deep to the trapezius. It extends from the median raphe of the neck, the thoracic vertebral spines, and the skull to the dorsal border of the scapula and scapular cartilage. It is divided into cervical and thoracic parts in all species; the carnivores and pig have a small capital part. It elevates the forelimb.

5. **Serratus ventralis (ser-RAY-tus) (L. *serratus*, a saw):** the serrated, fan-shaped muscle extending from the last five cervical vertebrae and first seven or eight ribs to the medial surface of the scapula. It supports the trunk.

6. **Superficial pectoral:** the flat muscle extending from the sternum to the cranial surface of the humerus. It is divided into two parts, a superficial descending pectoral and a deeper transverse pectoral, based on their fiber direction. It adducts and advances the limb.

7. **Deep (ascending) pectoral:** the broad muscle extending from the sternum to the greater and lesser tubercles of the humerus. It functions to draw the limb caudally and adduct it.

6. Supf. pectoral

7. Deep pectoral




Fig. IV-17 - Dog Thorax - ventr. view

## SPECIES DIFFERENCES

**Subclavius (Fig. IV-23, c):** pectoral muscle over the cranial border of the supraspinatus muscle in the horse and goat. It is small in the ox and absent in the carnivores.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
<b>Rhomboides</b> Cervical part Thoracic part Capital part (carnivores)	Dors. neck and thorax  Nuchal crest of skull	Dors. border of scapula & scapular cartilage	Draw shoulder dorsocranially	Dors. br. of spinal nn. (cerv. & thoracic)
<b>Serratus ventralis</b>  Cervical part  Thoracic part	  Vertebrae C3-7 (transverse processes)  Ribs 1-7 or 8	Scapula (serrated face) " "	Raise thorax (both), shift weight to contralateral limb (singly), support trunk (both)	Long thoracic
<b>Supf. pectoral</b>  Descending  Transverse	Sternum " "	Cran. surface of humerus " "	Adduct & advance limb (extend shoulder)	Pectoral
<b>Deep pectoral (ascending)</b>	Sternum	Humerus (lesser tubercle)	Adduct & retract limb (flex shoulder)	Pectoral & lat. thoracic






Fig. IV-18 - Dog - Lt. shoulder  
Extrinsic mm. - med. view

antebrachii



# INTRINSIC MUSCLES - SHOULDER & ARM

Thoracic limb 177

**INTRINSIC MUSCLES:** arise and insert on the thoracic limb bones.

## MUSCLES of the SHOULDER and ARM:

**8. Supraspinatus** (soop-ra-SPY-nayt-us): a shoulder extensor, it originates from and fills the supraspinous fossa. Curving over the shoulder joint, it inserts on the greater tubercle of the humerus. It acts as the shoulder's lateral collateral ligament.

**9. Deltoid** (G letter delta) (Fig. IV-16): extends from the scapular spine over the shoulder joint to the deltoid tuberosity of the humerus. Its aponeurosis covers the infraspinatus muscle. It acts to flex the shoulder.

**10. Infraspinatus:** lies deep to the aponeurosis of the deltoid muscle, originating from and filling the infraspinous fossa. Its strong tendon crosses the shoulder joint to insert on the greater tubercle of the humerus. It flexes the shoulder joint and acts with the supraspinatus muscle as the joint's lateral collateral ligament. There is an infraspinatus bursa between the tendon of insertion and the greater tubercle.

**11. Brachialis** (BRAY-koo-el-is) (G. brachium, arm): arises from the caudal part of the scapula, it curves just below the brachial groove. It crosses the cranial (flexor) surface of the humerus to insert on the radius. It flexes the elbow joint with the biceps brachii muscle. The musculocutaneous nerve innervates the brachialis and biceps brachii muscles.

**Teres minor** (d): the small muscle ventral to the tendon of insertion of the infraspinatus muscle. It crosses the lateral surface of the shoulder.

**Anconeus** (c): crosses the lateral aspect of the elbow joint under the triceps brachii muscle. A lateral approach to the elbow is through this muscle.

### SPECIES DIFFERENCES:

**Deltoid** (9): divided into acromial and spinous parts in all domestic animals, except the horse and pig. The horse and pig lack an acromion.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
<b>Deltoid</b>		Deltoid tuberosity	Flex shoulder	Axillary
Scapular part	Spine of scapula			
Acromial part (absent in horse & pig)	Acromion process			
<b>Supraspinatus</b>	Supraspinous fossa of scapula	Humerus (greater & lesser tubercles)	Stabilize & extend shoulder	Supra-scapular
<b>Infraspinatus</b>	Infraspinous fossa of scapula	Humerus (greater tubercle)	Stabilize, flex & extend shoulder	Supra-scapular
<b>Teres minor</b>	Caud. border of scapula	Teres minor tuberosity of humerus	Flex shoulder	Axillary
<b>Brachialis</b>	Brachial groove of humerus	Radius	Flex elbow	Musculo-cutaneous
<b>Anconeus</b>	Olecranon fossa	Olecranon	Extend elbow	Radial






Fig. IV-19 - Dog - Lt. shoulder & arm - Intrinsic mm. - lat view

e. Scapula  
f. Humerus  
g. Olecranon (ulna)



# INTRINSIC MUSCLES - SHOULDER & ARM

Thoracic limb-155

**12. Subscapularis:** the large muscle originating from the subscapular fossa. It crosses the shoulder joint and inserts on the lesser tubercle of the humerus. It adducts the shoulder and serves as the shoulder's medial collateral ligament.

**13. Triceps brachii (L. tri, three + ceps, heads):** composed of three or four heads. Its long head crosses the shoulder, and all heads cross the elbow joint to insert on the olecranon. It extends the elbow and its long head flexes the shoulder.

**14. Biceps brachii (L. bi, two + ceps, head):** arises from the supraglenoid tubercle, crosses the shoulder and elbow, and inserts on the radial tuberosity of the radius. It extends the shoulder, and more importantly, with the brachialis muscle, flexes the elbow joint.

**Coracobrachialis (b):** the small muscle extending from the cora-

coid process over the shoulder to the humerus on the medial side of the axilla.


**Teres major (a):** arises from the caudal border of the scapula and inserts with the latissimus dorsi muscle on the medial side of the humerus.

**Tensor fasciae antebrachii (Fig. IV-18,c):** the thin, insignificant muscle arising from the latissimus dorsi muscle and covering the medial surface of the triceps brachii muscle.

## SPECIES DIFFERENCES:

**Triceps brachii (13):** the long, lateral, and medial heads are found in all species. An accessory head occurs in all species except the horse.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Biceps brachii	Supraglenoid tubercle of scapula	Radial tuberosity	Flex elbow & extend shoulder	Musculo-cutaneous
Coracobrachialis	Coracoid process of scapula	Lesser tubercle of humerus	Flex shoulder	Musculo-cutaneous
Teres major	Caud. border of scapula	Teres major tuberosity of humerus	Flex shoulder	Axillary
Subscapularis	Subscapular fossa	Lesser tubercle of humerus	Adduct & extend shoulder joint	Subscapular
Triceps brachii		Olecranon	Extend elbow	Radial
Long head	Caud. edge of scapula	"		
Lat. head	Humerus	"		
Med. head	"	"		
Accessory head (absent in horse)	"	"		
Tensor fasciae antebrachii (Fig. IV-18,c)	Latissimus dorsi	Olecranon & antebrachial fascia	Extend elbow	Radial



a. Teres major  
b. Coracobrachialis

Fig. IV-20 - Dog - Lt. shoulder & arm  
- Intrinsic mm. - med. view






Fig. IV-21 - Ox - Lt. shoulder, extrinsic mm. - lat. view

1. Trapezius
  2. Latissimus dorsi
  3. Brachiocephalicus
  4. Rhomboid (IV-23)
  5. Serratus ventralis (IV-21)
  6. Supf. pectoral
  7. Deep pectoral
  8. Supraspinatus (IV-23)
  9. Deltoid (IV-21)
  10. Infraspinatus
  11. Brachialis
  12. Subscapularis (following pg)
  13. Triceps brachii
    - 13a. Long head
    - 13b. Med. head
    - 13c. Lat. head
  14. Biceps brachii
- A. Scapular cartilage (IV-23)
- B. Lacertus fibrosus
- a. Omotransversarius
- b. Tensor fasciae antebrachii
- c. Subclavius (absent in carnivores) (IV-23)
- d. Teres minor




Fig. IV-22 - Horse - Lt. shoulder, extrinsic mm. - lat. view






Fig. IV-23 - Horse - Lt. shoulder & arm  
- Intrinsic mm. - lat. view




Fig. IV-24 - Ox - Lt. shoulder & arm  
- Intrinsic mm., deltoid removed  
- lat. view



## 4. Rhomboideus




Fig. IV-26 - Horse - Lt. shoulder & arm  
- Extrinsic mm. - med. view





Fig. IV-25 - Ox - Lt. shoulder & arm  
- Extrinsic mm.  
- med. view



Fig. IV-27 - Horse - Lt. shoulder & arm  
- Intrinsic mm. - med. view



- A. Scapular cartilage  
B. Lacertus fibrosus (IV-27)
- a. Teres major  
b. Coracobrachialis (IV-27)  
c. Tensor fasciae antebrachii  
d. Subclavius (absent in carnivores) (IV-25)




Fig. IV-28 - Ox - Lt. shoulder & arm  
- Intrinsic mm. - med. view



# MUSCLES - FOREARM

Thoracic limb-159

**DORSOLATERAL FOREARM (antebrachial) MUSCLES:** extensors of the digits and carpus, and supinators of the paw. Most arise on or near the lateral (extensor) epicondyle of the humerus and are innervated by the radial nerve.

**15. Extensor carpi radialis:** the largest extensor muscle, it inserts on the metacarpal tuberosity. It extends the carpus and flexes the elbow.

**16. Common digital extensor:** the long muscle inserting on the extensor process of the third phalanx (phalanges). It extends the digit(s) and carpus.

**17. Lateral digital extensor:** originating from the proximal end of the radius and inserting on the lateral digits. It extends the digits and carpus.

**18. Ulnaris lateralis (lateral ulnar, extensor carpi ulnaris):** the most caudal extensor muscle. It inserts on the proximal part of a

metacarpal bone and the accessory carpal bone. Grouped with the extensors, in reality it flexes the carpus in most positions. This is an interesting anatomical point, but clinically of no importance.

## SPECIES DIFFERENCES


**Common digital extensor (16):** in the horse, it has one tendon of insertion for its one digit; in the other domestic species there is a tendon of insertion for each digit (carnivores have 5, ruminants 2 and pigs 4).

**Medial digital extensor (pg. 166):** the more medial muscle head of the common digital extensor that goes to the medial digit of the ruminants. It balances the lateral digital extensor.

**Lateral digital extensor (17):** has only one tendon of insertion on digit IV in the ruminants and on the lateral side of digit III in the horse. It inserts on digits 3, 4 and 5 in the dog and on digits 2, 3, 4 and 5 in the cat.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Extensor carpi radialis	Lat. epicondyle of humerus	Metacarpus	Extend carpal joint, flex elbow	Radial
Common digital extensor	Lat. epicondyle of humerus	Dors. portion of dist. phalanges	Extend digits	Radial
Lateral digital extensor	On or near lat. epicondyle	Middle phalanges	Extend digits	Radial
Lateral ulnar (extensor carpi ulnaris)	Lat. epicondyle of humerus	Prox. end of Metacarpal V	Flex carpal joint	Radial

**Fig. IV-29 - Dog - Lt. forearm  
- lat. view**



a. Anconeus  
b. Ulna



# MUSCLES - FOREARM

Thoracic limb-161

**19. Pronator teres** (PROH-nayt-or TEE-reez, [most people say TER eez]) (L. *teres*, round): the small muscle in carnivores extending from the medial epicondyle of the humerus obliquely to the radius. It pronates the paw (rotates the palmar side downward). In other domestic species, whose capacity to pronate the forelimb is lost or reduced because of fusion of the ulna and radius, the pronator teres is at best vestigial.

**20. Supinator** (SYOO-pi-nayt-or, SOO-pi-nayt-or): present in carnivores and occasionally in the pig. It extends from the lateral (extensor) epicondyle to the radius under the extensor carpi radialis muscle. It supinates the paw (rotates the palmar side upward, as when the cat drinks milk with its paw). It is absent from the other domestic species, because their radius and ulna fuse, negating the possibility of supination.

**Brachioradialis (d)**: the small muscle in the superficial fascia over the extensor carpi radialis muscle in carnivores.

**Oblique carpal extensor (b)**: also known as the abductor pollicis (digiti I) longus. (Pollicis refers to thumb, which none of the domestic animals have.) The carnivores have digit I, but none of the other species do. For comparative purposes, we use the anglicization of the NAV permitted extensor carpi obliquus. In the carnivores it has a small sesamoid bone in its tendon on the medial side of the carpus.

**Pronator quadratus**: a wide, short muscle bridging the length of the interosseous space between the ulna and radius. It is deep to the deep digital flexor muscle.

## CLINICAL

**Brachioradialis (d)**: in carnivores runs with the cephalic vein on the cranial aspect of the forearm. It is roughly the same size as the vein for which it may be mistaken in venipuncture.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Pronator teres	Med. epicondyle of humerus	Med. surface of radius	Pronates paw	Median
Supinator (carnivores)	Lat. epicondyle of humerus	Radius	Supinates paw	Radial
Oblique carpal extensor (long digital I abductor) (abductor digiti I [pollicis] longus)	Cran. surface of forearm	Prox. metacarpus	Extend carpus & abduct carnivore's 1st digit	Radial
Extensor pollicis longus et indicis proprius (carnivores)	Ulna	Metacarpals I & II	Extend digits I & II	Radial
Pronator quadratus (carnivores)	Dist. ulna	Dist. radius	Pronates paw	Median
Brachioradialis (long supinator) (carnivores)	Lat. condyloid crest of humerus	Cran. surface of radius	Supinates paw	Radial

Fig. IV-30 - Dog - Lt. forearm - cran. view





Fig. IV-31 - Dog - Lt. forearm, deep dissection - cran. view

- a. Extensor pollicis longus et indicis proprius
- b. Oblique carpal extensor
- c. Ulna
- d. Brachioradialis



# MUSCLES - FOREARM

Thoracic limb-162

**CAUDAL ANTEBRACHIAL MUSCLES:** the flexors of the carpus and digits, and pronators of the paw. They originate from or near the medial (flexor) epicondyle of the humerus, and are innervated by the median and/or ulnar nerves. They include the flexor carpi radialis (21), flexor carpi ulnaris (22), superficial digital flexor (23), deep digital flexor (24) and pronator teres (19).

**21. Flexor carpi radialis:** the long muscle inserting on the proximal metacarpus. It flexes the carpus.

**22. Flexor carpi ulnaris:** a two-headed muscle inserting on the accessory carpal bone. It has an ulnar and a humeral head and flexes the carpus. The humeral head can be mistaken for the superficial digital flexor. To differentiate them, follow them to their terminations.

**23. Superficial digital flexor:** arises from the medial (flexor) epicondyle of the humerus and inserts on the middle phalanx. It flexes the carpus and digits.

**Manica flexoria:** the sleeve of the superficial digital flexor tendon located at the metacarpophalangeal joints in all species. It

allows the deep digital flexor tendon to pass through and attach distally to the attachment of the superficial digital flexor.

## SPECIES DIFFERENCES

**Superficial digital flexor (24):** has tendons to each digit (carnivore - 5; horse - 1; ruminants - 2), except in the pig which has only 2 for its 4 digits. In the horse it inserts on the proximal end of the middle phalanx and the distal end of the proximal phalanx. These two insertions may prevent "dorsal bucking" (hyperflexion) of the proximal interphalangeal joint. The ruminant has two tendons, the deep one passing through the carpal canal and the superficial one passing through the flexor retinaculum.

**Accessory ligament of the superficial digital flexor:** a tendinous band that connects the tendon of the superficial digital flexor to the radius. This plays a part in the stay apparatus (pg. 196). It is also known as the "radial head", "proximal check ligament", "superior check ligament" and "radial check ligament".

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Flexor carpi radialis	Med. (flexor) epicondyle of humerus	Prox. metacarpus	Flex carpus	Median n.
Flexor carpi ulnaris		Accessory carpal bone	Flex carpus	Ulnar n.
Ulnar head Humeral head	Olecranon Med. epicondyle of humerus			
Supf. digital flexor	Med. epicondyle of humerus	Palm. surface of middle phalanges	Flex digits & carpus	Median n.




Fig. IV-32 - Dog - Lt. forearm - med. view

- a. Olecranon
- b. Oblique carpal extensor
- c. Suspensory br. of interosseous m.
- d. Brachioradialis m.



# MUSCLES - FOREARM

Thoracic limb-165

**24. Deep digital flexor:** the three-headed muscle arising from the humerus, radius and ulna and inserting on the distal phalanx (phalanges). It flexes the carpus and digits.

**25. Interosseous** (in'ter-OS-ee-us) (L. *interosseus*, *inter* between + *os* bone): a muscle of the manus, arising from the proximal palmar surface of the metacarpal bones. It extends distally and splits into two tendons. One tendon inserts on the sesamoid bones of the respective metacarpophalangeal joints. The other tendon, the extensor branch, joins the common digital extensor muscle's tendon of insertion.

## SPECIES DIFFERENCES

**Accessory ligament of the deep digital flexor:** a tendinous band from the palmar carpal ligament to the tendon of the deep digital flexor. It can be reached from the lateral side. It plays a part in the stay apparatus (pg. 196). Popular synonyms are: "distal check ligament", "carpal check ligament", and "inferior check ligament".

**Interosseous (25):** horse -3 muscles; dog and cat - 4; in the ruminants the 2 interosseous muscles are fused.

**Suspensory ligament (Fig. IV-35):** another term for the interosseous muscle in the horse. It is completely tendinous upon maturity and plays a role in the stay apparatus and locomotion.

## CLINICAL

**Bowed tendons (tendosynovitis):** a torn tendon in horses, usually resulting from racing stress. The superficial digital flexor of the thoracic limb and the suspensory ligament of the hind limb are most commonly affected. Depending on where they are in the metacarpal region they are classified as low, middle or high.

**Flexorial limb deformities or contracted tendons:** a congenital or acquired defect in foals involving the flexor tendons of the front or hind limb. Often the accessory ("check") ligaments are resected (cut) to help straighten out the distal limb.


Flexorial limb deformities are a better name because tendons can't contract (A. Simon Turner).

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
<b>Deep digital flexor</b>  Humeral head Radial head Ulnar head	Humerus, radius & ulna	Tuberosities of dist. phalanges	Flex digits & carpus	Median & ulnar nn.
<b>Interosseous</b>	Prox. end of metacarpals II, III, IV & V	Sesamoid bones of respective metacarpophalangeal joints		Deep br. of ulnar

# MUSCLES - FOREARM

Thoracic limb-166

Fig. IV-33 - Dog - Lt. forearm - caud. view




a. Olecranon  
b. Olecranon fossa  
c. Oblique carpal extensor

24. Deep digital flexor

Flexor carpi radialis

25. Interosseous


Fig. IV-34 - Dog - Lt. forearm, deep dissection - caud. view





# MUSCLES - FOREARM

Fig. IV-35 - Horse - Lt. forearm - lat. view



- 11. Brachialis
- 13. Triceps brachii
- 13a. Long head
- 13b. Med. head
- 13c. Lat. head
- 14. Biceps brachii
- 15. Extensor carpi radialis
- 16. Common digital extensor
- 17. Lat. digital extensor
- 18. Lat. ulnar
- 19. Pronator teres (absent in horse)
- 20. Supinator (carnivores)
- 21. Flexor carpi radialis
- 22. Flexor carpi ulnaris
- 23. Supf. digital flexor
- 24. Deep digital flexor
- 25. Interosseous (suspensory lig. - horse)

- A. Lacertus fibrosus (IV-37)
- B. Accessory lig. of the deep digital flexor
- a. Anconeus
- b. Oblique carpal extensor

Thoracic limb-167




Fig. IV-36 - Ox - Lt. forearm - lat. view

Fig. IV-37 - Horse - Lt. forearm - med. view





Fig. IV-38 - Ox - Lt. forearm - med. view



**MUSCLES of the LOIN, HIP and THIGH:** The hip is the region between the crest of the ilium and greater trochanter of the femur. The thigh is the region between the greater trochanter and the stifle. The loin is the proximal craniomedial region of the thigh. The rump (gluteal region) is the prominence formed by the gluteal muscles.

• **Loin and hip muscles:** divided into three groups: sublumber, rump, and inner pelvic muscles.

• **Sublumber muscles:** include the psoas minor, iliopsoas (psoas major and iliacus) and quadratus lumborum muscles. They originate from the ventral surface of the caudal thoracic and lumbar vertebrae and insert on the os coxae and femur. These muscles flex the hip and lumbar vertebral column and fix the lumbar vertebral column. The ventral branches of the lumbar nerves innervate the sublumber muscles.

• **Rump muscles:** the superficial gluteal, medial gluteal, deep gluteal, and tensor fasciae latae muscles, all originating from the ilium and inserting on the femur. The rump muscles mainly extend the hip joint, except the tensor fasciae latae which, by tensing the fascia of the thigh (fasciae latae), flexes the hip joint and extends the stifle. The cranial and caudal gluteal nerves innervate the rump muscles.

• **Inner pelvic muscles:** the internal obturator, gemelli, and quadratus femoris muscles, all originating caudomedial to the hip joint and inserting on or near the proximal caudal side of the humerus (trochanteric fossa, pg. 96, j). Their action is mainly outward rotation of the hip joint. They are innervated by the ischiatic nerve.

• **Thigh muscles:** divided according to their position: cranial, caudal, and medial:

• **Cranial thigh muscles:** The extensors of the stifle, innervated by the femoral nerve, they are the four-headed quadriceps femoris and the sartorius muscles. They cover the cranial, lateral, and medial surfaces of the femur, originating from the os coxae and femur and inserting on the tibial tuberosity. They extend the stifle joint and flex the hip.

• **Medial thigh muscles (adductor group):** They are the sartorius, gracilis, adductor, pectineus, and external obturator muscles. They originate from the os coxae and insert on the bones of the limb. They are innervated by the obturator nerve.

• **Caudal muscles of the thigh (hamstring muscles):** innervated by the ischiatic nerve, the biceps femoris, caudal crural abductor, semitendinosus, and semimembranosus muscles arise from the ischiatic tuberosity and insert on the medial and lateral sides of the stifle joint. The caudal thigh muscles have varied actions on the hip, stifle, and tarsus.

**MUSCLES of the CRUS:** the true leg, shank, or gaskin is covered with muscles on the craniolateral and caudal surfaces. There are no muscles on the medial surface, the tibia being directly under the skin. The muscle groups of the crus are not grouped as in the thoracic limb because the angles of the tarsal joint and the digits are opposite. The muscles either extend the digit and flex the tarsus, or flex the digit and extend the tarsus.

• **Craniolateral muscles:** extensors of the digits and flexors of the tarsus, innervated by the peroneal (fibular) nerve. They are the cranial tibial, peroneus longus (long fibular\*), long digital extensor, lateral digital extensor, and peroneus tertius (third fibular\*) muscles. Located on the craniolateral side of the leg, they originate from the proximal part of the tibia and fibula, except the long digital extensor and peroneus tertius (third fibular) muscles which originate from the extensor fossa of the femur (96, j).

• **Caudal muscles:** flexors of the digits and extensors of the tarsus, innervated by the tibial nerve. They are the gastrocnemius, caudal tibial, popliteus, and superficial and deep digital flexor muscles, originating from the caudal surfaces of the femur and tibia.

**MUSCLES of the PES:** There is little difference between the muscles of the pes and the manus of the forelimb and they are of the same significance in all the different species, except the interosseous muscle (suspensory ligament) of the horse.

\* Fibular may be used instead of peroneal to aid learning by associating muscles with the fibular side of the leg. This option is allowed by the N.A.V.

## LOIN & HIP MUSCLES:

• **Sublumber muscles:** - ventr. br. of lumbar nn.  
Psoas minor  
Iliopsoas  
Psoas major  
Iliacus

• **Rump muscles:** cran. & caud. gluteal nn.  
Superficial gluteal  
Middle gluteal  
Deep gluteal  
Tensor fasciae latae

• **Inner pelvic muscles:** ischiatic nerve  
Internal obturator  
Gemelli  
Quadratus femoris

## THIGH MUSCLES:

• **Cranial thigh muscles:** extensors of the stifle - femoral n.  
Quadriceps femoris  
Sartorius

• **Medial thigh muscles (adductor group):** - obturator n.  
Sartorius  
Gracilis

Adductor  
Pectineus  
External obturator


• **Caudal muscles (hamstring mm.):** - ischiatic n.  
Biceps femoris  
Gluteobiceps (rum.)  
Caud. crural abductor (cam.)  
Semitendinosus  
Semimembranosus

## MUSCLES OF THE CRUS:


• **Craniolateral muscles:** extensors of the digits & flexors of the tarsus - peroneal n.  
Cranial tibial  
Peroneus longus (cam. & rum.)  
Long digital extensor  
Lateral digital extensor  
Peroneus tertius (eq. & rum.)

• **Caudal muscles:** flexors of digits & extensors of tarsus - tibial n.  
Gastrocnemius  
Soleus (eq. & cat)  
Caudal tibial  
Popliteus  
Superficial digital flexor  
Deep digital flexor










**Fig. IV-41 - Horse**  
- Pelvic limb - lat. view




**Fig. IV-42 - Horse**  
- Pelvic limb - med. view


- |                              |                     |
|------------------------------|---------------------|
| 1. Middle gluteal            | 10. Adductor        |
| 2. Supf. gluteal (absent-ox) | 11. Sartorius       |
| 3. Tensor fasciae latae      | 12. Vastus medialis |
| 4. Rectus femoris            | 13. Pectineus       |
| 5. Vastus lateralis          | 14. Iliopsoas       |
| 6. Biceps femoris            | 15. Psoas minor     |
| 7. Semitendinosus            | 16. Psoas major     |
| 8. Semimembranosus           | 17. Iliacus         |
| 9. Gracilis (IV-42)          | 18. Cran. tibial m. |

- |                                      |
|--------------------------------------|
| 19. Long digital extensor            |
| 20. Lat. digital extensor (IV-41)    |
| 21. Third fibular (peroneus tertius) |
| 22. Gastrocnemius                    |
| 23. Interosseous                     |
| 24. Deep digital flexor              |
| 25. Supf. digital flexor             |





**Fig. IV-43 - Ox - Pelvic limb  
- med. view**



**Fig. IV-44 - Ox - pelvic limb  
- lat. view**



**SUBLUMBAR MUSCLES:** the psoas minor, psoas major, iliacus, and quadratus lumborum muscles arising on the ventral surfaces of the thoracic and lumbar vertebrae and inserts on the os coxae and the femur. They are innervated by ventral branches of the lumbar spinal nerves.

1. Psoas (SOH-as) minor: a long, thin muscle extending from the lumbar vertebral bodies to the ilium. It flexes or stabilizes the lumbar vertebral column.

**Iliopsoas:** the fused psoas major and iliacus muscles which act as


the chief flexors of the hip joint.

2. Psoas major (G. psoas, muscle of the loin): the strongest flexor of the hip, extending from the lumbar vertebrae caudoventrally with the iliacus muscle to the lesser trochanter of the femur. Butchers refer to the psoas muscle as the "tenderloin".


3. Iliacus (IL-ee-ak-us): A short muscle arising from the ilium; it joins the psoas major to insert on the lesser trochanter of the femur.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Psoas minor	Vertebrae T <sub>12</sub> -L <sub>5</sub>	Hip bone (body of ilium)	Stabilize back	Ventr. brs. of thoracic & lumbar nn.
Psoas major	Lumbar vertebrae	Lesser trochanter of femur	Flex hip & outwardly rotate thigh	Ventr. brs. of thoracic & lumbar nn. & femoral n.
Iliacus	Wing of ilium	Lesser trochanter of femur	Flex hip & outwardly rotate thigh	Ventr. brs. of lumbar n. & femoral n.
Quadratus lumborum	Transverse processes of lumbar vertebrae	Wing of sacrum & ilium	Stabilizes lumbar vertebrae	Ventr. brs. of lumbar n. & femoral n.





**Fig. IV-45 - Dog - Sublumbar mm.  
- ventr. view**



**Fig. IV-46 - Dog - Sublumbar mm., deep  
dissection - ventr. view**

- a. Crus of diaphragm
- b. Costal part of diaphragm
- c. Lesser trochanter
- d. Quadratus lumborum
- e. Ext. obturator
- f. Rectus abdominis



# **PELVIC MUSCLES**

Pelvic limb-175

**PELVIC MUSCLES:** the internal obturator, gemelli and quadratus femoris muscles. The gemelli and quadratus femoris are fairly insignificant muscles.

**4. Internal obturator (OB-tyoo-ray'tor):** a fan-shaped muscle arising medially from the pelvic floor and covering the obturator foramen. Its tendon travels over the lesser ischiatic notch to insert in the trochanteric fossa.

**5. EXTERNAL OBTURATOR:** a fan-shaped muscle arising from the ventral surface of the os coxae, covering the obturator foramen externally. It inserts in the trochanteric fossa (96, j) and

causes outward rotation of the femur. It is grouped with the medial thigh muscles (adductors), but has the same function as the pelvic muscles.

## **SPECIES DIFFERENCES**

**Internal obturator:** only in the horse and carnivores. Its tendon passes over the lesser ischiatic notch to reach the trochanteric fossa. In the pig and ruminants the similarly-placed muscle is known as the intrapelvic part of the external obturator muscle. Its tendon passes through the obturator foramen to reach the trochanteric fossa.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Internal obturator	Interior of pelvis	Caud. surface of femur (trochanteric fossa)	Rotate femur laterally	Ischiatic
Gemelli	Ischium	Caud. surface of femur (trochanteric fossa)	Rotate femur laterally	Ischiatic
Quadratus femoris	Ischium	Caud. surface of femur	Extend hip & adduct thigh	Ischiatic
Ext. obturator	Ventr. surface of pubis & ischium	Caud. surface of femur (trochanteric fossa)	Adduct thigh	Obturator




Fig. IV-47 - Dog - Pelvic mm. - dors. view

Fig. IV-48 - Ox - Pelvic mm. - dors. view





Fig. IV-49 - Ox - Pelvic mm. - ventr. view

- A. Ilium
- B. Femur
- C. Ischium
- D. Sacrotuberous lig.
- E. Rectus abdominis m.
- F. Levator ani m.
- G. Coccygeus m.
- H. Psoas minor m.
- I. Psoas major m.
- J. Iliacus m.
- K. Sacrum
- L. Lumbar vertebrae

- a. Trochanteric fossa
- b. Gemelli m.
- c. Quadratus femoris m. (IV-49)



# MUSCLES - HIP & THIGH

Pelvic limb-177

**6a. Superficial gluteal (GLOO-tee-al):** the caudally-located gluteal muscle arising above the hip joint and inserting on the third trochanter. It acts to abduct the limb.

**6b. Middle gluteal:** the largest gluteal muscle arising from the entire wing of the ilium. It runs over the deep gluteal muscle and hip joint to insert on the greater trochanter. It extends the hip joint and abducts the limb.

**6c. Deep gluteal (Fig. IV-47):** the muscle extending from the shaft of the ilium over the hip joint to the greater trochanter. It extends the hip joint and abducts the limb.

**7. Biceps femoris:** the largest and most lateral of the caudal thigh muscles. It arises from the ischiatic tuberosity, extending distally on the lateral side of the thigh to fan out and insert on the patella, tibia and calcaneal tuber, thus, crossing the hip, stifle and tarsal joints. It has complex actions, extending the hip, stifle and tarsal joints, flexing the stifle, or abducting the limb.

## SPECIES DIFFERENCES

**Gluteobiceps muscle:** the fusion of the superficial gluteal and the biceps femoris in ruminants. Therefore, the superficial gluteal muscle and third trochanter are absent.

**Accessory gluteal muscles:** part of the middle gluteal in the ungulates (hoofed animals - ruminants, pigs, and horses).

**Piriformis muscle:** only in carnivores, deep and caudal to the middle gluteal muscle. Fused with the middle gluteal, until recently, it was considered part of this muscle.

## CLINICAL

**Whorlbone disease:** an inflammation of the bursa between the middle gluteal muscle and the greater trochanter of the femur in the horse. Pain in this bursa causes the horse to "dog trot" (move its rear end to the side and cranially, away from the pain).

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Supf. gluteal (absent in ruminants)	Dors. to hip joint	Third trochanter	Abduct limb of femur	Gluteal nn.
Middle gluteal	Wing of ilium	Greater trochanter of femur	Extend limb, abduct limb	Gluteal nn.
Deep gluteal	Body of ilium	On or near greater trochanter	Extend limb, abduct limb	Gluteal nn.
Biceps femoris	Ischiatic tuberosity	Patella, tibia & calcaneal tuberosity	Extend hip, stifle & tarsus, flex stifle	Ischiatic




Fig. IV-50 - Dog - Hip - lat. view

- a. Tuber coxae
- b. Ext. anal sphincter
- c. Crural fascia



# MUSCLES - HIP & THIGH

Pelvic limb-179

8. **Tensor fasciae latae**: the triangular muscle, originating from the tuber coxae and inserting on the lateral femoral fascia (fascia lata) and, thus, the patella. Its action is to tense the fascia lata, flexing the hip and extending the stifle.

9. **Caudal crural abductor** (KROOYR-al): the strap-like "fire hydrant" muscle located deep to the biceps femoris muscle in carnivores. It has little clinical significance besides humor value.

10. **Semitendinosus**: the long "hamstring" muscle forming the caudal border of the thigh. It extends from the ischiatic tuberosity to the tibia and on the calcanean tuber by the calcanean tendon,

thus, crosses the hip, stifle and tarsal joints. It extends the hip, stifle and tarsal joints and flexes the stifle when the limb is not bearing weight.

## SPECIAL

**Tendon strand** (tarsal tendon): a fascial slip from the caudal edge of the semitendinosus muscle joining the calcanean tendon to insert on the calcanean tuber.

**Fascia lata** (L. broad band) (h): the deep fascia of the thigh, tensed when the tensor fasciae latae muscle contracts.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Tensor fasciae latae	Tuber coxae	Lat. femoral fascia	Tense lat. femoral fascia and thus flex hip joint & extend stifle	Gluteal
Semitendinosus	Ischiatic tuberosity	Tibia & calcanean tuberosity	Extend hip & tarsus, flex stifle	Ischiatic
Caudal crural abductor	Crural fascia		Abduct leg	Ischiatic




Fig. IV -51 - Dog - Hip, deep dissection - lat. view



# MUSCLES - THIGH

Pelvic limb-181

11. **Gracilis** (L. slender): the broad, superficial muscular sheet extending from the pelvic symphysis down the medial thigh to insert medially on the tibia. It adducts the femur and is the only adductor to cross the stifle.

12. **Pectineus** (L. *pecten* comb): a long, spindle-shaped muscle extending from the pubis to the medial side of the femur.

13. **Sartorius** (L. *sartor* a tailor): the strap-like muscle arising from the ilium and inserting on the medial side of the stifle. It flexes the hip and stifle joint (in the dog it also extends the stifle).

## SPECIES DIFFERENCES

**Sartorius (13):** divided proximally in the ruminants and pig; it has two bellies in the dog. It flexes the hip and stifle joints, and in the dog also extends the stifle (cranial belly). It is undivided in the horse and cat.


## CLINICAL

**Femoral triangle:** the area bounded by the sartorius muscle cranially, the pectineus muscle caudally, and the body wall dorsally. Take a pulse of the femoral artery passing through it in carnivores. It is not advised to try this in the larger animals. (Ouch!)

**Pectineal tenotomy:** cutting of the pectineus muscle to relieve the pain of hip dysplasia in dogs.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Sartorius	Ilium	Med. side of stifle	Flex hip & stifle	Femoral (saphenous n.)
Gracilis	Pelvic symphysis	Med. side of stifle	Adduct limb	Obturator
Pectineus	Pubis (prepubic tendon)	Femur	Adduct limb & flex hip	Obturator







**14. Quadriceps femoris** (L. *quadri* four + *caput* head): the large muscle covering the lateral, medial and cranial surfaces of the femur. Composed of four heads joining in a common tendon that contains the patella it inserts on the tibial tuberosity. All heads extend the stifle. The rectus femoris also flexes the hip.

- **14a. Rectus femoris** (L. *rectus* straight): crosses both the hip and stifle joints.

- **14b. Vastus lateralis** (L. *vastus* large).

- **14c. Vastus medialis.**

- **14d. Vastus intermedius:** surrounded by the other three heads and the femur. It is fused to the medial and lateral heads.

**15. Adductor:** largest of the adductors, it lies deep to the gracilis muscle, extending from the pelvic symphysis to the caudal surface of the femur. It adducts the limb and flexes the hip joint.

**16. Semimembranosus:** one of the "hamstring" muscles arising with the semitendinosus muscle from the ischiatic tuberosity. It splits into two bellies which arch medially to insert on the stifle; one belly on the femur, one on the tibia. It extends the hip, adducts the limb and has variable action on the stifle.

## SPECIAL

**Memory aid:** the semiMembranousus is Medial and the semiTendinous is laTeral.

**"Hamstring muscles":** consist of the biceps femoris, semitendinosus and semimembranosus muscles. The distal ends of these muscles feel like strings, hence the name.

**Symphyseal tendon (c):** the tendon of origin of the adductor and gracilis muscles at the pelvic symphysis.

## SPECIES DIFFERENCES

**Patellar ligament (d):** the tendon extending from the patella to the tibial tuberosity. It is singular in all domestic species, except the horse and ox where it is divided into three parts. The patellar ligament is part of the tendon of insertion of the quadriceps femoris muscle distal to the patella.

## CLINICAL

**"Hamstring" injections:** there is a danger of sticking the ischiatic nerve travelling deep to this area. Palpate the junction between the biceps femoris and the semitendinosus muscle. Direct the needle lateral to this junction into the biceps femoris, or medial into the semitendinosus or semimembranosus to avoid the ischiatic nerve.

**Fibrotic myopathies:** scar tissue replaces muscle tissue of the semimembranosus and semitendinosus muscles which can mechanically alter the gait of the horse. As the horse finishes its stride, the muscle can't stretch, causing the foot to be jerked back just before it lands.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
<b>Quadriceps femoris</b>				Femoral n.
Rectus femoris	Ilium	Patella and thus to tibial tuberosity	Flex hip & extend stifle	
Vastus lateralis	Prox. femur	"	Extend stifle	
Vastus medialis	"	"	"	
Vastus intermedius	"	"	"	
<b>Adductor</b>	Ventr. surface of hip bones	Femur	Adduct limb	Obturator n.
<b>Semimembranosus</b>	Ischiatic tuberosity	Femur & tibia	Extend hip, flex or extend stifle	Ischiatic n.



Fig. IV-53 - Dog - Thigh, deep dissection - med. view






Fig. IV-54 - Horse - Hip - lat. view






Fig. IV-55 - Ox - Thigh - lat. view



Fig. IV-56 - Horse - Thigh mm., deep dissection - lat. view



- |   |                             |
|---|-----------------------------|
| 1. Psoas minor (next pg.)                   | a. Gemelli (IV-56)          |
| 2, 3. Iliacus                               | b. Quadratus femoris        |
| 2. Psoas major (IV-56)                      | c. Soleus                   |
| 3. Iliacus                                  | d. Broad sacrotuberous lig. |
| 4. Internal obturator (next pg.)            |                             |
| 5. External obturator (next pg.)            |                             |
| 6. Gluteal (IV-54)                          |                             |
| 6a. Supf. gluteal (not present in ruminant) |                             |
| 6b. Middle gluteal                          |                             |
| 6c. Deep gluteal (IV-56)                    |                             |
| 7. Biceps femoris (IV-54)                   |                             |
| 8. Tensor fasciae latae                     |                             |
| 9. Caud. crural abductor (carnivores)       |                             |
| 10. Semitendinosus                          |                             |
| 11. Gracilis (next pg.)                     |                             |
| 12. Pectineus (next pg.)                    |                             |
| 13. Sartorius (next pg.)                    |                             |
| 14. Quadriceps femoris (IV-56)              |                             |
| 14a. Rectus femoris                         |                             |
| 14d. Vastus intermedius                     |                             |
| 15. Adductor                                |                             |
| 16. Semimembranosus                         |                             |

Fig. IV-57 - Ox - Thigh, deep dissection - lat. view







Fig. IV-58 - Horse - Thigh - med. view



Intrapelvic part of external obturator m.




Fig. IV-59 - Ox - Thigh - med. view







Fig. IV-60 - Horse - Thigh, deep view

- |   |                              |
|---|------------------------------|
| 1. Psoas minor                                | a. Symphyseal tendon (IV-59) |
| 1.2. Iliopsoas                                | b. Rectus abdominis (IV-58)  |
| 2. Psoas major                                | c. Int. abdominal oblique    |
| 3. Iliacus                                    | d. Levator ani               |
| 4. Int. obturator                             | e. Coccygeus                 |
| 5. Ext. obturator (IV-59, not shown in horse) | f. Broad sacrotuberous lig.  |
| 6. Gluteal (IV-61)                            |                              |
| 7. Biceps femoris                             |                              |
| 8. Tensor fasciae latae (IV-58)               |                              |
| 9. Caud. crural abductor (carnivores)         |                              |
| 10. Semitendinosus                            |                              |
| 11. Gracilis                                  |                              |
| 12. Pectineus                                 |                              |
| 13. Sartorius                                 |                              |
| 14. Quadriceps femoris                        |                              |
| 14a. Rectus femoris                           |                              |
| 14c. Vastus medialis                          |                              |
| 15. Adductor                                  |                              |
| 16. Semimembranosus                           |                              |

Fig. IV-61 - Ox - Thigh, deep dissection - med. view





# MUSCLES - CRUS

Pelvic limb-189

**MUSCLES OF THE CRUS:** muscles covering the craniolateral and caudal surfaces of the leg (between the stifle and hock). The craniolateral group of muscles extends the digits and flexes the tarsus and are innervated by the common peroneal (fibular) nerve. This is different from the similarly placed craniolateral group of the forelimb which extends the digits and the next most proximal joint, the carpus. The caudal group of muscles in the hindlimb flexes the digits and extends the tarsus. The caudal group in the forelimb flexes the digits and the next proximal joint, the tarsus.

**17. Cranial tibial muscle:** a tarsal joint flexor extending from the tibial crest and tuberosity distally to insert on the metatarsus.

**18. Peroneus longus muscle** (per'oh-NEE-us)(long fibular [FIB-yoo-lar]): the spindle-shaped muscle on the lateral side of the crus.

**19. Peroneus tertius** (third fibular) muscle: arises with the long digital extensor muscle from the extensor fossa of the femur and crosses the stifle and tarsal joints to insert on the metatarsal bones. It extends the stifle and flexes the tarsus.

**20. Long digital extensor muscle:** the spindle-shaped muscle extending from the extensor fossa to the extensor process of the distal phalanges (phalanx). It extends the digits and flexes the tarsus.

**21. Lateral digital extensor muscle:** a thin muscle arising from the fibula. It aids the long digital extensor in tarsal flexion and digital extension.

**"Cunean tendon":** the common name for the horse's medial insertion of the cranial tibial muscle (Fig. II-51, Fig. IV-69).

**Cunean bursa:** associated with the medial insertion of the cranial tibial muscle in the horse.

**Reciprocal apparatus in the horse:** consists of two tendinous cords crossing the stifle and the tarsus; the superficial digital flexor on the caudal aspect, and the peroneus tertius muscle on the cranial aspect. Flexion or extension of the stifle or tarsus causes a similar (reciprocal) movement in the other joint due to these two cords.

**Peroneus longus muscle (18):** absent in the horse.

**Peroneus tertius muscle (19):** absent in carnivores, fleshy in the ox, and entirely tendinous in the horse where it passively flexes the tarsal joint whenever the stifle joint is flexed (part of the reciprocal apparatus). The cranial tibial muscle passes through the peroneus tertius at the tarsus.

**Lateral digital extensor (21) insertions:** carnivores – digit V; ox – digit IV; and horse – unites with the long digital extensor muscle.

## CLINICAL

**Peroneus tertius (third fibular) (19):** rupture is diagnosed when the tarsus can be manually extended while the stifle is flexed in the horse.

**Cunean tendon:** often resected to relieve pain due to "bone spavin" (tarsal osteoarthritis) in the horse.

**Cunean bursitis:** inflammation of the cunean bursa. It can be confused with lameness caused by bone spavin.

## SPECIES DIFFERENCES

**Long digital extensor tendon (s) of insertion (20):** one in the horse; one to each digit in the other species; the same is true of the common digital extensor in the thoracic limb.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Cranial tibial m.	Prox. tibia	Prox. metatarsus	Flex tarsus	Fibular n. (peroneal n.)
Long digital extensor	Extensor fossa of femur	Extensor processes of dist. phalanges	Extend stifle & digits, flex tarsus	Fibular n. (peroneal n.)
Long fibular m. (peroneus longus) (absent in horse)	Lat. collateral lig. of stifle	Tarsal and/or metatarsal bones	Flex tarsus	Fibular n. (peroneal n.)
Third fibular m. (peroneus tertius) (absent in carnivores)	Extensor fossa of femur	Metatarsal bones	Extend stifle & flex tarsus	Fibular n. (peroneal n.)
Lat. digital extensor	Fibula	Lat. digit	Extend digits, flex tarsus	Fibular n. (peroneal n.)






Fig. IV-62 - Dog - Lt. crus & pes - lat. view



**CAUDAL CRURAL MUSCLES:** extend the tarsus and flex the digits. They are innervated by the tibial nerve.

**22. Gastrocnemius** (gas'trok-NEE-mee-us): the large, two-bellied muscle arising from the distocaudal surface of the femur. Its heads enclose the proximal end of the superficial digital flexor. Distally, it inserts on the calcaneal tuberosity as part of the calcaneal tendon. It extends the tarsal joint and flexes the stifle joint.

**Soleus** (Fig. IV-64, g): an insignificant muscle, except in the pig and man. It is absent in the dog, but present in the cat. It arises from the fibula and joins the lateral head of the gastrocnemius muscle. The two heads of the gastrocnemius and the soleus are collectively called the triceps surae.

**23. Deep digital flexor:** a large muscle composed of two or three muscle bellies (species dependent) extending from the caudal surface of the tibia and fibula to the distal phalanx. It flexes the

digits and extends the tarsus.

**24. Superficial digital flexor:** a thin muscle arising from the caudal aspect of the distal femur, deep to the heads of the gastrocnemius muscle. Extending distally, its tendon wraps medially around the gastrocnemius tendon and attaches superficially to the calcaneal tuberosity. It then continues on the plantar aspect of the limb to the middle phalanges. It flexes the digits and extends the tarsus.

- **Calcaneal tendon:** the tendon formed by the gastrocnemius and superficial digital flexor muscles and slips from other muscles (biceps femoris, semitendinosus, and, in the carnivores, the gracilis).

- **Calcaneal bursa:** an extensive bursa lying between the superficial digital flexor tendon and the calcaneal tuberosity.

**25. Interosseous** (interossei) (suspensory ligament in the horse): similar to the muscle in the front limb.

MUSCLE	ORIGINS	INSERTION	ACTION	NERVE
Gastrocnemius	Distocaud. surface of femur	Calcaneal tuberosity	Extend tarsus & flex stifle	Tibial
Popliteus	Dist. end of femur	Prox. tibia	Flex stifle	Tibial
Deep digital flexor	Tibia & fibula	Dist. phalanges		Tibial
Supf. digital flexor	Femur	Calcaneal tuberosity & middle phalanges	Flex stifle & digits, extend tarsus	Tibial
Interosseous	Prox. metatarsal, med. metacarpals	Prox. sesamoid & digital extensor tendon		Tibial n.
Soleus (absent in dogs)	Head of fibula (femur in pigs)	Tendon of lat. head of gastrocnemius	Extends tarsus	Tibial






Fig. IV-65 - Ox - Lt. hindlimb - lat. view





Fig. IV-64 - Horse - Crus - lat. view



- 1.-16. See pg. 185  
 17. Cranial tibial m.  
 18. Long fibular (peroneus longus) m. (absent in horse)  
 19. Third fibular m. (fibularis tertius) (absent in carnivores)  
 20. Long digital extensor  
 21. Lat. digital extensor  
 22. Gastrocnemius  
 23. Deep digital flexor  
 24. Supf. digital flexor  
 25. Interosseous

- A. Calcanean tendon  
 B. Lat. collateral lig. of stifle

- C. Lat. patellar lig.  
 D. Middle patellar lig.  
 E. Med. patellar lig.  
 F. Hoof

- a. Femur  
 b. Popliteal m.  
 c. Tibia  
 d. Calcanean tuberosity  
 e. Extensor fossa  
 f. Patella  
 g. Soleus m.



Fig. IV-66 - Horse - Lt. hindlimb - med. view





Fig. IV-67 - Ox - Lt. hindlimb - med. view



Fig. IV-68 - Horse  
- Lt. hindlimb  
- cran. view





Fig. IV-69 - Horse - Lt. hindlimb, deep  
dissection - cran. view

Fig. IV-70 - Ox - Lt. hindlimb - cran. view





Fig. IV-71 - Ox  
Lt. forearm, deep  
dissection - cran. view



- 1.-16. See pg. 185
- 17. Cranial tibial m.
- 18. Long fibular m. (absent in horse)
- 19. Third fibular m. (fibularis tertius) (absent in carnivores)
- 20. Long digital extensor
- 21. Lat. digital extensor
- 22. Gastrocnemius m.
- 23. Deep digital flexor
- 24. Supf. digital flexor

- A. Lat. collateral lig. of stifle
- B. Lat. patellar lig.
- C. Middle patellar lig.
- D. Med. patellar lig.
- E. Calcanean tendon (not shown in ox)
- a. Femur
- b. Popliteus m.
- c. Tibia
- d. Extensor fossa
- e. Patella
- f. Calcanean tuberosity
- g. Soleus m. (not shown in ox)
- h. Trochlear tubercle (horse)



The stay apparatus allows a horse to rest while standing with little muscular activity or fatigue. This ability allows instant action when danger threatens. The horse can then use its evolutionary speed to move away from the threat.

Mechanically, the structures of the stay apparatus bypass tension from the muscle bellies over "non-tiring" connective tissue elements, tendons and ligaments, to bones. This overcomes the tendency of the joints to collapse with minimal energy expenditure.

In the thoracic limb, the **body weight** is suspended from the two scapulae by **tendinous tissue** in the serratus ventralis muscles. The body weight pulls down on the scapula, flexing the shoulder until the tendons running through the biceps brachii stretch taut. The lacertus fibrosus (4), connecting the tendons of the biceps brachii (2) and extensor carpi radialis (5), transmits the rigidity from shoulder to carpi in an unbroken line (of force). The elbow is locked in extension by the collateral ligaments placement behind the joint's rotational axis. The suspensory apparatus and the superficial and deep digital flexor tendons and their accessory ligaments prevent hyperextension of the fetlock and digital joints.

To understand the stay apparatus, first understand how the animal's weight would collapse each joint. Then determine what prevents this from happening at each joint. The shoulder would tend to flex, elbow – flex, carpus – flex or extend, fetlock – hyperextend, and pastern – hyperflex or buckle.

## STAY APPARATUS of the THORACIC LIMB

**SHOULDER FLEXION** – prevented by the tendon of the biceps brachii muscle.

1. **Serratus ventralis**: Fibrous tissue in this muscle suspends the body from the scapulae, like a sling, when the horse is at rest. This causes the shoulder to flex.

2. **Tendon of the biceps brachii**: runs the entire length of the biceps brachii muscle. Flexion of the shoulder ceases when this tendon is stretched taut. The molded tendon of the biceps brachii over the intermediate tubercle plays a part in stabilizing the shoulder joint.

**ELBOW FLEXION** – prevented by placement of collateral ligaments behind (caudal to) the axis of the joint.

3. **Collateral ligaments of the elbow**: the two ligaments on either side of the elbow joint located caudal to the axis of rotation. Once the triceps brachii extends the elbow, an active counterforce is required to stretch the ligaments before flexion can occur. This passively maintains the elbow in extension.

**CARPUS FLEXION** – prevented by the combination of the tendon of the biceps brachii, the lacertus fibrosus, and the tendon of the extensor carpi radialis cranially, and by the flexor tendons and their accessory ligaments caudally.

4. **Lacertus fibrosus**: the tendinous band connecting the tendon of the biceps brachii muscle to the tendon of the extensor carpi radialis muscle, creating an unbroken line of force from shoulder to metacarpus. When the tendon of the biceps brachii is pulled tight, it pulls on the lacertus fibrosus, which in turn directs the tension past the fleshy part to the tendon of insertion of the extensor carpi radialis muscle.

5. **Tendon of the extensor carpi radialis muscle**: crosses the carpus and inserts on the proximal metacarpus. When pulled by the lacertus fibrosus, it maintains the carpus in extension.

**Superficial and deep digital flexor tendons and their accessory ligaments**: pull on the caudal aspect above and below the carpus to help hold it in extension.

**CARPUS HYPEREXTENSION** – prevented by the block shape of the carpal bones and the palmar carpal ligament.

**Block shape of the carpal bones**: prevents the carpal joints from hyperextension.

**Palmar carpal ligament**: holds the palmar aspect of the carpal bones together, preventing hyperextension of the carpal joints.

**FETLOCK HYPEREXTENSION** – prevented by the suspensory apparatus, the extensor branches of the suspensory ligament, and the flexor tendons and their accessory ligaments.

6,7,8. **Suspensory apparatus**: consists of the suspensory ligament, proximal palmar sesamoid bones, and the sesamoidean ligaments. These three subunits act as one structure, preventing hyperextension of the fetlock joint at rest. Interruption of any of these three components will result in dropping of the fetlock joint.

• 6. **Suspensory ligament (interosseous muscle)**: the entirely tendinous muscle extending from the proximal metacarpus to the proximal sesamoid bones. The suspensory ligament has **extensor branches** (12) crossing either side of the fetlock to join the extensor (common) tendon. This junction transfers the tension of the extensor tendon to the suspensory ligament.

• 7. **Proximal palmar sesamoid bones**: located in the middle of the suspensory apparatus.

• 8. **Sesamoidean ligaments**: a number of ligaments running between the sesamoid bones and the proximal and middle phalanges. These counteract the proximal pull of the suspensory ligament and stabilize the fetlock joint as part of the suspensory apparatus. They consist of "X, Y, V" ligaments: the straight (Y), oblique (V), and cruciate (X) sesamoidean ligaments.

9, 11. **Superficial and deep flexor tendons and the common digital extensor muscle** (long digital extensor muscle in the rear limb) (13): support the digital joints, and with the suspensory apparatus, support the fetlock in the resting animal.



**10. Accessory ligament of the superficial digital flexor:** the short tendon arising from the distal radius and joining the tendon of the superficial digital flexor. During rest, this ligament transfers tension in the tendon to the radius before it reaches the muscle belly. Other names for this ligament are the "radial check ligament", "superior check ligament", "proximal check ligament" or "radial head" of the superficial digital flexor muscle.

**12. Accessory check ligament of the deep digital flexor:** a short tendon arising from the palmar carpal ligament (the ligament covering the palmar side of the carpus) and joining the tendon of the deep digital flexor. It transfers the tension in the deep digital flexor tendon to the cannon bone before the tension reaches its muscle belly. It is also called the "distal check ligament" or "inferior check ligament".

**PASTERN JOINT HYPEREXTENSION** – prevented by palmar ligaments, the straight sesamoidean ligament, and the flexor tendons and their accessory ligaments.

**Palmar ligaments:** short ligaments on the palmar aspect of the pastern. Hyperextension is prevented when they are maximally extended.

**Straight sesamoidean ligament:** passes from the proximal sesamoid bones across the pastern joint to the middle phalanx.

**PASTERN JOINT-"DORSAL BUCKLING" (FLEXION)** – prevented by the double attachment of the superficial digital flexor tendon.

**Insertion of the superficial digital flexor tendon:** attaches to the distal part of the proximal phalanx as well as the proximal part of the middle phalanx. This double attachment on either side of the joint prevents flexion or "dorsal buckling" of this joint.




Fig. IV-72 - Horse - Stay apparatus of thoracic limb (schematic)



# STAY APPARATUS

195-Pelvic limb-199

In the pelvic limb, the stifle is stabilized by locking of the patella over the trochlear tubercle of the femur. This patellar lock also indirectly stabilizes the hip joint. The tarsus is held in extension by the connection of the tendinous superficial digital flexor to the femur and calcanean tuberosity. The digits are supported by structures similar to those of the thoracic limb.

the rested limb, shift its weight to the opposite tiring limb, and lock the patella.

**HIP FLEXION** – prevented by the "patellar lock".

Once the patella is locked, the weight of the animal flexes the hip and stifle joints until the medial patellar ligament stops these actions. Thus, the stifle and hip joints are stabilized.

**TARSUS FLEXION** – prevented by the superficial digital flexor.


**Superficial digital flexor (5):** Largely tendinous, its proximal part is a fibrous band (3) connected between the distal end of the femur and the calcanean tuberosity. With the patella "locked", the fibrous band is pulled taut by flexion of the tarsus, keeping the tarsus in extension.

The digital joints are stabilized by similar structures to those in the forelimb. The attachments of the superficial digital flexor to the calcaneus eliminates the need for an accessory ligament.

**STIFLE FLEXION** – prevented by the "patellar lock".

**Patellar lock:** a mechanism that passively immobilizes the stifle joint. Extension of the stifle and contraction of lateral muscles cause the patella (A) and medial patellar tendon to move over the trochlear tubercle (medial ridge of the patellar surface) (B) of the femur. The trochlear tubercle projects between the medial (C) and intermediate (middle) patellar ligaments (D). The weight of the animal then flexes the stifle until the medial patellar tendon is stretched to its limit. This locks the patella over the trochlear tubercle, and immobilizes the stifle. The patellar lock can be accomplished only in one limb at a time. The horse must unlock

Fig. IV-73 - Horse - Dist. sesamoidean ligg., tendons of supf. & deep digital flexor m. removed - caud. view



- a. Middle (oblique) dist. sesamoidean lig.
- b. Supf. (straight) dist. sesamoidean lig.
- c. 3rd phalanx
- d. Supf. digital flexor tendon
- e. Suspensory lig.
- f. Palmar ligg.




Fig. IV-74 - Horse - Patellar ligg. - cran. view

- A. Patella
- B. Trochlear tubercle
- C. Med. patellar lig.
- D. Middle patellar lig.
- E. Lat. patellar lig.
- F. Meniscus






Fig. IV-75 - Horse - Stay apparatus of the pelvic limb (schematic)



1. Ext. abdominal oblique

1a. Aponeurosis of the  
ext. abdominal oblique

7. Linea alba

4. Rectus abdominis

2a. Aponeurosis of the  
int. abdominal oblique

2. Int. abdominal oblique

Fig. IV-76 - Dog - Abdominal mm.,  
supf. dissection - ventr. view

Superficial inguinal ring

- a. Vaginal process
- b. Sartorius m.
- c. Gracilis m.
- d. Ribs
- e. Diaphragm (IV-77)

**Abdominal muscles:** four muscles forming the ventrolateral abdominal wall. Three are flat muscles (external abdominal oblique, internal abdominal oblique, and transversus abdominis) ending in aponeurotic tendons inserting on the linea alba (white line). These aponeurotic tendons form a sheath around the fourth strap-like muscle, the rectus abdominis. All are innervated by ventral branches of the caudal intercostal and lumbar nerves.

**1. External abdominal oblique:** the sheet-like muscle extending from the ribs and thoracolumbar fascia obliquely, caudoventrally to the ventral midline (linea alba), by a wide aponeurosis (ap'oh-nyoo-ROH-sis) (1a).

**Inguinal ligament:** the caudal free edge of the aponeurosis of the external abdominal oblique that extends from the tuber coxae around the iliopsoas muscle to the pubic tendon.

**2. Internal abdominal oblique:** the sheet-like layer deep to the external abdominal oblique muscle, arising from the tuber coxae and thoracolumbar fascia. Most of its fibers pass obliquely cranioventrally, crossing the fibers of the external abdominal oblique muscle at approximately right angles. It inserts on the ribs and the linea alba by an aponeurosis (2a).

**Cremaster muscle (male):** the caudal slip of the internal abdominal oblique muscle. It passes, along with the spermatic cord, through the inguinal canal (pg. 202) and attaches to the vaginal tunic around the spermatic cord and testicle.

**3. Transversus abdominis (trans-VERS-us ab-DOM-i-nis):** the deepest abdominal muscle; arising from the costal arch, ribs, and by an aponeurosis, from the thoracolumbar fascia. Its muscle fibers run transversely (dorsoventrally). It terminates in an aponeurosis (3a) on the linea alba. Its muscular part does not extend






Fig. IV-77 - Dog - Abdominal mm., deep dissection - ventr. view

usually to the inguinal ring.

**Rectus abdominis (REK-tus):** the two long, straight muscles extending from the sternum along the ventral abdomen on either side of the linea alba to the prepubic tendon (5). The aponeuroses of the other abdominal muscles ensheath the rectus abdominis on both lateral and ventral surfaces (external and internal rectus sheath).

## SPECIAL:

**Prepubic tendon:** the tendinous connective tissue mass across the ventral side of the pubic bones serving as the insertion of the rectus abdominis muscles.

**Transversalis fascia (Fig. IV-83):** covers the inner surface of

the transversus abdominis and the rectus abdominis muscles. It extends beyond the caudal edge of the transversus abdominis muscle to form the medial wall of the inguinal canal.

**7. Linea alba:** the fibrous cord formed by the joining of the aponeuroses of the abdominal muscles from both sides. It is on the ventral midline, extending from the xiphoid cartilage to the pelvic symphysis.

## CLINICAL

**8. Rectus sheath:** formed by the aponeuroses of the flat abdominal muscles as they pass on either side of the rectus abdominis muscle. Clinically the external rectus sheath, because of its connective tissue, is the holding layer when closing the abdomen after surgery.



# ABDOMINAL MUSCLES

Abdomen-203




Fig. IV-78 - Horse - Abdominal mm.  
- lat. view

1. Ext. abdominal oblique
- 1a. Aponeurosis of the ext. abdominal oblique
2. Int. abdominal oblique
- 2a. Aponeurosis of the int. abdominal oblique
3. Transversus abdominis
- 3a. Aponeurosis of the transversus abdominis
4. Rectus abdominis
5. Prepubic tendon
6. Transverse fascia
7. Linea alba
8. Deep inguinal ring
9. Supf. inguinal ring

a. Iliopsoas m.  
b. Fascia of the med. thigh




Fig. IV-79 - Horse - Abdominal mm.  
- med. view

**INGUINAL CANAL (ING-gwi-nal)**: the passageway for abdominal structures out of the abdomen. It is a collapsed canal between the deep and superficial inguinal rings. The testicle descends through the inguinal canal just before or after birth (depending on the species) to reach the scrotum.

**8. Deep inguinal ring**: the internal opening of the inguinal canal. Its boundaries:

- Cranially - caudal border of the internal abdominal oblique
- Caudolaterally - inguinal ligament
- Medially - lateral border of the rectus abdominis muscle

**9. Superficial inguinal ring**: the external opening of the inguinal canal. It is a slit in the aponeurosis of the external abdominal

oblique muscle.

**Lateral wall of the inguinal canal**: the aponeurosis of the external abdominal oblique muscle.

**Medial wall of the inguinal canal**: the transversalis fascia and a little of the internal abdominal oblique muscle.

**Structures passing in/out of the inguinal canal**:

- External pudendal artery and vein
- Genitofemoral nerve
- Vaginal process (female)
- Spermatic cord (male)
- Cremaster muscle (male).




Fig. IV-80 - Ox - Abdominal mm. - lat. view




Fig. IV-81 - Ox - Abdominal mm.,  
ext. abdominal oblique m. removed




Fig. IV-82 - Ox - Abdominal mm., peritoneum  
& transverse fascia removed




Fig. IV-83 - Ox - Cross section  
through 4th lumbar vertebra

- |   |  |
|---|--|
| 1. Ext. abdominal oblique                         | 3. Transversus abdominis                         |
| 1a. Aponeurosis for the<br>ext. abdominal oblique | 3a. Aponeurosis for the<br>transversus abdominis |
| 2. Int. abdominal oblique                         | 4. Rectus abdominis                              |
| 2a. Aponeurosis for the<br>int. abdominal oblique | 5. Prepubic tendon                               |
|   | 6. Transversalis fascia                          |
|   | 7. Linea alba                                    |

## CLINICAL

**Hernia:** a protrusion of part of an organ through the abdominal wall.

**Inguinal hernias:** the inguinal canal, a perforation in the abdominal wall, is a weak spot and possible site for hernias. These are common in the horse and pig.

**Umbilical hernias:** common in young animals.

## ABDOMINAL SURGICAL APPROACHES:

**Ventral midline incision:** through the avascular linea alba.


**Paramedian incision:** made lateral and parallel to the midline through the rectus abdominis m.

**Paracostal incision:** made caudal to the last rib and costal arch.

**Paralumbar incision:** made in the paralumbar fossa.



Fig. IV-84 - Dog - Supf. facial mm.  
- lat. view



- ✓ a. Caninus
- ✓ b. Levator labii maxillaris
- ✓ c. Levator nasolabialis
- ✓ d. Orbicularis oculi
- ✓ e. Levator anguli oculi medialis
- ✓ f. Zygomaticus

- g. Frontalis (absent in horse)
- h. Muscles of the ext. ear
- i. Parotidoauricularis
- j. Buccinator
- k. Orbicularis oris

**MUSCLES of the HEAD:** few are of any clinical significance. Some of interest are given below in the different subdivisions of the muscles of the head.

**MUSCLES of FACIAL EXPRESSION:** innervated by motor fibers in the facial nerve (Cn VII). These muscles are mentioned in passing because of their relative clinical insignificance. If the facial nerve (motor nerve) is paralyzed these muscles will be affected and cause distortion to the face. The muscles of the cheek and the lips include the orbicularis oris, caninus, levator nasolabialis, buccinator, mentalis and zygomaticus. The muscles of the orbit, forehead and rostral portion of ear can be considered a muscle complex (orbicularis oculi, frontalis, retractor anguli oculi lateralis et medialis, levator nasolabialis) and are of little clinical significance. The muscles of the external ear are divided into four groups: rostral, dorsal, caudal and ventral. Also of passing interest is the scutulum to which many ear muscles attach. The parotidoauricular muscle (i) of the ventral group is noticeable in all lateral views of the head musculature.

**MUSCLES of MASTICATION:** muscles receiving motor innervation from the mandibular branch of the trigeminal nerve (CN V). They are responsible for chewing (masseter, temporalis, and medial and lateral pterygoid muscles close the jaw; digastricus opens the mouth).

**1. Masseter** (mas-SEE-ter, mas-SE-ter) (G. *maseter* masticator or chewer): the most powerful muscle closing the jaw, covering the ramus of the mandible.

**EXTRINSIC MUSCLES of EYE:** innervated by the oculomotor (Cn III), trochlear (Cn IV) and abducent (Cn VI) nerves. (See pg. 550)

**MUSCLES of the TONGUE:** innervated by the hypoglossal nerve (Cn XII). They are the styloglossus, genioglossus and hyoglossus.

**MUSCLES of the PHARYNX and SOFT PALATE:** innervated by glossopharyngeal (Cn IX) and vagus (Cn X) nerves. These include the muscles in the pharyngeal wall and the two small muscles to the soft palate.

**MUSCLES of the HYOID APPARATUS and LARYNX:** most of intrinsic muscles of the larynx are innervated by the vagus (Cn X) nerve. The strap muscles of the neck (pg. 210) are innervated by the ventral branches of the cervical nerves.

**Dorsal cricoarytenoideus** (FIG. VI-26, 4): the muscle opening the cleft between the vocal folds is innervated by the termination of the recurrent laryngeal nerve (a branch of the vagus nerve).






Fig. IV-85 - Horse - Facial mm., lt. mandible removed




Fig. IV-86 - Ox - Facial mm., deep dissection

a. Caninus  
b. Levator labii superioris  
c. Levator nasolabialis  
d. Frontalis (absent in horse)  
e. Orbicularis oris  
f. Temporalis  
g. Digastricus  
h. Med. pterygoid

i. Lat. pterygoid  
j. Pharyngeal mm. (IV-86)  
j1. Pterygopharyngeus  
j2. Palatopharyngeus  
j3. Stylopharyngeus rostralis  
j4. Stylopharyngeus caudalis  
j5. Hyopharyngeus  
j6. Thryopharyngeus

j7. Cricopharyngeus  
k. Levator veli palatini  
l. Tensor veli palatini  
m. Tongue mm.  
m1. Genioglossus  
m2. Styloglossus  
m3. Hyoglossus

n. Hyoid apparatus mm.  
n1. Geniohyoid  
n2. Thyrohyoid  
n3. Stylohyoid  
n4. Mylohyoid  
n5. Occipitohyoid  
o. Longus capitis






Fig. IV-87 - Horse - Supf. muscles of head

- |                                       |  |                              |                                |
|---------------------------------------|--|------------------------------|--------------------------------|
| 1. Levator labii superioris           | 13. Zygomaticoauricularis                  | 24. Stylohyoideus (IV-89)    | a. Scutiform cartilage (IV-87) |
| 2. Levator nasolabialis               | 14. Scutuloauricularis superficialis       | 25. Longus capitis           | b. Auricular cartilage         |
| 3. Caninus                            | 15. Parotidauricularis                     | 26. Styloglossus             | c. Stylohyoid bone (IV-88)     |
| 4. Orbicularis oris                   | 16. Cervicoauricularis profundus           | 27. Genioglossus             | d. Trachea (IV-89)             |
| 5. Zygomaticus                        | 17. Splenius                               | 28. Hyoglossus               | e. esophagus                   |
| 6. Buccinator, buccal part            | 18. Occipitohyoideus (IV-88)               | 29. Geniohyoideus            | f. Tongue                      |
| 6'. Molar part (deep part) (IV-88)    | 19. Digastricus m., caud. belly, lat. part | 30. Tensor veli palatini     | g. Nasal cartilage 211         |
| 7. Depressor labii inferioris (IV-87) | 19'. Caud. belly, med. part                | 31. Levator veli palatini    |                                |
| 8. Malaris                            | 19". Rostr. belly (IV-89)                  | 32. Pterygopharyngeus        |                                |
| 9. Orbicularis oculi                  | 20. Thyropharyngeus                        | 33. Palatopharyngeus         |                                |
| 10. Levator anguli oculi medialis     | 21. Thyrohyoideus                          | 34. Stylopharyngeus caudalis |                                |
| 11. Frontoscutularis                  | 22. Mylohyoideus                           | 35. Hyopharyngeus            |                                |
| 12. Interscutularis                   | 23. Temporalis (IV-88)                     | 36. Cricopharyngeus          |                                |






Fig. IV-88 - Horse - Muscles of the head,  
second layer




Fig. IV-89 - Horse - Muscles of head.  
deep dissection



# MUSCLES - OX - HEAD

Head-209




Fig. VI-90 - Ox - Supf. muscles of head - lat. view




Fig. IV-91 - Ox - Supf. muscles of head - ventr. view

1. Levator nasolabialis
2. Levator labii superioris
3. Caninus
4. Depressor labii superioris
5. Orbicularis oris
6. Zygomaticus
7. Depressor labii inferioris
8. Mylohyoideus
9. Buccinator, buccal part
- 9' Molar part (IV-92)
10. Malaris (IV-90)
11. Orbicularis oculi

12. Frontalis
13. Frontoscutularis
14. Zygomaticoauricularis
15. Scutuloauricularis superficialis
16. Scutuloauricularis profundus
17. Cervicoscutularis
18. Parotidoauricularis
19. Cleidomastoideus
20. Cleidooccipitalis
21. Digastricus, caud. belly (IV-92)

- 21' Digastricus, cran. belly (IV-93)
22. Stylohyoideus
23. Omohyoideus (IV-92)
24. Splenius
25. Cricopharyngeus (IV-93)
26. Thyropharyngeus
27. Longus capitis
28. Thyrohyoideus
29. Temporalis
30. Lat. pterygoideus
31. Med. pterygoideus
32. Occipitohyoideus

33. Rectus capitis lateralis
34. Obliquus capitis cranialis
35. Longissimus capitis
36. Semispinalis

- a. Parotid salivary gl. (IV-90)
- b. Mandibular salivary gl.
- c. Scutiform cartilage
- d. Facial tuberosity (IV-92)
- e. Stylohyoid bone (IV-93)
- f. Trachea
- g. Wing of atlas






Fig. IV-92 - Ox - Supf. muscles of head, second layer - lat. view





Fig. IV-93 - Ox - Supf. muscles of head, third layer - lat. view



Fig. IV-94 - Dog - Supf. mm. of neck - lat. view



**MUSCLES OF THE NECK:** consist of a number of superficial muscles (platysma, sternothyroid, sternohyoid, trapezius, omotransversarius, serratus ventralis, and brachiocephalicus) and a number of deep muscles (rhomboid, longus colli, longus capitis, rectus capitis, scalenus, semispinalis, longissimus, splenius, and intertransversarii and the omohyoideus in the horse and ruminants).

**1. Sternocephalicus:** extends from the sternum to the head. It is divided in the carnivores, ox and goat; undivided in the pig, sheep, and horse. In each species they are named for their cephalic (head) attachment. In the goat the sternomandibular head attaches to the zygomatic arch and is sometimes called sternozygomaticus.

Carnivores -	sternomastoid (1b) sternooccipitalis (1a)
Ox and goat -	sternomastoid (1b) sternomandibularis (1c)
Pig and sheep -	sternomastoid (1b)
Horse -	sternomandibularis (1c)

**Strap muscles of the neck:** consist of the ventrally located sternohyoid and sternothyroid muscles. They cover the ventral surface of the trachea and are separated in an emergency tracheostomy approach.

**2. Sternohyoid:** the strap-like muscle extending from the first sternebra (manubrium) and first costal cartilage up the neck to insert on the hyoid apparatus (basihyoid bone).

**Sternothyroid:** arises with the sternohyoid and inclines laterally to insert on the thyroid cartilage of the larynx.



**Omohyoideus** (Fig. IV-101, 110): a thin muscle found in the cranial neck of the horse and ox. It is absent in the carnivores. In the horse it separates the external jugular vein from the common carotid artery in the cranial neck, but probably doesn't protect the common carotid from unskilled venipuncture.

## CLINICAL

**Jugular groove:** between the brachiocephalicus and sternocephalicus muscles in the horse and ruminants. The deep wall of the jugular groove is formed by the sternomastoid in the ruminants and the omohyoideus in the cranial part of the neck in horses.



Fig. IV-95 - Horse - Neck mm., brachiocephalicus & omotransversarius removed




211

- A. Brachiocephalicus
- B. Trapezius
- C. Masseter
- D. Deltoid
- E. Rhomboideus (IV-95)
- F. Serratus ventralis cervicis
- G. Longissimus cervicis (IV-96)
- H. Iliocostalis cervicis

- a. Omotransversarius
- b. Trachea (IV-95)
- c. Splenius
- d. Longus capitis
- e. Scalenus
- f. Omohyoideus (absent in carnivores)
- g. Intertransversarii
- h. Semispinalis capitis (IV-96)
- i. Longissimus capitis
- j. Longissimus atlantis
- k. Longissimus thoracis
- l. Iliocostalis thoracis

-96 - Ox - Neck mm., brachiocephalicus, omotransversarius, sternomastoides, sternomandibularis, omohyoid, splenius, serratus ventralis & forelimb removed.





**Fig. IV-97 - Horse - Fascia & muscles of neck cross section (C<sub>4</sub>)**

A-C. Supf. fascia  
A. Supf. layer  
B. Deep layer  
C. Fibrous raphe  
D-F. Deep fascia  
D. Supf. layer  
E. Deep layer  
F. Carotid sheath

a. Nuchal lig.  
b. Lamina nuchae  
c. Vertebra C<sub>4</sub>  
d. Common carotid a.  
e. Recurrent laryngeal n.  
f. Vagosympathetic trunk  
g. Ext. jugular v.

h. Trachea  
i. Esophagus  
j. Semispinalis m.  
k. Splenius m.  
l. Multifidus m.  
m. Longissimus capitis m.  
n. Longissimus atlantis m.

o. Intertransversarii m.  
p. Omotransversarius m.  
q. Longus colli m.  
r. Omohyoideus m.  
s. Cutaneus colli m.

Fig. IV-98 - Horse - Supf. muscles of neck





Fig. IV-99 - Horse - Neck muscles, deep dissection

1. Splenius
2. Cleidocephalicus (cleidomastoideus)
3. Cleidobrachialis
4. Omotransversarius (formerly cleidotransversarius)
5. Obliquus capitis (IV-99)
6. Longus capitis
7. Scalenus medius, dors. & ventr. parts
8. Complexus
9. Longissimus capitis
10. Longissimus atlantis
11. Iliocostalis cervical part

Sternothyrohyoideus

- a. Nuchal lig.
- b. Wing of atlas
- c. Mandible
- d. Trachea
- e. Esophagus
- f. First rib
- g. Manubrium






Fig. IV-100 - Ox - Supf. muscles of neck,  
first layer - lat. view




Fig. IV-101 - Ox - Muscles of neck,  
second layer - lat. view




Fig. IV-102 - Ox - Muscles of neck, deep layer  
- lat. view

- 9. Obliquus capitis cranialis
- 10. Longus capitis
- 11. Omohyoideus
- 12. Scalenus
- 13. Rectus capitis lateralis
- 14. Rectus capitis dorsalis minor
- 15. Rectus capitis dorsalis major
- 16. Rectus capitis ventralis

- 17. Obliquus capitis caudalis
- 18. Spinalis et semispinalis dorsi
- 19. Multifidus cervicis
- 20. Dors. & ventr. intertransversarii
- 21. Longus colli, cervical part
- 21'. Thoracic part






Fig. IV-103 - Dog - Supf. mm. of thorax  
- lat. view

**MUSCLES of the THORAX:** the muscles associated with the ribs, concerned with breathing. They are the internal and external intercostals, levatores costarum, subcostal, rectus thoracis, retractor costae, transversus thoracis, serratus dorsalis, scalenus muscles, and most importantly the muscles of the diaphragm (see pg. 224).

## Breathing:

**Inspiration:** increasing the volume of the thorax, allowing expansion of the lungs. This is facilitated by pulling the ribs forward and displacing the diaphragm caudally into the abdomen. The external intercostals, levatores costarum, rectus thoracis, cranial serratus dorsalis, scalenus and the diaphragm work in inspiration.

**Expiration:** opposite from inspiration, the ribs are drawn caudally, decreasing the transverse diameter and volume of the thorax. The internal intercostals, caudal serratus dorsalis and the diaphragm work in expiration.

## Muscles:

**1. External intercostal muscles:** located in the intercostal spaces, their fibers run caudoventrally between adjacent ribs. They act to expand the thorax (inspiration) by pulling the ribs forward.

**2. Internal intercostal:** the muscles deep to the external intercostal muscles, extending cranioventrally between adjacent ribs roughly perpendicular to the fibers of the external intercostal muscles. They pull the preceding rib caudally, reducing the transverse diameter of the thorax (expiration).

**Transversus thoracis muscle:** located on the floor of the thorax dorsal to the sternum. It can be considered morphologically continuation of the transversus abdominis muscle in the thorax.

**Rectus thoracis muscle (f):** located on the lateral thorax from the third to the first rib. It is the direct continuation of the rectus abdominis muscle.

**Serratus dorsalis cranialis muscle (b):** an insignificant muscle over the dorsal part of the ribs. It pulls the ribs forward during inspiration.

**Serratus dorsalis caudalis muscle(d):** located over the dorsal part of the caudal most ribs, this insignificant muscle pulls the ribs caudally during expiration.

**Scalenus muscle (c):** extends from the cervical vertebrae to the first ribs. It is an inspiratory muscle.







Fig. IV-104 - Ox - Supf. mm. of the thorax - lat. view

Fig. IV-105 - Horse - Thoracic mm., serratus dorsalis removed & ext. abdominal oblique cut



- A. Rhomboideus
- B. Longissimus cervicis
- C. Iliocostalis thoracis
- D. Serratus ventralis
- E. Pectoral mm.
- F. Rectus abdominis
- G. Ext. abdominal oblique
- H. Int. abdominal oblique (IV-104)
- I. Transverse abdominis (IV-105)

- a. Splenius
- b. Serratus dorsalis cranialis
- c. Spinalis
- d. Serratus dorsalis caudalis
- e. Scalenus
- f. Rectus thoracis
- g. Spinalis (IV-105)
- h. Multifidus

- 2. Int. intercostal m.






Fig. IV-106 - Horse - Muscles of the back




Fig. IV-107 - Ox - Muscles of the back, iliocostalis & longissimus removed

**MUSCLES OF THE VERTEBRAL COLUMN (back):** flex (bend forward), extend (bend backward), abduct (bend to the side), adduct (return to midline), and rotate (twist) the backbone. Back muscles can be divided into epaxial and hypaxial muscles.

**Epaxial muscles:** muscles of the back dorsal to the transverse processes of the vertebrae.

**Hypaxial muscles:** muscles below the transverse processes of the vertebrae.

**Flexors of the spine:** the rectus abdominis and the hypaxial muscles (the major and minor psoas and iliacus) flex the spine.

**Extensors of the spine:** the epaxial muscles, including the iliocostalis, longissimus, spinalis et semispinalis, spinalis capitis, multifidi, and intertransversarius muscles.

**1. Iliocostalis:** the most lateral column of the epaxial muscles, extending in overlapping bundles from the crest of the ilium to the transverse processes of the lumbar vertebrae, the ribs (L. costae) and the transverse processes of the cervical vertebrae. They act

together to fix or extend the vertebral column. Alone, they move the column laterally. They also aid in inspiration by pulling the ribs caudally.

**2. Longissimus (lon-JIS-i-mus) (L. longest):** the intermediate column of epaxial muscles extending in overlapping bundles from the iliac crest to the head. It is divided into thoracolumbar, cervical, atlantal and capital parts. It extends the back and neck and the atlantooccipital joint. Alone, they move the back, neck and head laterally.


**3. Transversospinalis system:** the most medial column of epaxial muscles. Its muscle bundles span one or two vertebrae up and down the spinal column.

## CLINICAL


**Dorsal laminectomies:** removal of the dorsal part of the vertebral arch (laminae) to increase room for the spinal cord. To reach the vertebral arch understanding of the epaxial muscles is important.



**Fig. IV-108 - Ox - Supf. back mm.  
- dors. view**



**Fig. IV-109 - Ox - Deep back mm., dors. view**






## MUSCLES - PERINEUM

Beginning-Pelvis-340

Fig. IV-110 - Ox - Male genitalia  
& pelvic diaphragm - lat. view



- A. Prostate gland
- B. Urinary bladder
- C. Vesicular gland
- D. Sigmoid flexum
- E. Bulbourethral gland
- F. Urethral m.
- G. Bulbospongiosus
- H. Ischiocavernosus
- a. Pelvic symphysis
- b. Rectum
- c. 3rd caud. vertebra

**PERINEUM** (per'i-NEE-um): the wall and associated structures closing the pelvic outlet and surrounding the anal and urogenital canals. The deep boundaries are the same as those for the pelvic outlet: dorsal - 3rd or 4th caudal vertebrae, lateral - sacrotuberous ligament, ventral - ischiatic tuberosity and ischiatic arch.

**Superficial boundaries of the perineum:**

- Dorsal - base of tail
- Lateral - sacrotuberous ligament
- Ventral - below vulva (base of udder in ruminants) or base of scrotum (in cats and pigs the scrotum, which is below the anus, is included in the perineum).

**Pelvic diaphragm:** the main muscular component of the perineum for containing the pelvic viscera. It consists of coccygeus and levator ani muscles.

**1. Coccygeus muscle** (kok-SIJ-ee-us): extends from the ischiatic spine of the hip bone to the tail. Along with the levator ani, it pulls the tail between the rear legs.

**2. Levator ani muscles:** two muscles arising from the floor of the pelvic cavity and inserting on the root of the tail to form a sling around the rectum. They act to compress the rectum, initiating defecation.

**3. External anal sphincter:** the striated muscle under voluntary control encircling the anal canal.

**Perineal body** (per'i-NEE-al): the aggregate of fibrous and muscular tissue between the anus and the vulva or the bulb of the penis.

**Ischiorectal fossa:** the space on either side of the anus between the pelvic diaphragm and the sacrotuberous ligament. It is usually filled with fat.

### CLINICAL

**Perineal hernia:** protrusion of an organ or tissue through the perineum. This can be caused by rents in the muscles of the pelvic diaphragm.

**Prolapse of the rectum or of the vagina and uterus:** the protrusion of the rectal mucosa through the anus; or of the vagina and/or uterus through the vulva.

**Perineal laceration:** the tearing of the perineum (which often may include the perineal body) during foaling.







Fig. IV-111 - Horse - Cutaneous trunci mm.  
- lat. view



**CUTANEOUS MUSCLES:** the thin interrupted sheets spread over the body in the superficial fasciae (platysma, cutaneous omobrachialis, cutaneous trunci, and the preputial muscles). These muscles twitch the skin (to remove flies).

**Platysma:** the cutaneous muscle over the neck and face.

**Preputial:** found in man, ruminants, and pigs, over the frontal

**cutaneous colli:** Best developed in the horse, it arises from the

external jugular vein. It is absent in the dog.

**Cutaneous trunci:** covers the side of the trunk and is present in all domestic species, but absent in man.

**Cutaneous omobrachialis:** a continuation of the cutaneous trunci muscle over the shoulder and arm of horses and ruminants.

**Preputial muscles:** cutaneous muscles found in carnivores, ruminants and pigs. All have cranial preputial muscles on the ventral midline connecting to the prepuce. The bull also has caudal preputial muscles.



# MUSCLES - PERINEUM

Fig. IV-112 - Ox - Thoracic limb, supf. fascia - lat. view




Fig. IV-113 - Ox - Prox. forearm, deep fascia - cross section

**FASCIA** (FASH-ee-ah) (pl=fasciae [FASH-ee-ee]): a sheet or layer of fibrous connective tissue that lies deep to the skin or around muscles and various organs of the body.

1. **Superficial fascia or subcutis:** the loose connective tissue lying deep to the skin covering the entire body. Functionally, it provides a storehouse of water and fat, and insulates and protects the body. It allows structures to move easily against each other.

2. **Deep fascia:** the dense connective tissue under the superficial fascia, investing most of the body. Septa, extensions of the deep fascia, extend between muscles to bones, thus, compartmentalize muscles or groups of muscles.

• **Retinaculum** (ret'i-NAK-yoo-lum) pl. retinacula [L. "a rope, cable"]: local thickenings of the deep fascia that hold tendons in place.

## CLINICAL

**Subcutaneous injections:** easily made into the superficial fascia. Because of its looseness, the skin can be pulled away from the body and the injection given.


**Facial planes:** Formed by the deep fascia around muscles, these dictate which way pus or fluid will flow. Pus in one region can migrate down the fascial planes to break out at a distant site, e.g., an infection in the deep neck running along the fascial planes to enter the thorax.

**Surgery:** fascial planes can be used as cleavage planes to reach deep structures relatively free of blood.



## Chapter V

# Digestive System








Fig. V-1 - Ox - Median section of body, viscera & serosa removed

**BODY CAVITIES:** the compartments of the body – thoracic, abdominal, and pelvic. The diaphragm separates the thoracic cavity from the abdominal and pelvic (abdominopelvic) cavities.

**1. THORACIC CAVITY** (toh-RAS-ik): the space within the thorax containing the thoracic organs, the pleura and pleural cavities, the pericardium and pericardial cavity. The cranial thoracic opening (thoracic inlet) (j) is the entrance into the thoracic cavity. It is formed by the first pair of ribs and the vertebrae and sternebrae to which they connect. The diaphragm closes the caudal thoracic opening.

**2. ABDOMINAL CAVITY:** the space within the trunk between the diaphragm and the pelvic cavity.

**3. DIAPHRAGM** (DY-a-fram) (G. *phren*): the dome-shaped muscle separating the thoracic and abdominal cavities, innervated by the phrenic nerve. It is the principal muscle concerned with respiration. Moving cranially or caudally decreases or increases the volume of the thorax during expiration or inspiration, respectively. The diaphragm projects as a dome into the bony

thorax. Therefore, the caudal bony thorax is filled with abdominal viscera. The diaphragm has three major openings between the thorax and the abdomen: the aortic hiatus, the esophageal hiatus, and the caval foramen.

**4. Crura or lumbar part:** the dorsal part of the diaphragm consisting of the right and left crura (sing. = crus). The crura connect to the ventral side of the lumbar vertebral bodies and form the aortic hiatus.

**5. Costal part:** the lateral muscular part of the diaphragm, extending between the thoracic (costal) wall and the tendinous center.

**6. Sternal part:** the ventral muscular part.

**7. Tendinous center:** the V-shaped aponeurotic (tendinous) center of the diaphragm.

**Cupula:** the cranial part of the dome of the diaphragm.






Fig. V-2 - Horse - Diaphragm - thoracic view

Fig. V-3 - Ox - Diaphragm - abdominal view

## OPENINGS INTO THE ABDOMINAL CAVITY:

**8. Aortic hiatus (hy-AY-tus)** (L. general term for a gap, cleft or opening): the opening in the dorsal part of the diaphragm for the passage of the abdominal aorta (also the azygos vein and the thoracic duct). It is formed between the crura and the lumbar vertebrae.

**9. Esophageal hiatus:** located ventral to the aortic hiatus through the crura. The esophagus, the ventral and dorsal vagal trunks, and the esophageal vessels enter the abdomen here.

**10. Caval foramen:** the opening in the center of the diaphragm (tendinous center) for the caudal vena cava.

**Pelvic inlet:** the communication between the abdominal and pelvic cavities.

**Abdominal opening of the uterine tube:** the opening to the outside of the abdominal (peritoneal) cavity in the female (pg.

340). In the male the abdominal cavity is closed.

**11. Inguinal canal:** the cleft through the abdominal wall that allows blood vessels, nerves, and the spermatic cord to pass through the abdominal wall.

**12. Femoral canal:** the opening out of the abdominal cavity to the pelvic limb for passage of nerves and vessels.

**13. PELVIC CAVITY (PEL-vik) or pelvis** (L. basin): the space bounded by the two hip bones, the sacrum, and the first two caudal vertebrae. It contains the rectum, the anal canal, and the pelvic parts of the reproductive and urinary viscera.

**Peritoneal part of the pelvic cavity:** the cranial portion lined by pouches of the abdominal peritoneum.

**Retroperitoneal part:** the caudal portion not lined by abdominal peritoneum.






Fig. V-4 - Dog - Topography of the thoracic & abdominal viscera - lt. view




Fig. V-5 - Dog - Topography of the deep thoracic & abdominal viscera - lt. view






Fig. V-6 - Dog - Topography of the thoracic & abdominal viscera - rt. view




Fig. V-7 - Dog - Topography of the thoracic & abdominal viscera, deep dissection - rt. view






Fig. V-8 - Horse - Topography of the thoracic & abdominal viscera - lt. view




Fig. V-9 - Horse - Topography of the thoracic & abdominal viscera - rt. view






Fig. V-10 - Ox - Topography of the thoracic & abdominal viscera, skin & mm. of the body wall removed - lt. view




Fig. V-11 - Ox - Topography of the thoracic & abdominal viscera, lungs & diaphragm removed, rumen & reticulum opened - lt. view






Fig. V-12 - Ox - Topography of the thoracic & abdominal viscera, skin & mm. of the body wall removed - rt. view




Fig. V-13 - Ox - Topography of the thoracic & abdominal viscera, lungs, diaphragm, greater omentum & mesoduodenum removed - rt. view



# TOPOGRAPHY - OX - RIGHT SIDE

Gen-232




Fig. V-14 - Ox - Topography of the thoracic & abdominal viscera, mediastinum, liver, lesser omentum, rt. kidney, jejunum & reproductive tract removed - rt. view





Fig. V-15 - Ox - Topography of the thoracic & abdominal viscera, ileum, cecum, prox. & dist. ansae of large colon, transverse colon & descending colon & rectum removed - rt. view





**Fig. V-16 - Llama - Topography of the thoracic & abdominal viscera - lt. view**




Fig. V-17 - Llama - Topography of the thoracic & abdominal viscera - rt. view






Fig. V-18 - Dog - Roof of oral cavity

- a. Philtrum (carnivores & small ruminants)
- b. Buccal vestibule (V-19)
- c. Angle of mouth
- d. Palatine ridges (V-18)
- e. Parotid duct opening (not shown in horse or ox)

- f. Palatopharyngeal arch (V-19) (not shown in horse or ox)
- g. Labial vestibule
- h. Palatoglossal arch (not shown in horse or ox)
- i. Palatine tonsil
- j. Frenulum
- k. Incisive papilla




Fig. V-19 - Dog - Floor of oral cavity

**MOUTH (os):** a term designating either the opening between the lips (oral fissure, cleft) or the whole oral cavity.

**ORAL CAVITY:** the space extending from the lips to the pharynx, bounded laterally by the cheeks. It is divided into the oral cavity proper and the vestibule.

**Labial vestibule (g):** the space between the incisors and the lips.

**Buccal vestibule (b):** the space between the cheek teeth and the cheeks.

**Frenulum (j):** the central fold of mucous membrane connecting the floor of the oral cavity and the ventral surface of the tongue.

**1. Sublingual caruncles:** the mucosal elevations on the floor of the oral cavity, under the tongue just caudal to the incisors. The



# ORAL CAVITY




Fig. V-20 - Ox  
- Sublingual floor

Fig. V-21 - Ox - Roof of  
oral cavity




Fig. V-22 - Horse  
- Sublingual floor




Fig. V-23 - Horse - roof  
of oral cavity

mandibular and sublingual salivary ducts open on the caruncles (pg. 259).

2. Interdental spaces (diastemata, sin. = diastema): the spaces between the teeth.

3, 4. LIPS (L. *labium*, sin. = *labia*): the structures bounding the oral fissure. They possess long, tactile hair, and regular hair.

Philtrum (a): the median cleft of the upper lip in carnivores and small ruminants.

Angle of the mouth (c): where the upper and lower lips unite.

5. CHEEK (L. *mala*, *bucca*): the caudolateral wall of the oral cavity.

6. GUMS or gingivae (jin-JI-vee): the oral mucosa over the jaws, enclosing the necks of the teeth.

PALATE: the roof of the oral cavity and oropharynx composed of a rostral bony part (the hard palate) and a caudal musculomembranous part (the soft palate). The palate separates

the respiratory and the digestive passages in the head.

7. Hard palate (L. *palatum durum*): the osseous plate and its highly vascular mucosal covering that separates the oral and nasal cavities. The osseous plate is formed by processes of the palatine, maxillary and incisive bones. The hard palate is bounded rostrally and laterally by the upper dental arch and continues caudally as the soft palate. Just behind the incisors is the incisive papilla (k) onto which the incisive ducts open. The ducts connect the nasal and oral cavity, absent in the horse.

Palatine ridges: six to ten paired elevations crossing the hard palate transversely.

8. Soft palate (L. *palatum molle*): the caudal extension of the hard palate, dividing the rostral region of the pharynx into oral and nasal parts.

## SPECIES DIFFERENCES

9. Dental pad: replaces the upper incisors and canines in ruminants. It provides a heavily cornified epithelium against which the lower incisors grind food.






Fig. V-24 - Dog - Tongue & opened pharynx - dors. view




Fig. V-25 - Horse - Extrinsic mm. of the tongue

- |                                 |   |
|---------------------------------|---|
| a. Esophagus                    | i. Tonsillar fossa (ox)                   |
| b. Laryngeal opening            | j. Filiform papillae                      |
| c. Epiglottis                   | k. Conical papillae                       |
| d. Soft palate                  | l. Fungiform papillae                     |
| e. Palatine tonsil (carnivores) | m. Foliate papillae (absent in ruminants) |
| f. Styloglossal m.              | n. Vallate papillae                       |
| g. Hyoglossal m.                | o. Lenticular papillae (ruminants)        |
| h. Genioglossal m.              |   |

**TONGUE** (*L. lingua*, *G. glossa*): the muscular organ filling the oral cavity. The many papillae (pa-PIL-ee) on its dorsal surface are named according to their shape. These papillae have a mechanical or gustatory (GUS-ta-toh-ree) (taste) function, or both. Filiform (FIL-i-form) papillae (j), covering the tongue's dorsum, are thorn-shaped structures serving the mechanical function of directing food caudally. In the ox and cat they are heavily cornified. Conical (k) and lenticular papillae (o), cone-shaped papillae located on the caudal third of the tongue's dorsum also have a mechanical function. The mushroom-shaped fungiform (FUN-ji-form) papillae (l), scattered among the more numerous filiform papillae, have taste buds and are therefore gustatory as well as mechanical. Foliate papillae (m), a series of leaf-shaped ridges separated by furrows (crypts) on the lateral border of the tongue, are gustatory (absent in the ox). Vallate papillae (n), the largest and least numerous of the papillae, are rostral to the root of the tongue. They are circled by a cleft filled with taste buds. Marginal papillae along the edge of the rostral half of the newborn puppy's tongue function in suckling, helping to prevent milk from spilling over the tongue's sides. They disappear when the diet

changes from milk to solids. The papillae, although interesting, are of little clinical significance (Doc, my dog can't taste sweets anymore!). They, especially the vallate papillae, shouldn't be mistaken for pathology. The tongue, especially in the dog, aids in temperature control through heat loss by panting. The ox's tongue is a prehensile structure for gathering grass.

1. Apex: the rostral free end of the tongue.
2. Body: the major part of the tongue attaching to the mandible.
3. Root: the caudal end of the tongue, attaching to the hyoid apparatus.

## INNERVATION OF THE TONGUE:


**Taste (special sense):** the sense of taste to the rostral two thirds of the tongue is carried over the chorda tympani nerve, a branch of the facial nerve (Cn VII). Taste from the caudal third of the tongue passes by the glossopharyngeal (Cn IX) and vagus (Cn X) nerves.



# TONGUE

Head-338

Fig. V-26 - Horse - Tongue  
- dors. view



4. Torus linguae




Fig. V-27 - Ox - Tongue & opened  
pharynx - dors. view

Sensation (pain, temperature and tactile): carried over the lingual branch of the mandibular nerve (Cn V).

Motor innervation: via the hypoglossal nerve (Cn XII).

**MUSCLES** of the TONGUE can be divided into intrinsic and extrinsic lingual muscles. The intrinsic muscles of the tongue or the lingual muscles proper are the many muscular bundles running in diverse directions to form the bulk of the tongue. They cause subtle changes in the shape of the tongue during swallowing, chewing, and vocalization. The extrinsic muscles of the tongue, anchoring it to the skeleton, are the paired styloglossal (f), hyoglossal (g) and genioglossal (h) muscles; they are responsible for its gross movements. In addition, because the tongue is attached to the hyoid apparatus, the muscles attaching to the hyoid bone (-hyoideus) also move the tongue.

## SPECIES DIFFERENCES

4. Torus linguae (L. *torus* swelling): a round swelling of the caudodorsal surface of the ox's tongue.

5. Lingual fossa or fossa linguae: depression in front of the ox's torus linguae. This is a site of penetration of foreign objects.

**Tongue cartilage:** the dog has a bar of cartilage (lyssa) embedded in the ventral surface of the apex. The horse has a similar structure embedded in the median plane of the dorsal surface.

## CLINICAL

**Bovine tongue:** a prehensile organ, therefore, its amputation should be avoided.






Fig. V-28 - Dog - Canine, low crowned tooth - sagittal section

**TEETH** or *dentes* (sin. = *dens*): perform the principle function of mastication, but also aid in food gathering (prehension) and are formidable weapons in some species.

**Dental arches:** arrangement of teeth into two opposing superior (upper) and inferior (lower) arches. The domestic species have two types of teeth – brachydont and hypsodont.

**Low-crowned or brachydont teeth** (Gr. *brachys* short + *odous* tooth): the simple teeth of man, carnivores, pig, ruminant's incisors and horse's deciduous incisors. They consist of a crown, neck and root.

**1. Crown:** the part projecting above the gum line covered with enamel.

**2. Neck:** the constriction between the crown and the root at the gum line.

**3. Root:** the part below the gum line embedded in the alveoli (bony sockets) of the incisive, mandible or maxillary bones.

**High-crowned or hypsodont teeth** (HIP-so-dont) (Gr. *hypsos* height + *odous* tooth) (evergrowing): the teeth having no distinct neck, as seen in all permanent horse teeth, the ruminant cheek teeth and the tusks of pigs. With the exception of the horse's canine teeth, they continue to erupt throughout life.

**4. Body:** different from low-crowned teeth because of the absence of a neck. Some anatomists divide the body into a crown (the exposed part of the tooth above the gum line) and a body (the embedded part below the gum line).

**5. Root:** the short, proximal part of the tooth.

**STRUCTURE of TEETH:** composed of three substances from outward in – cementum, enamel, and dentin.

**6. Enamel** (ee-NAM-el): the hardest substance in the body.

- Low-crowned (brachydont) teeth: the enamel covers only the crown.

- High-crowned (hypsodont) teeth: enamel envelops the body (crown & body), but not the root.

**7. Dentin** (ivory): a hard substance similar to bone forming the bulk of the tooth and surrounding the pulp cavity.

**8. Cementum** (see-MEN-tum): a thin, bone-like covering.

- Low-crowned (brachydont) teeth: the cementum covers the root only.

- High-crowned (hypsodont) teeth: covers the entire tooth, superficial to the enamel.

**9. Pulp cavity:** the central space of the tooth containing the pulp.






Fig. V-29 - Ox - Incisor, low crowned tooth - sagittal section





Fig. V-31 - Horse - Incisor (high crowned) - sagittal section

- |                      |                |
|----------------------|----------------|
| 1. Crown             | 6. Enamel      |
| 2. Neck              | 7. Dentin      |
| 3. Root (brachydont) | 8. Cementum    |
| 4. Body              | 9. Pulp cavity |
| 5. Root (hypsodont)  |                |

Fig. V-30 - Ox - 4th lower cheek tooth, high crowned tooth - sagittal section



**PULP:** the soft tissue filling the pulp cavity, including sensory nerves, arteries, veins, lymphatics, and primitive connective tissue.

**CUSPS (L. points):** the individual bumps on the occlusal (chewing) surface of teeth.

**ALVEOLI (al-VEE-oh-ly) (sin.= alveolus hollow):** the bony sockets of the incisive, mandible, and maxillary bones in which the roots of teeth are embedded.

**Lamina dura:** the thin shell of dense bone lining the alveoli. It shows up radiographically separated from the tooth roots by the radiolucent periodontal membrane. Radiographic loss of the

lamina dura indicates problems.

**10. PERIODONTAL MEMBRANE (per-ee-oh-DON-tal):** the dense fibrous connective tissue connecting the wall of the alveoli and the cementum covering the teeth.

**GOMPHOSIS (gom-FOH-sis):** the proper name for the implantation of teeth in the alveoli. This is not a true joint because the teeth are not part of the skeleton.

**"OVERSHOT" (prognathia):** an elongated jaw (mandible).

**"UNDERSHOT" (brachygnathia [brak-ig-NAY-thee-ah]):** a shortened jaw (mandible).






Fig. V-32 - Dog - Skull - lat. view

a. Lingual surface  
b. Vestibular surface  
c. Contact surface




Fig. V-33 - Dog - Upper arcade

**INCISORS, CANINES, PREMOLARS and MOLARS:** The teeth are divided into groups by their location and function: incisors, canines, premolars and molars. Each tooth has a number of surfaces. The vestibular surface (b) faces the lips or cheeks. The lingual surface (a) faces the tongue. The contact surface (c) is the side adjacent to the next tooth. The mesial contact surface faces the median plane on the incisors, and rostrally on the canine and cheek teeth. The distal contact surface faces away from the median plane on the incisors, and caudally on the canine and cheek teeth.

**1. Occlusal or masticatory surface** (L. *occlusio* to close up): faces the opposite dental arch and is where "chewing" takes place.

**I. Incisors (I)** (cutters): the rostral-most teeth embedded in the incisive bone (upper) and the mandible's incisive part (lower).

**C. Canine (C)** (L. *canis* dog) (piercers): the large tooth between the incisors and the cheek teeth.

**Cheek teeth (grinders):** a general term for the teeth caudal to the canine and incisors in the maxillary

**P. Premolars (P):** the rostral cheek teeth.

**M. Molars (M):** the caudal cheek teeth.

**DECIDUOUS and PERMANENT TEETH:** the two sets of teeth in all the domestic species. The eruption of both groups is orderly and may be used to estimate the animal's age.

**Deciduous dentition:** the "baby teeth" ("milk teeth") developing early in life, giving the young animal a functional set of teeth. They are smaller and fewer in number than the permanent dentition.

**Permanent dentition:** the second set of teeth replacing the deciduous dentition as the jaw lengthens. They must last the life of the animal.

## SPECIES DIFFERENCES

**2. Carnassial (sectorial) teeth:** the large, shearing teeth of both the dog and cat. They are the upper 4th premolar (P4) and the lower 1st molar (M1).

**Tusks (Fig. V-43):** the canine teeth of the pig. The lower tusks are larger than the upper, and the boar's are larger than the sow's.

**3. "Wolf teeth":** the horse's rudimentary upper first premolars. They are usually absent.



Fig. V-34 - Ox - Skull of 6 mo. old animal - lat. view





Fig. V-35 - Ox - Skull of mature animal - lat. view




Fig. V-36 - Horse - Skull - lat. view

# CLINICAL

**Carnassial tooth abscess (Upper P4):** results in swelling or draining (pus) below the carnivore's eye. Since it has three roots in both the dog and the cat it should be split when they are extracted. If not, because the roots diverge, a root may break off.

**"Needle teeth":** the pig's deciduous third incisors (Di3) and

canines (Dc). They are often "nipped" off in newborn pigs for the sow's benefit during suckling.

**"Floating":** the filing off of sharp edges (points) of the horse's cheek teeth.






Fig. V-37 - Dog - Upper arcade




Fig. V-38 - Dog - Lower arcade

**DENTAL FORMULA:** a shorthand representation indicating the number of teeth of an animal. Due to bilateral symmetry, only half of each dental arcade is numbered in the formula's parenthesis. The total number in the parentheses multiplied by the "2" gives the total number of teeth. The permanent teeth are represented by capital letters (Incisors=I, Canines=C, Premolars=PM or P and Molars=M). In the fraction following each letter, the numerator represents half the number of upper jaw teeth and the denominator half those in the lower jaw.

**DECIDUOUS DENTAL FORMULA:** identical to the permanent formula except the premolar one (Pm 1) and the molars have no predecessors. Deciduous teeth are represented by lower case letters following a "D".

**SPECIES DIFFERENCES:** The generalized pattern of 44 permanent teeth is seen only in the pig. The other domestic species have fewer teeth due to reduction in the number of cheek teeth, except the ruminants which are also missing the

upper incisors and canines. If premolars are missing, the more rostral ones are affected; if molars, the more caudal ones are affected (P4 is always next to M1).

**Pig:** has a full mouth of 44 permanent teeth.

**Dog:** missing upper M3 and therefore, has 42 teeth. Brachiocephalic breeds may be missing more teeth, so the dental formula for dogs is not constant, as it is in cats.

**Horse:** usually missing the upper P1 (wolf tooth) and always missing lower P1. In the mare, the canines often are small and may not erupt. With all these variations, the horse may possess from 36 to 42 permanent teeth. There are no deciduous canines, thus, only 24 deciduous teeth.

**Ruminants:** missing the upper incisors and canines; replaced by a dental pad. They also lack upper and lower P1, giving them 32 permanent teeth.

Fig. V-41 - Ox - Upper arcade of 3 yr. old animal




Fig. V-39 - Horse - Upper arcade

Fig. V-40 - Horse - Lower arcade

"Wolf tooth" (P<sub>1</sub>)




Fig. V-42 - Ox - Lower arcade - 7 yr. old

Species	Permanent	Deciduous
PIG	$2(I\ 3/3\ C\ 1/1\ P\ 4/4\ M\ 3/3) = 44$	$2(I\ 3/3\ C\ 1/1\ P\ 3/3) = 28$
DOG	$2(I\ 3/3\ C\ 1/1\ P\ 4/4\ M\ 2/3) = 42$	$2(I\ 3/3\ C\ 1/1\ P\ 3/3) = 28$
HORSE	$2(I\ 3/3\ C\ 1(0)/1(0)\ P\ 3(4)/3\ M) = 36-42$	$2(I\ 3/3\ C\ 0/0\ P\ 3/3) = 24$
RUMINANT	$2(I\ 0/4\ P\ 3/3\ M\ 3/3) = 32$	$2(I\ 0/4\ P\ 3/3) = 20$
CAT	$2(I\ 3/3\ P\ 3/2\ M\ 1/1) = 30$	$2(I\ 3/3\ C\ 1/1\ P\ 3/2) = 26$



# TEETH

Head-245

Different diets of the domestic species have resulted in evolution of different forms of teeth. The carnivores tear and bolt their fleshy food with little chewing. Their teeth reflect this in being sharp, tearing structures. The molars of the dog, which do more chewing than the cat, have a flattened occlusal surface. For the horse and ruminant's grazing diet (herbivores), the cheek teeth have enlarged and merged into a continuous occlusal surface. This accommodates the continuous grinding mastication with considerable wear.

Pig - aging teeth	Eruption
DI3	Before birth
Dc	Before birth
Remaining deciduous teeth	4 days - 7 wk.
Permanent	
P1	5 mo.
M1	4-6 mo.
Remaining permanent teeth	8-20 mo.

Fig. V-43 - Pig - Upper arcade





Fig. V-44 - Pig - Lower arcade



Dog - Aging teeth	Age
Deciduous teeth erupt	By 6 weeks
Permanent teeth erupt	By 6 months
Cusps worn of incisors	
Lower I1	1 1/2 yrs.
Lower I2	2 1/2 yrs.
Upper I1	3 1/2 yrs.
Upper I2	4 1/2 yrs.
Lower I3	6 yrs.
Incisors absent	16 yrs.
Canines absent	20 yrs.

**CANINE DECIDUOUS DENTITION:** For the first 3 weeks of life, the puppy has no teeth. By 6 weeks all its deciduous teeth have erupted. As the puppy's jaw grows the permanent teeth begin to replace the deciduous teeth and have all erupted by 6-7 months. This is useful information because puppy shots are usually given around 6 weeks and around 6 months dogs are spayed. There are no deciduous premolars for P1 and the molars.




Fig. V-45 - Cat - Upper arcade




Fig. V-46 - Cat - Lower arcade

## CLINICAL

Fig - Di3 and Dc ("needle teeth") erupt before birth and are often nipped off to prevent injuries to others.

### Roots of cheek teeth:

**Dog -** This is important in teeth extractions.

Upper

1st 1 has 1

Next 2 have 2

Last 3 have 3

Lower

First and last has 1

The rest have 2

**Cat -** three roots are found in upper P4 (carnassial tooth) and in upper Dp3 and Dp4.

## Cat - Aging Teeth

Deciduous teeth erupt	6 wks. (2 - 8 wks.)
Permanent teeth erupt	by 6 mo.



# HORSE TEETH

Head-247

**HORSE TEETH (adult):** typically herbivorous (grass eating) dentition with high crowned (hypsodont) teeth that, except for the canines, grow throughout life.

**HORSE INCISORS:** are numbered I1, I2 and I3 or central, intermediate, and corner incisors respectively. Each incisor is curved with the concavity on its lingual side.

**I1. Central incisor:** the 1st incisor, closest to the median plane.

**I2. Intermediate incisor:** the 2nd incisor.

**I3. Corner incisor:** the 3rd, most lateral incisor.

**STRUCTURE:** the horse's incisors are composed of three substances - dentin, enamel and cementum. With wear, the different structures on the occlusal surface of the teeth appear, giving clues to the age of the animal.

**Eruption:** the emergence of a tooth through the gum line.

**1. Cup, infundibulum or "mark":** the deep depression in the occlusal surface, lined by cementum and enamel. The cup is usually filled with black decaying material.

**2. Enamel spot:** the enamel at the bottom of the cup. When the cup is worn away, the spot remains for a while. Harder than the surrounding dentin, it is raised above the dentin.

**3. Dental star:** the darker, secondary dentin filling the pulp cavity as the occlusal surface nears it. The star first appears rostral to the enamel spot. As the spot disappears, the star becomes centrally located.

**In wear:** the removal of enamel due to contact of opposing teeth. A small area of yellow dentin surrounded by white enamel results.

**Level:** the flattening of the occlusal surface, showing the formation of two enamel rings separated by dentin. The outer enamel ring surrounds the entire tooth and the inner ring the infundibulum (cup).

**SHAPE OF THE OCCLUSAL SURFACE - INCISORS:** changes with age due to the long, curved, pyramidal shape of the incisors. The distal end is flattened rostrocaudally. The base is flattened from side to side. As the teeth wear, the shape of the occlusal surface changes. The young animal has a transverse oval surface. With wear it becomes round, then triangular, and finally longitudinally oval or rectangular.

**CHEEK TEETH:** premolar and molar teeth. They are rectangular with infoldings of enamel on their occlusal surface. Together they form a continuous grinding surface. They continue to grow after they come into wear. Isolated cheek teeth are indistinguishable from each other, except for the wolf tooth, P2 and M3. The upper arcade is wider than the lower causing wear to occur on the

inside (lingual edge) of the upper teeth and on the outside (labial edge) of the lower teeth resulting in "points" on the outside edge of the upper teeth and inside edge of lower teeth. The occlusal surface slants down and out (ventrobuccally).




Fig. V-47 - Horse - Cross section through 5th upper cheek tooth & 6th lower cheek tooth

Horse - Cheek teeth	
Teeth	Eruption
P1	5-6 mo.
P2	2-2 1/2 yrs.
P3	3 yrs.
P4	4 yrs.
M1	1 yrs.
M2	2 yrs.
M3	3 1/2-4 yrs.

## CLINICAL

**"Floating":** the periodic filing off of the points of a horse's cheek teeth.

**Points:** - Outside edge of the upper teeth  
Inside edge of the lower teeth


**Cap:** a deciduous tooth remaining attached to its permanent replacement. The only teeth affected are Dp2, Dp3 and Dp4.

**Memory aid:** Since the deciduous premolars are roughly replaced the year corresponding to their number, expect to see caps at those times.

Dp2 cap	2 to 2 1/2 years
Dp3 cap	3 years
Dp4 cap	4 years



Fig. V-48 - Horse - 1st incisor - sagittal section & occlusal surface



## HORSE TEETH - TERMS

**Scissor mouth:** when viewed from the front, an oblique angle to the incisors' occlusal surface due to uneven wear.

**Sow mouth:** an elongated mandible ("overshot" or prognathia).

**Parrot mouth:** a shortened mandible ("undershot" or brachygnathia).

**Shear mouth:** a narrow lower dental arch requiring frequent

floating (knocking off of points).


**Step mouth:** an uneven occlusal plane of the cheek teeth due to lack of wear of one or more of the teeth.

**Wave mouth:** a subtle form of step mouth.

**Bishoping:** the altering of an older horse's teeth to make it look younger. A common technique is drilling and staining false cups.



Fig. V-49 - Horse - Incisors - rostr. view



- A. Two year old, deciduous incisors  
B. Five year old, permanent incisors




Fig. V-50 - Horse - Incisors of 11 yr. old animal - lat. view




Fig. V-51 - Horse - Incisors - lat. view

- C. Five year old  
D. Twenty-five year old

**ROUGH ESTIMATE of a HORSE'S AGE:** Certain structures and appearances can give an estimate of the horse's age. They are unreliable and should be used in conjunction with eruption and wear times.

**Angle of the permanent incisors:** the angle the upper and lower incisors meet when viewed from the side. Because of the incisor's curved shape, more pronounced on its proximal end, the angle formed by opposing incisors is roughly  $180^\circ$  in a young animal. With age, wear makes this angle more and more acute ( $< 180^\circ$ ).

**1. Seven year (incisive) hook:** the bulge on the caudal end of the upper corner incisor. It forms because the bottom corner

incisor doesn't wear the entire occlusal surface of the upper one. The hook is said to appear at 7 years, disappear at 9 years and reappear at 11 years of age. It may or may not be present. If present, all that can be said is that the horse is probably older than 7 years (unreliable).

**2. Galvayne's groove:** a long groove on the middle of the upper corner incisor's labial surface. Wear from the lips removes the cementum of the tooth, except in the groove, leaving the white enamel surrounding the darker cementum in the groove. The groove is said to appear under the gum line at 10 years of age, half way down the tooth at 15, reaches the occlusal surface at 20, and disappears at 30. If present, the horse is probably over 10 years old. (Very subjective and unreliable.)



# DECIDUOUS INCISORS - HORSE


Head-250




8 Days



8 Wks.



2 Yr.



8 Mos.

Fig. V-52 - Horse - Deciduous incisors  
- occlusal surface

## DECIDUOUS INCISORS

	Di <sub>1</sub> (central)	Di <sub>2</sub> (intermediate)	Di <sub>3</sub> (corner)
Erupts	8 days	8 weeks	8 months
In Wear	1 year	1 year	2 years

**AGE of the NEWBORN HORSE:** deciduous incisors, smaller than permanent incisors, have a definite neck (low crowned - brachyodont teeth). A horse with deciduous incisors is less than 2 1/2 years of age. For easy recall, 8 days, 8 weeks, and 8 months

or 7-7-7 can be used for eruption of Di1, Di2 and Di3, respectively (1 week, 1 month and 8 months is more correct). At 1 year, Di1 and Di2 come into wear. At 2 years, Di3 is in wear.



**AGING a HORSE by the LOWER INCISORS:** The most definitive age of a horse is its birthday. If unknown, use eruption and wear of the lower incisors to estimate its age. The lower incisors are used because of accessibility (the upper incisors only increase difficulty without increasing accuracy). Due to individual variation and feed types, you must avoid being definitive. Thus, a horse should be said "to have the teeth of a horse of a certain age", not that the horse is so many years old. The major student pitfall is wanting to give the minute of birth and the phase of the moon. The following scheme will allow you to give valuable information to the horse owner. You will be able to tell him that the four year old horse he just bought is over ten. It will not make you an expert, but even a small animal practitioner can remember and use it at a Texas barbecue. To become an expert requires aging many horses and developing a feel (the art of aging). The *Official Guide for Determining the Age of the Horse* edited by Davis is a must to the expert.

**DECIDUOUS or PERMANENT:** Spread the horse's lips to see the incisors. First determine if the incisors are permanent or deciduous. If no permanent incisors have erupted, the horse has the teeth of a horse under 2 1/2 years old (see pg. 249). Students have the most problem with differentiating deciduous from permanent incisors. Deciduous incisors have a distinct neck, are smaller and usually lack the longitudinal ridges found on the labial surface of permanent incisor.

#### NO PERMANENT INCISORS - UNDER 2 1/2

**ERUPTION TIME:** The tooth breaking through the gum to become visible is the most accurate "estimate" of age. A common student pitfall is ignoring a tooth that has just broken through (can't be a "little" erupted or a "little" pregnant). Newly erupted permanent incisors will be covered by yellow cementum, lack a neck and be much larger than their deciduous counterparts.

**ERUPTION - I1 - 2 1/2 years**  
**I2 - 3 1/2 years**  
**I3 - 4 1/2 years**

Once the upper and lower incisors are in contact, the mouth must be gently opened to view the occlusal surface. Hold the lower lip and jaw and place a finger in the space behind the incisors (interdental space).

**IN WEAR:** when the occlusal surfaces are in contact, rubbing off the cementum and enamel to show dentin. This occurs approximately 6 months after eruption. If all the lower incisors are erupted and I3 is in wear (dentin seen on its occlusal surface), the horse has the mouth of a 5 year old. If all lower incisors are not erupted, then add 6 months to the eruption times of those present.

**IN WEAR - I1 - 3 yrs**  
**I2 - 4 yrs.**  
**I3 - 5 yrs.**

**LEVEL:** wear has flattened the occlusal surface, indicated when there are two enamel rings separated by dentin. Since this is hard to see in a live, moving horse, use the disappearance of cups rather than level times.

**CUP GONE:** disappearance of the infundibulum. It is unreliable due to variability in depth. I3 is very unreliable. The ease of seeing the cup gone (no black decayed material in it) makes it preferable to leveling times.

**CUP GONE - I1 - 6 yrs.**  
**I2 - 7 yrs.**  
**I3 - 8 yrs.**

Eruption, in wear, and cup gone times are the most accurate indicators of age, in that order. The data below is less accurate and should be disregarded if they conflict with the above.

**DENTAL STAR:** appearance is unreliable, a dental star (or what appears to be a dental star - staining) may appear at any age. Instead, next use cup gone for the upper incisors or rounding of the occlusal surface which occur at the same time.

**ROUND:** refers to the shape of the occlusal surface, which actually appears triangular. "Round" means the transverse diameter equals the longitudinal diameter. This is hard to determine, so for ease, check the disappearances of the cups in the upper incisors.

**CUP GONE - UPPER INCISORS:** are easily detected because the disappearance of the dark mark is apparent.

**CUP GONE** **I1 - 9 yrs.**  
**UPPER INCISORS** **I2 - 10 yrs.**  
**I3 - 11 yrs.**

**TRIANGULAR:** when the longitudinal dimension becomes greater than the transverse dimension of the occlusal surface (unreliable). This occurs at 16 and 17 years for I1 and I2, respectively. (I3 is very unreliable).

**TRIANGULAR I1 - 16 yrs.**  
**I2 - 17 yrs.**

**ENAMEL SPOT:** supposed to disappear from the occlusal surfaces between 13 and 16 years (unreliable).

**RECTANGULAR (longitudinally oval):** when the longitudinal direction is much larger than the transverse diameter.

**RECTANGULAR - over 18 yrs.**






Fig. V-53 - Horse - Incisors of 2 1/2 yr. old






Fig. V-54 - Horse - Incisors of 3 1/2 yr. old




These are all estimates in order of their reliability. When you are first stopped by any wear data, do not check later age indicators. An example: If I3 is not in wear (not 5 years yet) but the cup is gone from I1 (6 years), the horse is not yet 5 years old, much less 6. Most students want to look at the teeth for a minute and come up with a number (e.g., 13 yrs, 5 mo. 4 dys. 2 hrs. 5 min. 3sec.). Aging over 10 is really an art and should be given in ranges (e.g., a horse with all cups gone but no triangular teeth has the mouth

of a horse between 11 and 16). I have my students count out loud as they go through the aging indicators. Though you may feel silly, the numbers will start to flow in order and repetition will make it second nature. As a practitioner when a teenage horse owner asks what you are counting, explain and attempt to teach them the method. They will appreciate your effort and have their dad call you back next time "Flicka" has a problem.







**Fig. V-56 - Horse - 2 yrs.**  
- all deciduous in wear




**Fig. V-58 - Horse - 3 1/2 yrs.**  
- I2 erupted




**Fig. V-60 - Horse - 5 yrs.**  
- I3 in wear



**Fig. V-57 - Horse - 2 1/2 yrs.**  
- I1 erupted



**Fig. V-59 - Horse - 4 1/2 yrs.**  
- I3 erupted



**Fig. V-61 - Horse - 6 yrs.**  
- I1 cup gone

## Counting and aging

- Deciduous - under 2 1/2 yrs.
- Deciduous - erupted, 8 days, 8 weeks 8 months
- Deciduous - in wear, 1, 1, 2 years
- Permanent - erupted, 2 1/2, 3 1/2, 4 1/2
- Wear, 3, 4, 5
- Cups gone, lower, 6, 7, 8
- Upper cups gone, 9, 10, 11
- Triangular, 16, 17
- Rectangular, over 18
- Older, count on a crystal ball.



# AGING HORSE INCISORS

Head-254




Fig. V-62 - Horse - 7 yrs.  
- I2 cup gone



Fig. V-64 - Horse - 10-11 yrs.  
- I2 round




Fig. V-63 - Horse - 9 yrs.  
- I1 round




Fig. V-65 - Horse - 16 yrs.  
- I1 triangular




Fig. V-66 - Horse - 18 yrs. - rectangular

## The Age Of A Horse

To tell the age of any horse,  
Inspect the lower jaw, of course;  
The six front teeth the tale will tell,  
And every doubt and fear dispel.

Two middle nippers you behold  
Before the foal is eight days old;  
Before eight weeks, two more will come.  
Eight months the corners cut the gum.

The outside enamel will disappear  
From the middle two in just one year;  
Also one year for the second pair -  
In two years corners too will wear.

At two and a half the middle nippers drop;  
At three and a half the second pair can't stop;  
When four and a half the third pair goes,  
At five a new worn set he shows.

The deep black spots will pass from view  
At six years, from the middle two;  
The second pair at seven years,  
At eight the spot each corner clears.

From middle nippers upper jaw,  
At nine the black spots will withdraw;  
The second pair at ten are bright,  
Eleven finds the corners light.

As time goes on the horsemen know  
The oval teeth three-sided grow;  
They longer get, project before,  
Till twenty - when we know no more.

ANONYMOUS (modified)

HORSE - AGING - PERMANENT INCISORS			
	Center incisor	Middle incisor	Corner incisor
Eruption	2 1/2	3 1/2	4 1/2
In wear	3	4	5
Level	5	6	7
Cup gone (lower)	6	7	8
Dental star	8	9	10
Cup gone (upper) or round (lower)	9	10	11
Enamel spot gone	13	-	16
Triangular	16	17	16-17
Rectangular	18	19	20-21



# OX INCISORS

Head-255

**RUMINANT INCISORS** (low crowned [brachydont] teeth): There are four lower incisors (the canine being considered an incisor). The upper incisors are absent, replaced by the dental pad.

**I4. Canine:** looks like and located with the incisors, is considered the 4th incisor (I4).

**Dental pad:** a cornified connective tissue elevation replacing the upper incisors. It serves to oppose the lower incisors.

**SHAPE:** The incisors have a crown with a distinct neck and a round root (low-crowned [brachydont] teeth).

## SURFACES:

**1. Longitudinal ridges:** serrations marking the lingual surface.

**2. Occlusal surface:** contacting the dental pad, and appearing when the teeth come into wear. Its lingual border is at first wavy due to longitudinal ridges.

**LEVEL:** when the occlusal surface is not wavy, due to wear past the longitudinal ridges.

**AGING the OX by its INCISORS:** All of the ox's deciduous incisors have erupted by birth. They may still be covered by a thin pink membrane. By two weeks, the gums have receded to the neck of I1. At one month, all the incisors' crowns are exposed. Eruption of the permanent incisors I1, I2, I3 and I4 occurs by 1 1/2 - 2, 2 - 2 1/2, 3, and 4 years, respectively. All the incisors are in wear by 5 years. I1, I2, I3 and I4 become level at 6, 7, 8, and 9 years, respectively. By 15 years of age the crowns of those incisors remaining are worn off, leaving round "pegs".

**"Pegs":** the roots of the incisors when the crowns have been completely worn away.

**"Broken mouth":** when the crowns of the incisors are worn off leaving the pegs (roots) or some incisors are missing. This reduces the cattle's grazing efficiency, and often result in their being culled (removal from the herd).

**"Pearls":** the roots of the incisors worn down to the gums.

## ERUPTION of the LOWER INCISORS of the OX

**Birth:** All deciduous incisors have erupted at birth.

**2 weeks:** The crown is exposed on I1.

**1 month:** All the incisor crowns are exposed.

**SHEEP and GOAT:** the eruption of the numbered permanent incisors roughly corresponds to their age. I1 - 1 to 1 1/2 yrs.; I2 - 1 1/2 to 2 yrs.; I3 - 2 1/2 to 3 yrs.; I4 - 3 to 4 yrs.

**SUMMARY:** To roughly estimate the age of ruminants (cattle, sheep and goats) count the number of erupted permanent incisors for age in years. To be more correct with cattle, add one year to the first incisor - I1 - 2, I2 - 2, I3 - 3 and I4 - 4 years. If all incisors have erupted and are in wear, say 5 years. (see chart pg. 257)

## RUMINANT - AGING PERMANENT INCISORS

I1	1yr.
I2	2 yrs.
I3	3yrs.
I4	4 yrs.




Fig. V-67 - Ox  
- Deciduous incisors




Fig. V-68 - Ox  
- Permanent incisors




Fig. V-69 - Ox - 4th lower cheek tooth - sagittal section & occlusal surface






Fig. V-70 - Ox - 1 1/2-2 yrs. - I1 erupted




Fig. V-71 - Ox - 2-2 1/2 yrs. - I2 erupted




Fig. V-72 - Ox - 3 yrs. - I3 erupted




Fig. V-73 - Ox - 4 yrs. - I4 erupted




Fig. V-74 - Ox - 5 yrs. - all in wear




Fig. V-75 - Ox - 6 yrs. - I<sub>1</sub> level




Fig. V-76 - Ox - 7 yrs. - I<sub>2</sub> level




Fig. V-77 - Ox - 8 yrs. - I<sub>3</sub> level




Fig. V-78 - Ox - 9 yrs. - I<sub>4</sub> level




Fig. V-79 - Ox - 15 yrs. - missing or pegs


Teeth	Eruption	In wear	Level & Neck Emerged from Gum	Incisors Not Missing Reduced to Pegs
First Incisor (I <sub>1</sub> )	1 1/2 - 2 yrs.	All at 5 yrs.	6 yrs.	15 yrs.
Second Incisor (I <sub>2</sub> )	2 - 2 1/2 yrs.		7 yrs.	
Third Incisor (I <sub>3</sub> )	3 yrs.		8 yrs.	
Fourth Incisor (canine)(I <sub>4</sub> )	3 1/2 - 4 yrs.		9 yrs.	



# SALIVARY GLANDS

Head-259

Fig. V-80 - Dog - Head - lat. view



**SALIVARY GLANDS:** the extramural glands (glands outside the wall of the digestive system) emptying into the digestive system via ducts. The preparation of food (ingesta) for swallowing begins with lubrication and wetting by salivary secretions, saliva (sa-LY-va). Saliva consists primarily of water, some protein, glycoprotein, a significant amount of electrolytes, and antibodies (IgA). Salivary glands are classified by size, duct length, and by secretions. Secretions can be serous, mucous (MYOO-kus), or mixed (both). The parotid salivary gland has predominantly a serous secretion; the mandibular and sublingual are mixed. Parasympathetic and sympathetic ANS nerve fibers innervate the salivary glands.

**MINOR SALIVARY GLANDS:** located in the wall of the oral cavity and oral pharynx, having very short ducts. They are named based on location, i.e., labial, buccal and lingual (lips, cheek, and tongue). The minor salivary glands are only locally important.

**MAJOR SALIVARY GLANDS:** located some distance from the oral cavity and empty their secretions via long ducts.

1. Parotid (pa-ROT-id) (G para, near +eotis, ear) salivary gland: the unencapsulated, lobular gland below the auricular (ear) carti-

lage.

2. Parotid duct: pierces the cheek mucosa to drain its serous fluid into the buccal vestibule.

3. Mandibular salivary gland: the encapsulated, round or oval gland located caudal to the angle of the jaw. It is a mixed gland.

4. Mandibular duct: runs rostrally with the major sublingual duct, medial to the mandible under the floor of the mouth. It opens on or near the sublingual caruncle.

5. Sublingual salivary gland: the gland under the tongue having polystomatic and monostomatic parts. The polystomatic part (c) consists of diffuse clusters of glandular tissue on either side of the tongue, each cluster with its own duct. The monostomatic part (d) is caudal to the polystomatic sublingual gland, and rostral to the mandibular salivary gland. The monostomatic part and the mandibular salivary gland share a common capsule in the carnivores. The major sublingual duct accompanies the mandibular duct to the sublingual caruncle, where they open either together or separately.






Fig. V-81 - Dog - Head, deep dissection of mandibular & sublingual glands - lat. view

## SPECIES DIFFERENCES

**8. Zygomatic gland:** the large buccal glands medial to the zygomatic arch in carnivores. Its duct opens caudal to the parotid duct opening.

**Sublingual glands:** The dog and cat have a caudally-located monostomatic part and a rostrally-located polystomatic part. The horse has only a polystomatic part. The ruminants have both parts, but they have reversed positions, the monostomatic part being rostral to the polystomatic part.

### Parotid duct opening:

- Dog - across from the upper carnassial tooth (P4)
- Ox - across from the last or 5th upper cheek tooth
- Horse, goat and pig - across from the 3rd upper cheek tooth
- Cat - across from the 2nd upper cheek tooth

### Parotid duct's path:

- Carnivores and usually small ruminants: crosses the lateral surface of the masseter muscle.
- Horse, ox and pig: courses ventrally to the inside of the mandible and then onto the cheek with the facial vessels.

- a. Masseter m.
- b. Buccal m.
- c. Polystomatic part (V-81)
- d. Monostomatic part
- e. Major sublingual duct
- f. Parotid duct opening
- g. Zygomatic duct opening (carnivores)
- h. Sublingual caruncle

**LYMPH NODES:** lymphoid tissue often associated with the salivary glands of the same name.

**6. Parotid lymph node:** a small node near the rostral edge of the parotid gland. These drain the orbit and dorsal structures of the head.

**7. Mandibular lymph nodes:** two to four palpable nodes rostroventral to the mandibular salivary gland. These drain the ventral structures of the head.

**Retropharyngeal lymph nodes:** consist of medial and lateral groups of nodes. The medial retropharyngeal ones are located on the roof of the pharynx; the lateral (inconstant in dog) in the atlantal fossa (depression below atlas). They drain the head (deep structures and the parotid and mandibular lymph nodes) and adjacent neck, including the pharynx and larynx.








Fig. V-83 - Horse - Head, deep dissection of mandibular & sublingual glands - lat. view



# SALIVARY GLANDS

Head-262


Fig. V-84 - Ox - Head, dissection of parotid gland - lat. view



1. Parotid salivary gland
2. Parotid duct
3. Mandibular salivary gland
4. Mandibular duct (V-83)
5. Sublingual salivary gland
6. Parotid In. (V-84)
7. Mandibular In.

- a. Masseter m.
- b. Buccal m.
- c. Polystomatic salivary gland (V-83)
- d. Monostomatic salivary gland (V-85)  
(absent in horse)
- e. Major sublingual duct
- f. Buccal gland (minor salivary gland) (V-83)
- g. Labial gland (minor salivary gland) (V-82)

Fig. V-85 - Ox - Head, dissection of mandibular & sublingual glands - lat. view



## CLINICAL:

**Palpation of the dog's mandibular lymph nodes and salivary gland:** Grasp the skin and deep structures at the angle of the jaw. Let them slip through your fingers, and feel a big lump (the mandibular gland) and a few small lumps (mandibular lymph nodes).

**Mandibular or sublingual ducts:** may become blocked due to trauma or inflammation, resulting in an accumulation of saliva producing a swelling (mucocoele). Mucocoeles are named for their location: under the tongue - ranula or salivary cyst (sialocoele); the neck - cervical mucocoele. The gland itself may become blocked. Surgical removal of the glands and as much of the ducts as possible in the dog may be required to relieve either

condition. Both the mandibular and the sublingual salivary glands are removed together because they share a capsule, thus, one can't be removed without damaging the other.

**Lymph nodes:** the differentiation of an enlarged lymph node from a salivary gland is useful in diagnosis.

**Ox's parotid lymph node:** drains the orbit and is checked during slaughter because of cancer eye in cattle.

**Translocation of the parotid duct:** the surgical dissection of the parotid duct and its movement to the lateral canthus of the eye to treat dry eye (keratoconjunctivitis sicca) in the dog. Whenever a dog sees food it then salivates ("spits") onto its eyes.






Fig. V-86 - Dog - Pharynx - sagittal section

**PHARYNX (FAR-inks):** acts as the common passageway for the digestive and respiratory systems. It connects the nasal and oral cavities with the trachea and esophagus respectively, serving to direct the intake of food and air into their proper channels. The soft palate (5) divides the rostral portion of the pharynx into the oropharynx and the nasopharynx. The common caudal portion is the laryngopharynx.

**1. Nasopharynx (nay'zoh-FAR-inks):** a part of the respiratory channel, located dorsal to the soft palate and extending from the caudal nares to the laryngopharynx. The caudal free edge of the soft palate and the palatopharyngeal arches (a) demarcate the nasopharynx from the laryngopharynx.

**2. Oropharynx (or'oh-FAR-inks):** a part of the digestive channel, ventral to the soft palate, extending from the oral cavity to the base of the epiglottis. The palatoglossal arches (e) demarcate the oropharynx from the oral cavity.

**3. Laryngopharynx (layr-in'joh-FAR-inks):** the part of the pharynx where air from the nasopharynx crosses to reach the larynx, and food and water from the oropharynx crosses into the esophagus. Thus, it is part of both the respiratory and digestive channels. The laryngopharynx is between the base of the epiglottis and the esophageal entrance. The rostral portion of the larynx projects

into the laryngopharynx.

**4. Piriform recess:** the continuation of the floor of the oropharynx on either side of the larynx. It is part of the laryngopharynx.

**5. SOFT PALATE:** the caudal musculomucosal continuation of the hard palate that divides the rostral part of the pharynx into oropharynx and nasopharynx.

**MUSCLES of the PHARYNX:** make up the walls of the pharynx. All are constrictors, except the caudal stylopharyngeal muscle, that dilates the pharynx. The constrictor muscles (pterygopharyngeus, palatopharyngeus, stylopharyngeus rostralis, hyopharyngeus, thyropharyngeus and cricopharyngeus) act in an undulating fashion to move food toward the esophagus.


**OPENINGS of the PHARYNX:**

**6. Pharyngeal opening (aditus pharyngis or isthmus faucium):** the opening from the oral cavity to the oropharynx formed by the soft palate, the tongue and the palatoglossal arches.

**7. Caudal nares or choanae (KOH-ay-nee) (sin.= choana):** the osseous opening between the caudal nasal cavity and the nasopharynx.



Fig. V-87 - Dog - Pharynx (pharyngeal roof & soft palate cut on median plane) - dors. view



8. Pharyngeal openings of the auditory tubes: the slits in the lateral walls of the nasopharynx leading into the auditory tubes, thus, to the middle ear.

9. Laryngeal opening (aditus laryngis): the opening into the larynx surrounded by the rostral laryngeal cartilages.

10. Esophageal opening (aditus esophagi): opening at the caudal end of the laryngopharynx into the esophagus.

**TONSIL:** aggregation of lymphatic tissue in the pharyngeal mucosa. Some are distinct accumulations and others are diffuse and difficult to see. Named according to their locations (lingual, palatine, pharyngeal, tubal [around the entrance of the auditory tube], tonsil of the soft palate). They help to protect the openings of the pharynx against microorganisms and toxic substances.

11. Palatine tonsil: the lymphoid aggregation in the oropharynx. In carnivores it is a long cylindrical structure placed in a tonsillar fossa and covered medially by a semilunar fold (k).

12. **ESOPHAGUS** (ee-SOF-a-gus): the first part of the alimentary canal. It is a muscular tube that transports food from the oral cavity and pharynx down the neck and through the thorax to the stomach. It has cervical, thoracic and abdominal parts. Cornified, stratified squamous epithelium lines and protects the esophagus.

The esophagus passes down the neck at first dorsal to the trachea, and then shifts to the left of the trachea. Inside the thorax, it returns to a position dorsal to the trachea, passing over the tracheal bifurcation to the right of the aorta. The esophagus pierces the esophageal hiatus of the diaphragm and terminates in the short abdominal portion at the cardia of the stomach.

## CLINICAL:



**Pyriform recess in the dog:** is a site where bones may become lodged and shut off the laryngeal opening of the airway. Its wall is the site where the incision for a pharyngostomy tube is placed.

**Pharyngostomy:** surgical incision of the pharynx.

**Pharyngostomy tube:** is passed through the pharyngeal wall and down the esophagus to the stomach to feed dogs that can't take food through their mouth. The pyriform recess is located, a hemostat is pushed against its wall, and the wall is incised over the hemostat.

**Stomach tube - horse:** can be seen passing in the esophagus of a horse on the left side of the neck.





## SPECIES DIFFERENCES

**Pharyngeal (FAR-in-jee-al) diverticulum:** the blind, mucosal pouch in the roof of the nasopharynx of pigs. Directed caudally above the opening of the esophagus, it is often fatally mistaken for the esophagus when "pilling" pigs.

**Tonsilar opening of the palatine tonsil in the ox: opening in the wall of the oropharynx leading into a space where the palatine**

tonsils are.

**Horse:** the soft palate is extremely long. It lies ventral to and in front of the tip of the epiglottis. The horse, unable to voluntarily raise its soft palate, exclusively breathes through its nose. This also explains why horses vomit through their nose. Displacement of the soft palate over the epiglottis interferes with breathing as it is sucked into the larynx.






Fig. V-90 - Pharynx - Schematic cross section showing lymphatic tissue (modified from Nickel, et al, The Viscera of the Domestic Animals, Verlag, Paul, Parley, 1973)

- |  |   |   |
|--|---|---|
| 1. Nasopharynx                           | a. Palatopharyngeal arch                          | k. Tonsillar fossa (carnivores)                     |
| 2. Oropharynx                            | b. Larynx   | l. Semilunar fold (carnivores) (V-90)               |
| 3. Laryngopharynx                        | c. Oral cavity                                    | m. Tonsillar opening of palatine tonsil (ox) (V-88) |
| 4. Piriform recess                       | d. Root of tongue                                 | n. Lingual tonsil (V-90)                            |
| 5. Soft palate                           | e. Palatoglossal arch                             | o. Tonsil of soft palate                            |
| 6. Pharyngeal opening (aditus pharyngis) | f. Epiglottis                                     | p. Pharyngeal tonsil (V-88)                         |
| 7. Caudal nares (choanae)                | g. Lateral ventricle (absent in carnivores & cat) | q. Tubal tonsil (V-90)                              |
| 8. Pharyngeal opening of auditory tube   | h. Basihyoid bone                                 | r. Retropharyngeal ln. (V-88)                       |
| 9. Laryngeal opening (aditus laryngis)   | i. Trachea  | s. Pharyngeal septum                                |
| 10. Entrance to esophagus                | j. Pharyngeal mm.                                 |   |
| 11. Palatine tonsil                      |   |   |
| 12. Pharyngeal diverticulum (pig)        |   |   |

Type	Carnivores	Pig	Ruminants	Horse
Lingual tonsil	*	*	+	+
Palatine tonsil	+	-	+(1)	+
Tonsil of soft palate	*	+	*	+
Pharyngeal tonsil	+	+	+	+
Tubal tonsils (around pharyngeal opening of auditory tubes)	-	+	+	*
Paraepiglottic tonsil	*	+	+,-(2)	-

- + Identifiable  
 \* Diffuse, difficult to identify  
 - Absent  
 1 Tonsillar opening is seen in the oropharynx of the ox  
 2 Absent in ox, present in small ruminants

Adapted from Veterinary Anatomy, M.J. Shively,



# PHARYNX

Head-267




Fig. V-91 - Horse - Pharynx - sagittal section





A. Breathing

B. Swallowing

Fig. V-92 - Horse - Pharynx cavity (schematic)



Fig. V-93 - Horse - Pharynx



1. Nasopharynx
2. Oropharynx
3. Laryngopharynx
4. Piriform recess
5. Soft palate
6. Pharyngeal opening (aditus pharyngis)
7. Caudal nares (choanae)
8. Pharyngeal opening of auditory tube
9. Laryngeal opening (aditus laryngis)
10. Entrance to esophagus
11. Esophagus

Fig. V-94 - Horse - Roof of pharynx, tongue & upper respiratory tract split

- a. Palatopharyngeal arch (V-93)
- b. Larynx
- c. Oral cavity
- d. Root of tongue
- e. Palatoglossal arch
- f. Epiglottis
- g. Lingual tonsil
- h. Hyoid apparatus
- i. Trachea
- j. Guttural pouch (horse)
- k-q. Pharyngeal constrictors
- k. Pterygopharyngeus m. (V-95)
- l. Palatopharyngeus m.
- m. Stylopharyngeus rostralis m.
- n. Hyopharyngeus m.
- o. Thyropharyngeus m.
- p. Cricopharyngeus m.
- q. Stylopharyngeus caudalis m.
- r. Levator palatini
- s. Retractor veli palatini




Fig. V-95 - Horse - Pharyngeal mm.







Fig. V-96 - Dog - Stomach - parietal surface

- |  |                         |
|--|-------------------------|
| a. Gastric groove                              | e. Cardiac gland region |
| b. Pyloric opening                             | f. Fundic gland region  |
| c. Rugae                                       | g. Pyloric gland region |
| d. Non-glandular region (absent in carnivores) | h. Duodenum             |

Fig. V-97 - Dog - Stomach, parietal surface opened



## PARTS of the SIMPLE STOMACH

1. **Greater curvature (curvatura major):** the long, convex surface of the stomach extending from the cardia to the pylorus. The superficial leaf of the greater omentum attaches to the greater curvature externally.

2. **Lesser curvature (curvatura minor):** the short, concave surface of the stomach, also extending from the cardia to the pylorus. It is the attachment site of the caudal edge of the lesser omentum externally.

**Parietal surface:** the side of the stomach in contact with the liver.

**Visceral surface:** the side of the stomach in contact with the remaining the abdominal viscera.

3. **Cardia (KAR-dee-ah)(Gr. *kardia* heart):** the opening or the part of the stomach around the opening. The cardiac opening (ostium cardiacum) is the opening of the esophagus into the stomach. The cardiac part (pars cardiaca) is the portion of the stomach around the esophagus. It is the "fixed" point (doesn't move) of the stomach. Do not confuse it with the cardiac gland region which may or may not correspond to this location in the different species. The fundic and pyloric gland regions of the stomach mucosa also don't necessarily correspond to the external fundic and pyloric regions.

4. **Fundus (L. bottom):** the blind, expanded portion of the stom-

**STOMACH (G. *gaster*):** the dilation in the GI tract caudal (aboral) to the esophagus receiving ingesta from the esophagus and temporarily storing it. Gastric enzymes, chiefly pepsin, rennin, and hydrochloric acid, are secreted by the glands in the stomach wall. Muscular movements of the stomach mix ingesta and enzymes and slowly move them into the duodenum. Stomachs are lined by glandular epithelium, nonglandular epithelium or both. The nonglandular lining is a continuation of the stratified squamous epithelium of the esophagus. The glandular lining is a simple columnar epithelium that continues into the duodenum. Carnivores have a glandular stomach lining. A composite stomach is lined by nonglandular and glandular epithelium and is found in the ruminants, horse and pig. The wall of the stomach consists of an inner mucous membrane, a muscular coat and a serosal coat. The muscular coat is unique in having an extra layer, the internal oblique layer, in addition to the outer longitudinal and the inner circular layers. It is present only over the expandable fundus and body of the stomach. At the cardia its fibers are thicker and form the cardiac loop (ansa cardiaca).

**Simple stomach:** the single compartment stomach found in the carnivores, horse and pig. It has been incorrectly called monogastric, implying the complex stomach is polygastric (having more than one stomach).

**Complex stomach:** the four compartment stomach found in the ruminants. The additional three compartments are called the forestomachs and may be the source of the incorrect four stomach concept. The complex stomach is still only one stomach.



# STOMACH

Abdomen-270





Fig. V-98 - Horse  
- Stomach

8. Folded margin  
(margo plicatus)

Fig. V-99 - Horse  
stomach opened



9. Gastric diverticulum  
(pig only)




Fig. V-100 - Pig  
- Stomach

ach's left side, immediately adjacent to the cardia. It is often filled with gas that can be seen in radiographs.

5. Body (corpus): the largest part of the stomach, extending from the cardia to the pyloric part.

6. Pylorus: (py-LOR-us) (*G. pylorus*, gatekeeper): the distal opening of the stomach, surrounded by a strong band of circular muscle, and through which the stomach contents are emptied into the duodenum. This term is variously used to mean the pyloric part of the stomach, pyloric antrum, pyloric canal, pyloric opening and pyloric sphincter.

• Pyloric part: the portion of the stomach distal to the body.

• Pyloric antrum: the wide proximal part of the pyloric part.

• Pyloric canal: the narrow distal passage surrounded by a strong muscular band (sphincter).

## SPECIES DIFFERENCES

**HORSE:** a simple composite stomach.

• 7. Blind sac (saccus cecus): the extensive fundus of the horse's stomach lined by nonglandular mucosa, homologous to the forestomach of ruminants.

• 8. Folded margin or margo plicatus: the grossly visible, internal, irregular, raised line separating the stomach's nonglandular and glandular portions in the horse.

**PIG:** a simple composite stomach with a small nonglandular part around the cardia.

• 9. Gastric diverticulum (diverticulum ventriculi): the extension of the pig's fundus.

• Torus pyloricus: the round swelling of the pylorus in the lumen of the pyloric canal, also present in the ruminants.

**CARNIVORES:** a simple glandular stomach.

**RUMINANTS:** a complex composite stomach consisting of four compartments (see pg. 270).


## CLINICAL

**Pyloric stenosis:** constriction of the pyloric canal in carnivores. The serosa and muscular layer (but not the mucosa) can be cut (submucosal myotomies) to open the pyloric canal.

**"Bots":** the larva of *Gastrophilus* spp. flies found attached to the interior of the horse's stomach.



Fig. V-101 - Ox - Stomach - rt. lat. surface



**RUMINANT STOMACH:** a complex, composite stomach consisting of four compartments. The first (proximal) three compartments, forestomach (proventriculus) (the rumen, reticulum and omasum) are nonglandular and lined with stratified squamous epithelium. The distal compartment, the abomasum, is the glandular stomach.

**1. RUMEN (ROO-men):** the largest of the four compartments, filling most of the abdomen's left half. The rumen is divided into dorsal and ventral sacs by right and left longitudinal grooves and cranial and caudal grooves. The rumen is a fermentation vat for microorganisms to break down cellulose into metabolizable components. The rumen fills the left half of the abdomen, displacing the other organs to the right side.

**Grooves:** the external depressions in the rumen (longitudinal, cranial, caudal and coronary).

**Dorsal sac (g):** the upper part of the rumen.

**Ventral sac (h):** the lower part of the rumen.

• **Ruminal recess or recessus ruminis (i):** the cranial end of the ventral sac.

**Atrium or cranial sac (j):** the ventral part of the rumen, between the cranial pillar and the ruminoreticular fold.


**2. RETICULUM (re-TIK-yoo-lum):** the most cranial compartment of the ruminant stomach, located on the median plane against the diaphragm.

**3. OMASUM (oh'MAY-sum):** the spherical compartment caudal to the reticulum.

**4. ABOMASUM (ab'oh-MAY-sum):** the elongated "true stomach" lined by glandular tissue, located on the right side in contact with the ventral abdominal wall.



Fig. V-102 - Ox - Stomach - lt. lat. side



## CLINICAL

**Displaced abomasum:** the relocation of the abomasum to the right (RDA) or left (LDA) causing disturbances in digestion that may be life threatening. The abomasum may be repositioned and sutured in the correct position.

• **LDA, left displaced abomasum:** passes under the rumen and up its left side to become positioned between the rumen and the left abdominal wall. Auscultation and percussion of an LDA will reveal abnormal gas sounds.

**Rumen palpation:** the steady pressure against the left paralumbar fossa to feel the contractions of the rumen, which normally occur 2-3 times per minute.

**Stomach tube:** a long tube passed through the mouth and down the esophagus into the rumen to release gas. If a stomach tube fails, then a trocar can be used to relieve gas build up.

**Trocarization:** the placement of a hollow tube (trocar) through the left paralumbar fossa and rumen wall to release gas from the rumen.

**"Hardware disease":** a common term for traumatic reticulitis caused by perforation of the reticular wall by a sharp object. Due to its weight, metal entering the cardia falls into the reticulum. Normal contraction can force the metal through the reticular wall and into other structures (commonly the liver, occasionally the pericardium). Often a magnet is placed in the reticulum to gather "hardware" and prevent migration.

**Rumenotomy:** the surgical opening of the rumen. This is done through the left paralumbar fossa and dorsal sac of the rumen. If performed to relieve "hardware disease", the reticulum can be found by palpating along the dorsal wall of the rumen until the reticulum is reached. The cranial sac can be differentiated from the reticulum by its absence of a "honey comb" mucosa.

**Ruminal fistula:** a permanent opening of the rumen to the outside used to study rumen physiology. The left paralumbar fossa and the dorsal sac of the rumen are opened. The edges of the opening of the dorsal sac of the rumen are sutured to the edges of the paralumbar skin incision, and a removable, artificial plug is left in place.






Fig. V-103 - Ox - Stomach, reticulum & rumen opened

## INTERIOR - RUMINANT STOMACH

**1. RUMEN:** the interior of the rumen has pillars representing the exterior grooves. Many papillae (peg-like mucosal projections) give the surface a "pile rug" appearance.

- **Pillars:** the internal representations of the external grooves (longitudinal, cranial, caudal and coronary). The intraluminal opening (ostium) is between the dorsal and ventral sac formed by the longitudinal, cranial, and caudal pillars.

- **Dorsal sac (g):** the upper part of the rumen.

- **Ventral sac (h):** the lower part of the rumen.

**Recessus ruminis (b):** the cranial end of the ventral sac.

**Atrium or cranial sac (a):** the ventral part of the rumen between the cranial pillar and the ruminoreticular fold.

**2. Cardiac opening or cardia:** the esophageal entrance into the rumen. Heavy material (grain and metal) entering the rumen usually falls through the cranial part of the rumen into the reticulum, directly below the cardiac opening.

**3. RETICULUM:** the interior has a honeycomb appearance due to its intersecting mucosal crests.

**4. OMASUM:** the third compartment, sometimes called the "Butchers bible" or "Book" because of the page appearance of its muscular laminae.

**5. Omasal laminae:** Covered with short papillae, they are parallel, leaf-like structures projecting into the interior from the wall of the omasum.

**6. Ruminoreticular fold:** the inner septum corresponding to the






Fig. V-104 - Ox - Stomach, omasum & abomasum opened

- |                            |                          |                           |
|----------------------------|--------------------------|---------------------------|
| a. Cran. sac (atrium)      | g. Caudoventr. blind sac | m. Abomasal groove        |
| b. Ruminal recess          | h. Dors. sac             | n. Reticuloomasal opening |
| c. Cran. pillar            | i. Ventr. sac            | o. Omasoabomasal opening  |
| d. Rt. longitudinal pillar | j. Reticular groove      | p. Velum abomasacum       |
| e. Caud. pillar            | k. Caud. groove          |                           |
| f. Caudodors. blind sac    | l. Omasal groove (V-104) |                           |

external ruminoreticular groove. It separates the rumen from the reticulum.


**7. ABOMASUM:** the compartment lined with glandular mucosa similar to the simple stomach of the carnivore.

**8. Pylorus:** the part of the abomasum opening into the duodenum.

**9. Torus pyloricus:** a round elevation of the pylorus into the pyloric canal; similar to the pig.

**10. GASTRIC GROOVE:** the channel through the stomach following its lesser curvature, found in all the domestic species, but of greatest importance in suckling ruminants. Suckling with the head up causes the lips of this groove to close. This forms a tube from the cardiac opening to the abomasum. Through this tube milk bypasses the rumen, reticulum and omasum to empty directly into the abomasum. This reflex disappears in the adult, except in response to some liquid salts. The gastric groove is divided into the reticular groove (esophageal, milk groove) (j), the omasal groove (l) and the abomasal groove (m).





**SMALL INTESTINE:** the principal site of digestion and absorption, extending from the pylorus of the stomach to the large intestine and divided into duodenum, jejunum and ileum.

**1. DUODENUM** (dyoo'-OD-e-num or dyoo-oh-DEE-num) (L. *duodeni*, twelve): receives ingesta from the stomach.

- **Cranial part:** extends cranially from the pylorus. It then turns caudally at the cranial duodenal flexure.

- **Descending duodenum (a):** continues caudally on the abdomen's right side, in contact with the right abdominal wall. The bile and pancreatic ducts empty into the descending duodenum.

- **Caudal flexure (b):** the bend where the descending duodenum becomes the ascending duodenum (c).

- **Ascending duodenum:** travels on the right side of the root of the mesentery (pg. 284) and terminates in the duodenojejunal flexure (d). The duodenocolic ligament connects the caudal flexure of the duodenum and the ascending duodenum to the descending colon.

**2. JEJUNUM** (je-JOO-num) (L. *jejunus*, empty): the longest part of the small intestine. Beginning at the duodenojejunal flexure

(d), the jejunum runs ventrally and caudally, forming many coils and loops and occupying the ventral abdominal cavity. The jejunum has a long mesentery, allowing great range of motion.

**3. ILEUM** (IL-ee-um) (L. rolled up, twisted): the short, terminal portion of the small intestine. It is indistinguishable grossly from the jejunum. Arbitrarily, it can be said to start at the end of the ileocecal fold (connecting peritoneum between the ileum and colon) or end of the antimesenteric ileal artery. It empties into the large intestine.

## SPECIES DIFFERENCES

**Small intestines:** grossly similar in all the domestic species.

**Sigmoid loop:** the "s" shaped curve of the cranial part of the duodenum in the horse, ruminant and pig. It is located against the visceral side of the liver.

**Duodenal ampulla:** the dilated cranial part of the horse's duodenum.

**Flange of the bovine small intestine:** the part of the small intestine with the longest mesentery. The proximal and middle parts of the jejunum have a short mesentery. The flange,



# SMALL INTESTINE

Abdomen-276

Fig. V-106 - Horse - Intestines (schematic)





Fig. V-107 - Ox - Intestines (schematic)



consisting of the distal end of the jejunum and the proximal end of the ileum, has a long mesentery, thus, great mobility. The ruminants have a proximal convoluted part and a distal straight part to their ileum.

Ileocecal opening - into the cecum of the horse

Ileocolic opening - into the ascending colon of carnivores and ruminants. Some consider the ruminant to have an ileocecolic opening (a "T" junction into cecum and ascending colon).

## CLINICAL

**Torsion of the intestine:** the turning or twisting of the intes-

tine, cutting off its blood supply.

**Intussusception** (in'tus-sus-SEP-shun): the condition in which a segment of intestine inverts ("telescopes") into the lumen of the adjacent segment.

**Volvulus:** the specific term for a torsion of the intestine, causing obstruction.

**Intestinal resection and anastomosis:** the cutting out of a damaged section of intestine and reconnection of healthy bowel. To ensure the vascular supply, cut the mesenteric border longer than the antimesenteric border of the two ends to be rejoined.



# LARGE INTESTINE

Abdomen-277

**LARGE INTESTINE:** the cecum, colon, rectum and anal canal. It extends from the ileum to the anus, and functions to dehydrate fecal contents by absorbing water.

1. **CECUM** (SEE-kum) (L. *caccus*, blind): the blind diverticulum at the beginning of the colon.

2. **Cecocolic orifice:** the opening from the cecum into the colon.

**Ileocecal** (il'-ee-oh-SEE-kal) fold: the fold of connecting peritoneum between the cecum and the ileum.

**COLON** (KOH-lon) (G. *kolos*, large intestine, hollow): ascending, transverse and descending segments of the large intestine fixed in the dorsal abdomen by a short mesentery.

3. **Ascending colon:** the first part of the colon. In the carnivores, it is the right colon, extending cranially on the right side of the dorsal abdomen, medial to the descending duodenum.

4. **Ileocolic orifice:** the ileal opening into the colon, except in the horse.

5. **Transverse colon:** the middle colon arching cranially around the mesenteric root from right to left in all domestic species.

6. **Descending colon:** the longest segment of the large intestine. It extends from the transverse colon caudally on the left side of the dorsal abdomen to the pelvic inlet. Here it continues without demarcation as the rectum.

7. **Rectum** (REK-tum) (L. *rectus*, straight): the large intestine within the pelvic cavity, extending from the descending colon to the anal canal.

**Anal canal:** the short termination of the alimentary canal, opening to the exterior as the anus.

8. **Anus** (L. ring): the external opening of the intestine.

## SPECIES DIFFERENCES

**Ascending colon:** most species differences of the large intestine are due to modification of the ascending colon.

- **Carnivores:** have a short, straight ascending colon.
- **Pig and ruminants:** forms a coil, the spiral colon.
- **Horse:** forms a double horseshoe-shaped loop.

**Cecum:** located on the abdomen's right side, except in the pig, where it is on the left.

**Openings into the cecum:** the horse has two openings of the cecum, the ileocecal and cecocolic. The other domestic species have the cecocolic opening; while the ileum opens into the colon by the ileocolic opening.

**Anal sacs:** pouches located between the inner smooth and outer striated sphincter muscles of the carnivore's anus (cats as well as dogs). The anal sacs open into the anal canal at positions comparable to 4 and 8 o'clock.

**Bands (teniae):** the smooth muscle bands on the horse and pig cecum, the horse's colon and part of the pig's ascending colon. These bands cause the sacculations (hastra) of the gut wall.

**Rectal ampulla (c):** the dilated terminal part of the rectum in the horse, dog and ox.

## CLINICAL

**Anal sacs:** their ducts can become plugged, causing much discomfort (scooting). They may become infected and possibly rupture to the outside.

**Rectal prolapse:** the protrusion of the inner surface of the rectum through the anus.






Fig. V-108 - Dog - Intestines




Fig. V-109 - Dog - Ileocecal junction




Fig. V-110 - Dog - Ileocecal junction, ileum & colon opened

- |                        |                           |
|------------------------|---------------------------|
| A. Esophagus           | F. Duodenojejunal flexure |
| B. Stomach             | G. Jejunum                |
| B' Fundus              | H. Ileum                  |
| B'' Body               | I. Ileocecal fold         |
| B''' Pylorus           |                           |
| C. Descending duodenum | a. Rt. colic flexure      |
| D. Caud. flexure       | b. Lt. colic flexure      |
| E. Ascending duodenum  | c. Ampulla of rectum      |



**CECUM:** a huge, comma-shaped structure occupying much of the right abdominal cavity. It consists of a base, body and apex.

- 1. **Base:** the bulbous beginning of the cecum in the right paralumbar fossa.
- 2. **Body:** the continuation of the base cranially along the right wall and floor of the abdominal cavity.
- 3. **Apex:** the tapered end of the cecum on the floor of the abdominal cavity, caudal to the xiphoid cartilage. The ventral colon wraps around it.

4. **Ileocecal opening:** the ileal opening into the base of the cecum. In the other domestic species, the ileum opens into the colon.

5. **Cecocolic opening:** the opening at the base of the cecum to the ascending colon.

**COLON:** a highly modified structure with great capacity in the horse.

**Ascending colon:** due to its size, also called the great colon. Imagine the generalized short ascending colon grasped in its middle and stretched out. The formed loop then is folded on itself. This gives the double horseshoe loop of the horse's ascending colon. The two loops lie on top of each other, with the front of the loops toward the diaphragm, and the turn between the two loops at the pelvic inlet. The different portions of the ascending colon listed as they receive food are - right ventral colon - sternal flexure - left ventral colon - pelvic flexure - left dorsal colon - diaphragmatic flexure and right dorsal colon.

• 6. **Right ventral colon:** the beginning of the ascending colon at the cecocolic opening and extending cranially on the right abdominal floor to the sternum.

• 7. **Sternal flexure:** the connection between the right and left ventral colons curving around the apex of the cecum.

• 8. **Left ventral colon:** the continuation of the sternal flexure that ends in the pelvic flexure.

• 9. **Pelvic flexure:** the connection of the left ventral and left dorsal colons in the left paralumbar fossa, near the pelvic inlet.

• 10. **Left dorsal colon:** the continuation the pelvic flexure cranially on top of the left ventral colon, and against the left abdominal wall.

• 11. **Diaphragmatic flexure:** the continuation of the left dorsal colon on top of the sternal flexure.

• 12. **Right dorsal colon:** the greatly expanded continuation of the diaphragmatic flexure caudally to the transverse colon. The ampulla coli ("stomach-like" dilatation) is the expanded terminal portion of the right dorsal colon.

13. **Transverse colon:** the segment of colon curving from right to

left cranial to the root of the mesentery.

14. **Descending colon:** the continuation of the transverse colon to the rectum. Smaller than the ascending colon, the descending colon is called the small colon. Compared to the other domestic species, the horse's descending colon is long with a long mesocolon, allowing it a wide range of motion.

**RECTUM:** the terminal part of the intestines located in the pelvic cavity. In the horse, as in the dog and ox, it has a terminal dilation, the rectal ampulla.

**Mesocolon:** the connecting peritoneum arising from the abdominal roof and extending between the dorsal and ventral colons.

**Bands or teniae (TEE-nee ah) sin. tenia (L. "a flat band"):** the variable number of longitudinal smooth muscle cords on the cecum and the different segments of the colon. Some of these are hidden in the mesentery attached to the different segments. On the ventral colon there are two bands in the mesocolon and two free bands. The band on the pelvic flexure and the left dorsal colon is in the mesocolon. One of the bands of the right dorsal colon is in the mesocolon and two are free. The small colon has a mesocolic and a free band. The cecocolic fold connects the right ventral colon to the lateral band of the cecum. The ileocecal fold connects the ileum to the dorsal band of the cecum.

**Sacculations or haustra:** the series of pouches in the walls of the cecum and ventral colon formed by the bands of these intestinal segments.

## CLINICAL

**Bands and segment identification:** the teniae are used to distinguish between parts of the large intestine and, indirectly, the small intestine. The most significant segments to be differentiated are the descending colon (two bands), the pelvic flexure (one band) and the small intestine (no bands). These need to be distinguished because of their similar size and because they are all located in the left paralumbar fossa.

**Impaction:** tightly wedged intestinal contents so as to be immovable. In the horse, the cecum, pelvic flexure, and right dorsal colon are most likely to become impacted due to diameter changes from large to small. Common impaction sites:

- Pelvic flexure
- Cecum
- Transverse colon



**Volvulus:** twisting of the intestine. The start of the right ventral colon is connected to the base of the cecum and the end of the right dorsal colon is attached to the transverse colon. The rest of the ascending colon is free to move and possibly twist on itself. These usually can be diagnosed by rectal palpation.



# HORSE - LARGE INTESTINE

Abdomen-280

Fig. V-113 - Horse - Large intestine



## NUMBER OF BANDS ON HORSE INTESTINES

Small intestine	0
Cecum and ventr. colon including sternal flexure	4
Pelvic flexure	1
Lt. dors. colon	1
Rt. dors. colon	3
Small colon	2

Fig. V-114 - Horse - Cecum & ventr. colon opened - rt. side






Fig. V-115 - Ox - Intestines (schematic)

**1. CECUM - OX:** the large, blind tube extending caudally from the ileocecolic junction on the right side of the mesentery.

## COLON - OX

**Ascending colon:** the part of the large intestine divided into proximal, spiral and distal loops.

• **2. Proximal loop:** the S-shaped loop continuing the cecum cranially. It doubles back caudally on the right side of the mesentery, and then cranially on the left side of the mesentery to continue as the spiral loop.

• **3. Spiral loop:** the segment rolled up on itself, forming a flat disc attached to the left side of the mesentery. Usually two centripetal turns (a) spiral toward the central flexure. Two centrifugal turns (b) spiral away from the central flexure and continue as the distal loop.

**Sheep and goat:** the last centrifugal coil separates from the spiral loop and passes in the greater mesentery very near the

jejunal coils before continuing as the distal loop.

• **4. Distal loop:** U-shaped, it runs first caudally on the left side of the mesentery, and then cranially on the right side of the mesentery to become the transverse colon. It is attached high in the abdomen with the transverse colon and start of the descending colon.

**5. Transverse colon:** arches from right to left in front of the mesenteric root to become descending colon.

**6. Descending colon:** the continuation of the transverse colon caudally on the abdomen's left side next to the ascending duodenum.

• **7. Sigmoid flexure:** the region of the descending colon with a long mesocolon hanging down into the abdomen; it allows great range of motion during rectal palpation.

**8. RECTUM:** the continuation of the descending colon into the pelvic cavity to terminate in the anal canal and anus (9).






Fig. V-114 - Pig - Intestines (schematic)

**1. CECUM - PIG:** the blind sac extending caudally from the ileocolic junction. It has tendinous bands that form rows of sacculations as in the horse. Unlike the other domestic species, in the pig it is on the left side of the abdomen.

**COLON - PIG:** divided into ascending, transverse and descending parts.

**Ascending colon:** the highly modified part of the colon responsible for the pig's unique intestinal pattern.

**2. Spiral loop:** the coiling loop of the ascending colon forming a cone-shaped structure. The large first part makes centripetal turns clockwise (when viewed dorsally) on the outside of the cone to the cone's apex (central flexure). The thinner, second

part makes centrifugal turns counterclockwise inside the centripetal turns and then continues as the transverse colon. The centripetal turns have tendinous bands and sacculations.

**3. Transverse colon:** the continuation of the ascending colon from right to left around the front of the mesentery.

**4. Descending colon:** the continuation of the transverse colon in a straight line to the pelvic cavity.

**5. RECTUM:** the continuation of the descending colon through the pelvic cavity to terminate as the anal canal. The rectal ampulla (ampulla recti) (c) is the flask-like dilation of the terminal rectum.



**SEROUS MEMBRANE or SEROSA:** a thin continuous membrane lining the closed cavity of the body and covering the cavity's organs. The serosa consists of a layer of mesothelium\* backed by connective tissue. The serosa secretes a lubricating fluid, allowing movement of the organs without friction. The serous membranes of the abdominal and thoracic cavities are the peritoneum and pleura respectively.

**Parietal (pa-RY-e-tal) serosa:** lines a cavity wall, intimately.

**Visceral serosa:** invests the organs within a cavity.

**Connecting serosa:** the two layers of serosa uniting parietal and visceral serosal layers or two visceral serosal layers.

**PERITONEUM (per'i-toh-NEE-um):** the serosa lining the abdomen and covering its organs. It consists of parietal and visceral peritoneum that are continuous at folds of connecting peritoneum.

**A. Parietal peritoneum:** the serosa lining the inner wall of the abdominal, pelvic and scrotal cavities.

**B. Visceral peritoneum:** the serosa covering the organs of the abdominal and pelvic cavities.

**C. Connecting peritoneum:** the double-layered serosa connecting parietal and visceral peritoneum, or between visceral peritoneum. It includes the mesenteries, omentum, ligaments and folds.

1. Mesenteries: see pg. 284

2. Omentum: see pg. 286

**Ligaments:** connecting peritoneum between visceral peritoneum surrounding some organs and parietal peritoneum, or between visceral peritoneum of two organs.

• **3. Ligaments of the liver:** the connecting peritoneum (right and left triangular and coronary ligaments) between the liver and diaphragm.

**Falciform ligament:** a fold of connecting peritoneum extending from the liver to the ventral abdominal wall as far caudally as the umbilicus. In young animals the round ligament of the liver, the remnant of the fetal umbilical vein, is found in the free edge of the falciform ligament.

**Ligaments of the urinary bladder (Fig. VII-10):** the connecting peritoneum (median and lateral ligaments) between the bladder and pelvic wall.

\***Mesothelium:** a layer of cells derived from mesoderm that lines the body cavities of the embryo. In the adult, it forms the epithelium of all serous membranes.

**4. FOLD:** a connecting peritoneum between two visceral organs (e.g., ileocecal fold).

**D. PERITONEAL CAVITY:** the potential space between the parietal and visceral peritoneum. This potential cavity contains no organs, only a small amount of lubricating fluid. Entirely closed in the male, it is open in the female at the abdominal end of the oviduct. This opening leads to the outside of the body cavity through the urogenital tract. The ovarian bursa (pg. 348) and omental bursa (pg. 286) are subdivisions of the peritoneal cavity. The vaginal cavity (pg. 362) of the spermatic cord is a diverticulum of the peritoneal cavity.

**Pouches of the peritoneal cavity:** formed by the caudal reflection of the peritoneum between organs in the pelvic cavity.

• **Rectogenital pouch (a):** the reflection of the peritoneal cavity between the rectum and the reproductive organs.

– **Pararectal fossa (b):** the part of the rectogenital pouch on either side of the rectum.

• **Vesicogenital pouch (c):** the reflection of the peritoneal cavity between the urinary bladder and the internal genitalia.

• **Vesicopubic pouch (d):** the reflection of the peritoneal cavity between the ventral wall of the pelvic cavity (pubis of the ossa coxae) and the urinary bladder.

**E. Retroperitoneal (re'-troh-per-i-toh-NEE-al):** the term used for a structure between the peritoneum and cavity wall, thus, having no connecting peritoneum (e.g. kidneys). It also applies to the portion of the pelvic organs not covered by peritoneum.

## CLINICAL


**Peritonitis (per'-i-toh-NY-tis):** inflammation of the peritoneum.



# ABDOMINAL PERITONEUM


Abdomen-284

Fig. V-104 - Ox - Abdominal peritoneum (schematic) - caud. section



2. Omentum (Greater)

E. Retroperitoneal



2. Omentum (Lesser)

- a. Rectogenital pouch
- b. Pararectal fossa
- c. Vesicogenital pouch
- d. Vesicopubic pouch
- e. Abdominal wall
- f. Abomasum

- g. Rumen
- h. Rectum
- i. Uterus
- j. Urinary bladder
- k. Diaphragm
- l. Lung
- m. Lumbar vertebra
- n. Kidney
- o. Liver
- p. Intestines

Fig. V-116 - Ox - Abdominal peritoneum (schematic) - med. section






Fig. V-117 - Horse - Intestines (schematic) - rt. view

**MESENTERIES** (MEZ-en-ter-eez): a type of connecting peritoneum between the intestinal and reproductive tracts to the abdominal wall. They are the expansive, double-layered serosal folds between the visceral peritoneum and the parietal peritoneum. They contain the blood vessels, lymphatics and nerves supplying their respective organs. They are named according to the organs they suspend by adding the name of the organ to meso- (mesoduodenum, mesoileum, mesocolon, etc.). The "broad ligament" (mesovarian, mesometrium, etc.) is described in the chapter on reproduction (pg. 148).


**1. Mesoduodenum:** the peritoneal fold suspending the duodenum from the dorsal body wall. The descending mesoduodenum

encloses the right lobe of the pancreas.

**Duodenocolic ligament (k):** a peritoneal fold connecting the ascending duodenum to the descending colon.

**2. Root of the mesentery:** the narrow attachment of the long mesojejunum and mesoileum to the dorsal wall of the abdominal cavity. Located at the level of the second lumbar vertebra, it is thick because it contains the cranial mesenteric artery, intestinal lymphatics, and the mesenteric plexus of autonomic nerves. It is continuous toward the mouth (orad) with the mesoduodenum and away from the mouth (aborad) with the mesocolon.





- a. Descending duodenum
- b. Ascending duodenum
- c. Jejunum
- d. Ileum
- e. Cecum
- f. Ascending colon
- g. Transverse colon
- h. Descending colon
- i. Rectum
- j. Pyloric part
- k. Duodenocolic lig.

Fig. V-118 - Ox - Intestines (schematic) - rt. view

**3. Mesojejunum and mesoileum:** the continuation of the mesoduodenum that is very long and wide to support the jejunum and ileum.

**4. Ileocecal fold:** a fold of connecting peritoneum between the ileum and cecum. The jejunum and ileum are grossly indistinguishable. Use the proximal extent of this fold to roughly determine the beginning of the ileum. The proximal end of the antimesenteric ileal artery can also be used to roughly determine the junction of the ileum and jejunum.

**5. Mesocolon:** the serosal fold suspending the colon. It can be divided into ascending, transverse and descending mesocolons.

**6. Mesorectum:** the short mesentery suspending the rectum from the dorsal wall of the pelvic cavity.

## SPECIES DIFFERENCES

**Bovine mesentery:** short when compared to other species. This makes exteriorizing parts of the intestine difficult. The mesentery in young calves and emaciated adults is filled with fat which, during surgery, obscures parts lying deep to them. The mesenteries of the ascending duodenum, the distal loop of the ascending colon, the transverse colon and the cranial part of the descending colon are fused together into a "conjoined tendon". The "conjoined tendon" anchors these structures high in the abdomen, making them difficult to distinguish from each other.

**Bovine "flange":** the most mobile part of the small intestine due to its long mesentery. It consists of the distal part of the jejunum and the proximal part of the ileum.






Fig. V-119 - Dog - Abdominal peritoneum - med. section (schematic)

**OMENTUM** (oh-MEN-tum) (pl.= omenta) (Gr. *epiploon*): a double-layered connecting peritoneum between the stomach and abdominal organs or abdominal wall.

**1. Lesser omentum:** connects the lesser curvature of the stomach and first part of the duodenum to the porta of the liver. It is continuous aborad (away from the mouth) with the mesoduodenum.

- **Gastrohepatic ligament:** that portion of the lesser omentum connecting the lesser curvature of the stomach with the liver.

- **Hepatoduodenal ligament:** that portion of the lesser omentum connecting the liver to the duodenum.

**2. Greater omentum:** connects the greater curvature of the stomach to the dorsal abdominal wall. Greatly elongated in the dog, the greater omentum folds over itself. This results in a deep and a superficial leaf (four layers of peritoneum) between the viscera and the ventral abdominal wall.

- **Superficial leaf:** extends from the stomach caudally to the pelvic inlet where it reflects and returns cranially as the deep leaf.

- **Deep leaf:** attaches to the dorsal abdominal wall and contains the

left lobe of the pancreas between its peritoneal layers.

- **Gastrophrenic ligament:** connects the stomach to the diaphragm.

- **Gastrosplenic ligament:** connects the stomach to the spleen.

- **Phrenicosplenic ligament:** connects the spleen to the diaphragm.


**3. Omental bursa:** the potential space between the two leaves of the greater omentum and the structures to which they attach. It is a subdivision of the peritoneal cavity.

**4. Omental (epiploic) foramen:** the opening between the general peritoneal cavity and the omental bursa. It is located dorsally in the right side of the abdominal cavity between the caudal vena cava and the portal vein. It can be found by lifting the caudate lobe of the liver and placing a finger between these two vessels.

**6. Omental vestibule:** the cranial part of the omental bursa. The omental foramen opens into the omental vestibule.

**5. Caudal recess of the omental bursa:** the caudal part of the potential space between the two leaves of the greater omentum.





- |                            |                                     |                              |                     |                        |
|----------------------------|-------------------------------------|------------------------------|---------------------|------------------------|
| A. Parietal peritoneum     | F. Mesorectum                       | a. Diaphragm                 | f. Transverse colon | l. Recto-genital pouch |
| B. Visceral peritoneum     | G. Falciform lig.                   | b. Liver                     | g. Jejunum          | m. Vesicogenital pouch |
| C. Root of mesentery       | H. Lig. (coronary) of liver         | c. Kidney (retro-peritoneal) | h. Rectum           | n. Vesicopubic pouch   |
| D-F. Connecting peritoneum | I. Lig. (median) of urinary bladder | d. Stomach                   | i. Uterus           | o. Spleen (V-120)      |
| D. Mesojejunum             |                                     | e. Pancreas                  | j. Urinary bladder  | p. Xiphoid cartilage   |
| E. Mesocolon               |                                     |                              | k. Pararectal fossa | q. Descending duodenum |

Fig. V-120 - Dog - Abdominal wall removed






Fig. V-121 - Horse - Omentum  
- cranial view

## SPECIES DIFFERENCES

**Greater omentum:** as described above for animals with simple stomachs such as the carnivores, pig and horse. The ruminant, having several stomach compartments, has a different arrangement (pg. 290).

## CLINICAL

**Peritoneum:** should not be sutured separately when closing an abdominal incision (laparotomy). It can be included in other sutured layers. The less trauma to the peritoneum, the better the closure.

**Intestinal herniation or entrapment through the omental (epiploic) foramen:** rare.






Fig. V-122 - Horse - Omentum & epiploic foramen, transverse colon removed

- a. Rt. dors. colon
- b. Transverse colon
- c. Descending colon
- d. Lt. kidney
- e. Spleen
- f. Falciform lig.
- g. Body of stomach
- h. Lesser curvature
- i. Greater curvature
- j. Pylorus
- k. Cran. duodenum
- l. Descending duodenum

- m. Liver
- n. Pancreas
- o. Rt. kidney
- p. Ureter
- q. Aorta
- r. Caud. vena cava
- s. Portal v.
- t. Diaphragm
- u. 4th lumbar vertebra
- v. Rt. triangular lig. of liver




Fig. V-123 - Horse - Line of attachment of greater omentum






Fig. V-124 - Ox - Abdominal cavity - cross section at 3rd lumbar vertebra (schematic)

**OMENTUM - RUMINANT:** the omenta of the ruminants, because of their complex stomachs, are arranged differently than animals with simple stomachs.

**1. Lesser omentum:** the connecting peritoneum between the liver and the omasum, the lesser curvature of the abomasum, and the cranial duodenum. It covers the right side of the omasum.

**2. Greater omentum:** has two leaves as in the other species. The superficial leaf arises from the left side of the rumen, and the deep leaf from the right side of the rumen. Both leaves extend ventrally and to the right, forming a sling for the intestines to the right of the rumen. Both leaves ascend together along the right abdominal wall to attach to the descending duodenum. The two leaves are continuous around the caudal end of the rumen as the caudal edge of the greater omentum.

**3. Superficial leaf:** attaches to the greater curvature of the abomasum and the descending duodenum. It extends along the ventral abdominal wall to the left side to attach to the left longitudinal groove of the rumen.

**4. Deep leaf:** extends from the right longitudinal groove of the rumen to the descending duodenum.

**5. Omental bursa:** the space, as in the other domestic species, between the superficial and deep leaves of the greater omentum.

It is divided into a vestibule and a caudal recess.

**6. Omental (epiploic) foramen:** the opening between the omental bursa and the general peritoneal cavity. It is medial to the caudate lobe of the liver and between the caudal vena cava and the portal vein.

**7. Caudal edge of the greater omentum:** the joining of the superficial and deep leaves of the greater omentum at the caudal edge of the rumen. The caudal edge is attached on the right to the descending duodenum. On the left, it attaches to the caudal groove of the rumen where the superficial and deep leaves join.

**8. Supraomental recess:** the space above the deep leaf of the greater omentum. It is open caudally and contains the intestines.

## CLINICAL

**Omentum:** when opening the right paralumbar fossa of the ruminant, the greater omentum ("omental curtain"), the descending duodenum and mesoduodenum only are seen. The superficial and deep leaves of the greater omentum extend from the descending duodenum forming a sling under the intestines. To visualize the intestines in the supraomental recess, grasp the caudal edge of the greater omentum and move it cranially like a shower curtain.



Fig. V-125 - Ox - Omentum & abdominal viscera - rt. side




Fig. V-126 - Ox - Omentum, intestines removed, caudate process of liver pulled forward, and windows cut in omentum - rt. side




Fig. V-127 - Ox - Omentum, liver removed - rt. side

- a. Rumen
- b. Duodenum
- c. Lt. kidney
- d. Jejunum
- e. Rt. kidney
- f. Caud. lobe of liver
- g. Liver
- h. Gall bladder
- i. Abomasum
- j. Caud. vena cava
- k. Portal v.
- l. Esophagus
- m. Reticulum
- n. Omasum



# LIVER

Abdomen-293




Fig. V-128 - Dog - Liver  
- diaphragmatic surface

**LIVER** (*G. hevar*): the largest gland in the body. It is an extramural (outside the lumen of the GI tract) digestive gland of substantial importance in metabolism. Situated between the vessels draining the intestines and the general circulation, the liver has many complex functions, e.g., detoxification of drugs and toxins, formation and secretion of bile, metabolism of carbohydrates and fats, plasma protein production, urea formation, inactivation of polypeptide hormones, and reduction and conjugation of adrenal and gonadal steroid hormones.

The liver is in the abdominal cavity, abutting the diaphragm. The caudate process encloses the cranial pole of the right kidney in the right dorsal abdomen. The stomach and first part of the descending duodenum lie against the liver's visceral surface. Three distinct landmarks are used to orient the liver once it is removed from the body cavity – caudal vena cava, porta, and renal impression.

**1. Caudal vena cava:** runs through the dorsal portion of the liver.

**2. Porta:** the area where the vessels and nerves enter the organ on the visceral surface.

**3. Renal impression:** the indentation for the right kidney on the liver's right side.

**Diaphragmatic surface** (dy-a-fra-MAT-ik): the convex surface

in contact with the diaphragm.

**Visceral surface:** the side in contact with the abdominal viscera. The right kidney, stomach, duodenum, colon and jejunum produce impressions on the liver's visceral surface when the organ is hardened in situ.

**LOBES and PROCESSES of the LIVER:** deep fissures divide the liver into four basic lobes, and two processes. The right and left lobes may be divided into medial and lateral lobes, depending on the species.


**3. Left lobe:** lies to the left of the median plane except in the ruminants.

**4. Right lobe:** lies to the right of the median plane.

**5. Quadrate lobe:** located between the right and left lobes and ventral to the porta of the liver.

**6. Caudate lobe:** located dorsal to the porta of the liver, consisting of caudate and papillary processes. The **papillary process** (i) is the part of the caudate lobe to the left of the median plane lying in the lesser curvature of the stomach. The **caudate process** (h) is the most caudal region of the liver. It has a renal impression that cups the cranial end of the right kidney in all domestic species, except the pig.





A. Falciform lig. (V-128)  
 B. Lesser omentum  
 C. Lt. triangular lig.  
 D. Esophageal notch  
 E. Rt. triangular lig.  
 F. Coronary lig.  
 G. Renal impression

a. Esophagus (V-129)  
 b. Rt. crus of diaphragm  
 c. Costal part of diaphragm  
 d. Lumbar vertebra  
 e. Aorta  
 f. Sternum  
 g. Costal cartilage  
 h. Caudate process  
 i. Papillary process

Fig. V-129 - Dog - Liver, in situ  
 - visceral surface

## SPECIES DIFFERENCES:

**Carnivores:** the right and left lobes are divided into medial and lateral lobes. The caudate lobe is divided into a caudate process and papillary process as in the ox.

**Pig:** similar to the carnivores, except for the lack of the papillary process of the caudate lobe.

**Horse:** resembles the carnivores, except the right lobe is undi-

vided and the papillary process is also missing, as in the pig. The horse's liver is located obliquely across the diaphragm with the left lobe ventral and the right lobe dorsal.

**Ruminants:** resembles the carnivores, except that neither right nor left lobe is divided. The rumen has moved the liver to the right side of the abdominal cavity. The liver is also rotated, with the right lobe dorsal and the left lobe ventral.






Fig. V-130 - Horse - Liver, in situ  
- visceral surface

Fig. V-131 - Horse - Liver  
- diaphragmatic surface

**LIVER ATTACHMENTS:** The fibrous capsule is the strong, mainly collagenous, tissue layer closely investing the liver's surface and interior vascular and nervous elements. The liver is covered with visceral peritoneum.

**Coronary ligament of the liver (F):** the reflection of peritoneum from the diaphragmatic surface of the liver onto the diaphragm. It forms a circular area of reflection (corona means crown, thus, its name) around the caudal vena cava. The coronary ligament comes together in three places to form the two triangular and falciform ligaments.

**Right triangular ligament (E):** attaches the dorsal part of the right lateral lobe to the right crus of the diaphragm.

**Left triangular ligament (C):** attaches the dorsal part of the left lateral lobe to the left crus and tendinous center of the diaphragm.

**Falciform ligament (L. *falx*, sickle + *forma*, form) (A):** connects the ventral liver to the sternal part of the diaphragm and ventral abdomen.

**Round ligament of the liver:** contained in the free border of the falciform ligament, is a vestige of the umbilical vein of the fetus.

**Lesser omentum (B):** extends from the porta of the liver to the lesser curvature of the stomach and the cranial portion of the duodenum. It can be divided into hepatoduodenal and gastrohepatic parts.






Fig. V-132 - Ox - Liver, spleen & rt. kidney




Fig. V-133 - Ox - Liver - diaphragmatic surface

- |                       |                               |
|-----------------------|-------------------------------|
| 1. Lt. lobe           | A. Falciform lig.             |
| 1'. Lt. med. lobe     | B. Lesser omentum             |
| 1''. Lt. lat. lobe    | C. Lt. triangular lig.        |
| 2. Quadrate lobe      | D. Esophageal notch           |
| 3. Gall bladder       | E. Rt. triangular lig.        |
| 4. Rt. lobe           | F. Coronary lig.              |
| 5. Caud. vena cava    | a. Esophagus                  |
| 6. Caudate lobe       | b. Rt. crus of diaphragm      |
| 6'. Papillary process | c. Costal part of diaphragm   |
| 6''. Caudate process  | d. Lumbar vertebra            |
| 7. Hepatic vv.        | e. Aorta                      |
| 8. Hepatic a.         | f. Sternum                    |
| 9. Portal v.          | g. Costal cartilage           |
| 10. Cystic duct       | h. Spleen                     |
| (absent in horse)     | i. Rt. kidney                 |
| 11. Bile duct         | j. Splenophrenic lig. (V-118) |

## CLINICAL

**Hepatitis (hep-a-TY-tis):** inflammation of the liver.

## LIVER BIOPSY SITES

**Horse:** • Rt. 12th ICS (intercostal space) on a line between the tuber coxae and point of the shoulder.  
• Lt. 8th ICS (intercostal space) at the level of the deltoid tuberosity. Direct needle medially, dorsally and cranially.

**Ox:** Rt. 10th or 11th ICS about 1/4th of the length of the bony rib ventral to the vertebral column.

**Dog:** Laparotomy incision caudal to the xiphoid process, hold the left lobe of liver with your finger and insert the needle through a separate stab incision into the liver.



Lobes	Species			
	Carnivores	Ruminants	Horse	Pig
Left lobe	+	+	+	+
Lt. lat.	+	-	+	+
Lt. med.	+	-	+	+
Quadrangle	+	+	+	+
Right lobe	+	+	+	+
Rt. med.	+	-	-	+
Rt. lat.	+	-	-	+
Caudate lobe	+	+	+	+
Caudate process	+	+	+	+
Papillary process	+	+	-	-

**HISTOLOGY OF THE LIVER:** The structural unit of the liver is the lobule. It consists of cords of hepatic cells (1) radiating out from a central vein (3). Sinusoids between the cords receive blood from branches of the hepatic arteries and portal vein passing on the periphery of the lobule. The sinusoids empty into a central vein in the middle of the liver lobule.

**BLOOD SUPPLY:** the liver has a dual blood supply. Functional blood, to be processed by the organ itself, comes to the liver via the portal system, bringing nutrients freshly absorbed from the gut. It accounts for about 3/4 of the blood flow to the liver. Nutrient blood (oxygenated) comes from the hepatic artery to keep the hepatocytes alive. Both types of blood empty into the liver sinusoids. Blood in the sinusoids empties into central veins, then into hepatic veins that empty into the caudal vena cava.

**Lobule:** structural unit of the liver.

**1. Hepatic cells:** liver cells, arranged radially around a central vein.

**Portal vein:** the large vein carrying nutrient rich (functional) blood from the stomach, intestines, pancreas and spleen into the liver at the porta of the liver.

**Proper hepatic arteries:** carry oxygenated (nutritional) blood to

cells of the liver, also via the porta. They are branches of the common hepatic artery (a branch of the celiac artery).

**2. Liver sinusoids:** spaces where blood received from both the hepatic arteries and portal vein interacts with hepatic cells, then exits via central veins.

**3. Central veins:** course from the center of each liver lobule, receiving blood from liver sinusoids and carrying it to the hepatic veins.

**4. Hepatic veins:** the veins located inside the liver and emptying into the caudal vena cava. The central veins join to form the hepatic veins.

**BILE:** the liquid secretion of the liver cells into the duct system of the liver.

**6. Bile canaliculi:** small tubes immediately surrounding and collecting bile from the hepatic cells. They travel to the periphery of the lobule opposite the direction of blood flow, where they join to form interlobular ducts.

**7. Interlobular ducts:** ducts passing in the interstitial tissue between the lobules. They unite to form lobular ducts that course to the porta, joining to form the hepatic ducts.

**Hepatic ducts:** the 3 to 5 ducts that leave the porta to join with the cystic duct.

**GALL BLADDER** or cholecyst (KOH-lee-sist) [Gr. *chole* bile + *kystis* bladder]: the sac storing and concentrating bile. Bile aids in digestion and lubrication of food entering the duodenum from the stomach. The gall bladder is located in the fossa between the quadrangle and the right medial lobes of the liver.

**Cystic duct:** connects the gall bladder with the hepatic ducts. Together, these make the bile duct. The cystic duct is a two way street, bile can pass through it for storage in the gall bladder. When needed, the stored bile can pass through the cystic duct to the bile duct and into the duodenum. Bile is discharged through the cystic and bile ducts into the duodenum.


**Bile duct\*:** (Fig. V-118, 11): the duct formed by the junction of the hepatic ducts and the cystic duct. It travels in the lesser omentum (hepatoduodenal ligament) to enter the duodenum. It is joined by the pancreatic duct, and both open on the major duodenal papilla.

\*Frequently called the "common bile duct". "Common bile duct" indicates the joining of the hepatic ducts and cystic duct. This term is being replaced with bile duct so it can be applied to both animals with or without a gall bladder and cystic duct.



4. Hepatic v.

Fig. V-134 - Liver - Lobule (schematic)

**SPECIES DIFFERENCES:**

**Horse:** has no gall bladder and thus no cystic duct. Its hepatic ducts join to form the bile duct.

**CLINICAL**

**Cholecystectomy** (koh'lee-sis-TEK-toh-mee): surgical removal of the gall bladder.

**Cholecystitis** (koh'lee-sis-TY-tis): inflammation of the gall bladder.

**Cholecystoduodenostomy** (koh'lee-sis'toh-dyoo'oh-de-NOS-toh-mee): surgical anastomosis of the gall bladder to the duodenum.



# PANCREAS

Abdomen-299




Fig. V-135 - Dog - Pancreas - ventral aspect

**PANCREAS** (PAN-kree-as)[Gr. *pan* all + *kreas* flesh]: the V-shaped gland composed of two lobes joined by a body. It has both exocrine and endocrine functions.

**Endocrine:** the islet cells of the pancreas secrete insulin and glucagon into the blood, which keep the sugar concentrations of the blood at a constant level.

**Exocrine** (EK-soh-krin): pancreatic enzymes that aid in the digestion of carbohydrates, fats and proteins are carried to the descending duodenum by pancreatic ducts.

**1. Body:** the middle portion of the pancreas connecting the two lobes. It lies in contact with the pyloric part of the stomach.

**2. Right lobe:** the right portion of the pancreas in the mesoduodenum next to the descending duodenum.

**3. Left lobe:** lies in the deep leaf of the greater omentum. Extending from the body of the pancreas caudally and to the left, it lies along the dorsal abdomen toward the cranial pole of the left kidney.

## DUCTS OF THE PANCREAS

**4. Pancreatic (Wirsung's) duct:** the tube opening with the bile duct on the major duodenal papilla (6).

**5. Accessory pancreatic (Santorini's) duct:** the tube opening into the duodenum on the minor duodenal papilla (7).







Fig. V-136 - Horse - Pancreas

Fig. V-137 - Ox - Pancreas



## SPECIES DIFFERENCES

**Pancreatic duct:** the only duct present in the small ruminants and cat.

**Accessory pancreatic duct:** the only duct present in the pig, ox and occasionally dog.

**Both ducts:** present in the horse, usually in the dog and occasionally in the ox.

**Dog:** always has an accessory pancreatic duct. It usually has a pancreatic duct, but it is always the smaller of the two.

	Dog	Cat	Pig	Horse	Ox	Sheep & goat
Pancreatic duct	+	(-)	+	-	+	+
Accessory pancreatic duct	+	-	+	+	+	-


**Location of the minor duodenal papilla:** Horse - same level as the major, but on opposite wall; Carnivores and pig - a few centimeters away from the major; Ox - a foot distal to the major papilla.





## Chapter VI

# Respiratory System








Fig. VI-1 - Dog - Thorax, opened - lat. view

**RESPIRATORY SYSTEM:** the connected structures from the nostrils and oral cavity to and including the lungs. It is subdivided at the cranial end of the larynx into upper and lower respiratory tracts. The major function of the respiratory tract is transport and exchange of gaseous oxygen and carbon dioxide into and out of the blood. Oxygen is utilized by the cells for metabolism. Carbon dioxide is the resulting waste product.

The respiratory system is a portal of entry into the body and must be guarded. The tonsils of the pharynx are one part of this protective system. The upper respiratory tract, nasal cavity, and nasopharynx optimally warm or cool the gases brought into the body. Hairs associated with the nares filter out large particles. Smaller particles get stuck in the lining mucosa. Many ciliated lining cells drive the mucous coat back to the oral cavity for elimination.

**Phonation:** production of sound caused by movement of air across the vocal folds, causing them to vibrate. The associated resonance, changed and modified by the tongue, oral cavity, mouth and lips, produces characteristic sounds.

**Olfaction:** the sense of smell, perceived in the brain (cerebral cortex), involves receptors (olfactory nerve, CN I) located in the nasal cavity. Gaseous material and airborne particles are inhaled and detected (smelled) once dissolved in the mucous coat lining the nasal cavity.

**Heat regulation:** by panting, the dog helps control body temperature via evaporation. The lungs also play a role in acid-base

balance and regulation of circulating substances in the blood.

**NOSE:** the external nose, its associated cartilage, and the nasal cavity.

**External nose:** the rostral structure protruding slightly from the face.

**1. Philtrum** (G. *philtron* a love charm): the groove in the lip and middle of the nose separating the nostrils.

**2. Nostrils (cranial nares):** the external openings into the nasal cavity, thus, the respiratory system.

**3. Bony nasal aperture:** the rostral ends of the nasal bones and the incisive bones, referred to as the immovable nose. The nasal cartilages extend from the opening rostrally.

**Movable portion of the nose:** the nasal cartilages, their ligaments and skin coverings.

**4. Cartilage of the nose:** the structures giving the nose its characteristic appearance. The nasal cartilages project rostrally from the bony nasal aperture.

## SPECIES DIFFERENCES

**Philtrum:** deep in the carnivores and small ruminants; shallow or absent in the pig, ox and horse.






Fig. VI-2 - Dog - Muzzle




Fig. VI-3 - Ox - Muzzle

3. Bony aperture  
4. Nasal cartilage




Fig. VI-5 - Ox - Nasal cartilage



Fig. VI-4 - Horse - Muzzle




Fig. VI-6 - Horse  
- Nasal cartilage

A. Nasal septum

- a. Nasal plane (planum nasali) (carnivores, sm. ruminants)
- b. Nasolabial plane (planum nasolabialis) (ox)
- c. Arrow pointing into the nasal diverticulum of the horse
- d. Dors. lat. cartilage
- e. Ventr. lat. cartilage (absent in horse)
- f. Lat. accessory cartilage (absent in horse)
- g. Med. accessory cartilage
- h. Alar cartilage (horse)







Fig. VI-7 - Dog - Nasal cavity  
- sagittal section

Fig. VI-8 - Dog - Nasal cavity,  
nasal septum removed  
- sagittal section



**NASAL CAVITY (NAY-zul):** the facial portion of the respiratory tract extending from the nostrils to the caudal nares. It is divided into halves by the median nasal septum. The nasal cavity can be divided into three parts. The vestibule is the rostral part just inside the nostril. The middle part is filled with nasal conchae. These are thin scrolls of bone covered by mucous membrane. Passages between the conchae are called meatuses (meatus). The caudal part contains the numerous ethmoturbinates. The nasal cavity is connected to the paranasal sinuses (pg. 56) and the nasopharynx.

**Opening of the nasolacrimal duct:** at the junction between the skin and mucous membrane, just inside the nostril.

**1. Median nasal septum:** the perpendicular partition separating the nasal cavity into left and right halves. It is composed of bony (vomer, nasal and ethmoid bones), cartilaginous, and membranous parts. Its cranial cartilaginous part expands laterally, forming the nasal cartilages for each nostril.

**2. Ventral nasal concha:** the extensively folded structure filling

the middle lumen of the nasal cavity. It is a separate and distinct bone of the skull.

**3. Ethmoidal conchae:** the delicate, mucosa-covered, bony scrolls known as ethmotubines filling the caudal part of the nasal cavity. They are part of the ethmoid bone.

• **Dorsal nasal concha (a):** the upper concha extending from the ethmoid bone's cribriform plate to the rostral nasal cavity.


**Nasal conchae (KONG-kee) (L. shells) (sin.=concha):** the bony scrolls covered by nasal mucosa and filling each half of the nasal cavity. The nasal conchae and the median nasal septum divide the nasal cavity into passageways (meatuses).

**Nasal meatus (mee-AY-tus) (pl.=meatus or meatuses) (L. a way, path, course):** the passageways between the conchae of each half of the nasal cavity.


• **Dorsal nasal meatus (b):** the narrow passageway between the dorsal nasal concha and the nasal bones leading into the caudal nasal cavity.



**Fig. VI-9 - Horse - Nasal cavity, nasal septum removed - sagittal section**



**Fig. VI-10 - Ox - Nasal cavity - cross section**



**Fig. VI-11 - Ox - Nasal cavity, nasal septum removed - sagittal section**

• Middle nasal meatus (c): the passageway between the dorsal nasal concha and the ventral nasal concha leading into the caudal nasal cavity.

• Common nasal meatus (d): the narrow vertical space between the median nasal septum and the conchae, from the roof to the floor of the nasal cavity. Laterally it is continuous with the other meatuses.

4. Ventral nasal meatus: the largest meatus located between the ventral nasal concha and the hard palate. It leads directly into the nasopharynx.

5. Nasopharyngeal meatus: the short passageway connecting the ventral nasal meatus with the caudal naris (choana) on each side.

6. Caudal nares or choanae (ko-AY-nee) (sin.=choana): the two openings of the nasopharyngeal meatus into the nasopharynx, separated by the vomer bone.

### SPECIES DIFFERENCES

**Nasal diverticulum ("false nostril"):** the dorsal passage through the horse's nostrils into a blind cutaneous pouch. When "tubing" a horse, a thumb placed in the diverticulum will aid in directing the tube into the ventral nasal meatus.

**Rostral bone (os rostrale) (pg. 52,1):** the bone in the nose of a pig to help it "root".

### CLINICAL

**"Tubing":** the passage of a stomach tube through the nasal cavity, pharynx, and esophagus to the stomach. The tube must be passed through the ventral nasal meatus, nasopharyngeal meatus, and caudal nares to reach the pharynx and the esophagus. Passing the tube in the dorsal or middle nasal meatus would lead into the ethmoturbinates and cause massive hemorrhage. Tubing is done in the large animals and the cat.



# UPPER RESPIRATORY SYSTEM

Head-307




Fig. VI-12 - Horse - Head - sagittal section

Fig. VI-12 - Horse - Head - sagittal section






Fig. VI-13 - Ox - Head - sagittal section

1. Nostril
2. Nasal cavity
3. Choanae
4. Nasopharynx
5. Laryngopharynx
6. Larynx
7. Trachea
8. Oral cavity
9. Oropharynx
10. Esophagus

- a. Ventr. nasal concha
- b. Ventr. nasal meatus
- c. Hard palate
- d. Genioglossus m.
- e. Tongue
- f. Geniohyoid m.
- g. Mylohyoid m.  
(not shown in ox)

- h. Soft palate
- i. Opening into auditory tube
- j. Lingual process
- k. Epiglottic cartilage
- l. Cricoid cartilage
- m. Lat. laryngeal ventricle  
(horse & carnivores)
- n. Vocal fold

- o. Sternohyoideus m.
- p. Cerebral hemisphere
- q. Cerebellum
- r. Medulla oblongata
- s. Spinal cord
- t. Dors. arch of atlas
- u. Dens of axis






Fig. VI-14 - Dog - Laryngeal cartilages  
- lat. view




Fig. VI-15 - Dog - Laryngeal cartilages,  
lt. thyroid lamina removed  
- lat. view

**LARYNX** (LAR-inks) (G. upper end of windpipe): the musculocartilaginous tube connecting the laryngopharynx with the trachea and containing the vocal cords (the organs of phonation).

**LARYNGEAL CARTILAGES** (lah-RIN-jee-al): the group of cartilages forming the structure of the larynx. They consist of the single epiglottic, thyroid, cricoid, and paired arytenoid cartilages (and the insignificant sesamoid and interarytenoid cartilages in the dog).

**1. Epiglottis or epiglottic cartilage:** the rostral most cartilage giving structure to the epiglottis which closes the laryngeal opening during deglutition (swallowing), protecting the lungs from foreign bodies.

**2. Thyroid cartilage** (G. *thyroideus*, resembling a shield): the largest cartilage, single and open dorsally. The laryngeal prominence is the ventral projection of the thyroid cartilage, known as the palpable "Adam's apple" in man.

**3. Cricoid cartilage** (KRY-koyd) (G. ring): the signet ring-

shaped cartilage connecting the thyroid cartilage and the trachea.

**4. Arytenoid cartilages** (ar'e-TEE-noid): the paired, irregular cartilages articulating medially with the rostradorsal border of the cricoid cartilage. The arytenoid cartilages have a number of processes - vocal, muscular, corniculate, and cuneiform.

• **5. Vocal process:** the ventral projection of the arytenoid cartilage into the cavity of the larynx. It provides the dorsal attachment for the vocal cord. Ventrally the vocal cords attach to the floor of the thyroid cartilage.

• **6. Muscular process:** the lateral process of the arytenoid cartilage, providing a point of insertion of the intrinsic muscles of the larynx, especially the dorsal cricoarytenoideus muscle. The pull of this muscle swings the vocal process of the arytenoid cartilage and vocal cords laterally, thus, opening the space between them (glottic cleft).

• **7. Corniculate process:** the rostral horn-like process that forms the dorsal part of the laryngeal opening. It is absent in the cat.



Fig. VI-16 - Horse - Laryngeal cartilages  
- lat. view




Fig. VI-17 - Ox - Laryngeal cartilages  
- lat. view

Fig. VI-18 - Ox - Laryngeal cartilages, lt. thyroid  
lamina removed - lat. view

- |   |   |
|---|---|
| a. Petiolus of epiglottic cartilage (absent in cat) | h. Median crest of cricoid cartilage    |
| b. Lamina (thyroid cartilage)                       | i. Articular process                    |
| c. Rostr. cornu (except pig)                        | j. Cuneiform process (dog & horse)      |
| d. Thyroid notch (except pig)                       | k. Interarytenoid cartilage (dog & pig) |
| e. Caud. cornu                                      | l. Sesamoid (dog)                       |
| f. Cricoid arch                                     |   |
| g. Cricoid lamina                                   |   |



# LARYNGEAL CARTILAGES - HORSE

Head-311




Fig. VI-19 - Horse - Laryngeal cartilages - rostrolat. view




Fig. VI-20 - Horse - Laryngeal cartilages and part of hyoid apparatus - lat. view

1. Epiglottic cartilage
2. Thyroid cartilage
3. Cricoid cartilage
4. Arytenoid cartilage
5. Vocal process
6. Muscular process
7. Corniculate process

- a. Petiolus (absent in cat)
- b. Lamina (thyroid cartilage)
- c. Rostr. cornu (except pig)
- d. Caud. thyroid notch (except pig) (VI-23)
- e. Caud. cornu (VI-19)

- f. Cricoid arch
- g. Cricoid lamina
- h. Median crest
- i. Articular process
- j. Cuneiform process (dog & horse)






Fig. VI-21 - Horse - Laryngeal cartilages, lt. thyroid lamina removed - lat. view




Fig. VI-22 - Horse - Laryngeal cartilages - dors. view





Fig. VI-23 - Horse - Laryngeal cartilages - ventr. view



Fig. VI-24 - Dog - Larynx  
- median section



4. Dors. cricoarytenoid m.




Fig. VI-25 - Dog - Laryngeal muscles

Fig. VI-27 - Dog - Larynx





Fig. VI-26 - Dog - Lt. thyroid  
lamina removed,  
- lat. view



5. Vocal m.

**LARYNGEAL CAVITY:** the space enclosed by the laryngeal cartilages, muscles, ligaments, and mucous membrane. The laryngeal cavity is divided into three regions. The part just inside the laryngeal opening is the vestibule. The glottic cleft is the narrow middle part of the larynx. The infraglottic cavity is the part caudal to the glottic cleft.

**1. Laryngeal opening (aditus laryngis):** the passageway for air from the mouth or nose into the larynx. Its borders are the epiglottis, aryepiglottic fold (j), and the corniculate process of the arytenoid cartilage.

**2. Lateral ventricles of the larynx:** lateral depressions in the vestibule just cranial to the vocal folds. They allow the vocal fold lateral movement.

**3. Vocal fold or vocal cord:** the mucosa-covered vocal ligament and muscle caudal to the ventricle. It extends from the vocal process of the arytenoid cartilage to the interior floor of the thyroid cartilage.

**4. Glottic cleft (rima glottidis [L. *rima*, cleft]):** the narrowest space of the lumen of the larynx located between the structures of the glottis (the vocal cords and two vocal processes of the arytenoid cartilage).

**MUSCLES OF THE LARYNX:** laryngeal muscles cover the laryngeal cartilages in the undissected larynx. They are subdivided into extrinsic and intrinsic muscles. Extrinsic muscles extend from laryngeal cartilages to other body structures. Intrinsic muscles arise and terminate on laryngeal cartilage and are named according to their attachments: dorsal cricoarytenoid, lateral cricoarytenoid, transverse arytenoid, thyroarytenoid and cricothyroid).

**5. Dorsal cricoarytenoid muscle:** the only intrinsic muscle abducting (pulling apart) the vocal folds to open the glottis. It is innervated by the caudal laryngeal nerve (the end of the recurrent laryngeal nerve, a branch of the vagus nerve). The other intrinsic muscles either adduct (pull together) or alter the tension of the vocal folds.






Fig. VI-29 - Ox - Larynx - median section

**6. Vocal (vocalis) muscle:** the muscle of the vocal fold extending from the thyroid cartilage to the vocal process of the arytenoid cartilage. It relaxes the vocal fold by pulling the arytenoid cartilage downward.

**Cricothyroid muscles:** extend from the ventral side of the cricoid cartilage to the lateral sides of the thyroid cartilage. From the ventral side they look like a "bowtie" and can be used to judge midline.

**Cricothyroid ligament:** extends between the cricoid and thyroid cartilage.

## SPECIES DIFFERENCES

**Lateral ventricle of the larynx:** present in the horse, pig and dog; absent in the cat and ruminant.

## CLINICAL

**Laryngitis (lar'in-JY-tis):** inflammation of the larynx.

**Intubation:** placement of an endotracheal tube into the larynx and trachea. To intubate a tranquilized dog, open its mouth, grasp the tongue, and gently pull it rostrally. Use the endotracheal


tube to push the soft palate up to visualize the epiglottis. Then hold the epiglottis down with the tube and look into the larynx (through the laryngeal opening). See the space between the vocal folds (glottic cleft). Direct the tube between the vocal folds into the trachea. Inflate the endotracheal tube cuff and tie the tube around the upper jaw with gauze. Attach the tube to the gas anesthesia machine. As long as you see the tube go between the vocal cords you will be in the right place.

**"Roarer" - laryngeal hemiplegia in horses:** paralysis of the left (usually) recurrent laryngeal nerve to the abductor of the glottic cleft, the dorsal cricoarytenoid muscle. This results in the left vocal fold everting into the lumen of the larynx and causing a characteristic sound ("roar"). This is irritating and interferes with breathing, especially during a race. One corrective surgical procedure replaces the dorsal cricoarytenoideus muscle with a suture. The suture is tied so that the vocal process is permanently pulled laterally, opening the glottic cleft.

**Ventral laryngotomy in the horse:** opening the larynx. Incise the skin over the laryngeal prominence. Find the midline using the cricothyroid ("bowtie") muscles, then incise through the cricothyroid ligament that fills the caudal thyroid notch. This opens the larynx allowing access to it and the pharynx through the glottic cleft and laryngeal opening.




Fig. VI-30 - Horse - Larynx, thyroid cartilage cut - lat. view



1. Cricothyroid lig.

Fig. VI-31 - Horse - Larynx - median section



2. Dors. cricoarytenoid




Fig. VI-32 - Horse - Extrinsic mm. of larynx - lat. view




Fig. VI-33 - Horse - Intrinsic mm. of larynx - lat. view



# LARYNX - MUSCLES

Head-316

Fig. VI-34 - Horse - Larynx, lt. thyroid lamina removed - lat. view





Fig. VI-35 - Horse - Larynx - dors. view




Fig. VI-36 - Horse - Larynx - ventr. view

- 1. Cricothyroid lig.
- 2. Dors. cricoarytenoid m.
- 3. Cricothyroid m.
- 4. Vocalis m.
- A. Epiglottis (VI-31)
- B. Thyroid cartilage
- C. Cricoid cartilage
- D. Arytenoid cartilage
- E. Vocal process
- F. Corniculate process
- G. Cuneiform process
- H. Aryepiglottic fold

- I. Hyoid apparatus (VI-32)
- J. Lingual process of basihyoid bone
- K. Muscular process (VI-33)
- L. Tracheal ring
- M. Caud. thyroid notch (VI-36)
- a. Cricotracheal lig.
- b. Cricothyroid joint
- c. Cricoarytenoid joint
- d. Thyrohyoid articulation (cartilaginous)
- e. Thyrohyoid membrane

- f. Hyoepiglottic lig.
- g. Vestibular lig. (absent in cat)
- h. Vocal lig.
- i. Thyroepiglottic lig. (VI-31)
- j. Dors. cricoarytenoid lig.
- k. Anular lig. of trachea
- l thru p. Extrinsic mm. of larynx
- l. Sternothyroideus
- m. Thyrohyoideus
- n. Thyropharyngeus
- o. Cricopharyngeus
- p. Cricoesophageus

- q thru t and 2 thru 4. Intrinsic mm. of larynx
- q. Thyroarytenoideus (ventricularis & vocalis m.) (VI-34)
- r. Ventricularis
- s. Arytenoideus transversus
- t. Cricoarytenoideus lateralis
- u. Facet for caud. cornual process of thyroid cartilage
- v. Esophagus (VI-32)
- w. Tracheal m. (VI-35)
- x. Ceratohyoideus m.
- y. Hyoepiglotticus m. (VI-33)






Fig. VI-37 - Horse - Larynx - median section





Fig. VI-38 - Horse - Larynx  
 A. Glottic cleft closed  
 B. Glottic cleft closed (arrows indicating pull of dors. cricoarytenoid mm. on muscular processes of arytenoid)



Fig. VI-39 - Horse - Larynx - rostradors.  
view through the laryngeal  
opening, mucous removed



Dors. cricoarytenoid  
Cricoid cartilage  
Muscular process of  
arytenoid cartilage (VI-39)  
Thyroid cartilage

a. Vestibule  
b. Glottis (vocal fold  
& vocal process)  
c. Infraglottic cavity  
d. Med. ventricle

e. Aryepiglottic fold  
f. Cricoarytenoideus lateralis (VI-39)  
g. Arytenoideus transversalis  
h. Thyroarytenoideus



# THORACIC CAVITY

217-Thorax-319

**PLEURA:** the serosa\* lining the thoracic cavity and the thoracic organs; forming two pleural sacs on either side of the mediastinum.

1. **Pulmonary (visceral) pleura:** the serosa on the surface of a lung.

**Parietal pleura:** the serosa lining the walls of the thorax including the mediastinum and diaphragm.

• 2. **Mediastinal parietal pleura:** the serosa on the mediastinum.

3. **Pericardial pleura:** part of the mediastinal pleura on either side of the pericardium.

• 4. **Costal pleura:** the serosa lining the thoracic wall.

• **Diaphragmatic pleura:** the serosa covering the diaphragm's thoracic side.

**Connecting pleura:** the double layer of serosa connecting visceral pleura and parietal pleura.

• **Pulmonary ligaments:** the connecting pleura between the pulmonary pleura from the left and right caudal lung lobes to the mediastinal parietal pleura.

• **Plica vena cava:** the connecting pleura between the caudal vena cava and the diaphragm, pericardial sac, and floor of the thoracic.

6. **Mediastinum** (mee'dee-as-TY-num): the cleft or wall between the right and left mediastinal pleura. Near the median thoracic plane, it divides the thorax into two cavities. The thoracic organs, other than the lungs, (heart, esophagus, trachea, aorta, and thymus) help form the mediastinum. These organs can be considered to make a wall, the mediastinum, which separates the thorax into two cavities. The wall concept also helps explain why the pleura on the mediastinum is called parietal. In places the mediastinum is just formed by the contact between the two mediastinal pleurae. Such places may be fenestrated (perforated).

**Parts of the mediastinum:** The heart and its pericardium are located in the mediastinum, dividing it into cranial, middle, and caudal mediastinum. It also can be divided into dorsal (above the base of the heart) and ventral portions (below the top of the heart).

• **Cranial mediastinum:** part of mediastinum cranial to the heart.

• **Middle mediastinum:** part of mediastinum containing the heart.

• **Caudal mediastinum:** part of mediastinum caudal to the heart.

5. **PLEURAL CAVITIES:** the two cavities inside the pleural sacs, between the visceral and parietal layers of the pleura. Imagine the two pleural sacs as balloons of serosa blown up in the two cavities of the thoracic cavity. The space or wall between

where the two balloons abut each other on the midline is the mediastinum. The lungs grow out of the mediastinum and push the pleura ahead of them, thus, the lungs never enter the pleural cavities.

**Pleural cupula:** the cranial extent of the pleural cavity extending through the thoracic inlet. It can be mistakenly opened during caudal neck surgeries.

**Costodiaphragmatic recess:** the potential space between the costal wall and the dome-shaped diaphragm.

**Mediastinal recess:** the space filled by the accessory lobe of the right lung, between the mediastinum and the plica vena cava.

**Line of pleural reflection:** where the pleura reflects from the costal wall onto the diaphragm. Roughly, this line passes along the 8th costal cartilage and then curves dorsocaudally to the angle of the last rib. This line represents the separation of the thoracic and abdominal cavities. A needle inserted caudodorsally to this line will only enter the abdomen, one placed cranial will enter the thorax and if long enough the abdomen because of the doming of the diaphragm.

**Basal borders of the lungs:** the caudoventral border of the lungs. It parallels the line of pleural reflection, but is craniodorsal to it because the lungs do not fill the costodiaphragmatic recess. It extends from the 6th costochondral junction to the second to last intercostal space at the border of the epaxial muscles.

## CLINICAL


**Fenestrations or perforations in the mediastinum:** are found in the dog, horse and sheep. These are not found in the ox, goat, pig, or young animals of any species. In theory these could allow a unilateral pneumothorax or pyothorax to become bilateral. In reality unilateral pneumothorax is usually not fatal, but should be a consideration.

**Pneumothorax:** air or gas in the pleural space.

**Pyothorax:** thoracic empyema (accumulation of pus in a body cavity).

\* A serosa is any smooth membrane, consisting of a mesothelial layer and a connective tissue layer, lining the cavities of the body.






**Fig. VI-40 - Ox - Thoracic cavity - cross section through heart**

a. Thoracic vertebra  
b. Body wall  
c. Aorta  
d. Esophagus  
e. Rt. lung  
f. Lt. lung

g. Phrenic n.  
h. Rt. ventricle  
i. Lt. ventricle  
j. Rib  
k. Sternebra







**1. TRACHEA** (TRAY-kee-a) or windpipe: the cylindrical tube extending from the larynx down the neck into the thorax to the lungs. It terminates by bifurcating into the right and left primary bronchi above the base of the heart. The cervical part runs from the larynx to the thoracic inlet. The thoracic part continues to the bifurcation. The trachea, consisting of cartilaginous rings connected by annular ligaments, is covered by adventitia and lined by a mucous membrane.

**2. Bifurcation:** the splitting of the trachea into right and left primary bronchi above the base of the heart, just to the right of midline.

• **Tracheal carina:** the ridge at the bifurcation between the principle bronchi. Radiologists call the tracheal bifurcation the carina.

**3. Tracheal cartilages:** the "C"-shaped hyaline cartilage rings, incomplete dorsally. They make up the skeleton of the trachea and keep it open.

**Annular ligaments:** fibroelastic tissue uniting the tracheal cartilages, making the trachea a flexible tube.

**Trachealis muscle:** smooth muscle connecting the open, dorsal ends of the tracheal cartilages.

## BRONCHIAL TREE

**4. Right and left primary (principal) bronchi** (BRONG-ky) ([Gr. *bronchos*, windpipe] sin.= bronchus): the short, thick segment entering each lung's hilus to divide into lobar bronchi.

**5. Lobar ("secondary") bronchi:** the divided continuation of the principal bronchi ventilating one lobe and giving rise to segmental bronchi.

**6. Segmental ("tertiary") bronchi:** the branches of the lobar bronchi ventilating a bronchopulmonary segment.

**Bronchopulmonary segment:** a self-contained, cone-shaped section of lung tissue within a lobe.

**7. Bronchioles:** small tubes with no cartilaginous support, arising from segmental bronchi. The bronchioles are the last strictly conductive branches.

**8. Respiratory bronchioles** (BRONG-kee-ohl-es): terminal bronchioles whose walls contain some alveoli, therefore, conduct and "respire" (allow gas exchange with blood). They are present in dogs, cats, and horses.

**9. Alveolar** (al-VEE-oh-lar) **ducts:** passages from respiratory bronchioles surrounded by alveoli.

**10. Alveolar sacs:** terminations of alveolar ducts, surrounded by alveoli.

**11. Alveoli** (al-VEE-oh-ly) sin.= alveolus: thin walled sacs for gas exchange.

## SPECIES DIFFERENCES

**12. Tracheal bronchus:** the bronchus in ruminants and pigs arising cranial to the tracheal bifurcation to supply the right lung's cranial lobe.

## CLINICAL:

**Tracheostomy** (trayk-kee-OS-toh-mee): surgical opening the trachea to the outside. This usually is done in the upper neck, cranial to where the sternocephalic muscles diverge. Here the trachea is covered only by the strap muscles of the neck (sternohyoid and sternothyroid).

**Bronchus of the right middle lobe:** directed downward, thus, is a common site for infection to migrate.




Fig. VI-42 - Dog - Bronchial tree, dist end (schematic)



# LUNGS

Thorax-323




Fig. VI-43 - Dog - Lt. lung, costal surface - lat. view

Fig. VI-44 - Dog - Rt. lung, costal surface - lat. view

- a. Heart
- b. Interlobular fissure
- c. Groove for caudal vena cava
- d. Esophagus

**LUNGS** (*L. pulmones*): the paired organ of respiration occupying the thorax, and exchanging oxygen for carbon dioxide in the blood. Interlobar fissures divide the lungs into lobes. The generalized lobation pattern for domestic species is two lobes for the left lung and four lobes for the right lung. The cranial lobes of either lung can be further divided into cranial and caudal parts, depending on the species.

- |                               |   |
|-------------------------------|---|
| <b>Left lung</b>              | <b>Right lung</b>                         |
| • Cranial (apical) lobe       | • Cranial (apical) lobe                   |
| • Caudal (diaphragmatic) lobe | • Middle (cardiac) lobe                   |
|                               | • Caudal (diaphragmatic) lobe             |
|                               | • Accessory (intermediate or azygos) lobe |

**A. Apex:** the cranial end of the lungs lying in the thoracic inlet.

**B. Base:** the caudal end of the lungs resting on the diaphragm.




Fig. VI-45 - Dog - Lungs, diaphragmatic surface - caudoventr. view



Fig. VI-46 - Horse - Rt. lung, costal surface





Fig. VI-47 - Horse - Lt. lung




Fig. VI-48 - Horse - Lungs, diaphragmatic surface




Fig. VI-49 - Ox - Rt. lung, costal surface




Fig. VI-50 - Ox - Lt. lung, costal surface

	Left Lung	Right Lung
Generalized	Two lobes Cranial lobe Cranial part Caudal part Caudal lobe	Four lobes Cranial lobe Middle lobe Caudal lobe Accessory lobe
Carnivores	"	"
Pig	"	"
Ruminants	"	Four lobes, but cran. lobe divided into cran. and caud. parts
Horse	Cran. lobe not divided into cran. and caud. parts	Three lobes, middle lobe missing




Fig. VI-51 - Ox - Lungs, diaphragmatic surface

1. Trachea  
2. Lt. cran lobe  
2a. Lt. cran. part  
2b. Lt. caud. part  
3. Lt. caud. lobe  
4. Rt. cran. lobe

4a. Rt. cran. part  
4b. Rt. caud. part  
5. Rt. middle lobe (absent in horse)  
6. Rt. caud. lobe  
7. Accessory lobe  
8. Cardiac notch



# LUNGS

Thorax-325




Fig. VI-52 - Dog - Lt. lung, median surface




Fig. VI-53 - Dog - Rt. lung, median surface

## LUNG SURFACES and their IMPRESSIONS:

**Costal surface:** lies laterally against the thoracic wall.

**Medial surface:** faces the opposite lung through the mediastinum.

**1. Cardiac impression:** the impression formed by the heart on the lung's medial surface, between the 3rd and 6th rib.

**2. Diaphragmatic surface:** the concave surface conforming to the diaphragm.

**3. Hilus of the lung:** the area on the medial surface where the pulmonary bronchus and the pulmonary and bronchial vessels and nerves enter the lungs.

**Root of the lung:** the aggregation of structures entering the lung at the hilus.

**4. Cardiac notch:** the opening between lobes of the lungs where the heart sac comes in contact with the thoracic wall.

## PULMONARY VESSELS:

**Pulmonary (PUL-moh-ner'ee) trunk:** the vessel leaving the right ventricle which divides into right and left pulmonary arteries to the lungs. Upon entering the lungs the pulmonary arteries split into smaller and smaller branches paralleling the airways. These vessels do not supply the lung tissue, but exchange gases and return oxygenated blood to the heart via the pulmonary veins.

**Bronchial vessels:** supply lung tissue with oxygen. They arise from branches of the aorta.






Fig. VI-54 - Horse - Lt. lung, median surface




Fig. VI-55 - Ox - Lt. lung, median surface




Fig. VI-56 - Horse - Rt. lung, median surface




Fig. VI-54 - Ox - Rt. lung, median surface

- A. Lt. cran. lobe
- B. Lt. caud. lobe
- C. Rt. cran. lobe
- D. Rt. middle lobe

- E. Rt. Caud. lobe
- F. Accessory lobe
- G. Pulmonary a.
- H. Primary bronchi

- a. Pulmonary lig.
- b. Groove for caud. vena cava
- c. Interlobular fissure

- d. Aortic impression
- e. Impression for lt. subclavian a.
- f. Apex

- g. Esophageal impression
- h. Dors. border

## SPECIES DIFFERENCES

**Generalized pattern of lobes:** two lobes (cranial and caudal) on the left and four on the right (cranial, caudal, middle, and accessory).

**Carnivores, pig, and ruminants:** have the generalized pattern of lobes.

**Ruminants:** both right and left cranial lobes are divided into cranial and caudal parts. They also have distinct connective tissue septa in the lung tissue.

**Horse:** missing the right middle lobe, thus has only three lobes on the right, five total. The lobes are not divided by distinct fissures.

## CLINICAL

**Cardiac notch:** the site for directing a needle into the heart (cardiac puncture) without piercing lung tissue.



**PERCUSSION:** the act of striking a part with short sharp blows and listening for the sound made. This can aid in diagnosing the condition of the underlying parts. The noise of percussion is produced by three sources: 1) impact noise of a finger or hammer striking intercostal space (it is of little diagnostic value and is diminished by using a rubber hammer or the cushion of the finger); 2) vibration of the body wall; 3) resonance of the underlying air-filled cavity which acts like a drumhead. Solid structures don't resonate. Percuss with light force over an intercostal space to reduce the amount of wall in the vibration (percussion over ribs causes more of the wall to vibrate).

**Finger percussion method:** always used in small animals and more accurate in large animals. Place the middle finger over the intercostal muscle. Tap a finger just proximal to the fingernail with the tip of the middle finger of the other hand. Allow the finger to recoil. A hammer and pleximeter can be used in large animals.

**Percussing the basal border of the lung:** Systematically percuss one intercostal space at a time. Percuss two points; one over the lung and one well below the lung. Continue percussing, reducing the distance between these two points until you find the basal border. This will actually be above the anatomical border of the lung (the lung is very thin at the basal border).

**AUSCULTATION OF THE LUNGS:** listening to air passing through airways of the lungs with a stethoscope. The normal resting animal will have quiet or inaudible sounds. An excited, panting dog will have loud sounds. Normal lung sounds are louder over the trachea and its bifurcation, decreasing toward the periphery of the lungs. Normal sounds resemble wind gently rustling leaves.

## Abnormal sounds:

- **Discontinuous crackles:** intermittent, explosive sounds. They are caused by sudden opening of an airway or popping of secretion bubbles. They are associated with bronchopneumonia, interstitial pneumonia, or pulmonary edema.

- **Continuous wheezes:** caused by air passing through narrowed airways. On expiration these are associated with spasm, neoplasia, mucosal edema, foreign bodies, or tracheobronchial lymphadenopathy. On inspiration they are associated with narrowing (stenosis) of the larynx, trachea, or principal bronchi.

**Auscultation of the ox:** normal sounds are harsher and louder than in the horse.

**Auscultation triangle:** a restricted area due to the thoracic limb.

## Boundaries:

- Cranial - caudal border of triceps brachii
- Dorsally - epaxial muscles or line from caudal angle of scapula to tuber coxae
- Caudoventral - curved line from olecranon to next to last intercostal space

**LUNG BIOPSY:** must be done craniodorsal to the basal border of the lung (obviously!).

**PLEUROCENTESIS** or thoracocentesis: the surgical puncture of the chest wall for drainage of fluid. It is performed in the dependent (lowest) point on the standing animal. This is caudal to the heart and cranial to the diaphragmatic line of pleural reflection. This varies from side to side and species to species. *General rule:* puncture the middle of an intercostal space (avoid cranial and caudal branches of ventral intercostal vessels) dorsal to the costochondral junction.

- Ox: 6th or 7th intercostal space above the costochondral junction.
- Horse: 7th intercostal space above the superficial thoracic ("spur") vein.

**THORACOTOMIES:** surgical opening of the thoracic cavity. These openings can be through an intercostal space, by removal of a rib, or by splitting the sternum (mediastinotomy).

**Respiratory assistance during thoracotomies:** not needed in standing cattle because of their thick mediastinum, thus, opening one side will not collapse the opposite lung as it might in the dog.


**Vacuum of thorax:** necessary for breathing. When closing a thoracotomy, inflate the lungs maximally as the last closing sutures are placed.

**LOBECTOMY:** the removal of a lung lobe. Trauma and neoplasia are two common indications for this procedure. The bronchi and bronchial vessels must be ligated.



## Chapter VII

# Urinary System








Fig. VII-1 - Cat - Kidney

**URINARY SYSTEM:** considered part of the urogenital system, the urinary system includes the kidneys, ureters, urinary bladder, and urethra. The ureters connect the kidneys to the urinary bladder, which empties to the outside through the urethra.

**KIDNEYS** (*L. renes*): functional organs of the urinary system that filter blood and produce urine. Both kidneys are located high in the abdomen's lumbar region at the level of the thoracolumbar junction. They are retroperitoneal (behind the peritoneum) and against the crura of the diaphragm.

**1. Right kidney:** the more cranial kidney by a half-kidney length. Its cranial end is embedded in the renal impression (recess) of the liver's caudate lobe, except in the pig.

**2. Left kidney:** the more caudal kidney, except in the pig where both kidneys are at the same level.

**PERIRENAL FAT:** a mass of protective fat surrounding the kidney and holding it in place.

**FIBROUS CAPSULE:** the loosely attached (except at the hilus) capsule of collagenous and some elastic fibers. It peels away easily from the healthy kidney.

**4. ADRENAL GLANDS** (a-DREE-nal): paired glands located against the roof of the abdominal cavity at the thoracolumbar junction. Cranial to the kidneys, except in the horse where they are medial to the kidneys. They are endocrine glands producing mineralocorticoids (cortical, outer zone), glucocorticoids and sex hormones (cortical, inner zone) and norepinephrine and epinephrine (medulla). The adrenal glands are part of the sympathetic autonomic nervous system and participate in the "flight or fight" response by dumping epinephrine into the blood stream.

## SPECIES DIFFERENCES

### Shape:

- Bean-shaped and smooth (not lobated): **carnivores, small ruminants, pigs and the horse's left kidney.**
- Heart-shaped and smooth: **horse's right kidney.**
- Lobated: **ox**

**3. Capsular veins:** the normal, distinct veins under the capsule of the cat's kidney.

**Mobile kidneys:** the left kidney of the cat and ruminants hangs down into the abdominal cavity; thus, is not retroperitoneal. The rumen pushes the left kidney to the right of the median plane in ruminants.

**Location:** the right kidney is cranial to the left in all species, except the pig where they are at the same level. The cat's kidneys are a level caudal to the dog's kidneys level.

	Right kidney	Left kidney
Dog	T12-13 tp L2-3	Slightly more caudal
Cat	L1 to 4	L3 to 5
Ox	T13 to L3	L2-3 to L5
Small ruminants	T13 to L2	L4 to L6
Horse	T15-17 to L1	T16-18 to L2-3
Pig	L1 to L4	L1 to L4

## CLINICAL

**Nephritis** (ne-FRY-tis): inflammation of the kidneys.

**Phrenicoabdominal vein:** passes over the ventral surface of the adrenal gland. It is used to find the adrenal glands in surgery.



Fig. VII-2 - Dog - Kidney - dors. view





Fig. VII-3 - Horse - Kidneys - ventr. view



A. Hilus  
B. Ureter

a. Aorta  
b. Caud. vena cava  
c. Renal a. & v.  
d. Celiac a.  
e. Cran. mesenteric a.




Fig. VII-4 - Ox - Kidneys - ventr. view



Fig. VII-5 - Dog - Rt. kidney - longitudinal section




Fig. VII-6 - Horse - Rt. kidney - longitudinal section

**KIDNEY:** composed of many lobes, each lobe consists of a medullary pyramid capped by cortical tissue. The apex of the pyramid is the renal papilla. Fusion of kidney tissue accounts for the different types of kidneys.

1. **Cortex** (KOR-teks): the outer layer of the kidney parenchyma beneath the capsule; characterized grossly by its light color and granular appearance. The cortex contains the renal corpuscles and the convoluted parts of the renal tubules (Pg. 336)

2. **Medulla** (me-DUL-ah): the inner layer of the kidney parenchyma, characterized by its striated appearance. It contains collecting ducts and nephric loops.

3. **Lobes** (Fig. VII-8): the kidney units, obvious in the ox, but not in the other domestic species.

**Renal papilla** (REE-nal): the apex of a kidney lobule that drips urine into the proximal end of the ureter. The degree of fusion of the lobes results in individual papillae or a renal crest.

• 4. **Individual papillae** (Fig. VII-7): found in the ox and pig, results from incomplete fusion of the medullary pyramids.

• 5. **Renal crest:** the ridge resulting from complete fusion of the medullary pyramids, found in carnivores, small ruminants and horses.

**PROXIMAL END of the URETER:** the part of the ureter receiving urine from the renal papillae. Its shape varies depending on the species.

• 6. **Renal pelvis** (G. *pyelos* a tub or basin): the expanded proximal end of the ureters in kidneys with a renal crest (carnivores, small ruminants and horses), and in the pig (which has papillae).

• 7. **Calyx** (KAY-lik) (pl=calyces) (G. *kalyx* cup of a flower): the cup-shaped structure receiving urine from individual papillae in the ox and pig. In the ox individual calyces (KAL-iseez) empty into two branches of the ureter (sometimes called major calyces). In the pig, calyces empty into a renal pelvis.

9. **RENAL SINUS:** the potential space occupied by the ureter, branches of the renal artery and vein, and lymphatics and nerves entering the kidney.

10. **RENAL HILUS** (HY-lus): the opening into the renal sinus where the ureter and renal vessels enter the kidney.



# KIDNEYS

Abdomen-332





Fig. VII-7 - Pig - Kidney, opened

- a. Renal a.
- b. Renal v.
- c. Adrenal gland

Fig. VII-8 - Ox - Lt. kidney, opened



## SPECIES DIFFERENCES

	Papillae	Renal crest	Calyces	Pelvis
Carnivores		+		+
Horse		+		+
Small ruminants		+		+
Ox	+		+	
Pig	+		+	+

**Smooth kidneys:** appearance results from complete fusion of the kidney cortical tissue - **carnivores, horse, pig and small ruminants**. Kidneys of the dog, goat and sheep are hard to distinguish grossly.

**Pig:** has a smooth kidney due to fused cortical tissue, but has unfused medullary tissue resulting in papillae in a smooth kidney. It has no renal crest.

**Lobated kidney:** found in the ox, resulting from incomplete fusion of kidney lobes. It has calyces and papillae, but no renal pelvis.

**8. Terminal recesses - horse (Fig. VII-6):** the long tube-like


extensions that collect and carry urine from the kidney poles to the small renal pelvis. Different sources consider them either large collecting ducts or diverticulum of the renal pelvis. (To the student this argument is the least of problems!).

**Glands in the wall of the horse's renal pelvis:** secrete mucous which gives the horse's urine a turbid appearance.

All these renal terms (sinus, pelvis, hilus, crest) are confusing for the student. Organize structures into those that are part of the kidney parenchyma, those that are part of the ureter, and those that are neither.


	Kidney	Ureter	Neither
Cortex	+		
Medulla	+		
Papillae	+		
Renal crest	+		
Terminal recess	+	+	
Calyces		+	
Renal pelvis		+	
Renal sinus			+
Renal hilus			+





Dog - Cross section

Horse - Sagittal section



Pig - Sagittal section

Ox - Sagittal section

Fig. VII-9-12 - Kidneys, showing tissue of kidney & ureter

- |                   |                 |                     |                       |
|-------------------|-----------------|---------------------|-----------------------|
| 1-4. Renal tissue | 5. Renal sinus  | a. Glomerulus       | e. Pelvic recess      |
| 1. Cortex         | 6. Ureter       | b. Collecting ducts | f. Major calyx (pig)  |
| 2. Medulla        | 7. Renal pelvis | c. Medullary rays   | g. Minor calyx (pig)  |
| 3. Renal crest    | 8. Calyx        | d. Pseudopapilla    | h. Br. of ureter (ox) |
| 4. Papillae       |                 |                     |                       |







Fig. VII-13 - Horse - Abdomen, opened ventrally, viscera & caud. vena cava removed, urinary bladder opened



Fig. VII-14 - Dog - Kidney  
- cross section



- 1. Cortex
- 2. Medulla
- 3. Renal crest
- 4. Renal pelvis
- 5. Ureter
- 6. Renal a.
- 7. Renal v.
- 8. Arcuate a.

- a. Medullary ray
- b. Fat in renal sinus
- c. Pseudopapilla
- d. Pelvic recess
- e. Area occupied by pseudopapilla






Fig. VII-15 - Dog - Cast of  
renal pelvis



Fig. VII-16 - Blood supply to kidney



- A. Glomerular capsule
- B. Prox. convoluted tubule
- C. Nephric loop
- D. Dist. convoluted tubule
- E. Collecting tubule
- F. Collecting duct

- a. Pseudopapillae
- b. Pelvic recesses

Fig. VII-17 - Dog - Kidney  
- parasagittal section



## CLINICAL - KIDNEYS

**Nephrectomy** (Gr. *nephros*, kidney + *ektome*, excision): removal (excision) of a kidney. Always check that the other kidney is present and functioning first. Also check for double renal arteries.

**Nephrotomy** (Gr. *nephros* + *tome*, a cutting): surgical incision into a kidney. This can be done to remove a calculus.

**Pyelonephritis** (py'e-loh-ne-FRI-tis) (Gr. *pyelos*, pelvis + *nephros* + *itis*): inflammation of the kidney and its pelvis.

**Renal biopsy**: the removal of renal tissue for histopathological evaluation.

- **Horse**: push the left kidney per rectum against the left paralumbar fossa and direct the biopsy needle through the wall.

- **Ox**: as in the horse per rectum, but push the kidney to the right paralumbar fossa.

- **Dog**: oblique incision in the craniodorsal angle of the paralumbar fossa. Hold the kidney against the wall with a finger and insert the needle through a separate puncture site.

- **Cat**: palpate the kidney against the abdominal wall and direct the needle through the wall.

(From *Applied Veterinary Anatomy*, Habel and de Lahunta, 1986).

**Ectopic ureters**: a ureter that terminates some place other than the urinary bladder - uterus, vagina, or urethra. This results in urinary incontinence (dribbling urine). This affects small toy breeds more than large breeds. Reimplant the ureters by duplicating the oblique path through the wall of the urinary bladder to prevent reflux of urine up the ureter.

**Rectal palpation of the ureters**: possible in cattle with calculi or pyelonephritis.

**Patent (persistent) urachus**: connects the urinary bladder to the umbilicus. It usually degenerates after birth. If patent, it causes urine to dribble from the umbilicus; and should be surgically removed.

**Cystitis**: inflammation of the urinary bladder.

**Urinary calculi** (sin.=calculus): an abnormal concretion in any part of the urinary system. It is vesicular when in the bladder and renal when in the renal pelvis. Some are radiopaque and some are radiolucent.

**Cystotomy**: opening of the urinary bladder.

**Cystocentesis**: tapping of the urinary bladder with a needle to remove urine. This may be necessary to prevent rupture of a bladder in tomcats that have urethral calculi.

**NEPHRON** (NEF-ron): the microscopic, functional unit of the kidney, consisting of a urine-producing tubule and a renal corpuscle. Collecting ducts (not a part of the nephron) carry the urine produced by the nephron to the renal pelvis.

1. **Renal corpuscle** (KOR-pus'l): the glomerulus and the glomerular capsule.

2. **Glomerulus** (gloh-MER-yoo-lus): a tuft of arterial capillaries associated with the glomerular capsule.

3. **Afferent arteriole**: the small vessel entering the glomerulus.

4. **Efferent arteriole**: the small vessel leaving the glomerulus.

5. **Vascular pole of the glomerulus**: the point at which the afferent and efferent arterioles enter and leave the glomerulus.

6. **Glomerular (Bowman's) capsule**: the double-walled, cup-shaped, expanded end of the renal tubule surrounding the glomerulus. It has a visceral layer and a parietal layer.

- 7. **Visceral layer**: surrounds the glomerulus (capillary tuft).

- 8. **Parietal layer**: surrounds the urinary space, the visceral layer and the glomerulus. It is continuous with the visceral layer at the glomerulus' vascular pole.

- 9. **Urinary space or space of Bowman's capsule**: the space between visceral and parietal layers of the glomerular capsule. Fluid is filtered from the glomerulus through the visceral layer of the glomerular capsule, collects in this space, and drains into the lumen of the tubular part of the nephron.

**Tubular part of the nephron**: consists of the proximal convoluted tubule, the nephric loop, and the distal convoluted tubule.

10. **Proximal convoluted tubule**: the longest part of the nephron, a twisted tube extending from the glomerular capsule toward the medulla, where it straightens into the nephric loop.

11. **Nephric loop or loop of Henle**: descends into the medulla and then ascends to continue as the distal convoluted tubule. It has thick and thin parts.

12. **Distal convoluted tubule**: continues the nephric loop close to the glomerulus and then joins the collecting ducts.

13. **COLLECTING DUCTS**: the long tubes receiving urine from the distal convoluted tubules. They run through the medulla, joining other collecting ducts to open onto the renal crest or individual papillae as papillary ducts. These are not considered part of the nephron.

14. **Papillary ducts**: the openings of the collecting duct onto the renal crest or individual papillae, depending on the species.



# NEPHRON

Abdomen-338





Fig. VII-18 - Nephron (schematic)



Fig. VII-19 - Horse - Topographic anatomy - cran. view



- A. Rt. adrenal gland
- B. Lt. adrenal gland
- C. Rectum
- D. Deferent duct
- E. Deep inguinal ring
- F. Supf. inguinal ring
- G. Vaginal ring
- H. Parietal vaginal tunic
- I. Psoas major m.
- J. Psoas minor m.
- K. Transverse abdominal m.
- L. Int. abdominal oblique m.
- M. Rectus abdominis m.
- N. Aorta
- O. Caud. vena cava
- P. Celiac a.
- Q. Cran. mesenteric a.
- R. Testicular a.
- S. Ext. iliac a.
- T. Pudendoepigastric trunk
- U. Int. iliac a.

- a. 12th thoracic vertebra
- b. Costal cartilage
- c. Sacral ln.

2. Urinary bladder

3. Median lig.

4. Lat. lig.

**1. URETER** (yoo-REE-ter): the paired fibromuscular tubes carrying urine from the kidneys to the urinary bladder. Located retroperitoneally along the dorsal abdominal wall, each ureter runs caudally to the brim of the pelvis. They pass ventral to the ductus deferens, loop around the rectum and internal genitalia to reach the urinary bladder's dorsal surface. The ureters pass through the urinary bladder's wall at an acute angle, preventing backflow and still allowing urine to empty into a full bladder by peristaltic action.

**2. URINARY BLADDER:** the greatly distensible pouch receiving and storing urine from the kidneys for release out the urethra. The empty bladder lies almost entirely within the pelvic cavity, but with distention extends into the abdominal cavity. The bladder has a free apex, a body, and a neck.


**Trigone of the urinary bladder:** the internal area of the dorsal bladder between the two ureteral openings and the start of the urethra.

**Ligaments of the Urinary Bladder:** the three connecting peritoneal folds reflected from the urinary bladder onto the abdominal and pelvic walls. The median (ventral) ligament (3) reflects from the bladder's ventral surface to the pelvic floor and abdominal wall, as far cranially as the umbilicus. The urachus is the vestigial structure from the apex of the bladder to the umbilicus in the median ligament. The two lateral ligaments (4) connect the sides of the bladder to the lateral pelvic wall. The round ligament of the bladder, a remnant of the umbilical arteries of the fetus, travel in the edge of the lateral ligaments.



## Chapter VIII

# Reproductive System








Fig. VIII-1 - Bitch - Lt. ovary, ovarian bursa opened




Fig. VIII-2 - Bitch - Lt. ovary & uterine tube, broad lig. removed

**1. OVARIES** (OH-var-ees): the female gonads homologous to the male testicles. The ovaries are round or oval and may be nodular. They function in the maturation of the female germ cells (oocytes) and in hormone production. The visceral peritoneal covering of the ovary is called the superficial epithelium. The tunica albuginea (white tunic) is the condensed connective tissue underlying the epithelium surrounding the ovary.

**Cortex:** the outer zone of the ovary. It is composed of follicles in various stages of development, corpora lutea, and connective tissue stroma.

**Medulla:** the central area of the ovary. It contains blood vessels, nerves, lymphatics, smooth muscle fibers and connective tissue fibers.

**2. UTERINE TUBE** (YOO-ter-in) ("oviduct" or fallopian tube):

the duct running from the ovary, between the layers of the mesosalpinx (pg. 348), to the tip of the uterine horn. It conveys the oocytes or fertilized egg from the ovary to the uterus and conveys sperm toward the ovary. It is the site of fertilization of the ootid.

**3. Infundibulum** (L. funnel): the expanded, funnel-shaped ovarian end of the uterine tube.

**4. Fimbriae** (L. fringes): the irregular, finger-like projections on the free edge of the infundibulum. At ovulation, they pick up the oocyte from the surface of the ovary and direct it to the infundibulum.

**Abdominal opening of the uterine tube:** the opening in the center of the infundibulum. It is the only opening of the peritoneal cavity to the outside in the female animal. The male has no such opening.






Fig. VIII-3 - Mare - Rt. ovary & uterine tube




Fig. VIII-4 - Cow - Lt. ovary & uterine tube




Fig. VIII-6 - Sow - Ovary, mesosalpinx cut




Fig. VIII-5 - Cow - Lt. ovary, mesosalpinx moved to show ovarian bursa

- A. Mesovarium
- B. Mesosalpinx
- C. Ovarian bursa
- D. Proper lig. of ovary
- E. Mesometrium
- F. Uterine horn
- G. Suspensory lig. (carnivores)

- a. Last rib
- b. Round lig. of uterus

## SPECIES DIFFERENCES

### Location of the Ovaries:

Bitch, queen and mare: lie caudal to the kidneys in the sublumbar region.

Cow, ewe and sow: lie at the pelvic inlet due to caudal migration.

Mare: the cortex and medulla of the ovary are reversed, the

cortex being in the center surrounded by the medulla.

7. Ovulation fossa: the central depression in the mares's ovary where ovulation takes place.

## CLINICAL

Palpation of the ovaries per rectum: to determine the stage of estrus and condition of the ovary in the mare and cow.



# UTERUS

Pelvis-343




Fig. VIII-7 - Bitch - Reproductive tract, opened - dors. view

1. **UTERUS** (YOO-te-rus)(*G. hystera*): the highly expandable, tubular organ where the embryo/fetus develops.

2. **Cervix** (SER-viks)(*L. neck*): the constricted caudal part of the uterus joining the uterus to the vagina. It usually is located in the pelvic cavity.

3. **Cervical canal**: the channel through the cervix. Having openings at both ends (the internal uterine ostium and the external ostium) it is closed, except during estrus and birth.

4. **Body**: the part of the uterus between the cervix and the uterine horns. It opens into each uterine horn and into the cervix. The body of the uterus lies dorsal to the urinary bladder and ventral to the descending colon and rectum.

5. **Uterine horns**: the two musculomembraneous extensions of the uterine body which are continuous cranially with the uterine tubes. They are located entirely within the abdomen.






Fig. VIII-8 - Mare - Reproductive tract opened - dors.view

- A. Broad lig.
- B. Mesovarium
- C. Mesosalpinx
- D. Ovarian bursa
- E. Mesometrium
- G. Suspensory lig. (carnivores)

- a. Int. uterine orifice
- b. Ext. uterine orifice
- c. Ventr. commissure
- d. Fossa clitoridis
- e. Constrictor vestibuli m.
- f. Constrictor vulvae m.
- g. Openings of minor vestibular glands

## SPECIES DIFFERENCES

### Uterine horns and body:

**Carnivores and sow:** very long horns compared to their body, an adaptation for litter bearing (carrying several developing young).

**Mare:** relatively short horns, of equal length to its uterine body.

**Cow and ewe:** long horns and short bodies like the carnivores and pig. The ends of the uterine horns are coiled up like ram's

horns and continue back parallel to each other. They are bound together by the intercornual ligaments, giving the false impression of a long uterine body.


**Caruncles** (*L. carunculae*, small fleshy masses): the regularly-spaced, circular to ovoid, internal, specialized thickenings of the ruminant's endometrium, making up the maternal component of the placenta. The fetal component is the cotyledon. Together the caruncle and the cotyledon make up a placentome. The placetomes enlarge during pregnancy and can be palpated to estimate the stage of pregnancy.



# UTERUS

Pelvis-345

Fig. VIII-9 - Cow - Reproductive tract, opened - dors. view



## SPECIES DIFFERENCES

**6. Intercornual ligaments:** dorsal and ventral ligaments connecting the uterine horns in the cow and ewe.

### Cervix

**Mare and carnivores:** have a simple cervix bulging into the vagina (portio vaginalis) to form a distinct vaginal recess

(fornix).

**7. Spiral folds - cow and ewe:** have a very long cervix, characterized by transverse folds that interdigitate with each other to effectively occlude, along with the mucous secretions, the cervical canal. It is open only during estrous and parturition.

**8. Pulvini (L. pulvinus a cushion):** the mounds or cushions in the sow that interdigitate with each other, closing the canal.






Fig. VIII-11 - Sow - Reproductive tract, opened - dors. view

## CLINICAL

**Cesarean section:** removal of the fetus through incisions in the abdominal and uterine walls. It is performed most often on cows and small dogs. After the fetus is removed the uterus and abdomen are sutured closed.

**Uterine prolapse:** turning inside out of the uterus and vagina and their projection through the vulva. The prolapsed uterus can often be pushed back in and sutured in place until it heals.

**Uterine torsion:** twisting of the uterus on its long axis. It may be diagnosed by rectal palpation or vaginal exam.

**Pregnancy diagnosis in cattle and horses:** palpation of the reproductive tract per rectum to detect pregnancy.

**Intercornual ligaments (ox) (6):** grasped with a hand in the descending colon when palpating per rectum. Once grasped, it is used to flip the uterus into the pelvis for palpation of the uterus and ovaries.






Fig. VIII-12 - Bitch - Reproductive tract - median section

**1. VAGINA** (va-JY-na): the part of the reproductive tract between the cervix and the vulva. With the vestibule and vulva, it is the female's copulatory organ and the birth canal. The **hymen** is the poorly developed, vestigial, mucosal folds at the junction of the vagina and the vestibule.

**2. VESTIBULE** (VES-ti-byool) (L. *vestibulum*, antechamber): the part of the reproductive tract belonging to both the urinary and the genital systems. It connects the vagina with the external genital opening\*, the vulva.

**3. External urethral orifice**: the urethral opening at the vaginovestibular junction. This opens on a papilla, the **urethral tubercle**, in the carnivores.

**5. VULVA** (VUL-va): the external orifice that terminates the genital tract.

\*The shallow human vestibule is included in the external genitalia. In quadrupeds, where it is much longer, it is considered an internal rather than an external organ.

**6. Labia** (LAY-bee-a)(sin.= labium): the right and left lips of the vulva. The **vulvar cleft** is the opening between the labia leading into the vestibule.

**4. Clitoris** (CLI-to-ris): the homologue of the male penis, located within the ventral commissure of the vulva. The clitoris has left and right crura that attach to the ischiatic arch. The crura come together to form the body. The glans is the only exposed part of the clitoris. The glans is in the clitoral fossa surrounded by the clitoral prepuce.

**7. FEMALE URETHRA** (yoo-REE-thra): the tube transporting urine from the urinary bladder through the external urethral orifice to the vestibule.

**Urethral (urethralis) muscle**: the skeletal muscle covering the lateral and ventral sides of the urethra. The sphincter formed by the urethral muscle is under voluntary control.






Fig. VIII-13 - Cow - Reproductive tract  
- median section

### SPECIES DIFFERENCES

**8. Vaginal fornix (recess):** the cranioventral recess formed by the cervix bulging into the vagina (portio vaginalis) in the mare and bitch. The cow and ewe have a craniodorsal recess.

**Vestibular bulbs:** the organized erectile venous plexuses in the vestibular walls of the mare and bitch. During the dog's "tie" the bulbs are erect and press against the penis caudal to the enlarged bulb of the glans.

**9. Suburethral diverticulum:** the blind pocket just cranial and ventral to the external urethral opening in the sow and cow. This is clinically important when catheterizing a cow.

**Vestibular glands:** open into the vestibule and lubricate the reproductive organs during parturition and copulation. The cow, queen, and sometimes the ewe have major vestibular glands

("glands of Bartholin"); the bitch, ewe, mare and sow have minor vestibular glands.

**Os clitoridis:** a homologue os penis is found radiographically in some bitches.


### CLINICAL

**Vaginal smears:** the use of microscopic slides of vaginal secretions in the bitch to determine the stage of estrus.

**"Windsuckers" (pneumovagina):** a conformational defect in the mare in which the vaginal opening is deeply located and the lips of the vulva don't close properly. This becomes a reproduction problem when feces falls into or urine pools in the vestibule.



**Fig. VIII-14 - Bitch**  
- Genital tract  
- lat. view



**Fig. VIII- 15 - Bitch - Lt. ovary, ovarian bursa opened**

**BROAD LIGAMENT:** the fold of connecting peritoneum (serosa) connecting the visceral peritoneum of the female reproductive tract to the parietal peritoneum of the abdominal wall. It is subdivided into portions supporting individual parts of the reproductive tract: mesovarium, mesosalpinx and mesometrium.

**1. Mesovarium** (mes'oh-VAY-ree-um): the cranial part of the broad ligament attaching the ovary to the dorsolateral abdominal wall.

**2. Proper ligament of the ovary or ovarian ligament:** the caudal continuation of the mesovarium's cranial free edge connecting the ovary to the end of the uterine horn.

**3. Mesosalpinx** (mes'oh-SAL-pinks) (G. *salpin* tube or trumpet): the lateral fold arising from the mesovarium that holds the uterine tube between its two layers. The mesosalpinx is the only portion of the broad ligament not directly attached to the abdominal wall.

**4. Ovarian** (oh-VAR-ee-an) bursa: the small peritoneal cavity formed by the mesosalpinx and mesovarium into which projects the ovary.

**Mesometrium** (mes'oh-MEE-tree-um): the part of the broad ligament attaching the uterine horns and body to the dorsolateral body wall. The round ligament of the uterus (e) is the caudal continuation of the proper ligament of the ovary and is located in






Fig. VIII-16 - Mare - Genital tract - lat. view

the free edge of a secondary fold off the mesometrium. It extends through the inguinal canal.

## Structures associated with the broad ligament:

**Ovarian vessels:** the blood supply to the ovary traveling in the mesovarium.

**Uterine vessels:** the blood supply to the uterus traveling in the mesometrium. Upon reaching the uterus they course cranially along the sides of the uterus and uterine horns to anastomoses with the uterine branches of the ovarian arteries and veins.

## SPECIES DIFFERENCES

**6. Suspensory ligament of the ovary:** the mesovarium's cranial free edge attaching the ovary to the last rib, present only in the carnivores.

**Mesosalpinx:** completely covers the ovary, except for a small slit in the bitch. In the cow, sow and mare it is less extensive, just "draping" over the ovary.

**Cow:** the broad ligament is attached along the pelvic inlet instead of the dorsolateral body wall. The horns of the uterus coil back on themselves, placing the ovaries just cranial to the brim

of the pelvis; much farther caudal than the other domestic species.

**7. Vaginal process:** the evagination of the parietal and visceral peritoneum through the inguinal canal (in the carnivores). It contains the round ligament of the uterus.


## CLINICAL

**Suspensory ligament of the ovary (6):** broken when spaying a bitch to bring the ovary to the incision site.

**Ovariohysterectomy or "spay":** removal of the ovaries, uterine tubes, and uterus. (This is a veterinarian's "bread and butter"). A midline incision is made through the linea alba (make it large, not a "key hole" incision). Find a uterine horn. Pull this toward the incision. With a finger strum the suspensory ligament to break it down so the ovary can be brought to the skin incision. Ligate the ovarian vessels in the mesometrium. Follow the uterine horn back to the body and up the other horn to find the other ovary. Ligate its ovarian vessels. Break down the broad ligament back to the uterine body. Clamp and ligate the uterine body and uterine arteries together or separately. Sever the uterine body and remove it, the horns, and ovaries. Close the animal.



Fig. VIII-17 - Horse - Abdominal cavity, topographical - caud. view



- 1-2. Broad lig.
- 1. Mesovarium
- 2. Mesometrium
- 3. Ovary
- 4. Uterine horn
- 5. Body of uterus
- 6. Urinary bladder
- 7. Ovulation fossa (horse)
- 8. Dors. intercornual lig. (ruminants)

- A. Epaxial mm.
- B. Hypaxial mm.
- C. Rectus abdominis m.
- D. Ureter
- E. Aorta
- F. Caud. vena cava
- G. Ovarian a.
- H. Uterine a.
- I. Descending colon
- a. Lat. lig. of bladder
- b. Med. lig. of bladder
- c. 5th lumbar vertebra
- d. Abdominal wall
- e. Mesocolon




Fig. VIII-18 - Cow - Abdominal cavity, topographical - caud. view







Fig. VIII-19 - Ox - Pelvic region - sagittal section

- |                          |                              |                            |
|--------------------------|------------------------------|----------------------------|
| A. Descending colon      | G. Teat                      | M. Rectus abdominis m.     |
| B. Sigmoid loop of colon | H. Sacrum                    | N. Rt. internal iliac a.   |
| C. Rectum                | I. Coccygeus m.              | O. Rt. external iliac a.   |
| D. Anus                  | J. Levator ani m.            | P. Pudendoepigastric trunk |
| E. Retroperitoneal area  | K. Transverse abdominal m.   | Q. Ext. pudendal a.        |
| F. Body of udder         | L. Int. abdominal oblique m. |                            |





- a. Allantoic cavity
- b. Yolk stalk
- c. Urachus
- d. Umbilical stalk

Fig. VIII-20 - Horse - Extraembryonic membranes (schematic)

**EXTRAEMBRYONIC MEMBRANES:** membranes formed around the embryo for protection and implantation in the maternal endometrium.

**1. Amnion:** the inner embryonic membrane surrounding the amniotic cavity and fetus.

**2. Amniotic cavity:** the cavity encompassed by the amnion and filled with amniotic fluid, providing the fluid environment that protects the fetus.

**3. Chorion:** the outer embryonic membrane surrounding the allantoic cavity, amnion, amniotic cavity, and fetus. This layer makes up the fetal component of the placenta.

**4. Allantois:** an evagination from the hindgut. This extraembryonic membrane lines the inside of the chorion, forming the chorioallantoic membrane. It also lines the outside of the amnion, forming the allantoamnion. This layer provides the vasculature to the two membranes (chorion and amnion) it lines.

**5. Chorioallantois:** the fused chorion and allantois.

**PLACENTA:** the structure formed by apposition of fetal and maternal tissue. It functions to exchange nutrients and oxygen

from the mother to the fetus; and waste products from the fetus to the mother. It also has endocrine functions and forms a barrier between fetal and maternal blood.

**Fetal Component:** formed by the three layers of the chorioallantoic membrane, as follows:

**6. Fetal endothelium:** lines the allantoic blood vessels.

**7. Fetal connective tissue of the chorioallantois:** mesoderm surrounding the blood vessels.

**8. Chorionic epithelium:** the surface layer of the chorioallantoic membrane.

**Maternal Component:** consists of three layers of the endometrium (uterine mucosa), as follows:

**9. Maternal epithelium of the endometrium (uterine lamina epithelialis).**

**10. Maternal connective tissue:** surrounds the vessels of the endometrium.

**11. Maternal endothelium:** lines the vessels of the endometrium.



## SPECIES DIFFERENCES:

**A. Epitheliochorial placenta:** has all six layers (three fetal and three maternal), seen in the horse, pig, and ruminants.

- **Adeciduate** (a=not, deciduus=falling off) placenta: the maternal component is not sloughed during birth (horse and pig).

- **Partially deciduate placenta:** part of the endometrium (maternal component) is sloughed off (ruminants).

**B. Endotheliochorial placenta:** found in the carnivores. The maternal epithelium and connective tissue layers are absent, the maternal endothelium being in direct contact with the chorionic epithelium.

- **Deciduate placenta:** found in carnivores, the maternal endometrium is lost during birth.





Fig. VIII-22 - Placentae

## A. EPITHELIOCHORIAL



## B. ENDOTHELIOCHORIAL

Fig. VIII-21 - Placental components

**CLASSIFICATION of the PLACENTA:** shape and vascular arrangement of the apposition of maternal and fetal tissues.

**12. Diffuse placenta:** horse and pig; apposition over most of the chorioallantois by villi and microvilli evaginating into the endometrium.

**13. Cotyledonary placenta or placentomes:** found in ruminants where apposition is in discrete areas.

**Placentome:** the functional, discrete placental part consisting of a connected cotyledon and caruncle found in the ruminants. In the cow it is dome-shaped, in the small ruminant it has a dent in its top.

- **14. Cotyledon:** the fetal component of the placenta that forms villous processes that interdigitate with the maternal components.

- **15. Caruncles:** the maternal component consisting of discrete units scattered over the endometrium. They are proliferations of the connective tissue and are also found in non-pregnant animals.

**16. Zonary placenta:** found in carnivores, a broad band of apposition of maternal and fetal tissue around the transverse circumference of the chorioallantois.



Determining the stage of estrus or pregnancy in cattle is economically very important to the cattleman. This can be done by systematic, gentle, and efficient rectal palpation. To orient yourself, once in the rectum, find the cervix. It is a firm cylinder that may be over the brim of the pelvis or completely in the abdomen, depending on the stage of pregnancy. Sweep your open hand over the brim of pelvis to locate it. Next, retract the uterus into the pelvic cavity of cows open (not pregnant) or less than 90 days pregnant. If over 90 days pregnant, this can't be done. To retract the uterus, move cranially to the cervix to the uterine horns and locate the intercornual ligaments. Grasp the ventral intercornual ligament and flip the uterine horns and ovaries into the pelvic cavity.

Palpate the entire length of the uterine horns for consistency. An empty horn will have a meaty consistency. A pregnant horn will be fluid filled with resiliency and fluctuation.

There are four criteria to use to diagnose a positive pregnancy: 1. Palpable amnionic vesicle; 2. Slip of fetal membranes; 3. Palpable fetus; and 4. Palpable placetomes.

**Amnionic vessel:** can be palpated from 30 to 65 days of gestation (after 65 days it is too large and soft to palpate). It is found in the most distended part of the horn with the thinnest wall. It should not be used routinely to diagnose pregnancy because this may cause abortion.

**"Membrane slip":** chorioallantoic membranes can be felt at 30 to 35 days post breeding (with practice). Grasp the horn with the thumb and finger and let it slip through. The membrane will pass through first, followed by the uterine wall. The membrane "slip" feels like a taut string slipping lengthwise between the finger and thumb.

**Placetomes:** small ones can be detected at 70 to 75 days. They increase in size as pregnancy continues. Do not mistake one for an ovary!

**Fetus:** fairly reliable indication of pregnancy! It can be palpated after 65 to 70 days.

**Uterine (middle uterine) artery:** can be palpated going to the gravid horn at 85 to 90 days of gestation. A "buzzing" sensation, fremitus, can be palpated at 90 to 120 days in the artery. The movable uterine artery travels in the broad ligament to the horns of the uterus. By rectal palpation, run your fingers from the abdominal cavity to the pelvic cavity along the lateral wall. The first artery encountered is the immovable external iliac artery coursing down the cranial edge of the shaft of the ilium. The next artery is the movable uterine artery.

Common errors in pregnancy diagnoses are mistaking the urinary bladder and the rumen for the uterus. Pregnancy diagnosis is important to cattlemen between 35 and 120 days after

the bull has been taken away from the herd. If the cow is open (not pregnant), the cattlemen need to know when she will come into heat (estrus) again so she can be covered (bred). If the horns are empty (non-pregnant), palpate the ovaries to determine the stage of estrous.

**Palpation of the ovaries and uterus:** in conjunction with the chart, can tell the stage of estrous the animal is in. Thus, it can be estimated how long before the cow comes back into heat and will be ready to breed.

The ovaries are located on the ventrolateral margin of the pelvic inlet, just cranial to the external iliac artery. Pregnancy draws the ovaries forward. To palpate the ovaries they should be retracted by grasping the ventral intercornual ligament and flipping the horns and ovaries into the pelvic cavity.

**F (Mature follicle):** a spherical mass of cells containing a cavity and ovum (egg, female sexual cell). This is a soft, fluctuating structure that can be identified during rectal palpation.

**OVD (Ovulation depression):** the depression left in the mature follicle after ovulation, usually lasting 24 hours.

**CH (Corpus hemorrhagicum):** a ruptured follicle filled with blood. It is a soft, but not fluctuating, elevation on the ovary. Depending on its size, it is classified as a CH1 (1 cm), CH2 (1-2 cm) or CH3 (larger than 2 cm).

**CL (Corpus luteum):** results when the blood in a corpus hemorrhagicum is replaced by cells that produce hormones (progesterone). It feels firm to hard and is classified, depending on size, into CL3 (greater than 2 cm and firm), CL2 (1-2 cm and firm) and CL1 (1 cm and hard).

**S (Static ovary):** an ovary in which no follicle, corpus hemorrhagicum or corpus luteum can be felt.

**Uterus:** palpating the uterus can also indicate the stage of estrus and should be correlated to what is found on the ovaries.

UN - uterus normal


UT - uterus turgid

UE - uterus edematous

**Abbreviations used are:** F, follicle; OVD, ovulation depression, CH1, corpus hemorrhagicum 1 cm. in diameter (soft); CH2, 1-2 cm (soft); CH3, 2 cm. (soft) CL3, corpus luteum (fully developed); CL2, 1-2 cm. (firm); CL1, 1 cm. (hard); S, static; UT, uterus turgid; UE, uterus edematous; UN, uterus normal.

Chart from R. Zemjanis, "Diagnostic and Therapeutic Techniques in Animal Reproduction" 2nd ed. 1970, Williams & Wilkins-Baltimore





Correlation of findings indicative of stage of estrus cycle & time to next estrus

Findings in ovaries & uterus			Approx. estrus cycle	Days to predict estrus	
Rt. ovary	Lt. ovary	Uterus			
F	CL1	UT		20 - 21	0
OVD	CL1	UT		0	18 - 21
CH1	S	UT		1 - 3	19 - 20
CH2	S	UE		3 - 5	15 - 18
CH3	S	UN		5 - 7	13 - 17
CL3	F	UN		7 - 17	6 - 11
CL2	F	UT		17 - 19	1 - 4
CL1	F	UT		20 - 21	0 - 1






Fig. VIII-20 - Dog - Testicle, epididymis & deferent duct (schematic)

1. **TESTICLE** or **TESTIS** (TES-tis) (pl.= testes): the male gonad that produces both testosterone (male sex hormone) and spermatogonia, the male germ cell that differentiates into sperm. The testicles are contained in the scrotum and vary considerably in shape and size among the species.

A. **White tunic** or **tunica albuginea**: the strong, white, fibrous capsule enveloping the testicle.

B. **Mediastinum testis**: the cord of fibrous tissue running through the middle of the testicle, containing the rete testis. **Septae**, webs of connective tissue, radiate from the mediastinum to the tunica albuginea, dividing the testicle into numerous lobules.

C. **Lobules**: the units of the testicle, each contains a few seminiferous tubules.

D. **Seminiferous tubules** (sem'i-NI-fer-us TOO-byools): the hollow structures in which germ cells differentiate to spermatozoa. The major part of the tubules are the convoluted seminiferous tubules, where sperm production occurs. The straight seminiferous tubules are the short, straight part near the mediastinum. They do not produce sperm.

E. **Rete (REE-tee) testis**: the network of irregular, interconnecting channels continuing as the straight seminiferous tubules through the mediastinum to the efferent ductules.

F. **Efferent ductules**: the 8-15 channels leading into the head of the epididymis; they unite to form the epididymal duct.

G. **EPIDIDYMAL DUCT** (ductus epididymidis): the continuous, coiled channel forming the epididymis between the efferent ductules and the deferent duct.

2. **EPIDIDYMIS** (Ep'i-DID-i-mis): the structure adjacent to the testicle formed by the epididymal duct. The head (a) of the epididymis, consists of the efferent ductules and the first part of the epididymal duct. The body (b), the central part, consists of the highly coiled epididymal duct connecting the head and tail of the epididymis. The tail (c), the bulbous end of the epididymis, continues on as the ductus deferens. Spermatozoa mature in the head and body of the epididymis and are then transferred to the deferent duct as fertile sperm.

3. **PROPER LIGAMENT OF THE TESTICLE**: connects the tail of the epididymis to the testicle.

4. **SCROTAL LIGAMENT** and **LIGAMENT OF THE TAIL OF THE EPIDIDYMIS**: connects the tail of the epididymis to the scrotum. They are divided by the visceral vaginal tunic (pg. 362), into the part outside the tunic, the scrotal ligament; and the part inside the vaginal tunic, the ligament of the tail of the epididymis.




Fig. VIII-21 - Dog - Testicle



Fig. VIII-22 - Stallion - Lt. testicle  
- lat. view






Fig. VIII-23 - Stallion - Lt. testicle - med. view



**5. DUCTUS DEFERENS**, deferent (DEF-er-ent) duct (d) or "vas deferens": the continuation of the epididymal duct at the tail of the epididymis. It travels beside the body of the epididymis, up the spermatic cord, and through the inguinal canal to reach the abdomen. In the abdomen, it arches caudally to the pelvic cavity passing through the prostate gland to open into the pelvic urethra.

**Ampulla** (am-PYOOOL-a): the enlarged terminal end of the ductus deferens, absent in the boar and tomcat. Its wall is very glandular, causing an increase in the diameter of the duct, but not in the diameter of the lumen.

Fig. VIII-25 - Boar - Lt. testicle  
- lat. view.



- a. Head of epididymis
- b. Body of epididymis
- c. Tail of epididymis
- d. Visceral vaginal tunic
- e. Mesorchium
- f. Cremaster m.
- g. Skin
- h. Spermatic cord

Fig. VIII-24 - Cat - Rt. testicle  
- lat. view





Fig. VIII-24 - Bull - Rt. testicle  
- caudomed. view





# DESCENT OF THE TESTICLES

Pelvis-359

**DESCENT of the TESTICLES:** The testicles begin fetal development within the abdomen behind the kidneys. The epididymis and deferent duct connect the testicle caudally to the urethra. The gubernaculum, a jelly-like cord, extends from the testicle to the tail of the epididymis and then into the inguinal canal. The testicle, the epididymis, and the ductus deferens develop retroperitoneally, between the peritoneum and the body wall. They are thus, covered by visceral peritoneum, that is continuous with the parietal peritoneum. During development, the knoblike, free end of the gubernaculum, covered with visceral and parietal peritoneum, lies through the inguinal canal of the developing abdominal wall. The testicle and epididymis move caudally, following the gubernaculum through the inguinal canal and into the scrotum. Moving through the inguinal canal, the testicles carry their visceral peritoneum. They also pick up the parietal peritoneum and the fascial layers of the inner and outer abdominal wall. Once outside the abdominal cavity, the two peritoneal layers become known as the vaginal tunic (vaginal process). The gubernaculum shrinks to become the proper ligament of the testicle, the ligament of the tail of the epididymis, and the scrotal ligament.

## Time of descent of the testicles:

- Ruminants and pig: before birth.
- Carnivores: shortly after birth.
- Horse: 10-14 days before or after birth.

## CLINICAL

**Inguinal hernia:** the protrusion of a loop of organ or tissue through the inguinal canal. They are common and hereditary in the horse and pig. Affected animals should not be used for breeding. Preferably, they should be castrated so they will not produce this defect.

- **Direct inguinal hernia:** when herniated tissue explodes directly through the wall of the abdomen, without bothering to weave down the inguinal canal.

- **Indirect inguinal hernia:** when herniated tissue passes down the inguinal canal.

**Castration:** the removal of the gonads – testicles (and epididymis) in the male, ovaries in the female. The uterus is usually removed with the ovaries (spay, ovariectomy). "Closed" and "open" castrations refer to whether the abdomen has or has not been opened.

**"Open technique":** opens the abdominal cavity by cutting through the parietal vaginal tunic and opening the vaginal cavity, thus, the abdominal cavity. The spermatic cord, covered only by the visceral vaginal tunic, is ligated and then the cord is cut distal to the ligation.

**"Closed technique":** a castration that does not cut through the parietal vaginal tunic, thus, doesn't open the abdominal cavity. The parietal and visceral vaginal tunics and the spermatic cord are ligated. The cord is then transected distal to the ligation, therefore, the abdominal cavity is never opened.

**Emasculator:** an instrument used in castration of large animals. It has two closely connected parts; one crushes the vessels and spermatic cord and the other, at the same time, cuts the cord distally to the crush. *Memory Aid:* The emasculator's nut and cutting part are on the same side. The saying "nut to nut" when using an emasculator insures the cut will be distal to the crush.

**Castration of a calf:** "closed technique" at 1-8 weeks. The bottom of the scrotum is cut off and the tunic-covered testicles pulled distally. The parietal vaginal tunic is left closed as an emasculator crushes and cuts the spermatic cord.

**Castration of a piglet:** "open technique" in the first 3 weeks of life. With the piglet held up by its hocks, each testicle is pushed cranially and the skin over it incised. The testicle is pulled through the incision and the scrotal ligament broken. Maintaining traction on the testicle, the tunic-covered cord is scraped until it breaks (thus, opening the vaginal cavity) with a sterile scalpel.

**Castration of the cat:** "open technique" after 6 months. The plucked scrotum is incised over each tunic-covered testicle to free it from the scrotum. Each testicle, inside the unopened vaginal tunic, may be pulled until the cord tears away, opening the tunic ("pull technique"). (For those new veterinarians that don't want to be forced to use this technique by their first employer, develop speed in some other technique.) Alternatively, the parietal vaginal tunic may be incised and the spermatic vessels and deferent duct tied together, or all the structures of the cord may be ligated.

**Castration of the dog:** "open or closed technique" after 6 months. The testicle is pushed cranially and the skin over it incised. Each testicle is pushed through this incision. The spermatic cord can then be ligated ("closed"). To do an open castration, the parietal vaginal tunic is cut and moved proximally off the cord. The mesorchium is then broken; the structures of the cord ligated and cut.


## CASTRATION INCISIONS

Two scrotal incisions are used in horses, cats and older pigs.

One prescrotal incision is used in the dog.

Amputation of the distal scrotum or two scrotal incisions are used in the ruminants.







# CRYPTORCHIDISM

Pcivis-361




Fig. VIII-27 - Horse

The retained testicle can be anywhere between the scrotum and the caudal pole of the kidney.

**Stallion:** cryptorchidism is often called "ridglings", "originals" or "rigs" in the horse.

- **Inguinal cryptorchid:** the most common has an undeveloped testicle in the canal or just outside the superficial inguinal ring ("high flanker").

- **Descended epididymis:** when the tail of the epididymis and the ductus deferens are located in the inguinal canal and the testicle in the abdomen, just inside the vaginal ring.

- **Complete abdominal cryptorchid:** when the testicle and the epididymis lie within the abdominal cavity.

The undescended testicle should be removed. As abdominal surgery should be avoided whenever possible in the horse, the best approach is through the skin over the inguinal canal. Palpation of the inguinal region or rectal palpation may locate the cryptorchid. In an inguinal cryptorchid, incise over the inguinal canal and locate and remove the testicle. A descended epididymis can also be found by this approach. Once found it can be used to pull the testicle out. With a complete abdominal cryptorchid, try to find the gubernaculum and follow this through the inguinal canal to the tail of the epididymis and the testicle.

## CRYPTORCHIDISM

**HORSE CASTRATION:** both the "opened" and closed" techniques employ two separate incisions in the scrotum, between 1 and 2 years of age.

**"Open technique":** pull each testicle through its scrotal incision. Incise the parietal vaginal tunic. With an emasculator crush the ductus deferens, cremaster muscle and parietal vaginal tunic. Then crush the spermatic vessels. Enlarge the scrotal skin incisions for drainage.

**"Closed technique":** should be done in a sterile environment. Pull the tunic covered testicles through the scrotal incisions. Place a suture knot in the cremaster muscle and then bring suture around the cord and tie tightly. Transect the cord distal to the ligature. Enlarge the scrotal skin incisions for drainage. The ligature is a possible nidus for infection and is why this should be done in a sterile environment. An emasculator is not used in the closed technique for fear of the testicular artery slipping out of the crushed tissue.

**CRYPTORCHIDISM:** failure of one or both testicles to descend into the scrotum.





Fig. VIII-28 - Horse - Removal of complete retained testicle



Fig. VIII-29 - Horse - Caud. abdomen - cross section



a. Epaxial m.  
 b. Lumbar vertebra  
 c. Psoas major m.  
 d. Caud. vena cava  
 e. Aorta  
 f. Mesorchium

g. Int. abdominal oblique m.  
 h. Aponeurosis of ext. abdominal oblique m.  
 i. Rectus abdominis m.  
 j. Spermatic cord

k. Vaginal ring  
 l. Urinary bladder  
 m. Lat. lig. of bladder  
 n. Prepubic tendon  
 o. Inguinal lig.



## SPERMATIC CORD

Pelvis-363

**SPERMATIC CORD:** the structure extending from the testicle through the inguinal canal; consisting of the ductus deferens, the testicular vessels and nerves, and the lymphatics and their serous coverings.

**Vaginal tunic:** the double wall of serous membrane (visceral and parietal) around the spermatic cord and testicle in the male and the round ligament of the uterus in the female.

1. **Visceral vaginal tunic:** the continuation of the abdominal visceral peritoneum tightly investing the structures of the spermatic cord and the testicle.

2. **Parietal vaginal tunic:** the continuation of the abdominal parietal peritoneum through the inguinal canal. It surrounds the visceral vaginal tunic-covered spermatic cord and testicle.

3. **Mesorchium or connecting vaginal tunic:** the serosal fold connecting the visceral vaginal tunic with the parietal vaginal tunic. It is similar to the connecting serosa between the parietal peritoneum lining the abdominal walls and the visceral peritoneum covering the gut.

• **Mesoductus:** the fold of connecting vaginal tunic between the mesorchium and the ductus deferens.

• **Mesofuniculus:** the part of the mesorchium between the parietal vaginal tunic and where the mesoductus arises.

4. **Vaginal cavity:** the potential space between the two vaginal tunic layers. It is continuous with the peritoneal cavity at the vaginal ring.

5. **Vaginal ring:** the crescent-shaped opening located on the abdominal side of the deep inguinal ring. It is formed by the evagination of the parietal peritoneum through the inguinal canal.

6. **Pampiniform plexus:** the coils of the testicular veins around the testicular artery, making up the bulk of the spermatic cord. It functions to draw heat from the testicular artery, cooling the blood before it reaches the testicle.

7. **Testicular artery:** the convoluted artery supplying the testicle and arising from the abdominal aorta.

8. **Spermatic fascia:** the inner and outer abdominal fascia that, along with the peritoneum, invest the testicle as it passes through the inguinal canal.

**Uterus masculinus:** the remnant of the paramesonephric duct. It is usually present between the layers of the genital fold and between the ampulla of the ductus deferens in the horse. It is also often found in the bull.

### CLINICAL

Each ductus deferens loops dorsally over the ureter. This makes it possible to dislodge the ureters when using the "technique" to neuter a tomcat.



testicular a., v., n. & lymphatics

2. Parietal vaginal tunic

1. Visceral vaginal tunic

Deferent duct

8. Spermatic fascia

5. Vaginal ring

Fig. VIII-28 - Dog - Spermatic cord (schematic) - cross section

3. Mesorchium

6. Pampiniform plexus

Body of epididymis

4. Vaginal cavity

Head of epididymis


Testicle

Tail of epididymis

Fig. VIII-27 - Dog - Testicle (schematic of vaginal tunic)



Fig. VIII-29 - Dog - Pelvic cavity, sacrum removed  
- dors. view



**ACCESSORY SEX GLANDS:** the glands associated with the urethra that add the liquid portion to the ejaculate. They differ among the species and consist of the prostate, vesicular, and bulbourethral glands. Some consider the ampullae of the deferent ducts an accessory sex gland.

**1. Prostate gland (PROS-tayt):** adds prostatic secretions to the ejaculate to provide an optimum environment for sperm survival and motility. Present in some form in all the domestic species, it may consist of a visible body, surrounding the neck of the bladder; a disseminate part, consisting of lobules in the wall of the pelvic urethra; or both. The ductus deferens run through the gland to open into a papilla, the *colliculus seminalis*, in the dorsal part of the pelvic urethra. The prostatic ducts open into the entire length of the pelvic urethra.

**2. Vesicular glands:** the paired structures located dorsolateral to the neck of the bladder. They are present in the stallion, ruminant, and boar. They secrete an alkaline fluid rich in fructose into the urethra.

**3. Bulbourethral ("Cowper's") glands:** the paired glands on the dorsocaudal aspect of the pelvic proximal urethra near the bulb of the penis.

**MALE URETHRA:** the common passageway for sperm and urine extending from the bladder to the external urethral orifice. The pelvic part extends from the neck of the bladder to the pelvic outlet; its cranial portion (prostatic urethra) travels through the prostate, while the urethralis muscle encloses the rest. The penile or cavernous part (*pars spongiosa*) begins where the urethra enters the bulb of the spongy body (*corpus spongiosum*). The spongy body (*corpus spongiosum*) encircles the urethra to its external opening. The *colliculus seminalis* is a mound projecting from the dorsal part of the prostatic part of the urethra.

**4. Urethral muscle (m. urethralis):** the skeletal muscle enclosing the distal part of the pelvic urethra.

**External urethral opening:** the opening to the outside of the body, located at the tip of the penis.



# ACCESSORY SEX GLANDS

Pelvis-366




Fig. VIII-28 - Horse - Removal of complete retained testicle




Fig. VIII-32 - Boar Genital organs - dorsolat. view




Fig. VIII-31 - Bull Genital organs - dors. view

## SPECIES DIFFERENCES

**Stallion, ruminants and boar:** have all three.

**Dog:** has only a prostate gland. It has two lobes completely surrounding the urethra.

**Tom cat:** has prostate and bulbourethral glands, but no vesicular gland. The prostate does not completely surround the urethra ventrally.

**Small ruminants:** lack a prostatic body, having only a disseminate part, which can not be seen grossly.

**Boar:** its bulbourethra are two large cylinders extending cranially along the pelvic urethra covered by bulboglandularis muscle.

**Horse:** its vesicular gland has a lumen, therefore, is often called the seminal vesicle. The prostate does not contain a disseminate part; it has two lobes connected by an isthmus.

**Seminal vesicle:** the name of the vesicular gland in the horse because it has a lumen.


**Common excretory duct:** the duct of the ductus deferens and the vesicular gland in the horse, ruminant, and possibly the boar, which opens on the colliculus seminalis.

## CLINICAL

**Inflammation or hyperplasia of the prostate:** infection or increased growth of the prostate, occurring mainly in dogs.



**Fig. VIII-33 - Dog - Male genital organs**



**PENIS** (L. tail): the male copulatory organ, extending from the ischiatic arch cranially (except in the cat) between the thighs. The penis provides a passageway for semen and urine to the outside of the body, thus, is a part of both the urinary and genital systems.

**1. Root:** the proximal part of the penis attaching to the ischial arch. The root consists of the bulb of the penis and crura of the penis.

**2. Body:** the main part of the penis between the root and the glans.

**3. Glans:** the distal free part of the penis.

**CLASSIFICATION:** penises are classified according to their connective tissue content into fibroelastic and musculocavernous types.

**FIBROELASTIC PENIS:** characteristic of ruminants and the boar. The large connective tissue content causes them to be firm even when they are not erect. Erection is characterized by greatly increasing the length (straightening of the sigmoid flexure) and stiffening from engorgement with blood, without an increase in diameter.

**MUSCULOCAVERNOUS PENIS:** characteristic of carnivores






Fig. VIII-34 - Boar - Male genitalia - lat. view

and the horse. The low connective tissue content causes them to be flaccid when not erect. Erection is accomplished by engorgement of erectile tissue with blood, increasing the length and the diameter of the penis, while stiffening it.

**4. PREPUCE** (PREE-pyoos) (L. *preputium* foreskin): the cutaneous sheath around the free part of the penis in the quiescent state (nonerect). It has an inner lamina continuous with the skin over the glans penis. Its outer lamina is continuous with the skin on the abdomen.

**5. Preputial orifice:** the external opening of the prepuce to the outside environment.

**Preputial cavity:** the space between the prepuce and the glans of the penis in the nonerect state.

## SPECIES DIFFERENCES

**Tom cat's penis:** directed caudoventrally when not erect. All the other species are directed cranioventrally. Upon erection it faces cranioventrally like the rest.

**Os penis (baculum):** the bone found in the penises of carnivores. (The os penis of coyotes is sometimes called the "prospector's toothpick"! In the dog (not the cat) its ventral surface is grooved for the urethra.

**6. Preputial diverticulum:** a blind pocket in the dorsal wall of the boar's prepuce. It is partially divided midsagittally by a septum. Trapped material in this diverticulum gives the boar its characteristic odor.



Fig. VIII-35 - Billy Goat - Male genitalia  
- lat. view





Fig. VIII-36 - Stallion - Musculocavernous penis - lat. view



1. Root of penis
2. Body of penis
3. Glans penis
4. Prepuce
- a. Head of epididymis
- b. Body of epididymis
- c. Tail of epididymis
- A. Testicle
- B. Epididymis
- C. Deferent duct
- D. Prostate gland (only disseminate part in sm. ruminant)
- E. Vesicular gland (absent in carnivores)
- F. Bulbourethral gland (absent in dog)
- G. Urinary bladder
- H. Male urethra
- I. Ampulla of deferent duct

## SPECIES DIFFERENCES

**Horse's prepuce:** because of the great length attained on erection of the penis, the prepuce needs to be proportionately long or it would tear from the body whenever the horse gets excited. Instead of having a long prepuce that would drag the ground, it has an extra fold inside the first.

• **Preputial fold (pg. 378):** the second fold prepuce inside the preputial sheath of the horse.

• **Preputial ring (pg. 378,f):** the cranial edge of the preputial fold of the horse.

**7. Sigmoid flexure:** the double curve found in the penis of the ruminant and boar. The straightening of the sigmoid flexure causes the lengthening of the penis during erection.

## CLINICAL

**Urethral calculus (sin. = calculi):** a concretion obstructing the urethra. The tomcat has a high incidence of urethral obstruction (FUS). In the dog calculi usually lodge just proximal to the os penis; in the ox, in the distal part of the sigmoid flexure; in the sheep, in the sigmoid flexure or the urethral process.

**FUS, feline urolithiasis, plugged-tomcat syndrome:** common in male cats. The tomcat must be unplugged manually or it may require a catheter. In severe cases cystocentesis (needle aspiration of urine from the urinary bladder) may be required.

**"Broken penis" or hematomas of the penis:** caused by trauma causing a explosion of the corpus cavernosum through the tunica albuginea. It can occur in bulls (rarely in stallions) during mating or semen collection.






Fig. VIII-37 - Bull - Male genitalia  
- lat. view

## CLINICAL (cont.)

**"Teaser" bulls:** surgically altered bulls incapable of natural insemination, used to find cows in heat (estrus) for artificial insemination (A.I.).

**Paralysis of the penis:** the inability to retract the penis into the prepuce. This is due to several causes. Some tranquilizers have been reported to cause paralysis of the penis in the stallion.

**"Balling up":** masturbation by boars into their preputial diverticulum. Surgical closing of the diverticulum stops this "vice".

**Prolapse of the prepuce:** common in Brahma bulls.

**Inability to "extend the penis":** an inability to protrude the penis from the prepuce. This is due to several causes - phimosis, persistent frenulum, congenital short penis, adhesions and keratomas.

**Phimosis:** stricture of the preputial orifice.

**Paraphimosis:** protrusion of the penis through a constricted preputial orifice and the inability to retract it.

**Persistent frenulum:** the fold of tissue that joins the prepuce and the glans normally breaks down, but in this condition fails to do so. It can be transected so the penis can be extended.

**Catheterization of the urinary bladder:** possible in all species, except the bull where a fold of mucous membrane over the openings of the bulbo-urethral glands (urethral diverticulum) prevents catheterization. In the boar and small male ruminants the sigmoid flexure must first be straightened out before catheterization.






Fig. VIII-38 - Dog - Male genitalia  
- median section

- |                        |                             |
|------------------------|-----------------------------|
| A. Deferent duct       | G. Bulb of glans (dog)      |
| B. Prostate gland      | H. Long part of glans (dog) |
| C. Pelvic urethra      | I. Glans penis              |
| D. Bulbospongiosus m.  | a. Urinary bladder          |
| E. Penile retractor m. | b. Ureter                   |
| F. Urethra             |                             |

**STRUCTURE of the PENIS:** composed of erectile tissue divided into two cavernous bodies and one spongy body.

**1. Corpus cavernosum (cavernous body):** the paired erectile tissue with enlarged venous spaces. Proximally, the right and left cavernous bodies separate, forming the two crura. In the carnivores the two bodies are separated by a complete septum, but in the other species perforations in the septum result in one body.

**Crura (L. legs)(sin.= crus):** the proximal ends of the corpus cavernosum covered by the ischiocavernosus muscle. The right and left cavernous bodies attach separately to their respective sides of the ischial arch. The crura, along with the bulb, make up the root of the penis.

**Corpus spongiosum (spongy body):** the tube of erectile tissue directly enclosing the urethra. It forms the bulb and the glans of the penis.

**3. Bulb of the penis:** the expanded, proximal part of the corpus spongiosum at the ischial arch. The bulb is between the crura and is covered by the bulbospongiosus muscle.

**4. Tunica albuginea (white tunic):** the thick, fibroelastic capsules enclosing the cavernous bodies and the spongy body. Trabeculae, a connective tissue framework, runs inwards from the white tunic, supporting the blood spaces in both the cavernous and spongy bodies.






Fig. VIII-39 - Stallion - Penis  
- cross section

Fig. VIII-41 - Bull - Penis, dist. end  
- median section




Fig. VIII-40 - Bull - Penis, prostate gland &  
urinary bladder - median section





Fig. VIII-42 - Bull - Penis, prox.  
end - cross section




Fig. VIII-43 - Bull - Penis, dist.  
end - cross section






Fig. VIII-44 - Dog - Erectile tissue of the penis (schematic)

1. **GLANS PENIS:** the distal free end of the penis. It is erectile tissue derived from the corpus spongiosum surrounding the urethra. It differs greatly between the species.

## SPECIES DIFFERENCES

**Dog:** has a large glans penis subdivided into:

- **2. Bulb of the glans or bulbus glandis:** the part of the glans surrounding the proximal os penis. The bulb, due to its potential for great expansion, is responsible, along with expansion of the bitch's vestibular bulb and contraction of the vestibular muscles, for the "tie" during copulation.

- **3. Long part of the glans (pars longa glandis):** the distal part of the dog's glans surrounding the os penis.

**Cat:** has backward projecting cornified spines on its glans. This may explain the queen's (female) scream as the tom (male) withdraws.

**Boar:** has a twisted "corkscrew" glans.

**Ruminants:** like the boar, have a twisted glans. They also have an urethral process.

4. **Urethral process:** the free end of the urethra in ruminants, very long in the ram and goat (resembles a "party favor").

**Horse:**

- **Urethral process (pg. 377-8):** the short free end of the urethra.

- **Crown of the glans or corona glandis (pg. 377):** a ridge surrounding the glans penis of the horse.

- **Fossa of the glans (fossa glandis) (pg. 377-8):** the depression around the horse's urethral process.

- **Urethral sinus (pg. 378):** the dorsal diverticulum of the fossa of the glans.

- **Collum glandis:** the constriction (neck) caudal to the crown of the glans.

## CLINICAL

**"Bean":** the smegma (cheesy secretion of the sebaceous glands) and debris that becomes trapped in the urethral sinus of the horse's fossa glandis.



PENIS

Pelvis-374




Fig. VIII-45 - Cat - Penis, dist end (modified from Nickle, et al, The Viscera of the Domestic Animals, Verlag, Paul, Parley, 1973)




Fig. VIII-46 - Bull - Penis, dist. end




Fig. VIII-47 - Boar - Penis, dist. end




Fig. VIII-48 - Ram - Penis, dist. end

a. Ext. urethral opening  
b. Spines (cat)






Fig. VIII-49 - Dog - Muscles - caud. view




Fig. VIII-50 - Bull - Muscles  
- ventr. view

- a. Tail
- b. Anus
- c. Int. obturator m.
- d. Testicle

## MUSCLES OF THE PENIS

**1. Retractor penis muscle:** the paired smooth muscles originating from the first few caudal vertebrae. They travel laterally around the rectum and then continue side by side over the urethral surface of the penis to attach distally.

**2. Ischiocavernosus muscle:** the short skeletal muscle covering each crus of the penis, arising from the ischiatic arch and inserting on the cavernous body (corpus cavernosum).

**3. Bulbospongiosus muscle:** the paired skeletal muscles covering the bulb of the penis (proximal portion of the spongy body) and the bulbourethral glands. In the horse it extends distally all the way to the glans of the penis.

**Cranial and caudal preputial muscles:** the unimportant skeletal muscles that pull the prepuce cranially over the penis, or caudally to unsheath it.






Fig. VIII-51 - Bull - median view

A. Scrotum  
B. Testicles  
C. Body of penis  
D. Sigmoid flexure  
E. Glans penis  
F. Deferent duct

G. Spermatic cord  
H. Vaginal ring  
I. Vesicular gland  
J. Prostate gland  
K. Crus of penis

a. Sacrum  
b. Rectum  
c. Aorta  
d. Kidney  
e. Genital fold

f. Pelvic symphysis  
g. Transverse abdominal m.  
h. Int. abdominal oblique m.  
i. Rectus abdominis m.






Fig. VIII-52 - Dog - Scrotum & testicles (schematic) - cross section

**SCROTUM** (SKROH-tum): the pouch containing the testicles and epididymides. It consists of the skin, the dartos, fascia, and the vaginal tunics. In the pig and cat, the scrotum is located directly below the anus. The other domestic species have pendulous scrota a distance below the anus.

1. **Skin**: the pigmented integument of the scrotum.

2. **Dartos** (DAR-tohs) (tunica dartos): the fibromuscular layer just below the skin and in the scrotal septum. Contraction of the

dartos draws the testicles closer to the body in cold weather.

3. **Spermatic fascia**: the continuation of the inner and outer abdominal fascia around the testicle and spermatic cord.

Ligament of the tail of the epididymis and scrotal ligament: connect the tail of the epididymis to the scrotum.

4. **Vaginal tunic** (pg 362): evagination of the peritoneum through the inguinal canal covering the spermatic cord and testicle (visceral layer) and lining the inside of the scrotum (parietal layer).






Fig. VIII-53 - Stallion  
- Genitalia - lat. view






Fig. VIII-54 - Stallion - Penis, dist. end


- |                             |                                       |   |                 |
|-----------------------------|---------------------------------------|---|-----------------|
| a. Head of epididymis       | g. Pelvic urethra                     | l. Attachment of inner layer of prepuce | fold of prepuce |
| b. Body of epididymis       | h. Bulbospongiosus m.                 | m. Inner layer of int. fold of prepuce  | p. Ext. prepuce |
| c. Tail of epididymis       | i. Retractor penis m.                 | n. Preputial ring                       |                 |
| d. Ampulla of deferent duct | j. Cavernous body (corpus cavernosum) | o. Outer layer of int.                  |                 |
| e. Urinary bladder          | k. Free part of penis                 |   |                 |
| f. Ureter                   |                                       |   |                 |



**Fig. VIII-55 - Stallion - Genitalia - sagittal section**



**Fig. VIII-56 - Stallion - Penis - cross section**



**Fig. VIII-57 - Stallion - Penis, dist. end - sagittal section**

A. Testicle  
B. Epididymis  
C. Deferent duct  
D. Ampulla of deferent duct  
E. Urinary bladder  
F. Opening of ureter

G. Seminal vesicle  
H. Prostate gland  
I. Bulbourethral gland  
J. Pelvic part of urethra  
K. Penile urethra

a. Excretory duct of seminal vesicle  
b. Colliculus seminalis  
c. Urethralis m.  
d. Ducts of bulbourethral gland

e. Int. prepuce (VIII-57)  
f. Preputial ring  
g. Ext. prepuce  
h. Ext. fold of prepuce



Fig. VIII-58 - Stallion - Urinary bladder, opened ventrally




Fig. VIII-58 - Stallion - Section through penis & testicles (after Amann)

- |                         |   |   |  |
|-------------------------|---|---|--|
| a. Apex of bladder      | (opening of ductus deferens & excretory duct of seminal vesicles) | (vestige of umbilical a.)                   | r. Bulbourethral glands                  |
| b. Body                 | i. Opening of prostatic ductules                                  | l. Genital fold                             | s. Spermathecae (VIII-58)                |
| c. Neck                 | j. Urethralis m.  | m. Lat. lig. of bladder                     | t. Scrotal septum                        |
| d. Trigone              | k. Round lig. of bladder  | n. Int. urethral orifice                    | u. Cavernous body (corpus cavernosus m.) |
| e. Ureteric fold        |   | o. Seminal vesicles                         | v. Spongy body (corpus spongiosus m.)    |
| f. Urethral crest       |   | p. Prostate gland                           | w. Retractor penis m.                    |
| g. Colliculus seminalis |   | q. Openings of ducts of bulbourethral gland |  |
| h. Ejaculatory orifice  |   |   |  |






Fig. VIII-59 - Stallion - Genitalia

A. Aorta  
B. Ext. iliac a.  
C. Int. iliac a.  
D. Peritoneum  
E. Rectum  
F. Obturator foramen

G. Cavernous body,  
(corpus cavernosum)  
H. Ischiocavernosus m.  
I. Bulbospongiosus m.  
J. Retractor penis m.  
K. Testicular a.


L. Deep femoral a.  
M. Pudendoepigastric trunk  
N. Ext. pudendal a.  
O. Prostatic a.  
P. Caud. gluteal a.  
Q. Int. pudendal a.

a. Cran. aa. of the penis  
(br. of ext. pudendal a.)  
b. Obturator a.  
c. Middle a. of penis (horses)  
d. Dors. a. of the penis  
(br. of int. pudendal a.)



## Chapter IX

# Circulatory System








Fig. IX-1 - Ox - Arteries (schematic)  
- lat. view

**CIRCULATORY SYSTEM:** consists of the heart, blood vessels and lymphatics. It provides for the metabolic requirements – nutrition, waste removal, protection – of the body's cells via the blood, the interstitial fluid and the lymph. Blood acquires oxygen in the lungs, nutrients from the digestive tract and hormones from the endocrine glands. It then transfers them to the interstitial fluid in exchange for waste products and transports all waste to the lungs, kidneys and sweat glands for elimination from the body or to the liver for detoxification and recycling.

The circulatory system has two principal divisions: the blood vascular system and the lymph vascular system. The blood vascular system includes a powerful pump, the heart. Arteries leave the left side of the heart. They branch into progressively smaller arteries until they form microscopic vessels called capillaries. The permeable capillaries exchange oxygen and nutrients for waste products with the interstitial fluid. Capillaries feed into

small veins that join to form larger and larger veins, all carrying oxygen-depleted blood back to the right side of the heart. The heart pumps this blood to the lungs again via arteries, where CO<sub>2</sub> is exchanged for oxygen. Newly oxygenated blood returns through veins to the left side of the heart that pumps it to the rest of the body and heart via the aorta. The lymphatic system removes wastes and bacteria from the interstitial fluid and returns protein-rich fluid to the bloodstream.

**Interstitial fluid:** the fluid bathing the cells of the body. It carries on the necessary exchange between the cells, blood and lymph.

**Lymph vascular system:** consists of the lymph, lymph vessels, lymph nodes and lymphatic organs. This system returns protein-rich fluid from the interstitial fluid to the general circulation. It also filters waste and bacteria from the interstitial fluid.






Fig. IX-2 - Heart & pericardium - longitudinal section

**Blood vascular system:** consists of the blood, heart, arteries, capillaries and veins.

**Artery (AR-ter-ee):** a vessel carrying blood away from the heart. Arteries are generally thicker and stronger than veins, sustaining their higher pressure.

**Capillary (KAP-i-lar'ee):** a microscopic vessel that joins others to form an extensive network throughout the body tissue. Positioned between the arteries and veins, the permeable capillaries allow exchange of gases and nutrients between the blood and the interstitial fluid.

**Veins:** vessels carrying blood back to the heart. They are thinner-walled and carry greater volume than arteries.

**PERICARDIUM:** the fibroserous sac enclosing the heart; composed of the fibrous and serous\* pericardium, covered by mediastinal (pericardiac) pleura.

**7. Fibrous pericardium:** a tough, fibrous sac surrounding the serous pericardium, the heart and the pericardial cavity. It is closed above by its attachment to the great vessels of the heart. When discussing the pericardial serous membranes, the fibrous pericardium will be considered as a wall.

- **Sternopericardiac ligament:** connects the pericardium to the floor of the thorax.
- **Phrenicopericardiac ligament:** connects the pericardium to the diaphragm.

**2. Serous pericardium:** a serous\* membrane forming a closed cavity. It covers the heart (visceral layer [a]) and lines the inner surface of the fibrous pericardial sac (parietal layer [b]).

• **Parietal layer of the serous pericardium:** lines the inner surface of the fibrous pericardium (considered a wall). It reflects onto the surface of the heart as the visceral layer.

• **Visceral layer of the serous pericardium (b):** covers the

\*A serosa is any smooth membrane, consisting of a mesothelial layer and a connective tissue layer, lining the cavities of the body.

myocardium of the heart closely. It is also called the epicardium.

**3. Pericardial cavity:** a potential space between the visceral and parietal layers of serous pericardium. It has approximately one ml. of yellow fluid between the contacting layers, which acts as a lubricant to allow the heart freedom of movement during contraction. Other serous body cavities have almost no fluid.

**LAYERS OF THE HEART:** the three layers having "-cardium" in their name with prefixes telling the location of each ("epi-" meaning being on top of, "endo-" being inside of, and "myo-" the muscular part of).

**4. Myocardium:** the muscle layer making up the majority of the thickness of the heart wall. It is between the endocardium and epicardium.

**5. Endocardium:** a thin, mesothelial layer lining the atria and ventricles. This layer is continuous with the endothelium lining the great vessels entering and leaving the heart.

**6. Epicardium:** a thin layer of mesothelium covering the surface of the heart. The epicardium is the visceral layer of the serous pericardium.

## CLINICAL:

**"Surgeon's pericardium":** the structure a surgeon must incise to reach the pericardial cavity (for open heart surgery). It consists of the mediastinal (pericardial) pleura, the fibrous pericardium and the parietal layer of the serous pericardium. After open heart surgery the pericardium need not be sutured completely closed to prevent cardiac tamponade.

**Cardiac tamponade:** acute compression of the heart due to fluid effusion or hemorrhage into the pericardium.

**Hydrops pericardii:** an excessive production and concurrent retarded absorption of pericardial fluid, caused by pericarditis.



# THE HEART

Thorax-385

**HEART:** a muscular, four-chambered organ that drives the circulatory system. It has specific input channels (veins) and specific output channels (arteries).

**PULMONIC CIRCULATION:** through the right side of the heart to the lungs. The right (pulmonic) side receives blood from the body and pumps it to the lungs for oxygenation. It returns to the left side of the heart.

**SYSTEMIC CIRCULATION:** through the left side of the heart to the heart itself and to the rest of the body, delivering oxygenated blood from the lungs.

**CIRCULATION through the HEART:** Blood enters either atrium by veins, is pumped into the respective ventricles, and on to the lungs or body through the arteries. The right atrium receives deoxygenated venous blood through a number of veins, but primarily the caudal and cranial vena cavae. The blood then enters the right ventricle, which pumps it through the pulmonary trunk into the lungs (pulmonic circulation). Pulmonary veins carry oxygenated blood from the lungs to the left atrium. Blood then descends to the left ventricle. The left ventricle pumps it through the aorta to the rest of the body (systemic circulation).

Major vessels returning blood to the heart:

1. **Cranial vena cava:** the large vein returning blood from the head, neck and thoracic limbs to the right atrium.
  2. **Caudal vena cava:** the large vein returning blood from part of the thorax, the viscera and the caudal part of the body to the right atrium.
  3. **Right atrium (AY-tree-um):** the chamber of the heart receiving deoxygenated blood from the body.
  4. **Right ventricle (VEN-tri-kul):** the chamber receiving blood from the right atrium and sending it to the lungs. The conus is the funnel-shaped end of the right ventricle leading to the pulmonary trunk.
  5. **Pulmonary trunk:** the large vessel carrying blood from the right ventricle to the pulmonary arteries, thus, to the lungs.
  6. **Pulmonary arteries:** the two branches of the pulmonary trunk carrying blood to the lungs; one to the right lung, one to the left.
- Lungs:** receive deoxygenated blood through the pulmonary veins. It oxygenates the blood and sends it back to the heart through pulmonary veins.
7. **Pulmonary veins:** the numerous vessels emptying oxygenated blood from the lungs into the left atrium of the heart.
  8. **Left atrium:** receives oxygenated blood from the lungs via the pulmonary veins.

9. **Left ventricle:** sends oxygenated blood to the body and heart.

10. **Aorta:** the major outflow from the left ventricle into the systemic circulation.

## CLINICAL

The circulation through the heart is important to understand when dealing with problems of the heart.

- Problems in the right side of the heart (pulmonic circulation) cause blood to back up in the caudal vena cava, filling the abdomen with fluid (ascites) in dogs.
- Problems in the left side (systemic circulation) cause blood to back up into the lungs (congestion of the lungs).






Fig. IX-3 - Circulation through the heart  
(schematic)



# FETAL CIRCULATION

Thorax-387

During fetal development, the placenta functions as the lungs and liver for the fetus, supplying it with oxygen and nutrients and eliminating fetal waste products. The fetal lungs and liver need only enough blood to nourish their growing tissue as they are non-functional. The bulk of the blood is diverted to "functional" tissues (especially the heart and brain) by three shunts in the fetal circulation: the ductus venosus, the foramen ovale and the ductus arteriosus. These shunts bypass structures, creating a dual circulatory system – the one in the fetus shutting down within minutes after birth to allow the other, the adult circulation, to take over.

The umbilical vein brings nutrient- and oxygen-rich blood from the placenta into the fetus. It enters the liver to join the portal vein. The ductus venosus connects the umbilical vein with the caudal vena cava, allowing some of the umbilical blood to bypass the liver sinusoids and empty directly into the caudal vena cava.

The caudal vena cava empties into the right atrium where about three fifths of the oxygen-rich blood is shunted through the foramen ovale to the left atrium. Thus, the blood bypasses the pulmonary circulation and enters the systemic circulation. From the left atrium it passes into the left ventricle and out the aorta to supply the heart via the coronary arteries. Distally, the oxygen-rich blood travels over the brachiocephalic trunk into the arteries that supply the brain (common carotid arteries). Thus, the ductus venosus and the foramen ovale insure that the blood richest in oxygen reaches the heart and brain by the fastest route.

The cranial vena cava returns oxygen-poor blood from the cranial parts of the body to the right atrium to mix with the unshunted, oxygen-rich, caudal vena caval blood in the right ventricle. This mixed blood, although not as rich in oxygen as that shunted through the foramen ovale, is still oxygenated, therefore, is shunted away from the lungs via the right ventricle and pulmonary trunk.

The ductus arteriosus shunts blood from the pulmonary trunk to the aorta before it reaches the non-functional lungs. It enters the aorta distal to the origin of the brachiocephalic trunk, thus, supplying the caudal body without diluting the oxygen content of the blood coursing to the brain via the common carotid arteries (branches of the brachiocephalic trunk).

The umbilical arteries, large branches of the terminal aorta, return the fetal blood via the umbilical cord to the placenta for oxygenation and waste elimination.

At birth the umbilical cord is disrupted, stopping blood traveling over the umbilical vein. The ductus venosus becomes part of the portal liver circulation.

The newborn's first breath expands the lungs with air, relieving the pressure on the vessels and capillaries of the lungs and allowing them to expand for the first time. As the vessels open, resistance to blood flow drops, allowing more blood through pulmonary arteries to reach the lungs. The ductus arteriosus, a

muscular artery, begins to close shortly after birth due to the change in oxygen content of the blood flowing through it. It eventually becomes the ligamentum arteriosum. Closure of the ductus arteriosus allows even more blood to reach the lungs.

The greater volume of blood through the lungs returns through the pulmonary veins to the left atrium. This increases the left atrial pressure, functionally closing the "flap valve" of the foramen ovale. With time this functional closure becomes an anatomical closure as the walls of the foramen fibrose, leaving a remnant of the foramen ovale, a depression called the fossa ovale. Blood is no longer shunted from the right to the left atrium.

The closure of the three shunts gives the newborn an "adult circulatory system". Oxygen now comes from the newborn's lungs and nutrients from its intestines via the portal vein.

1. **Umbilical veins:** vessels carrying oxygen- and nutrient-rich blood from the placenta to the fetus. Paired in the umbilical cord, they become a single umbilical vein in the fetal abdomen, which then enters the liver.

2. **Ductus venosus (venous duct):** the fetal shunt from the umbilical vein directly through the liver to the caudal vena cava, bypassing the liver sinusoids.

3. **Foramen ovale (oval foramen):** the opening in the wall separating the two atria (the interatrial septum) allowing blood to shunt from the right to the left atrium. It is a double-walled structure with holes in each wall offset from each other. In the fetus, the pressure is greater in the right atrium, pushing blood through the opening in the right atrial wall, between the two walls, and out the opening in the left atrial wall. With the first breath at birth, blood returning from the lungs raises the pressure in the left atrium above that in the right, pushing the two walls together and effectively closing the foramen ovale.

• **Fossa ovale:** the adult remnant of the foramen ovale.

4. **Ductus arteriosus (arterial duct):** the shunt between the pulmonary trunk and the aorta, diverting most of the blood from the pulmonary trunk (pulmonic circulation) to the aorta (systemic circulation).

• **Ligamentum arteriosum (arterial ligament):** the adult remnant of the ductus arteriosus between the pulmonary trunk and the aorta.

5. **Umbilical arteries:** the pathways of oxygen-depleted blood from the fetus to the placenta. They arise from terminal branches of the aorta (internal iliac arteries), and travel via the umbilical cord to reach the placenta.






Fig. IX-4 - Dog - Fetal circulation (schematic)

1. Umbilical vv.

4. Arterial duct

3. Oval foramen




Fig. IX-5 - Section of heart & oval foramen

- a. Cran. vena cava
- b. Caud. vena cava
- c. Rt. atrium
- d. Rt. ventricle
- e. Pulmonary trunk
- f. Lungs
- g. Pulmonary vv.
- h. Lt. atrium
- i. Lt. ventricle
- j. Aorta
- k. Liver
- l. Intestines
- m. Portal v.
- n. Double wall of oval foramen

## CLINICAL:

**Patent ductus arteriosus:** the arterial duct doesn't close after birth. This should be corrected early through a left intercostal incision through the fourth intercostal space. The ductus is carefully isolated and ligated.

**Patent foramen ovale (interatrial channel):** normal in calves and of no clinical significance if found on necropsy.

**Aortic isthmus:** the part of a calf's aorta between the brachiocephalic trunk and the entrance of the ductus arteriosus. It is normally smaller than the rest of the aorta and the large ductus arteriosus. Do not mistake the combined pulmonary trunk, the ductus arteriosus and the descending aorta for an aorta coming out of the right ventricle.



Primitive heart tube



Adult heart

Fig. IX-6 - Development of heart and blood flow

**CARDIOGENESIS:** the development of the heart from a simple tube in the embryo (with one inflow and one outflow) to an "adult" four-chambered structure with two separate circulations in series (pulmonary and systemic). While these transformations prepare the fetus for life independent of the placenta (pg. 384), the heart must still meet the unique requirements of the fetus (pg. 386). Understanding the development of the heart makes the function and the anatomy of the adult heart and the fetal heart, and the structure and disability of common heart malformations more understandable.

Changes in the developing heart result from two different processes: one is growth, the other degeneration. Growth is an increase in size and/or number of cells. Degeneration is the death of cells. Both of these processes occur in a focal manner; areas of the heart tube grow while other areas degenerate, resulting in the shape of the adult heart.

As the fetus grows, diffusion becomes insufficient to meet the cellular needs, necessitating a circulatory system. The heart begins pumping primitive blood through a primitive vascular system while developing and changing. Within a matter of minutes after birth the animal must shift from the intrauterine to the extrauterine pattern of circulation. This requires a system that can modify itself as it functions during development.

## Stages in heart development:

- 1. Formation of the heart tube.
- 2. Cardiac loop formation.
- 3. Partitioning of the heart and outflow channels.

**FORMATION of the HEART TUBE:** The primitive embryo is a three-layered structure: the external layer is ectoderm [a], the internal is endoderm [b] and between is a mesoderm layer [c] (lying on the yolk). The mesoderm layer is most concerned with cardiogenesis.





Fig. IX-7 - Presomite embryo - sagittal section

The mesodermal cardiogenic tissue (1) which gives rise to the heart begins cranial to the head of the embryo. With growth, the cardiogenic tissue is drawn underneath the head into the throat (cervical) region and then into the thorax. As the embryo continues to fold, the cardiogenic tissue comes to be located ventral to the foregut (f) (future esophagus); the relationship found in the adult.

The heart begins as two tubes (2) located laterally. As the embryo folds, the paired tubes are brought together and fuse (3) to form a single tube, the endocardium (5). A thick layer of mesoderm (future myocardium) surrounds the endocardial tube. A thin layer of epicardium (mesothelium) envelopes both the myocardium and endocardium. This single tube develops by fusion progressing cranially to caudally.



2. Cardiogenic tubes

Fig. IX-8 - Transverse section through cardiac region of embryo




**Fig. IX-8 - Cephalic end of embryo - sagittal section**




3. Fusing cardiogenic tubes

4. Future myocardium




**Fig. IX-9 - Cephalic end of embryo - transverse section**




5. Endocardium

6. Myocardium

**Fig. IX-10 - 4 somite embryo - transverse section**



7. Truncus arteriosus



8. Ventricle

9. Atrium

10. Sinus venosus

**Fig. IX-11,12 - Developing heart - ventr. views**

The first part of the heart to differentiate and start beating is the truncus arteriosus (7) (aortic trunk), the common outflow of the primitive heart. Behind the truncus arteriosus, the tube is still paired and continuing to fuse. As the tube fuses caudally, forming the ventricle (8), the heart rate increases. The atrium (9) then forms and the heart rate again picks up. The last chambers to develop, the right and left sinus venosus (10), remain unfused until much later. They receive venous return from the vessels of the allantois, yolk sac and body of the fetus. With the appearance of each sinus venosus, the heart rate increases to its maximal level.

The increase in rate with the appearance of each new chamber is called the pacemaker phenomenon. Specialized cells of the heart spontaneously depolarize, generating action potentials which spread to the remainder of the heart. The sinus venosus contains the cells with the fastest depolarization rate, thus, become the pacemaker of the heart. In the adult these pacemaker cells are the SA node (the remnant of the right sinus venosus which becomes incorporated into the right atrium.) If the SA node becomes damaged, other parts of the heart can take over as slower pacemakers.

Legend for Fig. IX-6-12

- a. Ectoderm
- b. Endoderm
- c. Mesoderm
- d. Amniotic cavity
- e. Neural plate
- f. Foregut



# DEVELOPMENT OF THE HEART

Thorax-391




Fig. IX-14 - Early fetal blood flow (schematic)

**FORMATION OF THE CARDIAC LOOP:** the primitive, straight-tube heart is anchored at each end by vessels connected to it. Cranially it is anchored where the truncus arteriosus is connected to the ventral aortae (12) (future aortic arches [13]). It is anchored distally where the venous return comes into the sinus venosus. Thus anchored, the tube begins to bulge out to the right side (ventral view) as it lengthens. Continued growth forces the ventricle below and caudally, causing the previously cranially-located ventricle to become caudal and ventral to the atria; the orientation in the adult heart. The truncus pushes into the atrium, prestageing the two adult atria.




Fig. IX-15 - Fetal heart - ventr. view




Fig. IX-16 - Fetal heart - ventr. view

**PARTITIONING of the HEART:** Internally, at this time, the heart is partitioning in preparation for birth. As partitioning continues, shunts form so that fetal circulation can continue to bypass the pulmonic circulation.




Fig. IX-17 - Heart - frontal section






Fig. IX-18 - Fetal heart - frontal section




Fig. IX-19 - Fetal heart - frontal section

**Partitioning of the common atrioventricular passageway:** The common atrium is demarcated from the common ventricle by a constriction (i). The common AV opening is subdivided into two passageways by the atrioventricular endocardial cushions (15) which are growing out to meet each other.

**Partitioning of the common atrium:** Septum 1 (17) (septum primum) grows downward from the dorsal wall of the atrium toward the endocardial cushion to partition the common atrium. The diminishing opening formed by this septum is foramen 1 (20). Before reaching the cushions and completely partitioning the atrium, perforations develop high in the septum and coalesce to form foramen 2 (21). This allows continued communication between the right and left atria.

Septum 2 (19) grows downward, parallel with and to the right of septum 1, to cover foramen 2. It then stops growing, leaving an oval-shaped opening, the foramen ovale (20). During fetal life, the volume of blood coming into the right atrium causes a higher pressure than that in the left atrium. This high pressure forces blood through the foramen ovale, between the two walls of the septum and out foramen 2, bypassing the pulmonic circulation. Septum 1 acts like a flutter valve, thus, a functional partition is formed (which is also an opening). This permits a fetal circulation that is ready to switch immediately to the adult circulation at birth.




Fig. IX-20 - Heart - frontal section

**Partitioning of the ventricle and the outflow channel:** The ventricle is partitioned by the outgrowth of the interventricular (IV) septum (22). The septum extends upward from the ventral side of the heart toward the endocardial cushions, leaving an opening – the interventricular (IV) foramen (21). This closes later as a sequel to the partitioning of the common outflow tract of the ventricle.



**Partitioning of the truncus arteriosus:** The common outflow of the undivided ventricles, the truncus arteriosus, is connected to the ventral aortae. The two ventral aortae fuse to form the aortic sac (a) from which the aortic arches arise. The truncus arteriosus will be partitioned from the aortic arches to the ventricles so that each ventricle has one outflow connecting to the correct aortic arch.

Partitioning begins by the appearance of truncal ridges (23) in the lumen of the truncus arteriosus. The ridges grow toward each other, beginning first at the aortic sac and moving toward the ventricles. They spiral and fuse, forming the spiral septum (24). The two parallel outflow channels (aortic and pulmonary) spiral around each other, connecting the right ventricle to the pulmonary trunk (27) and the left ventricle to the aorta (26).

As the many aortic arches develop, some degenerate and some persist, determining the patterns that result. The 6th aortic arch gives rise to the pulmonary trunk and pulmonary arteries and is connected to the right ventricle in the adult, thus, forming the pulmonic circulation. The systemic circulation is formed by the 3rd and 4th arches. The left 4th aortic arch gives rise to the aorta, and in the adult is connected to the left ventricle. The two 3rd aortic arches give rise to the common carotid arteries. The ductus arteriosus (28) connects the pulmonary trunk to the aorta in the fetus, shunting blood from the pulmonic circulation to the systemic circulation. This duct closes at birth or soon after, becoming the ligamentum arteriosum.

**Closure of the interventricular foramen:** before closure, the incomplete interventricular (IV) septum (22) (with the interventricular (IV) foramen (21) above it) can be seen in an opened right ventricle (b). The left ventricle (c) can be seen through the interventricular foramen. Both ventricles still have a common outflow, the truncus. Further up, the truncus is partitioned. As partitioning continues, the two edges of the truncal cushions grow together with the endocardial cushions (15), closing off the interventricular septum and finishing the two outflows. The membranous part (25) of the interventricular septum is the last part to close.

## CLINICAL

**Ectopia cordis:** interference with the migration of the heart into the thorax, resulting in the heart being located somewhere other than the thorax (usually in the cervical region).

**Atrial septal defect (ASD):** One type of ASD results when the foramen ovale and second foramen overlap, allowing blood to flow from left to right, resulting in poor oxygenation of blood which can lead to cyanosis.

**Persistent right 4th aortic arch:** the right instead of the left 4th aortic arch becomes the aorta. The aorta is then on the right side of the esophagus instead of the left. The aorta, ligamentum arteriosum, and the base of the heart form a ring around the esophagus. This is the most common vascular ring anomaly. When a dog is weaned to solid food, large particles can't get past this constriction and the animal regurgitates undigested food. The ligamentum arteriosum is surgically isolated, ligated twice, and cut between the two ligatures.

**Transposition of the great vessels:** the correct ventricles do not match up with the correct outflow channels. This is fatal!

**Interventricular septal defect (VSD):** failure of the interventricular septum to close, involving the membranous part of the septum. The most common cardiac anomaly in large animals, it causes a systolic murmur.

**Tetralogy of Fallot:** this developmental anomaly has four components:

- Pulmonic stenosis
- The aorta over-rides both ventricles
- Ventricular septal defect
- Hypertrophy of the right ventricle






Fig. IX-21-23 - Fetal heart, rt. ventricle opened - schematic



# HEART - EXTERIOR

Thorax-395

**FREE HEART:** to orient a heart that has been removed from the body, first locate the apex which is directed downward (caudoventral) in the live animal. The base (or top of the heart) is opposite the apex. The cranial and caudal sides can be oriented by finding the aorta, which arches caudally; or the auricles, which point to the left, with the pulmonary trunk between them. With the heart oriented thusly, the right and left sides are easily identified.

- Apex - down
- Aorta - arches caudally
- Auricles - beside the pulmonary trunk, point to the left

Since the chambers of the heart are connected by specific vessels, locating vessels helps identify chambers; and identifying chambers helps locate vessels. So many vessels enter the heart, the majority of them pulmonary veins, it is confusing. To simplify identification, locate the great vessels first - the aorta, the pulmonary trunk and the two venae cavae. The remaining vessels are the pulmonary veins.

Find the vessels to locate the chambers they connect:

- Cranial and caudal vena cava locate the right atrium.
- Pulmonary veins locate the left atrium, where they terminate.
- Pulmonary trunk locates the right ventricle.
- Aorta locates the left ventricle.

**Coronary groove:** Partially encircling the heart, it marks the separation of the atria and ventricles.

**Interventricular grooves** on the heart's exterior indicate the interventricular septum separating the ventricles. The two grooves (the paraconal and subsinuosal grooves) carry similarly-named arteries.

**Left side (auricular surface\*):** the side of the heart where the auricles are seen with the pulmonary trunk in between them.

**Right side (atrial surface\*):** the side of the heart where the vena cavae (cranial and caudal) are seen entering the right atria.

1. **Apex:** the most caudoventral part of the heart, always formed by the left ventricle (and having a "tip").

2. **Base:** the hilus of the organ facing dorsocranially. (It is the broad "top" of the heart.) It receives the great veins and sends out the great arteries.

\***Sternocostal surface** and **diaphragmatic surface** are terms used to orient the human heart because of the human's ventrodorsally (anterioposteriorly) flattened thorax. The sternocostal surface faces the sternum and the diaphragmatic surface rests on the diaphragm. In domestic animals, with their laterally-flattened thorax, the tendency is to think of the heart from the lateral view, that is right or left sides.

3. **Right auricle:** seen from the left side of the heart, in front of the pulmonary trunk (c).

4. **Left auricle:** also seen on the left side of the heart, caudal to the pulmonary trunk.

5. **Conus:** the expanded outflow from the right ventricle into the pulmonary trunk.

6. **Paraconal interventricular groove:** the external indication of the interventricular septum separating the ventricles. The groove descends the left side of the heart, adjacent (para-) to the conus of the heart, thus, paraconal.

7. **Coronary groove:** a depression encircling the heart, except for the conus. The groove externally indicates the separation of the atria and ventricles and contains the coronary vessels.

8. **Left atrium:** the chamber into which the pulmonary veins empty.

9. **Left ventricle:** seen best from the left side, caudal to the paraconal groove. On the right side, it is seen caudal to the subsinuosal groove. It forms the caudal boundary of the heart and its apex.

10. **Ligamentum arteriosum (arterial ligament):** the remnant of the fetal ductus arteriosus (arterial duct) connecting the pulmonary trunk and the aorta.

11. **Right atrium (Fig. IX-25):** seen from the right side of the heart, with the venae cavae entering it.

12. **Right ventricle:** makes up most of the heart on the right side, below the coronary groove. It "wraps" around the cranial side of the heart to continue as the pulmonary trunk.

13. **Coronary sinus:** the termination of the great coronary vein emptying into the right atrium.

14. **Subsinuosal interventricular groove:** the long depression on the caudal right side of the heart. The groove is below (sub-) the coronary sinus (sinuosal). Like the paraconal interventricular groove, it marks the interventricular septum on the exterior.






Fig. IX-24 - Dog - Heart - lt. side

6. Paraconal  
interventricular groove


1. Apex  
13. Coronary sinus

14. Subsinuosal  
interventricular groove

Fig. IX-25 - Dog - Heart  
- rt. side

9. Lt. ventricle

- A. Cran. vena cava
- B. Caud. vena cava
- C. Pulmonary trunk
- D. Pulmonary aa.
- E. Pulmonary vv.
- F. Paraconal interventricular br.
- G. Subsinuosal interventricular br.
- H. Aorta



7. Coronary  
groove

12. Rt. ventricle

1. Apex



# HEART - EXTERIOR

Thorax-397




Fig. IX-26 - Ox - Heart  
- lt. side




Fig. IX-27 - Ox - Heart - rt. side

1. Base of heart
2. Pulmonary trunk
3. Arterial lig.
4. Pulmonary aa.
5. Pulmonary vv.
6. Great coronary v.
7. Coronary groove
8. Conus
9. Paraconal interventricular groove
10. Apex of heart
11. Aorta
12. Cran. vena cava
13. Caud. vena cava
14. Coronary sinus
15. Subsinuosal interventricular groove

- A. Rt. atrium  
B. Rt. ventricle  
C. Lt. atrium  
D. Lt. ventricle

- a. Rt. auricle  
b. Lt. auricle  
c. Brachiocephalic trunk  
d. Paraconal interventricular br.  
e. Subsinuosal interventricular br.  
f. Rt. asygos v.  
g. Lt. asygos v. (only ruminant & pig)



# HEART - EXTERIOR

Thorax-398

Fig. IX-28 - Horse - Heart, lt. side





Fig. IX-29 - Horse - Heart, rt. side





# HEART - COMPARTMENTS

Thorax-399

Fig. IX-30 - Dog - Heart, rt. atrium opened





Fig. IX-31 - Ox - Heart, rt. atrium & rt. ventricle opened



**COMPARTMENTS of the HEART:** the heart has four chambers. The two atria receive blood and pump it down into the respective ventricles, which pump it away from the heart.

**1. RIGHT ATRIUM:** the compartment receiving deoxygenated blood from the body and most of the heart.

**Vena caval sinus (sinus venarum cavarum):** the main part of the right atria were the vena cavae and coronary sinus open. This doesn't include the auricle.

**2. Right auricle (AW-ri-kl) (L. auricula, a little ear):** the blind pocket of the atria, characterized by pectinate muscles in its wall.

**3. Pectinate muscles:** the interdigitating, criss-crossing, muscular bands in the walls of both auricles.

**4. Interatrial septum:** the wall separating the two atria.

• **Fossa ovale (oval fossa) (a),** a shallow depression in the interatrial septum. It is the vestige of the oval foramen.

**5. Coronary sinus:** the end of the great cardiac vein which opens into the right atrium.


**Intervenous tubercle (b):** a projection from the dorsal wall of the right atrium that diverts the flow of both the cranial and caudal vena cava into the right ventricle.

**Fossa ovale (a):** a remnant of the foramen ovale of the fetus.

**Openings into/out of the right atrium:** cranial vena cava, caudal vena cava, coronary sinus, and right atrioventricular orifice.



Fig. IX-32 - Horse - Heart, rt. ventricle &amp; rt. atrium opened - rt. side





# HEART - INTERIOR

Thorax-401





Fig. IX-33 - Dog - Heart, rt. half - sagittal section

- 1. Rt. atrium
- 2. Rt. auricle
- 3. Pectinate mm.
- a. Cran. vena cava
- b. Aorta
- c. Pulmonary a.
- d. Aortic valves
- e. Lt. atrioventricular valve
- f. Rt. atrioventricular valve
- g. Trabeculae carnae
- h. Moderator bands (trabeculae septomarginalis)

4. Lt. AV opening

Fig. IX-34 - Dog - Heart, lt. half - sagittal section



6. Rt. ventricle

8. Conus arteriosus

## COMPARTMENTS of the HEART (cont.)

**6. RIGHT VENTRICLE:** the compartment receiving blood from the right atrium and pumping it, via the pulmonic circulation, through the pulmonary trunk and the pulmonary veins to the lungs. The right ventricular wall is thinner than the left because less pressure is required to move blood through the lungs than through the body.

**Openings into/out of the right ventricle:** the right AV opening and the pulmonary trunk.

**7. Right atrioventricular (AV) opening:** the opening between the right atrium and right ventricle, functionally opened and closed by the right atrioventricular valve.

**8. Conus arteriosus or conus:** the funnel-shaped outflow of the right ventricle leading to the pulmonary trunk.

**Pulmonary opening:** the opening in the pulmonary trunk protected by the pulmonary valve.

**Moderator band or trabeculae septomarginalis (h):** a cord of






Fig. IX-35 - Ox - Heart, rt. half  
- sagittal section

myocardium crossing the lumen connecting the outer wall with the interatrial septum. Purkinje fibers travel over these bands to help synchronize contraction and emptying of the ventricle.

**9. LEFT ATRIUM:** the compartment receiving oxygenated blood from the lungs via the pulmonary veins.

**10. Left auricle:** a blind pocket with characteristic pectinate muscles as seen in the right auricle.

**Openings in/out of the left atrium:** the pulmonary veins and the left atrioventricular orifice.

**11. LEFT VENTRICLE:** the compartment receiving oxygenated blood from the left atrium and sending it out the aorta to the body and the heart (systemic circulation). The left ventricle is thicker walled than the right because of the higher pumping pressure required for systemic circulation.

**Openings into/out of the left ventricle:** the left AV orifice and the aorta.

**12. Left atrioventricular (AV) orifice:** the opening between the left atrium and left ventricle; operated by the left atrioventricular valve.

**13. Aortic opening:** the opening from the left ventricle into the aorta. The aortic valve prevents backflow from the aorta into the left ventricle.



#### STRUCTURES COMMON to both VENTRICLES

**14. Papillary muscles:** the muscular projections serving as attachments for the tendinous cords (chordae tendineae) of the atrioventricular (AV) valves.

**15. Chordae tendineae (tendinous cords):** the tough strands anchoring the free edges of the atrioventricular (AV) valves to the papillary muscles and preventing eversion of the valve leaflets into the atrium upon ventricular contraction (systole).

**16. Interventricular septum:** the wall separating the ventricles.






- a. Rt. coronary a.
- b. Aorta
- c. Pulmonary a.
- d. Aortic valve
- e. Lt. atrioventricular valve
- f. Rt. atrioventricular valve
- g. Trabeculae carneae
- h. Moderator bands (trabeculae septomarginales) (IX-37)
- i. Great coronary v.
- j. Lt. coronary a. (circumflex br.)

**Fig. IX-37 - Horse - Heart, rt. half - sagittal section**





- a. Nodule
- b. Opening of coronary sinus
- c. Rt. coronary a.
- d. Lt. coronary a.
- e. Fibrous rings
- f. Rt. AV opening
- g. Lt. AV opening
- h. Aortic opening
- i. Pulmonic opening
- j. Ossa cordis (ox & older horses)

Fig. IX-38 - Horse - Heart, base of ventricles




Fig. IX-39 - Ox - Heart skeleton

**VALVES OF THE HEART:** the fibrous structures guarding the openings between the atria and the ventricles and the ventricles, and the two main heart outflows - the aorta and the pulmonary trunk.

**Atrioventricular (ay'tree-oh-ven-TRIK-yoo-lar) (AV) valves:** prevent backflow into the atria during ventricular (systolic) contractions. The AV valves are anchored in the ventricles by tendinous cords (chordae tendineae) and attach peripherally to the fibrous rings of the cardiac skeleton.

**1. Right AV (tricuspid) valve:** operates the right AV opening. There are only two major cusps (parietal and septal) in the dog, with intervening secondary cusps. In man and other domestic species, there are three major cusps (angular, parietal and septal), thus "tri-".

**2. Left AV (bicuspid, mitral) valve:** similar to the right AV valve, but has a heavier construction due to greater pressure of the

left ventricle during contraction (systole). (A miter is a two cusp hat worn by bishops in the Catholic church. Someone thought they looked like the left AV valve, hence mitral.)

**3. Aortic (semilunar) valve:** the three semilunar cusps attached to the aortic fibrous ring in the origin of the aorta.

**4. Pulmonary (semilunar) valve:** the valve between the conus of the right ventricle and the pulmonary trunk. It is similar to the aortic valve, but of lighter construction.

**Memory aid:** for the common names of the AV valves: "tri before you bi". This is related to the direction of flow through the heart.

**"SKELETON" OF THE HEART:** the connective tissue skeleton separating the atria from the ventricles and supplying attachments for the heart valves. It contains cartilage in all the species and two bones (ossa cordis) in the ox and older horses.



**HEART AUSCULTATION** (aws-kul-TAY-shun): listening to heart sounds. Heart sounds are caused by the closing of the different heart valves. Ventricle contraction (systole) causes a rise in ventricular pressure and closure of the AV valves (1st heart sound) and opening of the aortic and pulmonic valves. During ventricular relaxation (diastole), the AV valves open and the aortic and pulmonic (semilunar) valves close (2nd heart sound) due to back pressure in the aorta and pulmonary trunk.

- **Systole:** contraction of the ventricles; occurs between the 1st and 2nd heart sound.
- **Diastole:** relaxation of the ventricles; occurs between the 2nd and 1st heart sounds.
- **1st heart sound ("lub"):** caused by the closure of the AV valves.
- **2nd heart sound ("dub"):** caused by the closure of the semilunar valves (aortic and pulmonic).

**LOCATION of the HEART** in most species: from the 2nd or 3rd ICS to the 5th or 6th ICS (intercostal space) and from sternum about 2/3 of the way up the thorax. The olecranon is located at the 5th intercostal space in the normal standing animal, therefore, there is very little heart caudal to the arm. To auscultate the heart you need to press up between the triceps brachii muscle and thoracic wall.

- **Tip of THE olecranon:** at the level of the 5th intercostal space when the animal is standing in a normal square position.

**POINT OF MAXIMUM INTENSITY (PMI)** or *puncta maxima*: the spot on the thoracic wall where a valve sound is loudest. Put the stethoscope at the points listed below and move to find the PMI.

- **Left AV valve:** left 5th intercostal space at the level of the olecranon (low).
- **Pulmonic valve:** left 3rd intercostal space at the level of the olecranon (low).
- **Aortic valve:** left 4th intercostal space at the level of the shoulder (high).
- **Right AV valve:** right 4th intercostal space at the level of the olecranon (low).

**P<sup>A</sup>M-3<sup>4</sup>5:** is a *memory aid* for the PMI of the valves on the left side of the chest. P, A, M stand for the pulmonic, aortic and mitral valves respectively, and 3, 4, 5 stand for the intercostal spaces they are found in. The staggered positions indicate high or low in each respective spaces.

**HEART MURMURS:** abnormal sounds caused by bloodflow turbulence, due to valvular or nonvalvular problems.

**Valvular murmur:** a sound due to a leaky or narrowed valve. To identify murmurs, first, determine if the murmur is in systole or diastole. Then, by find the PMI of the murmur to determine which valve is affected.

- **Leaky (insufficiency) murmur:** caused by turbulence due to backflow through a valve not fully closed.
- **Narrowing (stenosis) murmur:** a constriction of the opening causing a turbulence past that opening.
- **Systolic murmur:** occurs between the 1st and 2nd heart sounds, when the AV valves should be fully closed and the aortic and pulmonic valves open.

– **AV leaky (insufficiency):** systolic murmur (left AV insufficiency is the most common).

– **Aortic or pulmonic narrowing (stenosis):** systolic murmur (aortic stenosis is common).

- **Diastolic murmur:** occurs between the 2nd and 1st heart sounds when the aortic and pulmonic valves should be closed and the AV valves opened (AV stenosis or semilunar valve insufficiency).

– **AV narrowing (stenosis):** diastolic murmur (very rare).

– **Aortic or pulmonic leaking (insufficiency):** diastolic murmur (rare).

**Non-valvular murmurs:**

- **PDA (patent ductus arteriosus):** a failure of the fetal ductus arteriosus (arterial duct) to close. The resulting murmur sounds like a washing machine. It is continuous, thus systolic and diastolic.

• **Interatrial septal defect (patent foramen ovale):** failure of the opening (oval foramen) between the two fetal atria to close.

• **Interventricular septal defect (ISD):** failure of the interventricular septum to close. It results in a systolic murmur heard loudest on the right side near the sternum.

**HEART WORMS (dirofilariasis):** adult round worms (nematodes - *Dirofilaria immitis*) of the dog live in the right ventricle, causing a great strain on the right side of the heart. This results in enlargement of the right ventricle, pulmonary trunk and pulmonary arteries due to increased pressure required to pump blood through the worm mass, thus, increasing the work load.






Fig. IX-40 - Ox - Rt. thoracic cavity (schematic)

A. Esophagus  
B. Trachea  
C. Thoracic duct  
D. Pericardium (cut)  
E. Central tendon of diaphragm

F. Tracheal bronchus  
G. Phrenic n.  
H. Vagosympathetic trunk  
I. Stellate ganglion  
J. Vagus n.  
K. Recurrent laryngeal n.

a. Rt. asygos v.  
b. Costocervical trunk  
c. Dors. scapular a. & v.  
d. Supreme intercostal a. & v.  
e. Deep cervical a. & v.  
f. Vertebral a. & v.  
g. Int. jugular v.

h. Supf. cervical a. & v.  
i. Cephalic v.  
j. Ext. thoracic a. & v.  
k. Int. thoracic a. & v.  
l. Dors. intercostal a. & v.  
m. Bronchoesophageal a.  
n. Ansa subclavia



# CORONARY ARTERIES

Thorax-407

**AORTA:** the great artery leaving the left ventricle and arching caudally. It sends oxygenated blood from the left heart to the heart itself and to the rest of the body through its systemic branches. The aorta is divided into the ascending aorta, aortic arch and descending aorta. The descending aorta has thoracic and abdominal segments.

**1. ASCENDING AORTA:** the initial part of the aorta, originating from the left ventricle at the center of the heart's base.

**2. Aortic sinuses:** the pockets between the aortic valve's cusps and the vessel wall. Right and left coronary arteries arise from the cranial and left sinuses respectively.

**Coronary (KOR-oh-na-ree) arteries (L. *corona*, crown):** the arteries encircling the base of the heart like a crown. These are the first branches off the aorta.

**3. Right coronary artery:** originates from the right aortic sinus. It courses cranially under the right auricle and then to the right in the coronary groove. In some species it continues as the subsinuosal interventricular branch ((horse and pig).

**4. Left coronary artery:** arising from the left aortic sinus, it courses to the left under the left auricle and immediately branches into descending (paraconal) and encircling (circumflex) branches. In some species, the circumflex branch, after reaching the heart's right side, descends as the subsinuosal interventricular branch.

**5. Paraconal interventricular branch:** the descending branch of the left coronary artery in the paraconal interventricular groove.

**6. Circumflex branch:** the branch of the left coronary artery coursing in the coronary groove from the left to the right side of the heart.

**7. Subsinuosal interventricular branch:** the descending artery in the subsinuosal interventricular groove. This branch is derived from either the right coronary or circumflex branch of the left coronary artery, depending on the species.

## SPECIES DIFFERENCES:

**Dog and ruminants:** the left coronary artery gives rise to both the paraconal and subsinuosal interventricular branches.

**Horse and pig:** the rt. coronary artery gives rise to the subsinuosal interventricular branch.

**Cat:** the subsinuosal interventricular branch can arise from either coronary artery, but usually from the circumflex branch of the left coronary artery as in the dog and ruminants.




Fig. IX-41 - Horse & Pig - Coronary aa. (schematic)




Fig. IX-42 - Dog & Ruminants - Coronary aa. (schematic)






Fig. IX-43 - Dog - Heart, base of ventricles - cross section




Fig. IX-44 - Ox - Heart, base of ventricles - cross section




Fig. IX-45 - Horse - Heart, base of ventricles - cross section

- |                      |                   |
|----------------------|-------------------|
| A. Aorta             | E. Rt. AV valve   |
| B. Pulmonic valve    | F. Aortic valve   |
| C. Lt. AV valve      | G. Nodule         |
| D. Great coronary v. | H. Coronary sinus |



## 5. Thoracic Aorta

## 1. Aortic arch

## 3. Common carotid a.

## 4. Subclavian a.

## 2. Brachiocephalic trunk

## 6. Axillary a.

Fig. IX-46 - Ox - Lt. thoracic cavity (schematic)

- |                    |                           |  |                             |
|--------------------|---------------------------|--|-----------------------------|
| A. Ext. jugular v. | a. Esophagus              | g. Costocervical trunk                 | m. Recurrent laryngeal n.   |
| B. Cephalic v.     | b. Trachea                | h. Thoracic duct                       | n. Pericardium (cut)        |
| C. Paraconal br.   | c. Vasosympathetic trunk  | i. Sympathetic trunk                   | o. Phrenic n.               |
| D. Lt. azygos v.   | d. Vertebral ganglion     | j. Cervicothoracic (stellate) ganglion | p. Int. thoracic a. & v.    |
| E. Caud. vena cava | e. Supf. cervical a. & v. | k. Pulmonary trunk                     | q. Crus of diaphragm        |
| F. Cran. vena cava | f. Ext. thoracic a. & v.  | l. Vagus n.                            | r. Costal part of diaphragm |

**1. AORTIC ARCH:** the continuation of the ascending aorta, it sends branches to the head, neck, and thoracic limbs.

**2. Brachiocephalic trunk:** the first branch of the aortic arch, present in all the domestic species. It gives rise to the common carotid artery and the right subclavian artery.

**3. Right and left common carotid arteries:** ascend the neck to supply the head, face, and brain.

**4. Right and left subclavian arteries:** supply the neck, thoracic limb, and the cranial portion of the thoracic wall. Each has many branches:

- **Vertebral artery:** the first branch off either subclavian artery. It courses cranially to pass through the transverse canal of the cervical vertebrae.

- **Costocervical trunk:** arises near and lateral to the vertebral artery. Its branches can include the deep cervical, dorsal scapular, supreme intercostal (thoracic vertebral in the dog) and vertebral arteries.

- **Superficial cervical artery:** arises near the thoracic inlet and runs onto the superficial neck in front of the shoulder.

- **Internal thoracic artery:** arises opposite the superficial cervical artery and passes on the floor of the thorax.

**DESCENDING AORTA:** the part of the aorta caudal to the aortic arch, divided into the thoracic aorta and the abdominal aorta by the diaphragm.

**5. Thoracic aorta:** the division of the descending aorta in the thoracic cavity. It helps supply the thoracic wall via the dorsal intercostal arteries.






Fig. IX-47 - Horse - Rt. thoracic cavity (schematic)

A Ext. jugular v  
B Cephalic v.  
C. Subsinuosal interventricular  
br. of rt. coronary a. (horse)  
D. Azygos v.  
E Caud. vena cava  
F. Cran. vena cava

a. Esophagus  
b. Trachea  
c. Vagosympathetic trunk  
d. Middle cervical ganglion  
e. Costal part of diaphragm  
f. Crus of diaphragm  
g. Costocervical trunk

h. Thoracic duct  
i. Sympathetic trunk  
j. Cervicothoracic (stellate) ganglion  
k. Int. thoracic a.  
l. Vagus n.  
m. Recurrent laryngeal n.  
n. Phrenic n.

## SPECIES DIFFERENCES

**Common carotid arteries:** dogs – arise separately; ungulates (hooved animals) – arise by a short, common bicarotid trunk.

**Branches of the aortic arch:**

**Carnivores and pig:** brachiocephalic and left subclavian arteries arise separately from the aortic arch.

**Horse and ruminants:** only the brachiocephalic artery arises from the aortic arch. Both subclavian arteries arise from the brachiocephalic trunk.

**Subclavian arteries:** branches (vertebral, costocervical, deep cervical, superficial cervical and internal thoracic) vary in their origins between the species:

- **Ruminant:** the vertebral artery arises from the costocervical trunk, thus, the subclavian arteries have only three branches.

- **Carnivores:** the vertebral and costocervical arteries arise separately, thus, the subclavian arteries have four branches.

- **Horse:** the same as the dog on the right - four branches. On the left the deep cervical artery arises from the subclavian, not the costocervical trunk and, thus, the left subclavian has five branches.



# AORTIC ARCH - BRANCHES

Thorax-414




Fig. IX-48-51 - Branches of the Aortic Arch


a. Rt. coronary a.  
b. Lt. coronary a.  
c. Bicarotid trunk  
(ungulates)  
d. Vertebral a.

e. Costocervical trunk  
f. Deltoid a.  
g. Deep cervical a.  
h. Thoracic vertebral a.  
h' Supreme intercostal a.

i. Internal thoracic a.  
j. Supf. cervical a.  
k. Axillary a.



Fig. IX-52 - Horse - Arteries to neck








Fig. IX-53 - Ox - Head, supf. arteries - lat. view




Fig. IX-54 - Ox - Head, deep arteries (ramus of mandible & caud. portion of bony orbit removed) - lat. view

a. Occipital a.  
b. Middle meningeal a.  
c. Condylar a.  
d. Linguofacial trunk  
e. Lingual a.  
f. Sublingual a.  
g. Inferior labial a.  
h. Supf. labial a.

i. Angularis oris a.  
j. Nasal aa.  
k. Auricular aa.  
l. Supf. temporal a.  
m. Transverse facial a.  
n. Palpebral aa.  
o. Inferior alveolar a. (IX-55)  
p. Mental a.

q. Buccal a.  
r. Ext. ophthalmic a.  
s. Malar a.  
t. Angularis oculi a.  
u. Infraorbital a.  
v. Sphenopalatine a.  
w. Palatine aa.



- |                            |                        |
|----------------------------|------------------------|
| A. Ventr. spinal aa.       | H. Olfactory bulb      |
| B. Caud. cerebellar a.     | I. Optic nerve         |
| C. Rostr. cerebellar a.    | J. Cerebral hemisphere |
| D. Caud. cerebral a.       | K. Pons                |
| E. Caud. communicating br. | L. Cerebellum          |
| F. Rostr. cerebral a.      | M. Medulla oblongata   |
| G. Middle cerebral a.      |                        |

**1. COMMON CAROTID ARTERIES** (right and left): arise separately or together (bicarotid trunk) from the brachiocephalic trunk. They ascend the neck with the vagosympathetic trunk to terminate in the internal and external carotid arteries supplying the head, face, and brain. The thyroid and laryngeal arteries are the only branches of the common carotid arteries.

**2. External carotid artery:** the large, direct continuation of the common carotid artery that becomes the maxillary artery. Its first small branch is the occipital artery. It terminates by first giving off a caudal auricular artery and then branching into superficial temporal and maxillary arteries.

**3. Linguofacial artery or separate lingual and facial arteries:** branch(es) of the external carotid artery. The facial artery winds around the ventral border of the mandible to supply the face.

**4. Maxillary artery:** the direct continuation of the external carotid artery to the space below the orbit (the pterygopalatine fossa). Its branches supply the orbit, teeth, chin, nose, nasal cavity and palate.

**5. Internal carotid artery:** the smaller terminal branch of the common carotid artery. It enters the cranial cavity, joining the basilar artery to form the arterial circle. It has an enlargement, the carotid sinus, near its origin.

**6. Arterial circle (circulus arteriosus cerebri, circle of Willis):** located ventral to the hypothalamus encircling the infundibular stalk. It is formed by the paired internal carotid arteries and the basilar artery. It supplies the brain.

**7. Basilar artery:** arises from the vertebral artery and ventral spinal artery.

**Blood brain barrier:** inability of most substances to cross the capillaries of nervous tissue due to tight connections between the capillary endothelial cells.

5. Int. carotid a.

7. Basilar a.




Fig. IX-55 - Ox - Blood supply to brain

## VENOUS DRAINAGE OF THE HEAD

Maxillary and linguofacial veins join to form the external jugular vein. The external jugular veins and subclavian veins join to form the brachiocephalic vein in carnivores and pigs. The brachiocephalic veins then join to form the cranial vena cava. In horses and ruminants the external jugular veins and subclavian veins join to form the cranial vena cava.

### SPECIES DIFFERENCES



**Bicarotid trunk:** in ungulates, the common origin of the two common carotid arteries (in carnivores they arise separately).

**Internal carotid artery:** in cats and ruminants the part outside the skull degenerates.

**Linguofacial trunk:** the common origin for the lingual and facial artery horses and ruminants (in the carnivores and pig they arise separately).



**Fig. IX-56 - Ox - Thoracic aorta**  
(schematic) - lat. view



**Bronchoesophageal artery (m):** arises from the aorta or from one of the dorsal intercostal arteries. Its bronchial branch is the nutritional supply to the tissues of the lung.

**3. Dorsal intercostal arteries:** the first few arise as branches of the costocervical trunk, the rest arise directly from the aorta. Their main branch courses on the caudal aspect of the ribs to anastomose with the ventral intercostal arteries. The dorsal costoabdominal artery is similar to the dorsal intercostal arteries, but travels caudal to the last rib, therefore, is not located intercostally.

**1. Internal thoracic artery:** a branch of the subclavian artery, coursing through the ventral part of the thoracic cavity. It perforates the diaphragm to continue as the cranial epigastric artery on the floor of the abdomen. Collateral branches supply the structures of the ventral thorax.

**2. Ventral intercostal arteries:** arise from the internal thoracic artery and course between the ribs, supplying the ventral thoracic wall.

## CLINICAL

**Intercostal vessels and nerves:** in all species course on the caudal aspects of the ribs. Therefore, an incision to open the thoracic wall (intercostal incision) is made in the middle of the intercostal space.

**Fig. IX-57 - Ox - cross section (schematic)**



Fig. IX-58 - Horse - lat. view (schematic)






Fig. IX-59 - Horse - cross section (schematic)



- A. Rt. coronary a.
- B. Subsinuosal inter-ventricular br.
- C. Lt. coronary a.
- D. Paraconal interventricular br.
- E. Circumflex br.
- a. Costocervical trunk (IX-58)
- b. Dors. scapular a.
- c. Superior intercostal a.
- d. Dors. intercostal aa.
- e. Deep cervical a.
- f. Dors. intercostal a. I
- g. Ventr. intercostal br.
- h. Perforating br.
- i. Sternal br.
- j. Musculophrenic a.
- k. Supf. cervical a.
- l. Deltoid br.
- m. Bronchoesophageal a.
- n. Bronchial br.
- o. Esophageal br.
- p. Dors. intercostal aa.
- q. Dorsal br. (IX-59)
- r. Spinal br.
- s. Interspinous br.
- t. Med. cutan. brs. of p.
- u. Lat. cutan. brs. of p.
- v. Dors. costoabdominal a. (IX-60)
- w. Phrenic brs.
- x. Pulmonary aa.



Fig. IX-60 - Dog - Thoracic limb aa.  
- med. view (schematic)



- a. Ext. thoracic a.
- b. Lat. thoracic a.
- c. Subscapular a.
- d. Caud. circumflex humeral a.
- e. Thoracodorsal a.
- f. Cran. circumflex humeral a.
- g. Deep brachial a.
- h. Bicipital a.
- i. Collateral ulnar a.
- j. Transverse cubital a.
- k. Common interosseous a.

- l. Cran. interosseous a.
- m. Caud. interosseous a.
- n. Deep antebrachial a.
- o. Radial a.
- p. Supf. palm. arch
- q. Deep palm. arch
- r. Palm. metacarpal aa.
- s. Palm. common digital aa.
- t. Palm. proper digital aa.
- u. Dors. common digital aa.
- v. Dors. proper digital aa.
- w. Supf. brachial aa.

**1. AXILLARY ARTERY:** the direct continuation of the subclavian artery around the first rib to the thoracic limb. It supplies the structures of the shoulder and continues as the brachial artery after the subscapular artery branches off.

**Subscapular artery (c):** passes dorsocaudally between the subscapular and teres major muscles. It gives off the caudal circumflex humeral artery and thoracodorsal artery (to the latissimus dorsi muscle).

**2. Brachial artery:** the continuation of the axillary artery on the medial aspect of the arm, which it supplies. It continues as the median artery in the forearm after it gives off the common interosseous artery. Its major branches – the deep brachial (g) (to the triceps brachii muscle), bicipital (h) (to the biceps brachii muscle), collateral ulnar (i) (toward the olecranon), and the transverse cubital (j) (under the biceps brachii muscle) arteries.

**Common interosseous artery:** dives through the interosseous space between the radius and ulna. It has caudal and cranial interosseous branches. The cat has no common interosseous artery because the cranial and caudal interosseous arteries arise separately. In dogs the caudal interosseous can't be occluded with a tourniquet in the mid-forearm because it is protected between the radius and ulna.

**3. Median artery:** the continuation of the brachial artery past the common interosseous artery. It supplies the forearm (antebrachium) by its branches – the deep antebrachial (n) (to the caudomedial muscles), and the radial (o) (to the digits). It passes through the carpal canal to join branches of the common interosseous artery to form palmar arterial arches.

**Palmar arches;** give off palmar metacarpal arteries (deep) and palmar common digital arteries (superficial) that supply the palmar aspect of the forearm and manus.

**4. Digital arteries:** the blood vessels of the metacarpus and digits. Their distribution varies between the species. Number the digital arteries from medial to lateral.



Fig. IX-61 - Dog - Metacarpal & digit aa. - palm. view (schematic)





Fig. IX-62 - Dog - Metacarpal & digit aa. - dors. view (schematic)




Palmar common digital arteries (s): the superficial arteries located on the palmar side of the metacarpus. Carnivores also have dorsal common digital arteries.

Dorsal and palmar metacarpal digital arteries (r): the deep arteries of the metacarpus traveling next to the metacarpal bones. They parallel the larger common digital arteries and usually contribute

to the formation of the proper digital arteries.

Proper digital arteries (t & v): the distal branches of the common digital arteries past the proximal end of the digits. They extend down the sides of the digits as axial and abaxial proper digital arteries.





**Fig. IX-63 - Horse - Thoracic limb aa. - med. view (schematic)**

**2. Brachial**

**1. Axillary a.**

**3. Median**

- a. Ext. thoracic a.
- b. Lat. thoracic a.
- c. Subscapular a.
- d. Caud. circumflex humeral a.
- e. Thoracodorsal a.
- f. Cran. circumflex humeral a.
- g. Deep brachial a.
- h. Bicipital a.
- i. Collateral ulnar a.
- j. Transverse cubital a.
- k. Common interosseous a.

**5. Med. plam. a.**

**4. Digital aa.**

**7. Med. digital a.**

**3. Median a.**

**5. Med. plam. a.**

**6. Lat. palm. a.**

**Fig. IX-64 - Horse - Metacarpal & digit aa. - palm. view (schematic)**

**4. Digital aa.**

**7. Med. digital a.**

**8. Lat. digital a.**

**9. Terminal arch**

- l. Cran. interosseous a.
- m. Caud. interosseous a.
- n. Deep antebrachial a.
- o. Radial a.
- p. Supf. palm. arch (IX-64)
- q. Deep palm. arch
- r. Palm. metacarpal aa. (IX-67)
- s. Palm. common digital aa.
- t. Palm. proper digital aa.

## DIGITAL ARTERIES - HORSE

**5. Medial palmar (second palmar common digital) artery:** the main supply to the digits. Proximal to the metacarpophalangeal joint (fetlock) it divides into the digital arteries.


**6. Lateral palmar (third palmar common digital) artery:** much smaller than the medial palmar artery.

**7 & 8. Medial and lateral digital (medial and lateral proper common digital) arteries:** pass on the abaxial surface of the proximal sesamoid bones and the flexor tendons.

**9. Terminal arch:** the distal continuation of the digital arteries after they enter the solar canal through the solar foramina.




**Fig. IX-67 - Ox - Metacarpal & digit aa. - palm. view (schematic)**



**Fig. IX-66 - Ox - Metacarpal & digit aa. - dors. view (schematic)**

Dorsal metacarpal a. III

1. Axillary a.
2. Brachial a.
3. Median a.
4. Digital a.
- a. Ext. thoracic a.
- b. Lat. thoracic a.
- c. Subscapular a.
- d. Caud. circumflex humeral a.
- e. Thoracodorsal a.
- f. Cran. circumflex humeral a.
- g. Deep brachial a.
- h. Bicipital a.
- i. Collateral ulnar a.
- j. Transverse cubital a.
- k. Common interosseous a.
- l. Cran. interosseous a.
- m. Caud. interosseous a.
- n. Deep antebrachial a.
- o. Radial a.
- p. Supf. palm. arch (IX-64)
- q. Deep palm. arch
- r. Palm. metacarpal aa. (IX-67)
- s. Palm. common digital aa.
- t. Palm. proper digital aa.



**Fig. IX-65 - Ox - Thoracic limb aa. - med. view (schematic)**

## OX


3. Median artery: continues to the distal metacarpus where it becomes the third palmar common digital artery.

5. Common palmar digital artery III: the continuation of the median artery on the medial side.

6. Axial palmar proper digital arteries: the continuation of the third common palmar digital artery on the axial sides of the third and fourth digits.

7. Dorsal metacarpal artery III: travels in the dorsal longitudinal groove.





**Fig. IX-68 - Horse - Arteries of the arm - med. view**



## VEINS - THORACIC LIMB

There are superficial and deep veins of the thoracic limb. The deep veins travel with like-named arteries. The superficial veins travel usually by themselves just beneath the skin.

**Accessory cephalic vein:** arises from the dorsal digital arteries. It travels proximally to empty into the cephalic vein above the carpus.

**Cephalic vein:** In carnivores (pg. 488-489), arises from the palmar digital veins. Proximal to the carpus it crosses the medial side of the forearm to reach the cranial surface. It is joined by the accessory cephalic vein before continuing up the cranial surface of the forearm and lateral surface of the arm under the brachiocephalic muscle. It empties into the external jugular vein. It branches (omobrachial and axillobrachial arteries) provide other drainage routes.


**Median cubital vein:** connects the cephalic and brachial vein over the flexor surface of the elbow (cubit).

### SPECIES DIFFERENCES

**Horse:** the accessory cephalic vein empties into the cephalic vein near the elbow, not above the carpus as in the carnivores and ox.

### CLINICAL

**Venipuncture:** most commonly and easily performed in the cephalic vein in the dog. The cephalic and median cubital veins are held off by finger pressure across the flexor surface of the elbow. A needle is then threaded into the cephalic or accessory cephalic vein distally on the cranial aspect of the limb.



**Fig. IX-69 - Horse - Arteries, forearm - med. view**

a. Suprascapular n.  
b. Thoracodorsal n.  
c. Axillary n.  
d. Radial n.  
e. Subscapular n.  
f. Pectoral n.  
g. Subcapular a.

h. Thoracodorsal a., v., & n.  
i. Collateral ulnar a.  
j. Ulnar n.  
k. Musculocutaneous n.  
l. Median n.  
m. Bicipital a.  
n. Med. palm. n.

o. Flexor retinaculum  
p. Communicating br.  
q. Caud. cutan. antebrachial n.  
(br. of ulnar n.)  
r. Med. palm. metacarpal n.  
s. Cran. cutan. antebrachial n.  
(br. of axillary n.)

t. Med. cutan. antebrachial n.  
(br. of musculocutaneous n.)  
u. Deep pectoral m.  
v. Coracobrachialis m.  
w. Teres major m.  
x. Triceps brachii m.  
y. Extensor carpi radialis



**1. ABDOMINAL AORTA:** the part of the descending aorta caudal to the diaphragm. It courses beneath the vertebrae next to the caudal vena cava and terminates in the two internal iliac arteries and the median sacral artery at the level of the last lumbar vertebra. Its main branches to the abdominal viscera are the unpaired celiac, cranial and caudal mesenteric arteries; and the paired renal and gonadal arteries.

**Phrenic arteries:** supply the diaphragm. In the carnivores the caudal phrenic artery arises with the cranial abdominal artery by a common trunk - the phrenicoabdominal artery.

**2. Celiac artery:** supplies the stomach, part of the duodenum, liver, and spleen. It has three main branches, the left gastric, hepatic and splenic arteries.

**3. Cranial mesenteric artery:** supplies most of the intestines.

**4. Renal arteries:** originating caudal to the cranial mesenteric artery, usually forming one artery to each kidney.

**5. Gonadal arteries (testicular or ovarian):** the tiny vessels supplying the gonads that usually arise just caudal to the renal arteries.

**6. Caudal mesenteric artery:** supplies the descending colon and rectum.

**Lumbar arteries:** homologous to the dorsal intercostal arteries, these paired branches course dorsal to the lumbar area.

**Deep circumflex iliac arteries (k):** arise from the aorta only in the carnivores. In the other species they arise from the external iliac artery.

**7. Internal iliac arteries:** the terminal aortic branches supplying the pelvic viscera and part of the hip and thigh.

**8. External iliac arteries:** the branches of the terminal aorta supplying the pelvic limb.

**9. Median sacral artery:** the unpaired artery of the tail. Its caudal continuation in the tail is called the caudal artery.

**VEINS - ABDOMEN:** the paired branches travel with arteries of like name. Those draining areas supplied by the unpaired branches of the aorta (celiac, cranial and caudal mesenteric) do not return to the caudal vena cava, but join to form the portal vein.




Fig. IX-70 - Ox - Abdominal aorta  
- dors. view (schematic)

**A. Caudal vena cava:** formed by the joining of the right and left common iliac veins. It receives blood from the branches that drain the areas supplied by the paired branches of the aorta. It also receives the blood brought to the liver by the portal vein through the hepatic veins.

**B. Portal vein:** formed by the joining of the cranial and caudal mesenteric veins. It then receives the gastroduodenal and splenic veins. The portal vein drains into the liver allowing intestinal blood to be processed and cleaned before it is sent on to the general circulation.

**Liver sinusoids (a):** spaces in the liver where the portal blood is processed.

**Hepatic veins (b):** drain the portal sinuses to the caudal vena cava. Since the caudal vena cava passes through the edge of the liver and the hepatic veins are in the liver tissue they can't be seen unless the caudal vena cava is opened.







Fig. IX-71 - Horse - Abdominal aorta  
- dors. view (schematic)

Fig. IX-72 - Horse - Caud. vena cava  
- dors. view (schematic)



- |                        |                            |                        |
|------------------------|----------------------------|------------------------|
| 1. Abdominal a.        | A. Caud. vena cava         | e. Ext. iliac v.       |
| 2. Celiac a.           | B. Portal v.               | f. Int. iliac v.       |
| 3. Cran. mesenteric a. | a. Liver sinusoids (IX-72) | g. Caud. mesenteric v. |
| 4. Renal a.            | b. Hepatic vv.             | h. Splenic v.          |
| 5. Gonadal a.          | c. Renal v.                | i. Lt. gastric v.      |
| 6. Caud. mesenteric a. | d. Gonadal v.              | j. Cran. mesenteric v. |
| 7. Int. iliac a.       |                            |                        |
| 8. Ext. iliac a.       |                            |                        |

## SPECIES DIFFERENCES

Median sacral artery: reduced or absent in the horse. The caudal artery is present as a branch of the caudal gluteal artery.

## CLINICAL

Median sacral artery: used to take blood, "tail bleed", in cattle.

Cranial mesenteric artery: a common site for an aneurysm (bulging of a blood vessel) in the horse, caused by the parasitic worm, *Strongylus vulgaris*. Parasitic blockage of this artery or its branches may cause colic.




# CELIAC ARTERY

Abdominal aorta

Abdomen-425

**Fig. IX-73 - Dog - Viscera supplied by the celiac a. (schematic)**



**1. Celiac artery:** the first visceral branch of the abdominal aorta, arising unpaired between the crura of the diaphragm. It terminates as the hepatic, splenic and left gastric arteries supplying the cranial part of the GI tract (stomach, part of the duodenum, liver and spleen.)

- **Left gastric artery (a):** supplies the left side of the lesser curvature of the stomach.

- **Splenic artery (f):** enters, by many terminal branches, the long hilus of the spleen in the dog. In the ruminant it enters a small hilus.

- **Left gastroepiploic artery (g):** passes to the greater curvature of the stomach.

- **Short gastric arteries (l):** arise from the splenic artery and pass to the fundus of the stomach.

- **Hepatic artery (b):** sends hepatic branches to the liver and a cystic branch to the gall bladder. It then continues on to supply

parts of the stomach, duodenum, and pancreas.

- **Right gastric artery (e):** anastomoses with the left gastric artery to supply the lesser curvature of the stomach.

- **Gastroduodenal artery (c):** crosses the stomach to branch into right gastroepiploic and cranial pancreaticoduodenal arteries.

- **Right gastroepiploic artery (h):** supplies the greater curvature along with the left gastroepiploic artery.

- **Cranial pancreaticoduodenal artery (d):** passes distally along the descending duodenum to supply it and the pancreas.

## SPECIES DIFFERENCES

**Ruminal arteries:** travel in the right and left longitudinal grooves of the rumen. Both can arise from the splenic artery.






Fig. IX-74 - Horse - Viscera supplied by the celiac a. (schematic)




Fig. IX-75 - Ox - Viscera supplied by the celiac a. (schematic)

## CLINICAL

**Splenectomy in the carnivores:** the vessels to the spleen must be ligated close to the spleen along the hilus so the short gastric and left gastroepiploic arteries are not compromised.

**Gastrotomy:** when opening the stomach of a dog, cut between the two curvatures to avoid the major blood vessels.

**Rumenotomy:** open the dorsal sac above the longitudinal groove, thereby avoiding its arteries.

- A. Fundus of stomach
- B. Spleen
- C. Stomach
- D. Duodenum
- E. Liver
- F. Pylorus
- G. Pancreas
- H. Rumen (IX-75)
- I. Reticulum
- J. Omasum
- K. Abomasum

- a. Lt. gastric a. (IX-75)
- b. Hepatic a.
- c. Gastroduodenal a.
- d. Cran. pancreaticoduodenal a.
- e. Rt. gastric a.
- f. Splenic a.
- g. Lt. gastroepiploic a.
- h. Rt. gastroepiploic a.
- i. Lt. ruminal a. (IX-75)
- j. Reticular a.
- k. Rt. ruminal a.






Fig. IX-76 - Dog - Arterial supply to the intestines (schematic)

**1. Cranial mesenteric artery:** the largest visceral branch of the abdominal aorta, arising just caudal to the origin of the celiac artery. It courses caudoventrally in the mesentery to supply most of the intestines.

- Caudal pancreaticoduodenal artery: anastomoses with the cranial pancreaticoduodenal artery.

- Ileocolic artery, branches to:

- Middle colic artery (d): supplies the transverse ("middle") colon.

- Right colic artery (e): supplies the second half of the ascending colon.

- Colic branch of the ileocolic artery (g): supplies the first part of the ascending colon.

- Antimesenteric ileal artery (k): travels on the antimesenteric side of the ileum in the ileocecal fold.

- Jejunal and ileal branches (b): come off the continuation of the cranial mesenteric artery. These branches anastomose, making arcades from which short jejunal and ileal arteries extend to reach the organs.

**2. Caudal mesenteric artery:** the smallest unpaired major branch of the abdominal aorta. It arises near the termination of the abdominal aorta and supplies the descending colon and rectum through its left colic and cranial rectal arteries respectively.

## SPECIES DIFFERENCES

**Memory aid:** consider the ascending colon (AC) to be the "right" colon and divided into two parts. Consider the transverse colon the "middle" colon and the descending colon the "left" colon. Then name the arteries supplying the second part of the right colon, the middle colon and the left colon the right, middle and left colic arteries respectively. This leaves the first part of the AC which is supplied by the colic branch. This simplification works for all the domestic species.

**Horse:** the first part of the AC is the ventral colons from the cecum to the pelvic flexure (colic branch). The second part is the left and right dorsal colons from the pelvic flexure to the transverse colon (right colic artery).

**Ox:** the first part of the AC is from the cecum to the central flexure (proximal loop and centripetal coils) (colic branch). The second part is from the central flexure to the transverse colon.







Fig. IX-77 - Horse - Arterial supply to intestines (schematic)

Fig. IX-78 - Ox - Arterial supply to intestines (schematic)



A. Descending duodenum  
B. Ascending duodenum  
C. Jejunum  
D. Ileum  
E. Cecum  
F. Ascending colon  
G. Transverse colon  
H. Descending colon  
I. Rectum

a. Caud. pancreatico-duodenal a.  
b. Jejunal a.  
c. Ileal aa.  
d. Middle colic a.  
e. Rt. colic a.  
f. Ileocolic br.  
g. Colic br.  
h. Cecal br.  
i. Lt. colic a.  
(off caud. mesenteric a.)  
j. Cran. rectal a.  
k. Antimesenteric ileal a.  
(absent in horse)

	1st part AC- colic br.	2nd part AC - Rt. colic
Horse	Rt. & lt ventr. colon to pelvic flexure	Lt. & rt. dors. colon
Ox	Prox. loop & spiral loop to central flexure	Spiral loop dist. to central flexure & dist. loop

## CLINICAL

**Intestinal resection and anastomoses:** removal of a piece of jejunum and the reconnection between the cut ends. Cut the antimesenteric side shorter than the mesenteric side to keep the vasculature from being compromised.



**1. EXTERNAL ILIAC ARTERY:** the large branch of the terminal aorta. It gives off the deep femoral artery, then penetrates the abdominal wall through the femoral canal (lacunae) to reach the medial side of the rear limb. Once out of the abdominal cavity it becomes the femoral artery. The caudal abdominal artery usually arises from the external iliac artery after the deep femoral artery and supplies the caudal abdominal wall (carnivores, sheep and cattle).

**2. Deep femoral artery:** the only branch of the external iliac artery present in all species. It has the following branches:

- **3. Pudendoepigastric trunk:** a short branch off the deep femoral artery giving rise to the caudal epigastric and external pudendal arteries.

- **4. Caudal epigastric artery:** courses cranially on the deep surface of the straight abdominal muscle (rectus abdominis).

- **5. External pudendal artery:** passes through the inguinal canal and branches into the superficial caudal epigastric and ventral scrotal or ventral labial arteries (the latter supplying the scrotum or labia of the vulva, respectively).

- **6. Superficial caudal epigastric artery:** courses cranially under the skin of the ventral abdominal wall to anastomose with the cranial epigastric artery.

**7. INTERNAL ILIAC ARTERIES:** the terminal branch of the aorta that enters the pelvic cavity. It branches into caudal gluteal and internal pudendal arteries. This division occurs at different levels, thus, giving rise to either a "long" or "short" internal iliac artery.

**8. Internal pudendal artery:** can be "short" or "long", depending on where it and the caudal gluteal artery separate. It terminates as the ventral perineal artery and the artery of the penis or clitoris.

**9. Prostatic or vaginal artery:** the branch of either the internal pudendal or internal iliac, depending on which is longer. It supplies the urogenital organs in the pelvic cavity. Its branches are named for the organs they supply: uterine/uterine branch (ductus deferentis artery/branch), urethralis, middle rectal, and caudal vesical arteries.

- **Uterine artery:** the main blood supply to the uterus. It arises differently in the different species.

**10. Umbilical artery:** arises from the internal iliac or internal pudendal (horse) artery and passes to the apex of the urinary bladder. In the fetus the umbilical arteries were the vascular return from the fetus to the mother. After birth they regress from the umbilicus to the bladder. The last branch of the umbilical artery is the cranial vesical artery.

- **11. Round ligament of the bladder:** the part of the umbilical artery in the edge of the lateral ligament of the bladder. Its lumen

is usually obliterated (not patent).

**Artery of the penis:** the continuation of the internal pudendal artery in the male. It rounds the arch of the ischium and trifurcates:

- **12. Artery of the bulb:** supplies the corpus spongiosum penis.

- **13. Deep artery of the penis:** enters and supplies the corpus cavernosum penis.

- **14. Dorsal artery of the penis:** travels along the dorsal surface of the penis.

**Artery of the clitoris:** analogous to the artery of the penis. It branches into the artery of the vestibular bulb, the deep artery of the clitoris (except in horses) and dorsal artery of the clitoris (except in horses).

**Ventral perineal artery (d):** the other terminal branch of the internal pudendal artery. It supplies the perineum.

## SPECIES DIFFERENCES

**15. Uterine artery:** branches off various arteries:

- Vaginal artery in the carnivores.
- External iliac artery in the horse.
- Umbilical artery in the ruminants. The horse and ruminants also have a uterine branch of the vaginal artery.

**Internal iliac artery (7):** carnivores and horses have short internal iliac arteries; ruminants and pig have long ones.

**Internal pudendal artery (8):** carnivores and horses have "long" internal pudendal arteries; ruminants and pigs have "short" ones.

**Prostatic or vaginal artery (9):** arises from the internal pudendal artery in the carnivores and horses. In the ruminants and pig it arises from the internal iliac artery.

**16. Obturator artery:** usually arising from the cranial gluteal artery in the cat and horse, it travels through the obturator foramen. In the horse it gives off the middle artery of the penis (clitoris). It is absent in the dog and usually absent in the ox.


## CLINICAL

**Uterine arteries (15):** ligated before the body of the uterus is ligated and removed in the carnivores (spay).

**"Saddle thrombi":** a blood clot at the termination of the aorta seen in cats. This can block the external iliac arteries and result in lameness, paresis, or paralysis of the hind limbs.



**Fig. IX-79 - Dog - Arterial supply to pelvic organs & ext. genitalia (schematic)**



**Fig. IX-80 - Bitch - Arterial supply to pelvic organs & ext. genitalia (schematic)**


- |  |                            |                            |                               |
|--|----------------------------|----------------------------|-------------------------------|
| 1. Ext. iliac a.                             | 9. Prostatic a./vaginal a. | A. Testicular (ovarian) a. | a. Median sacral              |
| 2. Deep femoral a.                           | 10. Umbilical a.           | B. Caud. mesenteric a.     | b. Caud. gluteal              |
| 3. Pudendoepigastric trunk                   | 11. Round lig. of bladder  | C. Rectum                  | c. Cran. gluteal              |
| 4. Caud. epigastric a.                       | 12. Artery of bulb         | D. Urinary bladder         | d. Ventral perineal           |
| 5. Ext. pudendal a.                          | 13. Deep a. of penis       | E. Ductus deferens         | e. Artery of penis (clitoris) |
| 6. Caud. supf. epigastric (cran. mammary) a. | 14. Dors. a. of penis      | F. Body of penis           |                               |
| 7. Int. iliac a.                             | 15. Uterine a.             | G. Pelvic symphysis        |                               |
| 8. Int. pudendal a.                          |                            | H. Ovary                   |                               |
|  |                            | I. Uterus                  |                               |



# EXTERNAL & INTERNAL ILIAC ARTERIES

Pelvis-431

Fig. IX-81 - Stallion - Arterial supply to pelvic organs & ext. genitalia (schematic)



## HORSE - SPECIES DIFFERENCES

15. Uterine artery: comes off the external iliac artery in the horse.

16. Obturator artery: arises from the cranial gluteal artery and gives off the middle artery to the penis (clitoris) in the horse.

17. Cranial artery of the penis: a branch of the external pudendal artery in the horse.

18. Middle artery of the penis: arises from the obturator artery in the horse.

Dorsal artery of the penis (14): in the horse has little or no contribution from the continuation of the internal pudendal. But in the midhigh region, it is formed by anastomoses from the cranial and middle arteries of the penis, branches of the external pudendal, and obturator arteries respectively.

Deep artery of the clitoris and dorsal artery of the clitoris: arise from the middle artery of the clitoris, a continuation of the obturator artery.




Fig. IX-82 - Mare - Arterial supply to pelvic organs & ext. genitalia (schematic)






Fig. IX-83 - Cow - Arterial supply to pelvic organs & ext. genitalia (schematic)




Fig. IX-84 - Bull

## RUMINANT - SPECIES DIFFERENCES

**15. Uterine artery:** a branch of the umbilical artery in the ruminant.

**Long internal iliac and short internal pudendal:** note how far caudally the internal iliac branches into caudal gluteal and internal pudendal in the ruminant. Because of this the prostatic or vaginal artery is a branch of the internal iliac artery.

**"Cranial mammary artery":** another name for the superficial caudal epigastric in the ruminants and mare.

**"Caudal mammary arteries":** the ventral labial arteries in the cow and mare.

**"Milk vein" or "superficial abdominal vein":** common names for the satellite vein (superficial caudal and cranial epigastric) of the superficial epigastric arteries in the ruminant.

1. Ext. iliac a.
2. Deep femoral a.
3. Pudendoepigastric trunk
4. Caud. epigastric a.
5. Ext. pudendal a.
6. Caud. supf. epigastric (cran. mammary) a.
7. Int. iliac a.
8. Int. pudendal a.
9. Prostatic a./vaginal a.
10. Umbilical a.
11. Round lig. of bladder
12. Artery of bulb
13. Deep a. of penis
14. Dors. a. of penis
15. Uterine a.
16. Obturator a. (horse)
17. Cran. a. of penis (horse)
18. Middle a. of penis (horse)

- A. Testicular (ovarian) a.
- B. Caud. mesenteric a.
- C. Rectum
- D. Urinary bladder
- E. Ductus deferens
- F. Body of penis
- G. Pelvic symphysis
- H. Ovary
- I. Uterus
- a. Median sacral
- b. Caud. gluteal
- c. Cran. gluteal
- d. Ventral perineal
- e. Artery of penis (clitoris)
- f. Middle artery of clitoris (br. of obturator in horse)



## ARTERIES - DOG - PELVIC LIMB

199-Pelvic limb-433

**1. INTERNAL ILIAC ARTERY:** terminates into internal pudendal (pg. 428) and caudal gluteal arteries.

**2. Caudal gluteal artery:** after giving off the cranial gluteal artery it leaves the pelvic cavity to supply the gluteal and proximal part of the caudal thigh ("hamstring") muscles.

**3. Cranial gluteal artery:** arises from the caudal gluteal and passes over the greater ischiatic notch to supply the middle gluteal muscle.

**4. EXTERNAL ILIAC ARTERY** (cont. from pg. 428): penetrates the abdominal wall through the femoral canal (lacuna vasorum) to become the femoral artery.

**5. Deep femoral artery:** arising from the external iliac artery just inside the abdomen. It gives off the pudendoepigastric trunk. It then passes out the femoral canal (lacunae) to the medial thigh where it becomes the medial circumflex femoral artery.

**6. FEMORAL ARTERY:** the continuation of the external iliac artery coursing in the femoral triangle on the proximomedial side of the thigh. Passing distally deep to the semimembranosus muscle, it continues as the popliteal artery caudal to the stifle joint. Its first branch, the lateral circumflex femoral artery, passes laterally between the rectus femoris and vastus medialis muscles to anastomose with the medial circumflex artery. Proximal, middle and distal caudal femoral arteries supply the caudal aspect of the thigh. The constant branch in all the domestic species is the distal caudal femoral artery.

**7. Saphenous artery:** arises from the femoral artery in the femoral triangle. It passes subcutaneously with a vein and nerve on the medial side of the thigh. It gives off the descending genicular artery to the stifle. Past the stifle it divides into cranial and caudal branches in the carnivores and horse.

**8. Distal caudal femoral or caudal femoral artery:** arises from the terminal end of the femoral artery and passes caudally on the gastrocnemius muscle to supply the caudal thigh ("hamstring") muscles.

**9. Popliteal artery:** the continuation of the femoral artery behind the stifle and between the two heads of the gastrocnemius muscle. It branches into cranial and caudal (small) tibial arteries.

**10. Cranial tibial artery:** the larger branch of the popliteal artery, passing in the interosseous space between the tibia and fibula to the cranial surface of the crus.

**11. Dorsal pedal artery:** the direct continuation of the cranial tibial artery over the tarsus.

**Perforating tarsal artery:** passes between the tarsal or metatarsal bones to reach the plantar aspect.

**Metatarsal and digital arteries:** similar to the metacarpal and digital arteries of the forelimb.




Fig. IX-85 - Dog - Lt. pelvic limb  
- med. view (schematic)



Fig. IX-86 - Dog - Lt. pes - dors. view (schematic)




Fig. IX-87 - Dog - Lt. pes - plant. view (schematic)

**Common digital arteries:** the superficial arteries (dorsal and plantar) in the metatarsal region.

**Metatarsal arteries:** the deep arteries (dorsal and plantar) of the metatarsal region.

**Proper digital arteries (dorsal and plantar):** formed from the joining of the common digital and metatarsal arteries. They have "axial" or "abaxial" added to their name, depending on which side of the digits they pass.

#### SPECIAL

**Femoral canal or vascular lacunae:** the opening between the abdominal cavity and the medial thigh.

#### SPECIES DIFFERENCES

**Carnivores and pig:** there is little clinical significance to the arteries distal to the tarsus. In the carnivores the dorsal digital arteries are formed by the cranial branch of the saphenous artery and the cranial tibial artery; plantar arteries arise from the caudal branch of the saphenous artery.

#### CLINICAL

**Collateral circulation:** The many different blood vessels supplying the pelvic limb allow ligation (tying off) of the femoral artery without permanent ill effects in a healthy dog.

**Pulse:** can be palpated in the femoral artery in the femoral triangle along the medial thigh of the dog and cat. This is also a convenient site for catheterization for angiocardiology due to its superficial position.


a. Median sacral a.  
b. Int. pudendal a.  
c. Lat. circumflex femoral a.  
d. Med. circumflex femoral a.  
e. Caud. tibial a.

f. Anastomotic br. (horse)  
g. Perforating tarsal a.  
h. Lat. plantar a.  
i. Med. plantar a.

j. Deep plantar arch  
k. Metatarsal aa. (IX-89)  
l. Common digital aa.



Fig. IX-88 - Horse - Lt. pelvic limb  
- caudodors. view (schematic)



HORSE

12. "Great metatarsal artery" or dorsal metatarsal artery III: the continuation of the dorsal pedal artery (11), and the main supply distal to the tarsus. It runs distally on the dorsolateral side of the metacarpus in a groove between the cannon and lateral splint (Mt III and IV). Halfway down the metatarsus it passes between the cannon and lateral splint as the distal perforating branch to reach the plantar surface of the limb. It then branches into lateral and medial digital arteries.

13, 14. Medial and lateral (proper) digital arteries: continuations of the great metatarsal artery (distal perforating branch) on the sides of the digits similar to the forelimb.

Caudal branch of the saphenous artery: receives an S-shaped anastomosis (f) from the caudal tibial artery and then branches into lateral and medial plantar arteries (h,i) at the tarsus. A deep branch of the lateral plantar artery joins with the perforating tarsal artery to form the deep plantar arch (j). Plantar metatarsal arteries (k) arise from the deep plantar arch. Both plantar and metatarsal arteries contribute to the digital arteries by joining the digital arteries or the distal perforating artery of the great metatarsal artery.

Fig. IX-89 - Horse - Lt. pes - plant. view (schematic)

- |                     |                              |   |                          |
|---------------------|------------------------------|---|--------------------------|
| 1. Inter. iliac a.  | 9. Popliteal a.              | a. Aorta                                      | g. Perforating tarsal a. |
| 2. Caud. gluteal a. | 10. Cran. tibial a.          | b. Median sacral a. (usually absent in horse) | h. Lat. plantar a.       |
| 3. Cran. gluteal a. | 11. Dors. pedal a.           | c. Int. pudendal a.                           | i. Med. plantar a.       |
| 4. Ext. iliac a.    | 12. Dorsal metatarsal a. III | d. Med. circumflex femoral a.                 | j. Deep plantar arch     |
| 5. Deep femoral a.  | 13. Lat. digital a.          | e. Caud. tibial a.                            | k. Metatarsal a. (IX-80) |
| 6. Femoral a.       | 14. Med. digital a.          | f. Anastomotic br. (horse)                    | l. Common digital a.     |
| 7. Saphenous a.     |                              |   | m. Proper digital a.     |
| 8. Caud. femoral a. |                              |   |                          |



# OX - ARTERIES - PELVIC LIMB

Fig. IX-90 - Ox - Rt. pelvic limb - med. view





Fig. IX-91 - Ox - Rt. pes - plant. view




Fig. IX-92 - Ox - Rt. pes - dors. view

## OX

**12. Dorsal metatarsal artery III:** the continuation of the dorsal pedal artery (11), courses in the dorsal longitudinal groove. It gives off a perforating tarsal and continues as the dorsal common digital artery III which gives off proper digital arteries and then passes between the digits to anastomose with plantar common digital artery III.

**Saphenous artery:** doesn't have cranial and caudal branches, divides at the tarsus into lateral and medial plantar arteries (h,i). Branches from the plantar arteries anastomose with the perforating tarsal artery (g) to form the plantar metatarsal arteries (k).

**Medial plantar artery (i):** divides into plantar common digital arteries II and III. The plantar common digital artery II continues on as the abaxial proper digital artery III. The common digital artery III anastomoses with dorsal common digital artery III and then bifurcates into axial proper digital arteries III and IV.






Fig. IX-93 - Dog - Pelvis & thigh - med. view



Med. saphenous v.

Saphenous a.

Fig. IX-94 - Dog - Rt. crus &amp; pes - med. view

**VEINS - PELVIC LIMB:** deep veins parallel the arteries of the same name. Superficial drainage occurs via the medial and lateral saphenous veins that do not parallel similarly-named arteries.

**Medial saphenous vein:** passes on the medial side of the limb with the saphenous artery and vein. It empties into the femoral artery at the apex of the femoral triangle.

**Lateral saphenous vein:** travels on the lateral side of the limb to enter the caudal popliteal region and empty into the distal caudal femoral vein.

#### CLINICAL

**Lateral saphenous vein:** can be used for venipuncture in the dog when the cephalic vein is unavailable. Injecting where it crosses the lateral side of the leg is difficult because of its mobility. Injecting it more proximally, where it dives into the hamstring muscles, is easier.


**Cranial branch of the median saphenous vein:** in the horse crosses the dorsomedial aspect of the tarsus. This crosses the "cunean" tendon (medial insertion of the cranial tibial muscle) and the injection site of the dorso-medial pouch of the talocrural joint.

**Intravenous local anesthetic of the bovine pes:** apply a tourniquet below the tarsus to distend the five superficial veins in the area. Inject any one to anesthetize the distal limb.

Lat. saphenous v.

A. Femoral n.  
B. Saphenous n.  
C. Obturator n.  
D. Tibial n.

a. Middle sacral n.  
b. Deep femoral a.  
c. Lat. plantar n. (tibial n.) (IX-94)  
d. Med. plantar n. (tibial n.)  
e. Med. plantar a.





## VEINS - BODY

5. Caud. vena cava

382-General-439

4. Cran. vena cava

6. Portal v.

1. Ext. jugular v.

2. Cephalic v.

3. Subclavian v.

A. Pulmonary vv.  
B. Great cardiac v.  
C. Caud. supf. epigastric (milk) v.

7. Saphenous v.

*Pesquini '82*

Fig. IX-95 - Ox - Veins - lat. view (schematic)

**VEINS:** the vessels returning oxygen-depleted blood from the body tissues to the heart.

**1. External jugular vein:** the large vein in the neck returning blood from the head to the heart.

**Veins of the thoracic limb:** the deep veins usually parallel the arteries of the limb and take the same names. Superficial veins pass under the skin not accompanied by like-named arteries.

**2. Cephalic vein:** arises from the digital veins on the palmar aspect of the paw. It extends proximally around the medial side of the forearm just above the carpus to reach the cranial surface of the limb. Here it is joined by the accessory cephalic vein. It continues up the limb crossing the flexor surface of the elbow and lateral side of the arm. It empties into the external jugular vein.

**Accessory cephalic vein:** arises from the digital veins on the dorsal surface of the paw. It extends proximally to join the cephalic vein above the carpus in the carnivores and ox and near the elbow in the horse.

**3. Subclavian vein:** the vessel returning blood from the thoracic limb to the heart.

**Brachiocephalic vein:** found only in the carnivores and pig,

formed by the intersection of the external jugular and subclavian veins.

**4. Cranial vena cava:** the great vessel emptying into the cranial part of the right atrium, returning blood from the head, neck, thoracic limbs and cranial part of the walls of the thoracic cavity.

**5. Caudal vena cava:** the great vessel emptying into the caudal part of the right atrium, returning blood to the heart from the abdomen, pelvis and pelvic limbs.

**6. Portal vein:** the large vein carrying essentially all the blood from the abdominal viscera to the liver and its internal sinusoids. Hepatic veins located inside the liver, return to the caudal vena cava.

**Veins of the pelvic limb:** Deep veins parallel the arteries of the same name. Superficial drainage occurs via the saphenous veins.

**7. Medial and lateral saphenous veins:** the superficial drainage of the pelvic limb. They do not parallel similarly-named arteries. The median saphenous vein travels on the medial side of the limb and empties into the femoral vein in the femoral triangle. The lateral saphenous vein travels on the lateral side of the limb and empties into the caudal femoral vein behind the stifle.



## SPECIES DIFFERENCES

**External jugular vein:** empties into the brachiocephalic vein in carnivores and pigs; directly into the cranial vena cava in ruminants and horses.

**Subclavian vein:** empties into the brachiocephalic vein in the carnivores and pig; into the cranial vena cava in the ruminants and horse.

**Brachiocephalic vein:** present only in the carnivores and pig; formed by the convergence of the external jugular and subclavian veins.

**Cranial vena cava:** formed by the converging of the brachiocephalic vein in the carnivores and pig and by the external jugular and subclavian veins in the horse and ruminants.

## CLINICAL

**Venipuncture:** placing a needle into a vein in order to withdraw blood or inject a substance.

**Sites of venipuncture:**

**Dog:**

- **Cephalic vein:** most common site of venipuncture.
- **Jugular vein:** the second most common site.
- **Lateral saphenous vein:** a third choice, but a poor choice, after the cephalic and external jugular veins.
- **Sublingual vein:** sometimes used during surgery.

**Large animals:**

- **External jugular vein:** the most common site.

**LYMPHATIC SYSTEM:** consists of lymphatic tissues and vessels. This system returns protein-rich fluid to the blood circulation that escapes from the blood capillaries into tissue spaces. It is, therefore, part of the circulatory system. The lymphatic system is involved in lymphocyte and antibody production, phagocytosis of particulate matter, and movement of fats from the digestive system to the circulation. Thus, it may be considered part of the hemopoietic (blood forming), immune, reticuloendothelial, and digestive systems. Lymph vessels are not present in the brain, spinal cord, or bone marrow.

The pumping of the heart causes hydrostatic pressure that filters out all components of the blood, except blood cells and platelets,

from the capillaries into surrounding tissue. The lymphatic vessels have greater permeability than the capillaries, easily "picking up" proteins and large molecules. Muscle contractions compress the lymphatic vessels, moving the "lymph" along. Lymph nodes are scattered along the course of the lymphatic vessels and contain primitive cells and macrophages. The primitive cells differentiate into lymphocytes and/or plasma cells. Macrophages lining the lymph nodes engulf substances, including metastasizing cancer cells, entering the lymph nodes. Lymphocytes are also produced by the spleen, thymus, and tonsils. The spleen also phagocytoses aged erythrocytes.

**Lymph capillaries:** blind-ended tubes located throughout the body. More permeable than blood capillaries, they "pick up" the excess interstitial fluid, which is then called "lymph".

**Lymphatic vessels:** the larger vessels formed by the convergence of lymph capillaries. Similar to veins, the lymphatic vessels differ in having thinner walls, more valves, and lymph nodes along their course.

**Lymph nodes (lnn., sin.=ln.):** the ovoid or bean-shaped, encapsulated structures located along the course of the medium-sized lymphatic vessels. The lymph nodes function as filters and germinal centers for lymphocytes. Each node has a capsule of fibrous connective tissue. Trabeculae extend from the capsule into the lymph node. The outer cortex and inner medulla make up the parenchyma of the node. Lymph enters the periphery of the lymph node by afferent lymphatic vessels, passes through the parenchymal sinuses, and out the hilus of the lymph node by a single efferent lymphatic vessel. Lymph picks up lymphocytes and is subjected to macrophages as it passes through the node.

**Primitive cells:** Located in lymph nodes, they differentiate into lymphocytes and/or plasma cells.

**Macrophages:** the phagocytic cells lining the walls of the sinuses.

**LYMPHOCENTERS:** groups of lymph nodes draining the same region of the body in all species. Outlined on the next few pages are the lymphocenters of the body and their major lymph nodes (minor nodes have been ignored). Trunks and ducts drain the lymphocenters back to the general circulation at the so-called "venous angle". The "venous angle" is where the ducts or trunks empty into the large veins in the thoracic inlet.

## HEAD and NECK - LYMPHOCENTERS:

**1. Parotid lymph node:** represents the parotid lymphocenter. It is located under the cranial edge of the parotid gland. It drains the dorsal part of the head, including the orbit and parotid gland, then the lymph continues to the retropharyngeal nodes. It is palpable in the dog and ox.

**2. Mandibular lymph nodes:** represents the mandibular



## LYMPHOCENTERS - BODY

General-441

lymphocenter and consists of a group of nodes located ventral to the angle of the jaw. They drain that part of the head not drained by the parotid gland to the medial retropharyngeal node. Present in all species, they are palpable in the dog, ox, and horse.

**Retropharyngeal lymphocenter:** drains the deeper structures of the head and neck, including the pharynx and larynx. They also receive lymph coming from the parotid and mandibular lymph nodes.

• 3. **Medial retropharyngeal lymph node:** the largest lymph node of the head and neck, present in all species. It lies between the larynx and the wing of the atlas and is not normally palpable.

• 4. **Lateral retropharyngeal lymph node:** usually absent in the dog and palpable in the ox.

5. **Superficial cervical lymph nodes:** represent the superficial cervical lymphocenter. They are present in all species and palpable in the dog, ox, and horse. Located in front of the shoulder joint under the superficial neck muscles, they drain the superficial neck and dorsal thorax along with the proximal part of the forelimb.

6. **Deep cervical lymphocenter:** the chain of deep lymph nodes (cranial, middle and caudal) along the length of the trachea. It drains the deep and ventral structures of the neck into the thoracic duct on the left side or into the lymphatic duct on the right.

**A. RIGHT and LEFT TRACHEAL (JUGULAR) TRUNKS:** traveling along the trachea, draining the lymph nodes of the head and neck. They empty into the thoracic duct on the left side, the right lymphatic duct, or the vessels of the thoracic inlet.

**THORACIC LIMB and THORAX LYMPHOCENTERS:** the thoracic lymphocenters can be divided into parietal (dorsal and ventral thoracic lymphocenters represented by the intercostal and sternal lymph nodes, respectively) and visceral groups (mediastinal and bronchial lymphocenters).

7. **Mediastinal lymphocenters:** consist of the cranial mediastinal lymph nodes in all species. The carnivores lack the caudal mediastinal lymph nodes that are huge in the ruminants.

8. **Bronchial lymphocenters:** consist of nodes located around the tracheal bifurcation. All species have left tracheobronchial lymph nodes.

9. **Axillary lymph node** (part of the axillary lymphocenter): constantly present in all species and palpable in the dog. Located in the axilla, it drains the forelimb and the thoracic wall, including the first three pairs of mammary glands in the dog. The accessory axillary lymph node is present in the cat and inconstant in the dog and ox. The horse has a palpable cubital lymph node.

### ABDOMENAL LYMPHOCENTERS:

10. **Lumbar lymphocenters:** consist of lumbar lymph nodes

located along the abdominal aorta. They drain the kidney, loins, adrenal glands, and abdominal portion of the urogenital system, including the testes, into the lumbar trunks or cisterna chyli. The carnivores lack renal lymph nodes.

11. **Celiac lymphocenter:** consists of splenic, gastric, hepatic, and pancreaticoduodenal lymph nodes that drain associated structures to the cisterna chyli (see below). The ruminants have many nodes associated with the compartments of their stomach.

12. **Cranial mesenteric lymphocenter:** consists of the jejunal, cecal, and colic lymph nodes. They are located near these organs and drain into the cisterna chyli.

• 13. **Cranial mesenteric lymph nodes:** a surprisingly large node located in the root of the mesentery of the dog.

14. **Caudal mesenteric lymphocenter:** represented by the caudal mesenteric lymph nodes draining the descending colon.

**G. VISCERAL TRUNKS:** drain the celiac, cranial and caudal mesenteric lymphocenters to the cisterna chyli.

### PELVIS and PELVIC LIMB LYMPHOCENTERS

15. **Popliteal lymphocenter:** represented by the superficial popliteal lymph nodes in the carnivores (palpable in the dog) and the deep popliteal lymph nodes in the other species. They drain the distal limb into the medial iliac center.

16. **Ischial lymphocenter:** absent in the dog.

17. **Deep inguinal lymphocenter:** located along the external iliac artery. The horse has deep inguinal lymph nodes.

**Superficial inguinal lymphocenter:** drains the groin, caudal mammary glands, and scrotum into the iliosacral or deep inguinal lymph nodes.

• 18. **Superficial inguinal lymph nodes:** present in all species, they are palpable in the dog, ruminants, and horse.

• 19. **Subiliac or "prefemoral" lymph node:** absent in the dog and palpable in the ruminants and horse. It is also called the mammary or scrotal lymph node because it drains these structures.

20. **Medial iliac and sacral lymph nodes** (part of iliosacral lymphocenter): located near the termination of the aorta in the abdominal and pelvic cavities. They drain the surrounding region, the pelvic organs, and the hindlimb into the lumbar trunks.

**B. LUMBAR TRUNKS:** extend from the medial iliac lymph nodes to the cisterna chyli. It receives lymph over the visceral, celiac, intestinal, jejunal, hepatic and colic trunks.

**C. CISTERNA CHYLI:** the dilation at the thoracolumbar junction.



Fig. IX-96 - Ox - Supf. lymph nodes (schematic)





Fig. IX-97 - Ox - Lymphocenters of the body (schematic)


tion receiving lymph from the lumbar and intestinal (visceral) trunks (draining the lymph nodes of the abdomen, pelvis and pelvic limb).

azygos vein and the aorta. Passing to the left side of the thorax in the cranial mediastinum, it empties near the thoracic inlet ("venous angle") into the jugular vein or the caudal vena cava.

**D. THORACIC DUCT:** the major lymphatic vessel draining the entire body, except the right thoracic limb, right cranial thorax, and right side of the neck. It begins at the cisterna chyli, passes through the aortic hiatus cranially on the right side between the

**E. RIGHT LYMPHATIC DUCT:** drains the right cranial thorax, right thoracic limb and right side of the neck into the venous system where the caudal vena cava is formed.






**Fig. IX-98 - Horse - Spleen - visceral surface**

- a. Splenic a.
- b. Splenic v.
- c. Phrenicosplenic lig.
- d. Area covered by peritoneum

**Fig. IX-99 - Ox - Spleen - visceral surface**



## OTHER LYMPHOID STRUCTURES

**Tonsils:** masses of unencapsulated lymphoid tissue below mucous membranes (pharyngeal, palatine and lingual). The major ones protect the entrance to the larynx and esophagus from incoming pathogens.

**Peyer's patches:** diffuse accumulation of lymphatic tissue in the wall of the ileum.

**Hemal nodes:** filter blood instead of lymph found in the ruminants along the aorta. They are easily distinguished from lymph node by their dark, reddish brown color.

**SPLEEN:** the largest lymphoid organ in the body. It is a flat, elongated structure interposed in the blood stream located next to the left abdominal wall. In the fetus it produces red blood cells. In the adult it stores red blood cells that can be squeezed back into circulation when needed. It also produces lymphocytes, stores

iron, and destroys worn out red blood cells.

**1. Hilus:** the area where vessels and nerves enter the spleen. It is a long groove in the carnivores, horse and pig, and a small indentation in ruminants.

## CLINICAL

**Splenectomy:** removal of the spleen. This is a common procedure in the dog, indicated for tumors in or traumatic rupture of the spleen. The animal can do quite well without its spleen.


**Superficial lymph nodes:** can be an important indicator of an illness because they enlarge and become palpable in response to infection.

**Meat inspection and necropsy:** pathogenic changes in lymph nodes make them important in these disciplines.



## Chapter X

# Nervous System








Fig. X-1 - Ox  
- Peripheral nervous system

**NERVOUS SYSTEM:** the control center allowing the body to react to the environment. It stores, integrates, and initiates all appropriate response to information it receives. It is organized into a communication network.

**Organization of the Nervous System:** Functionally, it can be divided into the somatic and autonomic nervous systems.

**STRUCTURAL CLASSIFICATION:** divided into the central and peripheral nervous system. This is an artificial division because many of the nerves of the body are partly in both divisions.

**Central nervous system (CNS):** the control center consisting of the brain and spinal cord.

**Peripheral nervous system (PNS):** all nerve processes connecting to the central nervous system, consisting of cranial and spinal nerves.

**IMPULSE CLASSIFICATION:** takes into account the impulses (sensory or motor) carried by nerves and the directions they travel.

**Sensory (afferent) system:** conducts sensory (afferent) information from the periphery to the central nervous system (CNS). Sensory information travels in ascending tracts from the spinal cord ("lower") to the brain ("higher").

- **Ascending tracts:** sensory fibers in the spinal cord that travel toward the brain.

**Motor (efferent) system:** consists of motor (efferent) nerves that conduct from higher to lower levels of the central nervous system and from the central nervous system to the periphery.

- **Upper motor neurons (UMN):** extend from the brain down descending tracts in the cord to synapse on lower motor neurons (LMN).

- **Lower motor neurons (LMN):** extend away from the spinal cord and brain to the muscles and glands of the body.

- **Descending tracts:** bundles of upper motor neuron fibers that move caudally in the spinal cord.

This system doesn't hold up under close scrutiny, especially the integrating components in the spinal cord. It is still a valuable concept for understanding damage to the central or peripheral systems (see appendix).

**FUNCTIONAL CLASSIFICATION:** takes into account the activities that are directed by the nervous system.

**Somatic nervous system (soma, body):** carries conscious voluntary information from the central nervous system to the skeletal muscles along cranial and spinal nerves. It functions to keep the






Fig. X-2 - Ox  
- Sympathetic nervous system

body in balance with its external environment. This system allows the animal to move and interact with its environment.

**Autonomic nervous system (ANS)** (*auto*, self; *nomos*, law): carries involuntary information (sensory and motor) to and from smooth muscle, cardiac muscle, and glands of the body along cranial and spinal nerves to the spinal cord and brain. It functions to regulate the balance (homeostasis) of the body's internal environment.

**FIBERS - FUNCTIONAL CLASSIFICATION** (pg. 560): divides fibers of peripheral nerves according to their function into afferent and efferent nerves which in turn are divided into somatic and visceral divisions, and then subdivided into general and special categories. It also takes into account their embryonic branchial mesoderm origin. Three capital letters (GSA, GSE, SVE, GVA, GVE, SSA, and SSV) are given to each of the subdivisions. Although this may be a convenient shorthand for the neurologists that uses them all the time, it is extremely difficult the student. Not only is it confusing and hard to learn, if not continually used, it is soon forgotten.

**FIBERS-SIMPLIFIED FUNCTIONAL CLASSIFICATION:** the author proposes a simpler system for teaching purposes. Although it may not hold up to close scrutiny, it reduces the confusion when learning basic neurology.

- **Somatic fibers (motor and sensory):** from nerves of the somatic

nervous system to skeletal muscle; and from skin and deeper somatic structures.

- **Somatic motor (efferent) fibers (SVE, GSE):** supply skeletal (somatic) muscles, no matter what the branchial arch origin.

- **Somatic sensory (afferent) fibers (GSA):** carry sensory information from skin and deeper somatic structures (skeletal muscle, skin, tendons, joint capsules, bones, etc.).

- **ANS fibers:** from nerves of the autonomic nervous system. They innervate smooth muscle, cardiac muscle, and glands. They are subdivided into fibers of the sympathetic and parasympathetic divisions. Sympathetic fibers are carried by branches of all spinal and most cranial nerves. Parasympathetic fibers are restricted to some sacral spinal nerves (pelvic nerve) and only a few cranial nerves (Cn III, VII, IX, and X).

- **ANS motor (efferent) fibers:** these can be further divided into sympathetic and parasympathetic fibers.

- **ANS sensory (afferent) fibers:** carry sensory fibers from blood vessels and viscera throughout the body. Some somatic sensory fibers also affect ANS motor fibers.

- **Special sensory fibers:** carry special sensory information of taste, smell, vision, hearing, and vestibular function to the brain.



**COMPONENTS of the NERVOUS TISSUE:** consists of two types of cells - nerve cells or neurons and neuroglial cells. These are bathed in the extracellular fluid.

**Neuroglia** (nyoo-ROG-lee-ah): the supporting structure of nervous tissue consisting of neuroglial cells. These specialized cells support, nourish and insulate nerve cells. They replace the supporting connective tissue the not present in the CNS.

**NEURONS** (NYOO-ron) (G. *neuron*, nerve) or nerve cell: the functional units of the nervous system. Their specialized properties make the nervous system unique. The largest cells in the body, they are also the most numerous (on the order of 10 to the 12th power, a million million cells). Most of these are in the central nervous system as compared to the peripheral nervous system. A number of characteristics make neurons so specialized that no two cells are identical.

**Compartmentalization:** the different portions of a neuron have different membrane properties and to a degree different internal organelles, therefore, making them functional and structural compartments. This concept explains how diseases can effect only specific compartments. These specialized compartments communicate with each other by transport systems.

**Biochemical specialization:** nerves cells are grouped biochemically by their neurotransmitters, allowing each set to carry out specific functions. Clinically, diseases can attack sets of neurons based on their specific neurotransmitters.

**Nonreproducible:** nerve cells uniquely lack the ability to divide. A neuron dies if it is damaged and its function is lost. Other nerve cells may take over this function.

**Complex connections:** distinguishes nervous tissue from other tissues and is central to the functioning of nervous tissue. These connections are very precise (e.g., a specific point on the brain is connected to the little finger).

**Information:** neurons are the information cells of the body. They are specialized to process or integrate information, conduct it to different parts of the body, transfer it from one cell to another, store and/or generate information.

1. **Cell body (soma [SOH-ma] or perikaryon):** arranged as a nucleus and its neuroplasm (cytoplasm) which contains typical organelles (e.g., mitochondria, RER, and golgi [with the exception of the organelles used in mitosis like the centrioles]). Rough endoplasmic reticulum (RER) is in high concentrations because neurons are the most metabolically-active cells in the body, producing huge amounts of protein. The RER is clumped into large, granular, basophilic inclusions called Nissl (NIS-lz) bodies scattered throughout the neuroplasm of the cell body and dendrites, but not in the axon. This feature makes the body the control (trophic) center of the neuron. The cell body synthesizes enzymes and other molecules essential to the normal function and the survival of the other compartments of the neuron (dendrites and axon). If the cell body is damaged, the rest of the cell dies. On the other hand, if an axon in the periphery is damaged, it has the

possibility of regenerating. Neurofibrils form a network extending into the nerve fibers, functioning in support and transport of materials between the compartments of the neuron.

2. **Nucleus:** well-defined with a prominent nucleolus and granular chromatin. After four years of age the nucleus appears to be unable to undergo mitosis, therefore, unable to increase or replace neurons.

**Nerve processes:** two types extend from the cell dendrites and axons. A cell usually has one axon, but may have many dendrites.

• 3. **Dendrites (DEN-dryt)** (G. *dendron*, tree): the multiple processes acting as the receptor portion of the neuron that conduct information (electrical impulses) toward the cell body. They are usually multi-branched processes containing cytoplasmic organelles and Nissl bodies.

• 4. **Axon:** carries information (electrical impulses) away from the cell body to other neurons or tissue. It is a long cylindrical process, usually singular, that may have tiny side branches (axon collaterals). Axons have neurofibrils, but no Nissl bodies. Their terminal branches (telodendrites) end in synaptic knobs (end feet). The axon usually originates from the axon hillock, a small elevation on the cell body.

• 5. **Synaptic knobs** (also called end feet, boutons, or buttons): form the presynaptic side of a synapse (pg. 449) and contain synaptic vesicles that store chemicals for release at the synapse.

**CLASSIFICATION of NEURONS:** nerves are classified as sensory neurons, motor neurons, or interneurons. 99.997% of the neurons of the CNS are interneurons.

• **Sensory (afferent) neuron:** brings information from receptors in the periphery to the central nervous system. These neurons have their cell bodies located outside the central nervous system.

• **Motor (efferent) neuron:** carries information from the central nervous system to peripheral muscles, glands, or other neurons. The neurons of the motor nervous system have their cell bodies in the central nervous system (brain or spinal cord) and their axons (motor, efferent) extending to the periphery.

• **Interneuron, association, connecting or internuncial neurons:** carry sensory impulses from sensory neurons to motor neurons. The whole interneuron (cell body, dendrites and axon) is located in the CNS (brain or spinal cord).


**Classification of neurons based on processes:**

• **Multipolar:** receive many dendrites and has one axon.

• **Bipolar:** receive one common trunk formed by its dendrites and sends out one axon.

• **Unipolar or pseudounipolar:** receive one common trunk formed by the axon and dendrite.





## CLINICAL

**Neuritis (noo-RY-tis):** inflammation of a nerve.

**Compartmentalization:** allows diseases to differentially affect separate parts of the nerve cell.

**Neurotransmitters:** because neurotransmitters are different for different sets of neurons, disease processes can selectively affect specific sets of neurons.



**NEUROGLIA** (nyoo-ROG-lee-al) (neuro + G. *glia*, glue): the second cellular component of nervous tissue. They are about 10 to 50 times more abundant than nerve cells. Neuroglial cells function as a binding agent to maintain the form of the nervous system. They also provide metabolic support for nerve cells and play a role in repair of damaged nervous tissue. Unlike neurons, they are able to divide, therefore, are the primary source of intrinsic (coming from the tissue itself) tumors.

**NEUROGLIA of the CNS:** astrocytes, oligodendrocytes and microglia.

**Astrocytes** (AS-troh-syt) (G. *astron*, star): star-shaped cells that supply support to nervous tissue. The processes of astrocytes extend to form a membrane around the capillaries of the CNS. They bring nutrients from the capillaries to the neurons, thus, providing nutritional support.

**Oligodendrocyte** (ol'e-goh-DEN-droh-syt) (G. *oligo*, few): Smaller and less branched than astrocytes, they wrap around the axons of nerve cells to form myelin. Myelin increases the speed of conduction along the axon, resulting in faster information transfer.

**Microglia** (my-KROG-lee-ah) (sin.= microglial cell): the smallest neuroglial cells of the CNS. They migrate and act to phagocytize waste products in nerve tissue.

## PERIPHERAL NEUROGLIAL CELLS

**1. Schwann cells:** the neuroglia of the PNS. They form myelin sheaths by winding around nerve processes. They are the equivalent of the oligodendrocyte of the CNS.

**Nodes of Ranvier** (rahn-ve-ay)(Fig. X-4,h): unmyelinated gaps between segments of the myelin sheath.

**Myelin** (MY-e-lin): a lipoprotein (all cell membranes are composed of lipoproteins) forming a sheath around nerve processes. Axons or dendrites can both have myelin sheaths (myelinated) or remain naked (unmyelinated). Myelin sheaths function to increase the speed of impulse conduction and to insulate the nerve process. In the PNS, the myelin sheath is produced by Schwann cells winding themselves around the process, leaving several continuous layers of its cell membrane. The remaining portion of the Schwann cell encircling the sheath is known as the **neurolemma**, which assists in regeneration of injured axons. Schwann cells also enclose unmyelinated fibers, but without the multiple wrappings.

**Myelinated fiber:** a process having a myelin sheath.

**Unmyelinated fiber:** a process lacking a myelin sheath, but still having a Schwann cell covering.

## CLINICAL

**Astrocytes:** proliferate after brain damage, forming a scar (gliosis). This can be detrimental, mechanically placing stress on the surrounding brain tissue, causing irritation of adjacent tissue, and/or a possible epileptic focus.




Fig. X-5,6,7 - Schwann cell, wrapping around nerve process






Fig. X-8 - Neuromuscular junction (schematic)

**SYNAPSE** (SIN-aps) (G. *synapsis*, connection): a specialized site of apposition where information passes from one nerve cell to another cell. The first cell is the presynaptic cell, the second the postsynaptic cell. Between the two cells is a synaptic cleft. The presynaptic cell is always a nerve; the postsynaptic cell can be a nerve, a muscle or a gland.

**Nerve action potential (NAP):** an electrical event that travels down an axon.

**Presynaptic cell:** the neuron that is transferring information to the postsynaptic cell.

**Synaptic button, bouton, or knob:** the terminal end of the presynaptic nerve that is in apposition with the postsynaptic cell. It contains synaptic vesicles.

**Synaptic vesicles:** membrane-bound organelles containing neurotransmitters located in the synaptic button.

**Neurotransmitters:** a chemical substance within the synaptic vesicle that mediates information transfer between nerve cells and other cells at synapses. Different sets of neurons use different

neurotransmitters.

**Postsynaptic cell:** the neuron, muscle, or gland receiving information from the presynaptic cell.

**Receptors:** integral proteins inserted in the membrane of the postsynaptic cell. They function to bind with a neurotransmitter, resulting in a change in the membrane of the postsynaptic cell.

**Synaptic event:** A nerve action potential propagates down the axon to reach the synaptic knob. This causes the synaptic vesicles to release their neurotransmitters into the synaptic cleft. The neurotransmitters diffuse across the cleft to bind to receptors on the postsynaptic membrane. This binding causes a change in the postsynaptic membrane. If the postsynaptic cell is a nerve, it can initiate or inhibit another nerve action potential in the postsynaptic nerve.

**Neuromuscular junction:** the synaptic connection between a neuron and muscular tissue where electrical impulses pass from the neuron to the muscle cell. This can result in contraction of the muscle.



# REFLEX ARC

General-451




Fig. X-9 - Reflex arc - schematic

**REFLEX ARC:** the simplest impulse pathway. A reflex is an involuntary response to a sensory stimulus. The reflex arc (the pathway of a reflex) involves a sensory neuron, an interneuron (internuncial neuron), and a motor neuron (the patellar tap lacks an interneuron). Specialized receptors at the end of sensory neurons receive a stimulus, resulting in an impulse. The impulse travels through the dendrite, body, and axon of the sensory neuron into the spinal cord. In the spinal cord, the sensory neuron synapses on an interneuron that carries the impulse to a synapse on a motor neuron. The motor neuron innervates a receptor organ (muscle) to contract (pull away from the stimulus).

- **Stimulus:** a change in the environment (e.g., hot stove).
- **Receptor:** the end of a sensory neuron's dendrite that responds to change (stimulus) by developing a nerve impulse.
- **Sensory (afferent) neuron:** sends sensory impulses to the CNS.
- **Interneuron, association (internuncial) neurons:** located in the spinal cord, connect a sensory neuron with a motor neuron. They also can connect with other neurons, thus, send information up to the brain (so when the reflex is over, it can be commented on, "ouch!").

• **Motor (efferent) neuron:** carries an impulse (information) to an effector organ.

• **Effector (target) organ:** the muscle or gland innervated by a motor neuron to react to the stimulus (pull away from the stove).

**NUCLEUS:** aggregations of nerve cell bodies (perikarya) located in the brain. Their dark color sets the nuclei off from the white nerve fibers.

**GANGLION** (pl.=ganglia): a group of nerve cell bodies outside the central nervous system, manifested as a swelling of a nerve.

**GRAY MATTER:** that part of nervous tissue consisting of neuronal cell bodies.



**WHITE MATTER:** that part of nervous tissue consisting mainly of myelinated nerve fibers.

**NERVE:** a bundle of nerve processes outside the CNS.

**NERVE TRACTS or FASCICULI** (fah-SIK-yoo ly): nerve fiber bundles of common origin in the brain and spinal cord. They are usually named for their origin and destination.



Fig. X-10 - Ox - Brain &amp; cranial nn.

Fig. X-11 - Spinal cord - cross section  
(schematic)



**BRAIN:** that portion of the central nervous system (CNS) contained within the skull. It can be divided into three major parts; the cerebrum, the cerebellum, and the brain stem. The cerebrum forms the bulk of and performs the higher functions of the brain. The cerebellum, the large mass behind the cerebrum, houses reflex centers coordinating voluntary movements. The brain stem connects the cerebrum, cerebellum, and spinal cord; and is also concerned with visceral (internal organs) activities. *Encephalon* (G. *enkephalos*, brain) is the basis of many medical terms relating to the brain (e.g., encephalitis).

**CEREBRUM** (SER-ee-brum) or telencephalon (L. brain): the largest part of the brain, divided by the median fissure into two cerebral hemispheres. The cerebrum carries out the higher brain functions. It interprets sensory inputs from sense organs, initiates voluntary skeletal muscle movements, and stores memory. Specific areas of the cerebral cortex have been mapped for their functional activity. These areas are interconnected by fiber tracts to coordinate their interactions.

- 1. Cerebral hemispheres: the two structures created by the longitudinal fissure dividing the cerebrum. They are connected deeply by the corpus callosum.
- Cerebral cortex: the thin, superficial layer of gray matter made up of nerve cell bodies.
- White matter: the myelinated nerve axons connecting the cortex with other parts of the cortex, brain, and spinal cord. Association fibers are the axons connecting nerve cells in different parts of the same cerebral hemisphere. Commissural fibers are the axons passing between nerve cells of both hemispheres and from the corpus callosum. Projection fibers are the axons connecting the cerebral cortex to other parts of the brain and the spinal cord.
- Basal ganglia (GANG-lee-a) (basal nuclei): the masses of nerve cell bodies located deep in the white matter of the cerebrum. (They include the caudate nucleus, putamen, and globus pallidus).
- 2. Convolutions or gyri (JY-ry) (sin.=gyrus): the numerous folds on the surface of the cerebral hemispheres greatly increasing its surface area.
- Grooves: the depressions between the gyri (convolutions), divided into two groups according to their depth. Fissures are deep grooves; sulci are shallow.
- 3. Longitudinal fissure: the deep groove separating the cerebrum into two cerebral hemispheres.
- 4. Transverse fissure: the deep groove separating the cerebellum from the cerebral hemispheres.
- 5. Sulci (SUL-sy) (L. furrow) (sin.=sulcus): the shallow grooves between convolutions (gyri).

- Lobes and functional areas: the lobes of the cerebral hemisphere are named for the bones overlying them. The cortex has been mapped for sensory and motor areas. The motor area, the caudal part of the frontal lobe, receives axons from motor neurons that cross to the opposite side in the brain stem. Therefore, the right hemisphere controls skeletal muscle movements on the body's left side, the left hemisphere the body's right side. Specific points in the motor cerebral cortex control specific muscles.

- 6. Frontal lobe: the rostral part of each cerebral hemisphere. The caudal part of the frontal lobe houses the motor area (f) of the brain.

- 7. Occipital lobe: the caudal part of each cerebral hemisphere where the centers for vision are located.

- 8. Temporal lobe: the lateral side of the cerebrum caudoventral to the lateral fissure (h). This is the location of the hearing centers.

- 9. Parietal lobe: the dorsal part of the cerebrum. The rostral parietal lobe (g) is the area of temperature, pressure, touch, and pain sensations.

- Ventral cerebrum: the centers for smell.

- Association areas: the areas next to the sensory and motor areas. They analyze sensory input and are concerned with memory.

**LATERAL VENTRICLES** (pg. 473): the two spaces of the ventricular system, each surrounded by a cerebral hemisphere and filled with cerebrospinal fluid (CSF).



Fig. X-12 - Dog - Brain - dors. view

1. Cerebral hemispheres

6. Sulci

2. Gyri

3. Longitudinal fissure

7. Occipital lobe

4. Transverse fissure

9. Parietal lobe

8. Temporal lobe

6. Frontal lobe




Fig. X-13 - Dog - Brain - lat. view

A. Cerebellum  
B. Medulla oblongata  
C. Olfactory bulb  
D. Pons

a. Cruciate sulcus  
b. Lat. rhinal sulcus  
c. Ectosylvian sulcus  
d. Coronal sulcus

e. Piriform lobe  
f. Motor area  
g. Rostr. parietal lobe  
h. Lat. fissure






Fig. X-14 - Horse - Brain - sagittal section

**DIENCEPHALON** (dy-en-SEF-a-lon) (G. *dia*, through + *enkephalos*, brain): the rostral brain stem between the cerebrum and the midbrain, surrounding the third ventricle. The diencephalon is composed primarily of the **thalamus** and the **hypothalamus**, both gray matter grouped into nuclei. Cranial nerve II (optic nerve) enters the brain through the optic nerves which cross as the optic chiasm and continue as the optic tracts through the diencephalon.

**1. Thalamus** (THAL-a-mus) (G. *thalamos*, innerchamber): the two oval masses, mainly gray matter, connected by the **interthalamic adhesion**. The thalamus functions as a **central relay center** for **sensory** impulses to the cerebral cortex, and contains some motor fibers from the cortex to other brain centers. All senses, except smell, come to the thalamus, which sends them on to their appropriate cerebral cortical areas. The thalamus also interprets an awareness of pain, touch, and temperature.

**3. Hypothalamus** (hy-po-THAL-a-mus) (G. *hypo*, under): the floor of the diencephalon. Seen in a ventral view of the brain, it is located beneath the thalamus. The hypothalamus communicates with the cortex, thalamus, and other parts of the brain, as well as with the pituitary gland via the infundibular stalk. Through the pituitary gland, the hypothalamus is the main link between the two regulating systems of the body—the nervous system and the

endocrine system.

The hypothalamus regulates the viscera by controlling and integrating the **autonomic nervous system (ANS)**. Through the ANS, it controls heart rate, blood pressure, body temperature, and gastrointestinal secretions and motility.


Another way the hypothalamus regulates the body is by producing two hormones, antidiuretic hormone (ADH) and oxytocin, that are sent to the posterior pituitary gland for storage and release. The hypothalamus also serves as an intermediary between the nervous and endocrine systems through production and release of regulating factors which control hormonal release by the anterior pituitary gland.

**4. Pituitary gland** (pi-TOO-i-tair'-ee) or **hypophysis** (hy-POF-i-sis): the small gland of internal secretion attached to the hypothalamus by the infundibulum. It consists of two main parts: the anterior lobe (adenohypophysis [ad'-i-noh-hy-POF-i-sis]) and the posterior lobe (neurohypophysis). Its secretions are important in growth, maturation, and reproduction.

**5. Infundibulum** (in'-fun-DIB-yoo-lum): the stalk attaching the pituitary gland to the hypothalamus. The third ventricle evaginates into the infundibulum, forming a recess.



**Fig. X-15 - Ox - Brain, pituitary gland removed - ventr. view**



## CLINICAL:

**Temperature regulation:** the hypothalamus of the newborn does not regulate body temperature as efficiently as the hypothalamus of an adult.



# MIDBRAIN & MESENCEPHALON

Head-457

Fig. X-16 - Ox - Brain, sagittal-section





Fig. X-17 - Ox - Brain - dors. view

- a. Cut surface between cerebrum & brain stem (X-18)
- b. Stria habenularis thalamus
- c. Habenular commissure
- d. Pineal body
- e. Lat. geniculate body
- f. Med. geniculate body
- g. Cuneate nucleus
- h. Fasciculus cuneatus
- i. Optic tract (X-19)
- j. Mamillary body
- k. Crus cerebri
- l. Trapezoid body
- m. Median fissure
- n. Rostr. colliculus
- o. Caud. colliculus

**1. MIDBRAIN** or mesencephalon (mes-en-SEF-alon) (*G. mesos*, middle): located between the diencephalon and the pons, it connects lower brain centers and the spinal cord with higher brain centers. The roof (tectum) of the midbrain is composed of four colliculi (corpora quadrigemina). The rostral colliculi (ko-Lik-yoo-ly) (n) are the two rounded eminences containing visual reflex centers. The caudal colliculi (o) are two rounded eminences behind the rostral colliculi which contain auditory reflex centers. Cranial nerves III and IV (oculomotor and trochlear) have their nerve cell bodies of origin in and emerge from the midbrain.


**2. Cerebral (mesencephalic) aqueduct:** the ventricular tube running through the midbrain, connecting the third and fourth ventricles.

**3. PONS** (L. bridge): the bulge (ventral metencephalon) between the midbrain and the medulla oblongata. Functionally, it bridges the spinal cord and brain, and different parts of the brain. Nuclei within the pons, working with nuclei in the medulla oblongata, regulate breathing. Several cranial nerves have their cell bodies of origin located in the pons, including the trigeminal (Cn V), abducens (Cn VI), facial (Cn VII), and vestibular branches of the vestibulocochlear (Cn VIII) nerves, but only the trigeminal nerve (Cn V) emerges from the pons.

**4. CEREBELLUM** (ser-e-BEL-um) (L. little brain): the second largest subdivision of the brain. It is the dorsal metencephalon, located dorsal to the pons and medulla and caudal to the occipital lobes, from which it is separated by the transverse fissure.




**Fig. X-18 - Dog - Brain, cerebrum & cerebellum removed - dors. view**



1. Midbrain

3. Pons

9. Cerebellar peduncles



**Fig. X-19 - Dog - Brain, cerebrum & cerebellum removed - ventr. view**

The cerebellum functions as a motor reflex center in coordinating subconscious and conscious skeletal muscle movements. Proprioceptors, located in muscles, tendons, and joints, sense the relative position of one body part to another. Vestibular receptors of the inner ears and visual receptors of the eyes also provide input related to proprioception (sensing position). These proprioceptors send sensory information to the cerebellum, which in turn evaluates this input and sends out motor impulses to adjust muscle actions, thus, maintaining posture and balance, and coordinating skeletal muscle movements.

**5. Vermis (VER-mis) (L. worm):** the central part of the cerebellum.

**6. Lateral masses:** the parts on either side of the vermis. The

lateral masses and the vermis are indented to form parallel ridges (folia), increasing the surface area.


**7. Cerebellar cortex:** the thin, outer layer of gray matter.

**8. Arbor vitae (AR-bohr VEE-tee):** the white matter tracts branching into the cerebellum.

**9. Cerebellar peduncles (pe-DUNG-kulz):** bundles of fibers connecting the cerebellum to the brain stem. The caudal cerebellar peduncles connect the medulla, spinal cord, and the cerebellum. The middle cerebellar peduncles connect the cerebellum and the pons. The rostral cerebellar peduncles connect the midbrain and the cerebellum.



Fig. X-20 - Horse - Brain - ventr. view



**1. MEDULLA OBLONGATA** (me-DUL-la ob'long-GAT-a) or **MEDULLA**: the caudal portion of the brain stem which continues caudally as the spinal cord.


Within the medulla are three vital reflex centers. The cardiac center regulates the rate and strength of the heart contraction. The vasomotor center regulates the diameter of the blood vessels; thus, blood pressure. The rhythm of breathing is regulated by the respiratory centers. Besides these vital reflex centers, the medulla has "nonvital" reflex centers regulating coughing, sneezing, swallowing, and vomiting. The cell bodies of origin of several

cranial nerves are located in the medulla, including the vestibulocochlear (VIII) (cochlear part), glossopharyngeal (IX), vagus (X), accessory (XI) (cranial part), and hypoglossal (XII) nerves.

**2. Pyramids**: formed by motor tracts coming from the cerebral cortex on the ventral surface of the medulla. These tracts cross from one side to the other in the pyramids.

**3. FOURTH VENTRICLE** (pg. 473): located between the medulla and cerebellum.





**Fig. X-21 - Dog - Brain stem, cerebellum removed - dors.view**

**CRANIAL NERVES:** the medulla contains the cell bodies of all or part of VIII, IX, X, XI and XII cranial nerves.

**LIMBIC SYSTEM or emotional brain:** the interconnected parts of the cerebellum, hypothalamus, thalamus, basal ganglia and other nuclei dealing with the emotional aspects of behavior such as fear, anger, pleasure, rage and sorrow. Through these emotions the limbic system modifies the actions of the animal to help insure its survival.

**RETICULAR FORMATION (re-TIK-yoo-lar):** a network of nerve fibers and islands of gray matter located in the brain stem, from the spinal cord to the diencephalon. It is connected to the hypothalamus, basal ganglia, cerebellum, and cerebrum. It functions in consciousness and arousal. When sensory input comes into the brain, the reticular formation arouses the cerebral cortex to respond to such input. Without the reticular formation, an animal would remain unconscious or unaware (coma).



# CRANIAL NERVES

Head-461

**CRANIAL NERVES (CN):** the twelve pairs of nerves arising from the brain. These nerves, along with the spinal nerves, form the peripheral nervous system. All cranial nerves attach to the brain stem, with the exception of Cranial nerve I (olfactory) which enters the cerebrum. All twelve pairs leave the cranial cavity through foramina to reach the head, neck, and body cavities. They are given Roman numerals to indicate the order in which they attach to the brain, from "front" to "back" (rostral to caudal). Their names indicate their functions. Most of the nerves are mixed, meaning they carry both sensory and motor fibers. Some, such as I, II and VIII, are completely sensory, carrying fibers of special senses. Some carry both voluntary and involuntary motor impulses. All these different combinations can be very confusing. In hope of clarification, the different components have been separated into somatic motor nerves, somatic sensory nerves, autonomic (ANS) nerves (sensory and motor) and special sensory nerves. For a complete functional classification of neurons, see appendix A.

I	On	Olfactory
II	Old	Optic
III	Olympus	Oculomotor
IV	Towering	Trochlear
V	Topps	Trigeminal
VI	A	Abducens
VII	Fat	Facial
VIII	Vested	Vestibulocochlear
IX	German	Glossopharyngeal
X	Viewed	Vagus
XI	Some	Spinal accessory
XII	Hops	Hypoglossal

## TYPES OF CRANIAL NERVES:

**Mixed nerve:** a nerve carrying both somatic sensory and motor fibers. They also carry ANS sympathetic motor fibers.

**Motor nerve:** a nerve carrying primarily somatic motor fibers to voluntary (skeletal) mm. These are understood to also carry sensory fibers from muscles innervated by motor fibers. They usually also carry ANS sympathetic motor fibers.

**Sensory nerve:** a nerve carrying only somatic sensory fibers to the brain.

**Special sensory nerve:** a nerve carrying special sensory fibers associated with smell, vision, hearing, or taste (special senses).

**Autonomic (ANS) fibers:** fibers from nerves of the autonomic nervous system. They innervate smooth muscle, cardiac muscle, and glands and are subdivided into fibers of the sympathetic and parasympathetic divisions. Sympathetic fibers are carried by branches of all spinal and most cranial nerves. Parasympathetic fibers are restricted to some sacral spinal nerves (pelvic nerve) and a few cranial nerves (CN III, VII, IX, and X).

## CELL BODIES:

**Motor neuron:** a neuron whose cell body is located in nuclei within the CNS (brain or spinal cord).

**Sensory neuron:** a neuron whose cell body is located in groups (ganglia) outside the CNS.

**I. OLFACTORY (Cn I) NERVE (ol-FAK-toh-ree):** the first cranial nerve, entirely special sensory, dealing with smell. Its cell bodies, located in the lining of the caudal nasal cavity, send their axons into the cranial cavity through the cribriform plate of the ethmoid bone. The axons join the olfactory bulbs of the cerebrum and travel through the olfactory tracts to the pyriform lobe of the cerebrum. The olfactory nerve is the only cranial nerve not entering or exiting the brain through the brain stem.

**II. OPTIC NERVE (Cn II) (OP-tik):** the second cranial nerve, it is also special sensory, dealing with vision. Its cell bodies are located in the retina of the eye. Their axons combine to form the optic nerve which tranverses the orbit to enter the cranial cavity through the optic foramen (1). Both eyes send axons to both visual cortices. Axons coming from the nasal (medial) sides of the eyeballs cross over in the optic chiasm. The visual impulses continue via optic tracts to the thalamus, which relays them to the visual cortex in the occipital lobe of the cerebrum.

**Optic chiasm (ky-AZ-um, G. a crossing) (B):** the joining of the two optic nerves inside the cranial cavity, just rostral to the hypothalamus. It is the site of crossing of some optic fibers.

**Optic tracts (Fig. X-19,i):** the paths from the optic chiasm to the thalamus.

**Occipital lobe of the cerebrum (Fig. X-13;1):** the location of the visual centers.


**III. OCULOMOTOR NERVE (Cn III):** The third cranial nerve arises from the midbrain. It is primarily a motor nerve to most of the eye's voluntary (skeletal) extraocular muscles-the dorsal, medial, and ventral rectus muscles, and the ventral oblique muscle. It also is motor to the superior palpebral levator, the muscle that raises the upper eyelid.

The oculomotor nerve also has ANS motor fibers controlling the involuntary smooth muscles of the eye (ciliary and pupil sphincter muscles). These alter the shape of the lens for focusing (accommodation), and adjust the pupil size. The sensory limb for these visceral reflexes is carried by the optic nerve.

**IV. TROCHLEAR (TROK-lee-ar) NERVE (Cn IV):** the smallest cranial nerve, motor to the dorsal oblique muscle of the eyeball.



Fig. X-22 - Ox - Brain (schematic)  
- ventr. view




- A. Eyeball
- B. Optic chiasm
- C. Ophthalmic, maxillary n. (V)
- D. Mandibular br. (V)
- E. Lingual br. of mandibular n., division of V
- F. Major petrosal n.
- G. Nerve of pterygoid canal
- H. Chorda tympani (VII)
- I. Tympanic n.
- J. Tympanic plexus
- K. First cervical spinal n.

- a. Foramina in cribriform lamina
- b. Optic foramen
- c. Foramen orbitotundum
- d. Oval foramen
- e. Int. acoustic meatus
- f. Stylomastoid foramen
- g. Jugular foramen
- h. Hypoglossal canal
- i. Lat. foramen of atlas
- j. Cavity of middle ear
- l. Pterygopalatine ganglion

- m. Otic ganglion
- n. Trigeminal ganglion (V)
- o. Mandibular ganglion
- p. Geniculate ganglion (VII)
- q. Vestibular ganglion (VIII)
- r. Spiral ganglion (VIII)
- s. Prox. ganglion (IX)
- t. Dist. ganglion (IX)
- u. Prox. ganglion (X)
- v. Dist. ganglion (X)



Fig. X-23 - Ox - Eyeball & CN II, III, IV & VI



**V. TRIGEMINAL NERVE (CnV):** The largest cranial nerve, arises from the pons and is a mixed nerve with three divisions- the ophthalmic, maxillary and mandibular divisions.

**1. Ophthalmic division (V1) (of-THAL-mik):** a sensory division to the skin of the forehead, the skin lateral to the eye, most of the nasal cavity and the cornea of the eye. Its cell bodies are located in the trigeminal ganglion within the cranial cavity, but still outside the brain.

- **Infratrochlear nerve (f):** the principal supply to the horn of small ruminants.

- **Long ciliary nerve (d):** supplies sensation to the cornea.

**2. Maxillary division (V2):** a sensory trigeminal subdivision exiting the cranial cavity and traveling rostrally through the infraorbital canal as the infraorbital nerve to innervate the upper teeth. It exits the canal through the infraorbital foramen to innervate the skin of the nose (muzzle) and face, and the oral cavity.

- **Cornual nerve (j):** the major sensory nerve to the horn of the ox.

- **Infraorbital nerve (n):** passes through the infraorbital canal and exits the infraorbital foramen to supply sensory innervation to the middle part of the face.

**3. Mandibular division (V3):** mixed nerve (both sensory and



## 1. Ophthalmic division of CN V

Colored to indicate if





Fig. X-22 - Ox

Fig. X-24 - Ox - Trigeminal n. (schematic)

a. Lacrimal n.  
b. Frontal n.  
c. Nasociliary n.  
d. Long ciliary n.  
e. Ethmoidal n.  
f. Infratrochlear n.  
g. Zygomatic n.

h. Zygomaticofacial n.  
i. Zygomaticotemporal n.  
j. Cornual br. of CN V  
k. Pterygopalatine n.  
l. Major & minor palatine nn.  
m. Caud. nasal n.  
n. Infraorbital n.

o. Nasal br.  
p. Masseteric br. of mandibular div.  
q. Deep temporal n.  
r. Pterygoid nn.  
s. Auriculotemporal n.  
t. Parotid brs. of CN V

u. Transverse facial n.  
v. Buccal n.  
w. Lingual & sublingual nn.  
x. Inferior alveolar n.  
y. Mylohyoid n.  
z. Mental n.

motor). It supplies motor innervation to the muscles of chewing (mastication). Sensory fibers innervate the lower cheek and jaw, and the rostral two-thirds of the tongue (not taste).

• Mental nerve (z): the continuation of the inferior alveolar nerve (x) as it exits the mental foramen. It supplies sensation to the chin.

**VI. ABDUCENT (ab-DYOO-sent) or ABDUCENS (L., drawing away) NERVE (Cn VI):** (Fig. X-23): The sixth cranial nerve, it is the motor innervation to two skeletal extraocular muscles of the eye; the lateral rectus and part of the retractor bulbi muscles. It originates from the medulla and exits the cranial cavity to enter the orbit. *Memory Aid:* To remember which muscle it innervates, remember that to abduct (move laterally, as in abducent) the eye requires the lateral rectus.

### CLINICAL

**Infraorbital nerve:** can be palpated and anesthetized as it comes out of the infraorbital foramen.

**Mental nerve:** can be palpated and anesthetized as it comes out of the mental foramen.

**Injury to the trigeminal nerve:** can result in sensory deficit of the face and drooped jaw due to paralysis of the muscles of mastication.

**Injury to abducens nerve:** results in inability to gaze laterally.



# FACIAL NERVE

Head-465





Fig. X-25 - Ox - Supf. vessels, 7 nerves of head - lat. view

Fig. X-26 - Horse - Skull (schematic) - lat. view

- a. Ext. jugular v.
- b. Linguofacial v.
- c. Parotid salivary gl.
- d. Mandibular salivary gl.
- e. Parotid duct
- f. Masseter m.
- g. Rostr. auricular n. (VII)
- h. Zygomatic br. (VII)
- i. Palpebral br. (VII)
- j. Caud. auricular n. (VII)
- k. Digastric br. (VII)
- l. Dors. buccal br. (VII)
- m. Ventr. buccal br. (VII)
- n. Auriculopalpebral n. (VII)



**VII. FACIAL NERVE (Cn VII):** a mixed nerve originating in the pons and exiting the cranial cavity from the medulla to travel across the face under the skin. It innervates the muscles of facial expression (including the orbicularis oris muscle). Sensory branches (chorda tympani nerve) from the rostral two-thirds of the tongue carry the sense of taste to the brain. The facial nerve also carries ANS motor fibers to the lacrimal gland (major petrosal), and the sublingual and mandibular salivary glands.

ANS parasympathetic: innervate the lacrimal glands and salivary glands. Lacrimalization is very important because it is only controlled by Cn VII; whereas salivation is also caused by Cn IX.

**VIII. VESTIBULOCOCHLEAR NERVE (Cn VIII)** (ves-tib'-yoo-loh-KOHK-lee-ar) (Fig. X1-39, A & B): the special sensory nerve dealing with hearing and equilibrium. It is divided into two branches; the cochlear and the vestibular. (For more see pg. 556)

## CLINICAL

Middle ear infections: can cause paralysis of the facial nerve.


This can cause loss of taste, facial paralysis and loss of lacrimation. Dogs have little vanity about their appearance, the glossopharyngeal nerve also has taste fibers, but without a functioning lacrimal gland or the orbicularis oculi muscle the eye can seriously dry up.

**Auriculopalpebral nerve (n):** innervates the eyelids and can be blocked for procedures of the eye.

**Buccal branches of the facial nerve:** cross the lateral aspect of the masseter muscle. These can be injured, causing facial paralysis (example, horse lying on a harness buckle during surgery [buccal on buckle]).

**Facial/trigeminal reflex arc:** the facial nerve supplies the motor component to the sensory component of the trigeminal nerve. Pricking the face with a pin checks this arc. If either nerve is paralyzed, then a twitch of the muscles will not be elicited.





**IX. GLOSSOPHARYNGEAL NERVE (Cn IX)** (glos'oh-fa-RIN-jeal): a mixed nerve supplying, as its name suggests, the tongue and pharynx. It deals with taste, swallowing and salivation. Motor fibers with those of the vagus nerve supply muscles in the pharynx that aid in swallowing. The special sense of taste from the caudal third of the tongue is carried by the glossopharyngeal nerve. Autonomic (ANS) sensory and motor fibers regulate the secretion of the parotid salivary gland. Sensory (ANS) fibers from the carotid sinus play a major role in sensing and regulating blood pressure.

**X. VAGUS NERVE (Cn X)** (L. wandering): a mixed nerve. Its motor fibers innervate the muscles to the pharynx (with the glossopharyngeal nerve) and larynx that control swallowing and vocalization. Its parasympathetic (ANS) fibers to the viscera of the cervical region, the thorax and abdomen regulate these organs' activities (pg. 526). The recurrent laryngeal nerve is part of the vagus that peels off in the thorax and returns up the neck to supply motor innervation to the muscles of the larynx, including the dorsal cricoarytenoideus muscle.

**XI. ACCESSORY NERVE (Cn XI)**: a motor nerve to some neck muscles, including the trapezius. It is divided into cranial and spinal portions, with cell bodies located in the medulla and spinal cord, respectively. Both portions leave the cranial cavity together, then branch immediately. The cranial portion (g) is the somatic motor innervation to the soft palate, pharynx and larynx dealing with

swallowing and vocalization. The spinal portion (h) descends into the neck to supply the trapezius muscle and parts of the sternocephalicus, brachiocephalicus and omotransversarius muscles.

**XII. HYPOGLOSSAL NERVE (Cn XII)**: motor nerve supplying the muscles (voluntary) of the tongue, controlling vocalization and swallowing.

#### CLINICAL:

**Damage to the glossopharyngeal or vagus:** may cause difficulty in swallowing.

**Rabies:** of zoonotic importance, causing hydrophobia (fear of water, as in drinking) due to paralysis of the pharynx (IX & X). With pharyngeal paralysis, salivation, or choke first think rabies!

**Damage to the recurrent laryngeal nerve:** common in race horses causing paralysis of the muscle that opens the larynx (dorsal cricoarytenoideus), resulting in a condition called "roaring".

**Damage to the hypoglossal nerve:** causes paralysis to the tongue's muscles and unilateral damage causes deviation of the tongue toward the normal side.




CRANIAL NERVE	FUNCTION
I. Olfactory	Special Sense - smell (SVA)
II. Optic	Special Sense - vision (SSA)
III. Oculomotor Short ciliary n.	Motor - extrinsic eye mm. (dors., med., & ventr. oblique & superior levator) (GSE) ANS - parasympathetic - ciliary & sphincter pupillae mm. (GVE)
IV. Trochlear	Motor - dors. oblique m. (GSE)
V. Trigeminal	
V <sub>1</sub> . Ophthalmic	Sensory - area of forehead (skin of forehead & caud. nose, med. side of eye, eyeball, nasal mucosa) (GSA)
V <sub>2</sub> . Maxillary	Sensory - area of upper jaw (skin of lat. eye, nose, upper lip, cheek; mucosa of nasal cavity, soft & hard palate, upper lip; teeth of upper jaw & gums.) (GSA)
V <sub>3</sub> . Mandibular	Mixed Motor - muscles of mastication (masseter, temporalis, med. & lat. pterygoid, rostr. belly of digastricus & mylohyoid) (SVE) Sensory - area of lower jaw (skin of lower chin, lower lips; roots of teeth of lower jaw; mucosa of tongue, oral vestibule, floor of mouth); temporal & zygomatic regions (skin of temporal & zygomatic regions, ext. acoustic meatus, tympanic membrane, parotid salivary gland & guttural pouch in horse) (GSA)
VI. Abducent	Motor - lat. rectus & retractor bulbi mm. (GSE)
VII. Facial "Intermediate"	Motor - muscles of facial expression (SVE) Special Sense - taste (rostr. 2/3 of tongue [chorda tympani n.]) (SVA) ANS - parasympathetic - lacrimal, nasal & palatine glands; mandibular & sublingual salivary glands. (GVE)
VIII. Vestibulocochlear	
Cochlear	Special Sense - hearing (organ of corti) (SSA)
Vestibular	Special Sense - equilibrium (semicircular canals, utricles & saccule) (SSA)
IX. Glossopharyngeal	Mixed Motor - stylopharyngeus caudalis, levator veli palatini, tensor veli palatini mm. (SVE) Sensory - pharyngeal region (mucosa of caud. 1/3 of tongue, soft palate, tonsils, pharynx, auditory tube & middle ear; carotid sinus & carotid body) (GVA) ANS - parasympathetic - parotid & buccal salivary glands (GVE) Special Sense - taste (caud. 1/3 of tongue) (SVA)
X. Vagus	Mixed Motor - pharyngeal & laryngeal mm. (pharyngeal mm. & skeletal m. of esophagus, caud. cricothyroideus m. [cran. laryngeal n.], intrinsic mm. of larynx except cricothyroid m. [recurrent laryngeal n.]) (SVE) Sensory - baroreceptors in aortic arch & chemoreceptors in aortic bodies. (GVA) ANS - parasympathetic - pharynx, larynx, trachea, esophagus, thoracic & abdominal organs (GVE)
XI. Accessory	
Ext. br.	Motor - trapezius, sternocephalicus, cleidocephalicus, omotransversarius mm. (SVE)
Int. br.	Motor - intrinsic mm. of larynx via fibers traveling in the recurrent laryngeal n. (CN X) (SVE)
XII. Hypoglossal	Motor - intrinsic & extrinsic mm. of tongue (genioglossus, styloglossus & hyoglossus mm.) (GSE)



**Fig. X-28 - Horse - Supf. vessel & nerves of head**  
- lat. view

- VII. Facial n.**
- a. Linguofacial v.
  - b. Angularis oculi a. & v.
  - c. Dors. buccal br. (CN VII)
  - d. Ventr. buccal br. (CN VII)
  - e. Parotid salivary gland
  - f. Parotid duct
  - g. Buccinator m.
  - h. Zygomaticus m.



**HEAD - NERVE BLOCKS:** Before general anesthesia allowed animals to be put down and recovered safely, nerve blocks of the head were commonly used. There are several problems of the equine head that require general anesthesia or nerve blocks: teeth removal for abscesses, open tooth roots, sinusitis, draining sinus impactions. Today general anesthesia is used instead, but can be supplemented by specific nerve blocks.

**Mental nerve block:** anesthetize the mental nerve as it comes out of the mental foramen to anesthetize the lower chin.

**Mandibular alveolar nerve block:** injection at the mandibular foramen. The foramen is on the medial side of the mandible, opposite the point at which a line across the occlusal surface of the cheek teeth crosses a perpendicular line from the caudal edge of the eye. Insert a 6" needle medial to the mandible straight up to this point and inject anesthetic. This anesthetizes the lower lip, but doesn't get the incisors because those fibers are internal. This block can be used when repairing lacerations of the lower lip.

**Infraorbital nerve block:** palpate the rostral end of the facial

crest. Run your finger dorsally to the infraorbital foramen and palpate the nerve under the levator labii superioris muscle. This block only anesthetizes superficial structures from the point of the foramen to the lip. Remember, nerves do not respect the midline, so do both sides to anesthetize the middle of the upper lip. This can be used when repairing lacerations on the lips or the bridge of the nose. Injecting into the foramen one inch, which is difficult, anesthetizes the face back to the orbit.

**Maxillary nerve block:** find the caudal angle of the eye and palpate the notch in the lower part of the zygomatic arch, just below the caudal angle of the eye. Pass the needle under the notch and aim rostrally and ventrally to anesthetize the maxillary nerve where it enters into the maxillary foramen. This anesthetizes the upper cheek teeth.

**Supraorbital block** (a branch of the ophthalmic division): palpate the foramen in the zygomatic process of the frontal bone. Inject a "bleb" of anesthetic over the foramen and rub it in. This anesthetizes the area over the forehead between the eyes. Do not inject into the foramen and thus the eyeball.



Fig. X-29 - Ox - Structures of head,  
second layer - lat. view






Fig. X-30 - Ox - Structures of the head,  
third layer - lat. view





**Fig. X-31 - Ox - Structures of the head, fourth layer - lat. view**

- |                                |                                     |  |  |
|--------------------------------|-------------------------------------|--|--|
| A. Int. jugular v. (X-29)      | K. Cornual a.                       | a. Auriculopalpebral n. (VII)(X-29)            | j. Palpebral br. of zygomatic br.(VII) |
| B. Maxillary v.                | L. Inferior alveolar a.             | b. Dors. buccal br. (VII)                      | k. Mylohyoid n. (V)                    |
| C. Ext. carotid a. (X-30)      | M. Infraorbital a.                  | c. Ventr. buccal br. (VII)                     | l. Inferior alveolar n. (V)            |
| D. Supf. temporal a.& v.       | N. Parotid duct (X-29)              | d. Auriculotemporal n. (V)                     | m. Lingual n. (V)                      |
| E. Transverse facial a. (X-29) | O. Thyroid gland                    | e. Zygomaticotemporal n. (V)                   | n. Infraorbital n. (V)                 |
| F. Deep facial v.              | P. Lat. retropharyngeal lnn.        | f. Cornual n. (V)                              |  |
| G. Buccal a.                   | Q. Med. retropharyngeal lnn. (X-31) | g. Buccal n. (V)                               |  |
| H. Linguofacial v.             | R. Mandibular duct                  | h. Caud. auricular n. (VII)(X-30)              |  |
| I. Angularis oculi v.          | S. Parotid salivary gland (X-29)    | i. Zygomatic br. of auriculopalpebral n. (VII) |  |
| J. Maxillary a. (X-30)         |                                     |  |  |






Fig. X-32 - Spinal cord & spinal nn. - cross section (schematic)

**SPINAL CORD:** the long column of nervous tissue located within the vertebral (spinal) canal that, along with the brain, makes up the central nervous system (CNS). The spinal cord is the direct continuation of the caudal brain stem (medulla oblongata) beginning at the level of the foramen magnum. It extends only to the lumbosacral region of the spinal canal because the cord grows slower than the spinal column ("back bone"). Because of this the last spinal nerves must pass progressively caudally to reach their exit from corresponding intervertebral foramina.

**Divisions of the spinal cord:** divided into cervical (C), thoracic (T), lumbar (L), sacral (S) and caudal (coccygeal) regions which give rise to the spinal nerves that exit between the vertebrae.

**Spinal segment:** a region of the spinal cord from which a pair of spinal nerves arise. The spinal cord stops growing before the spinal column resulting in the spinal cord segments not always lining up with the corresponding vertebrae. The caudal thoracic and cranial lumbar cord segments lie over the vertebrae of the corresponding numbers. The last lumbar, the sacral, the caudal segments and the end of the spinal cord are more cranial to the corresponding vertebrae.

**1. Cervical enlargement:** the enlargement of the caudal part of the cervical and cranial part of the thoracic spinal cord regions; the spinal nerves serving the thoracic limb (brachial plexus) emerge here.

**2. Lumbar enlargement:** the enlargement of the spinal cord where nerves to and from the pelvic limb attach.

**3. Conus medullaris (KOH-nus med-yoo-LAR-is):** the tapered, terminal end of the spinal cord. The location in the vertebral canal varies among the species.

**4. Filum terminale (FY-lum ter-min-AL-ee):** the fibrous cord derived from the pia mater, extending from the conus to the caudal vertebrae. It helps anchor the spinal cord in the spinal canal.

**5. Cauda equina (KAW-da ee-KWY-na) ("Horse's tail"):** the structure formed by nerve roots leaving the caudal part of the spinal cord, traveling caudally to reach their exit from the vertebral canal.

**6. Dorsal median fissure:** the dorsal groove extending the length of the dorsal surface of the spinal cord. Along with the ventral median fissure, it divides the cord into symmetrical lateral halves.

**7. Ventral median fissure:** the groove extending the length of the ventral surface of the spinal cord.

**CROSS SECTIONS** of the spinal cord show the fissures mentioned above and a central H-shaped mass of gray matter surrounded by white matter.


• **8. Gray matter:** the nerve cell bodies and synapses organized into the shape of an "H". This is further anatomically divided into horns (columns).

• **9. White matter:** the axons running up and down the cord in specific tracts (fasciculi). These tracts connect the brain and interconnect the various spinal segments of the cord. The myelin around the nerve fibers gives the region its white color.

– **Ascending tracts** are the axons traveling up the spinal cord carrying sensory impulses (information) to the brain.

– **Descending tracts** are the axons of nerve cell bodies in the brain. They travel down the spinal cord carrying motor impulses.






Adapted from Applied Veterinary Anatomy, Habel and de Lahunta, 1986



Fig. X-35 - Horse - Spinal cord & meninges  
- transverse section (schematic)



**1. SPINAL NERVES:** the joined dorsal and ventral roots arising from the spinal cord. They are mixed nerves carrying sensory impulses toward the spinal cord and motor impulses away from the spinal cord. Just after a spinal nerve emerges through an intervertebral foramen, it splits into dorsal, ventral, and communicating branches.

**2. Dorsal (sensory) root:** the root bringing sensory fibers to the spinal cord.

**3. Dorsal root ganglion:** a swelling on the dorsal root containing the cell bodies of the sensory (afferent) neurons (pseudounipolar) making up the dorsal root.

**4. Ventral root (motor):** the root carrying motor (efferent) nerve fibers from cell bodies in the spinal cord to effector structures (organs, muscles, glands, etc.) of the body.

**5. Dorsal branch (rami) of spinal nerves:** extend dorsally to

innervate deep muscles and skin above the transverse processes of the vertebrae. It carries sensory and motor fibers.

**6. Ventral branch (rami) of spinal nerves:** supply the muscles and skin of the limbs and the lateral and ventral areas of the trunk. It also carries motor and sensory fibers.

**7. Communicating branches:** connect the spinal nerves to the autonomic nervous system (ANS) (sympathetic trunk) (pg. 524).

**SPINAL NERVE ORGANIZATION:** the endoneurium, a delicate connective tissue that surrounds individual fibers in a spinal nerve. The perineurium, a connective tissue sheath, surrounds bundles of endoneurium-covered nerve fibers (fascicles). A fascicle is a bundle of nerve fibers surrounded by perineurium. The epineurium is the connective tissue covering the entire spinal nerve. It is continuous with the spinal meninges at the intervertebral foramen.






Fig. X-36 - Ox - Ventricles - craniolat. view

**VENTRICLES** (VEN-tri-kulz): a series of interconnected cavities in the cerebral hemispheres and brain stem. They are directly continuous with the central canal (Fig. X-32,e) and the subarachnoid space between the meningeal layers (see meninges) surrounding the brain and spinal cord.

1. **Lateral ventricles:** the largest of the ventricles. There is one located within each cerebral hemisphere.
2. **Third ventricle:** located in the diencephalon, encircling the interthalamic adhesion.
3. **Interventricular foramina:** the two channels connecting the third ventricle with the two lateral ventricles.
4. **Cerebral (mesencephalic) aqueduct:** the small canal running longitudinally through the midbrain to connect the third and fourth ventricles.
5. **Fourth ventricle:** located between the brain stem and the overlying cerebellum. It is directly continuous with the central canal of the spinal cord.
6. **Openings between the fourth ventricle and the subarach-**

noid space: two lateral apertures (a).

**Choroid** (KOH-royd) **plexuses** (G. *choroid* delicate membrane): the capillary network extending into the ventricles from their walls. They secrete cerebrospinal fluid (CSF). The CSF produced in the lateral ventricles circulates through the interventricular foramina to the third ventricle where more fluid is added by the plexuses in its roof. The fluid then passes through the cerebral aqueduct to the fourth ventricle, where its choroid plexus adds more fluid. The fluid then goes to the spinal canal or out through apertures in the roof of the fourth ventricle into the subarachnoid space.

**CEREBROSPINAL** (se-ree'broh-SPY-nal) **FLUID** (CSF): a clear fluid produced by the choroid plexuses which circulates through the ventricles, central canal and subarachnoid space surrounding both the brain and spinal cord. The brain and spinal cord (CNS) "float" in the cerebrospinal fluid which acts as a protective shock absorber.

**Arachnoid villi** (granulations): projections of the arachnoid and subarachnoid space into the sagittal dural sinus. They provide escape of the CSF into the general circulation.






Fig. X-37 - Ox - Cranium & brain  
- median section

**MENINGES** (me-NIN-jeez) (sin.=meninx) (L. membranes): the three membranes surrounding the brain and spinal cord. The spinal and cranial meninges are continuous at the foramen magnum.

**1. Dura mater** (DYOO-ra may-ter) (L. *dura* hard + *mater* mother): the outermost meninx made of strong connective tissue. The cranial dura mater has two layers where the spinal dura has one. **Pachymeninx** (G. *pachys* thick + *meninx* membrane) is another name for the dura mater.

**2. Epidural space:** the cavity between the dura mater and the wall of the vertebral canal. Because the cranial dura mater is fused with the periosteum of the bones of the cranium, there is no epidural space surrounding the brain.

**3. Subdural space:** a potential space located between the dura mater and the arachnoid.

**4. Arachnoid** (a-RAK-noyd) (G. *arachne* spider + *eidos* resembles): the delicate middle meninx.

**5. Subarachnoid space:** the cavity between the arachnoid and the pia mater where cerebrospinal fluid (CSF) circulates.

**6. Pia mater** (PEE-a-may-ter) (L. *pius* tender + *mater* mother): the innermost meninx, closely investing the spinal cord and brain.

**Leptomeninges** (G. *leptos* slender + *meninges* membranes): refers to the pia and arachnoid together.

**7. Trabeculae** (tra-BEK-yoo-lee) (L. beams): connective tissue fibers spanning the subarachnoid space to join the arachnoid and pia.

**CRANIAL MENINGES:** the three meningeal layers surrounding the brain. The cranial and spinal subarachnoid and pia mater are similar and continuous at the foramen magnum.

**Cranial dura mater:** the outer membranous covering of the brain, composed of two layers: a tough, outer layer and a thin, inner layer. The two layers of the dura separate over the fissures of the brain; the inner layer extends into the fissures forming partitions and dural sinuses. The cranial dura mater is continuous






Fig. X-38 - Ox - Cranium & brain - cross section

with the spinal dura mater at the foramen magnum.

**8. Outer (periosteal) layer:** the tough, fibrous layer attached to the bones of the cranium, forming the inner periosteum of the cranial bones.

**9. Inner (meningeal) layer:** the thinner layer.

**Partitions:** the folding and protrusion of the inner layer of the dura into the large fissures between parts of the brain.

**10. Falx (L. "sickle") cerebri (falks ser'e-bry):** the partition extending into the longitudinal fissure, separating the right and left cerebral hemispheres.

**11. Tentorium cerebelli (ten-TOH-ree-um ser'e-BEL-lee):** the partition extending into the transverse fissure between the occipital lobes of the cerebral hemispheres and the cerebellum.

**12. Dural sinuses:** the venous spaces formed where the two dural layers separate from each other. The dural sinuses are filled with venous blood returning to the heart from the brain. The cerebro-

spinal fluid (CSF) is transferred from the subarachnoid space into these venous sinuses through arachnoid villi and returned to the general circulation. Since secretion and absorption is usually equal, the pressure of the cerebrospinal fluid is relatively constant.

**13. Cisterna magna (L. reservoir + large):** an expansion of the subarachnoid space located between the caudal surface of the cerebellum and the dorsal surface of the medulla, just inside the foramen magnum. This is a common site for a CSF "tap" (removal of CSF).

## CLINICAL:

**Internal hydrocephalus (G. hydro water + enkephalos brain):** an accumulation of cerebrospinal fluid in the brain's ventricles due to obstruction of the flow of fluid. The blockage can occur in the cerebral aqueduct or the lateral apertures.

**External hydrocephalus:** an accumulation of CSF in the subarachnoid space due to interference with absorption into the dural venous sinuses.



# SPINAL MENINGES

472-Neck & Back-477




Fig. X-39 - Spinal cord at 10th thoracic vertebra - cross section

- A. Brain
- B. Spinal cord
- C. Dors. root of spinal n.
- D. Dors. root of ganglion n.
- E. Ventr. root of spinal n.
- F. Spinal n.
- G. Central canal
- H. Gray matter
- I. White matter
- J. Foramen magnum

- a. 10th thoracic vertebra
- b. Epineurium of spinal n.
- c. Ventr. spinal a.
- d. Int. vertebral venous plexus
- e. Lumbar cistern




Fig. X-40 - Ox - Spinal cord & meninges (schematic) - sagittal section

**SPINAL MENINGES:** the membranes surrounding the spinal cord, continuous with the cranial meninges at the foramen magnum.

**14. Denticulate ligaments** (*L. dentatus* toothed): the membranous extensions of the pia mater connecting to the dura mater between the spinal nerves; anchoring the spinal cord laterally.

**15. Filum terminale:** the fibrous strand formed by the meninges attaching the dural tube to the caudal vertebrae.

## CLINICAL:

**Caudal epidural analgesia:** injection of a small volume of analgesic into the epidural space at either the sacrocaudal (S5-

Ca1) or first intercaudal space (Ca1-Ca2). This inexpensive, simple procedure is commonly performed on cows, sheep, and goats for obstetrical manipulations and surgeries involving the tail, anus, rectum, vulva, perineum and prepuce. Just enough analgesia to block the sacral and caudal nerves is needed. If the analgesic travels further up the spinal column, it may cause loss of locomotor function of the hind limbs. Pump the tail up and down while palpating for the first movable space. This may be the sacrocaudal (S5-Ca1) or first intercaudal space (Ca1-Ca2). In older cows the sacrocaudal space ossifies with age. Insert a 1 1/2 to 2" needle on the median plane through disinfected skin between the S5-Ca1 or Ca1-Ca2 ventrocranially at an angle of 10° to the vertical. Pass the needle to the floor of the canal, then withdraw needle slightly to be sure you are in the canal. Inject 5 ml per 100 pounds of body weight. Success causes paralysis of the tail, in an animal that remains standing.






Fig. X-41 - Ox - Spinal plexuses - lat. view

A. Trigeminal n. (V)  
B. Facial n. (VII)  
C. Hypoglossal n. (XII)  
D. Accessory n. (XI)  
E. Radial n.

F. Ulnar n.  
G. Digital n.  
H. Femoral n.  
I. Saphenous n.  
J. Ischiatic n.

K. Tibial n.  
L. Common fibular n.  
M. Digital n.  
N. Obturator n.  
O. Pudendal n.

a. Dors. br. of spinal nn.  
b. Ventr. br. of spinal nn.  
c. Costoabdominal n.  
d. Iliohypogastric n.  
e. Ilioinguinal n.  
f. Genitofemoral n.

**SPINAL PLEXUSES** (*plexus braid*): the interlacing of the ventral branches of spinal nerves in every region, except the thorax. The major plexuses so formed are cervical, brachial, and lumbosacral.

**1. Cervical plexus** (L. *cervix* neck): the joining of many ventral branches of the cervical nerves, supplying structures in the neck.

**2. Phrenic nerve**: arises from the cervical plexus and supplies motor fibers to the diaphragm. This is why a broken neck can result in respiratory paralysis.

**3. Brachial plexus**: a network formed by the ventral branches of the last few cervical nerves and the first one or two thoracic nerves. It supplies most of the muscles of the thoracic limb.

**4. Lumbosacral plexus**: the ventral branches of the lumbar and sacral nerves. It supplies muscles and skin of the abdominal wall, the pelvic limb, external genitalia, rump and perineum.

**5. INTERCOSTAL (THORACIC) NERVES**: the ventral branches of the thoracic nerves do not form a plexus, but pass in the intercostal spaces as intercostal nerves. They supply the intercostal muscles and the overlying skin. The costoabdominal (last thoracic) nerve runs behind the last rib and helps supply the flank.

**DERMATOME** (DER-ma-tohm): an area of skin supplied by a single spinal nerve.



Fig. X-42 - Horse - Spinal nerves & brachial plexus (schematic) - lat. view




Fig. X-43 - Horse - Neck - cross section

A. Accessory n. (XI)  
B. Cran. cervical ganglion  
C. Hypoglossal n. (XII)  
D. Brachial plexus

a. Med. br. of dors. br.  
b. Lat. br. of dors. br.  
c. Cutaneous br.  
d. Spinal n. C<sub>1</sub>  
f. Spinal n. C<sub>2</sub>  
g. Major occipital n.  
(dors. br.)

h. Br. to accessory n.  
i. Great auricular n.  
j. Transverse cervical n.  
k. Spinal n. C<sub>6</sub>  
l. Supraclavicular nn.  
(cutan. brs. of k)  
m. Spinal n. T<sub>1</sub>

n. Intercostal n.  
o. Axillary n.  
p. Radial n.  
q. Median n.  
r. Ulnar n.







Fig. X-44 - Ox - Thorax (schematic)  
- cross section

Fig. X-45 - Ox - Thorax (schematic)  
- lat. view



A. Mixed ramus communicans  
B. Thoracic sympathetic chain  
C. Brachial plexus

- a. Med. br. of dors. br.
- b. Lat. br. of dors. br.
- c. Lat. (prox.) cutan. br.
- d. Lat. perforating br. of intercostal n.
- e. Lat. (dist.) cutan. br.
- f. Connecting br. to lat. thoracic n.
- g. Ventr. perforating br. of intercostal n.
- h. Ventr. cutan. n.
- i. Long thoracic n. (C7-8) (X-45)

- j. Thoracodorsal n. (C7-8)
- k. Lat. thoracic n. (C8-T2)
- l. Intercostobrachial n.
- m. Costoabdominal n. (T13)
- n. Spinalis et semispinalis m. (X-44)
- o. Longissimus thoracis m.
- p. Iliocostalis thoracis m.

- q. Ext. intercostal m.
- r. Int. intercostal m.
- s. Ascending pectoral m.
- t. Transversus thoracis m.
- u. 7th thoracic vertebra
- v. Sternum
- w. Costal pleura



**BRACHIAL PLEXUS:** the network of nerves formed from the ventral branches of the last few cervical and first one or two thoracic spinal nerves. The nerves arising from this plexus innervate the intrinsic and some of the extrinsic muscles of the thoracic limb and, via the phrenic nerve, the diaphragm. The brachial plexus has roughly the same organization and distribution in all the domestic species, with the exception of the digits. Clinical information can be obtained by knowledge of the muscles innervated, areas of cutaneous sensation, and the spinal cord segments contributing to each nerve.

1. **Suprascapular nerve:** extends from the brachial plexus around the cranial surface of the neck of the scapula to innervate the infraspinatus and supraspinatus muscles.

2. **Radial nerve:** supplies the extensors of the elbow, carpus and digits (caudal arm muscles and the craniolateral forearm muscles). Extending from the brachial plexus into the triceps brachii muscle, it then passes around the caudal aspect of the humerus to reach the lateral side of the arm. Continuing distally, it branches into superficial and deep branches to the forearm. The superficial branch of the radial nerve supplies the skin of the craniolateral forearm in all domestic species. It is sensory to the dorsal surface of the manus in all, except the horse.

3. **Ulnar nerve:** motor to some caudomedial forearm muscles (flexor group) and muscles of the manus. It runs from the brachial plexus on the medial side of the forearm with the median and musculocutaneous nerves. At the elbow, it separates from these nerves to reach the caudal aspect of the forearm. It is sensory to the caudal forearm and palmar manus. In the dog it is the cutaneous innervation to the fifth (most lateral) digit.

4. **Median nerve:** along with the ulnar nerve, supplies motor innervation to the flexor muscles of the carpus and digits. It, with the ulnar nerve, is sensory to the palmar surface of the manus. The median nerve runs with the brachial vessels and the musculocutaneous and ulnar nerves in the arm. It continues on the medial side of the forearm to divide into medial and lateral palmar nerves, just proximal to the carpus.

5. **Long thoracic nerve:** innervates the serratus ventralis muscle.

6. **Thoracodorsal nerve:** innervates the latissimus dorsi muscle.

7. **Musculocutaneous nerve:** innervates the flexors of the elbow (biceps brachii and brachialis muscles) and the coracobrachialis muscle. It gives off the median cutaneous antebrachial nerve.

8. **Axillary nerve:** innervates the true flexors of the shoulder (teres major, teres minor and deltoid muscles). It dives between the teres major and subscapular muscles medially to reach the lateral side of the shoulder. Its cutaneous branches supply the lateral surface of the arm and cranial aspect of the forearm (lateral cutaneous brachial and cranial cutaneous antebrachial nerves).

**Lateral thoracic nerve (not shown):** supplies the cutaneous trunci muscle and cutaneous innervation to the ventrolateral abdominal wall.

## SPECIES DIFFERENCES

**Horse:** the radial nerve doesn't extend past the carpus

**Ungulates:** the median and musculocutaneous nerve appear as one nerve in the brachium, except for the musculocutaneous muscular branches. The two nerves are separate in the carnivores.

## CLINICAL

**"Sweeney" or "shoulder slip":** a condition seen in the horse due to injury of the suprascapular nerve. This results in rapid atrophy of the supraspinatus and infraspinatus muscles which produces a prominent scapular spine. Before atrophy, the shoulder is unstable and slips laterally, appearing to be dislocated.

**Radial (nerve) paralysis:** the most common and clinically significant nerve problem of the forelimb. It is usually due to traumatic injury. Clinical manifestations vary with location of the injury.

**"High" radial nerve paralysis:** proximal to where the nerve innervates the triceps brachii muscle. This results in an inability to extend the elbow, thus, inability to bear weight on the limb.

**"Low" radial nerve paralysis:** occurs distal to the triceps innervation, thus, weight can be born on the limb. The extensor muscles of the carpus and digits are affected, manifested clinically in "knuckling over" (dragging the dorsum of the foot on the ground). Most animals compensate by "flipping" the foot forward when moving the limb so the foot lands in the proper position.

**Brachial plexus avulsion:** results in damage to many nerves of the limb, resulting in a flaccid limb that is dragged.

**Ulnar or medial nerve damage:** has little clinical manifestation due to the overlap of their motor innervations.

**Panniculus (cutaneous trunci) response:** contraction of the cutaneous trunci muscle in response to a pin prick. The sensory component of the reflex passes over the spinal nerves to the spinal cord at the level of the pin prick. The information passes up the spinal cord to the motor nerves of the lateral thoracic nerve in the caudal cervical region. This test is done systematically from caudal to cranial along the thorax. A positive panniculus response indicates the spinal cord is intact from roughly the level of the stimulus to the cervical area. A negative panniculus response may indicate the level of spinal cord damage (see Appendix - pg. 566).






Fig. X-46 - Dog - Brachial plexus  
- ventr. view

A. Phrenic n.  
B. Axillary a. & v.  
C. Subscapular n.  
D. Supf. radial n., med. br.  
E. Med. cutan. antebrachial n.

a. Brachiocephalicus m.  
b. Supraspinatus m.  
c. Subscapular m.  
d. Teres major m.  
e. Latissimus dorsi m.

f. Tensor fasciae antebrachii m.  
g. Triceps brachii m.  
h. Biceps brachii m.  
i. Extensor carpi radialis m.  
j. Pronator teres m.

k. Supf. pectoral m.  
l. Deep pectoral m.  
m. Serratus ventralis m.  
n. Scalenus m.






Fig. X-47 - Dog - Lt. thoracic limb (schematic) - med. view







Fig. X-48 - Dog - metacarpus & digits (schematic) - dors. view

Fig. X-49 - Dog - Lt. metacarpus & digits (schematic) - palm. view





**NERVE DISTRIBUTION TO THE EQUINE ANTEBRACHIUM:** Understanding the distribution of the nerves in horses is very important in lameness diagnosis with nerve blocks.

**Radial nerve:** does not extend past the carpus as it does in the other domestic species.

**Median, the ulnar and the median cutaneous antebrachial (a branch of the musculocutaneous):** are the three nerves passing the carpus in the horse.

**Median nerve:** bifurcates into the medial and lateral branches proximal to the carpus.

**Median palmar nerve:** is a direct continuation of the median nerve in the canon region.

**Ulnar nerve:** bifurcates just proximally to the carpus into dorsal and palmar branches.

**Dorsal branch of the ulnar nerve:** wraps around the cannon



bone and descends on the dorsolateral side of the cannon region to the fetlock.

**Palmar branch of the ulnar nerve:** joins with the lateral branch of the median nerve to form the lateral palmar nerve.

**Medial and lateral palmar nerves:** travel down either side of the flexor tendons. At the level of the fetlock they give off a dorsal branch and continue as the palmar digital nerves.

**Medial and lateral digital nerves:** pass distally on the palmar aspect of the digit to innervate the heel region of the foot. They form a triad along with the digital vein and the digital artery on each side. These triads are arranged vein, artery, nerve (VAN) from dorsal to palmar/plantar.

**Dorsal branches of the digital nerves:** passes distally to innervate the toe region of the foot.

**Communicating branch:** carries fibers from the medial palmar nerve (median nerve fibers) to the lateral palmar nerve (ulnar and median nerve).

**Dorsal branch of the palmar digital nerve and the palmar digital nerves:** travel together for a small segment past the fetlock. This is important when trying to block one without getting the other.

**Deep branch of the lateral palmar nerve or deep branch of the ulnar nerve:** arises at the carpus from the lateral palmar nerve then dives deep and travels in close association to the metacarpal bones below the suspensory ligament.

**Palmar metacarpal nerves:** are extensions of the deep ulnar nerve. They course distally in between the splint bones and the cannon bone. At the buttons of the splints they become superficial and continue to the fetlock joint.

**Medial cutaneous antebrachial nerve:** is the cutaneous continuation of the musculocutaneous nerve. It extends distally to the fetlock.




Fig. X-51 - Horse - Rt. metacarpus & digit (schematic) - dors. view

Fig. X-52- Horse - Rt. metacarpus & digit (schematic) - palm. view



# NERVES - THORACIC LIMB

Thoracic limb-487

NERVES	MOTOR	SENSORY
Suprascapular	motor - supraspinatus & infraspinatus mm.	
Subscapular	motor - subscapular m.	
Pectoral nn.	motor - pectoral mm.	
Long thoracic	motor - serratus ventralis m.	
Thoracodorsal	motor - latissimus dorsi m.	
Lateral thoracic	motor - cutaneous trunci	sensory - skin, ventr. thoracic & abdominal walls
Musculocutaneous	motor - coracobrachialis, biceps brachii & brachialis mm.	
medial cutaneous antebrachial		sensory - med. surface of forearm
Axillary	motor - true flexors of shoulder (teres major, teres minor & deltoid mm.)	
		sensory - cran. aspect of arm & forearm
Radial	motor - extensors of elbow, carpus & digits (triceps brachii, anconeus, tensor fasciae antebrachii, ext. carpi radialis, common digital extensor, lat. digital extensor, lat. ulnar m., oblique carpal extensor & supinator mm.)	
Supf. br.		sensory - skin - craniolat. forearm in all species, & dors. surface of manus in all except horse
Ulnar	motor - to some flexor mm. of forearm & mm. of manus	
Caud. cutaneous antebrachial		sensory - caud. surface of forearm
Dorsal br.		sensory - lat. side of forefoot
Palmar br.		sensory - with median n., palm. side of forefoot
Median	motor - to most of flexors of forearm	
Medial palmar		
Lateral palmar		



# NERVES - OX - THORACIC LIMB

Thoracic limb-486

Fig. X-53 - Ox - Rt. thoracic limb  
(schematic) - med. view





Fig. X-54 - Ox - Rt. metacarpus  
& digits (schematic)  
- dors. view




Fig. X-55 - Ox - Rt. metacarpus  
& digits (schematic)  
- palm. view

1. Suprascapular n.
2. Radial n.
3. Ulnar n.
4. Median n.
5. Long thoracic n.
6. Thoracodorsal n.
7. Digital nn. (X-55)

- a. Subscapularis n. (X-53)
- b. Pectoral n.
- c. Lat. thoracic n.
- d. Loop of musculocutaneous n. before joining median n.
- e. Med. cutan. antebrachial n. (musculocutaneous n.)

- f. Radial n., Supf. br.
- g. Radial n., Deep br.
- h. Caud. cutan. antebrachial n. (ulnar n.)
- i. Ulnar n., dors. br. (X-54)
- j. Ulnar n., palm. br. (X-55)
- k. Ulnar n., deep br.
- l. Communicating br.

- m. Palm. common digital nn.
- n. Palm. abaxial digital nn.
- o. Palm. axial digital nn.
- p. Dors. common digital nn. (X-55)
- q. Dors. abaxial digital nn.
- r. Dors. axial digital nn.






Fig. X-56 - Dog - Rt. shoulder & arm - med. view






Fig. X-57 - Dog - Rt. forearm  
- med. view





Fig. X-58 - Dog - Rt. forearm  
- lat. view



# NERVES - HORSE - THORACIC LIMB

Thoracic limb-491

Fig. X-59 - Horse - Rt. shoulder & arm  
- med. view



A. Axillary a.  
B. Brachial a.  
C. Median a. & v.  
D. Median cubital v.  
E. Cephalic v.  
F. Med. a. & v.  
G. Digital a. & v.

a. Med. cutan. antebrachial n.  
(musculocutaneous n.)  
b. Caud. cutan. antebrachial n.  
(ulnar n.) (X-60)  
c. Lat. cutan. antebrachial n.  
(radial n.) (X-61)  
d. Radial n., deep br.  
e. Ulnar n., dors. br.  
f. Communicating br.  
g. Med. palmar n. (X-60)

h. Med. palmar digital n.  
i. Lat. palmar n. (X-61)  
j. Lat. palmar digital n.  
k. Subscapular a. (X-59)  
l. Collateral ulnar a. & v.  
m. Accessory cephalic v. (X-60)  
n. Radial a. & v.  
o. Med. palmar a. & v.  
p. Med. digital a. & v.  
q. Deep pectoral m. (X-59)

r. Coracobrachialis m.  
s. Biceps brachii m.  
t. Extensor carpi radialis m.  
u. Flexor carpi radialis m.  
v. Flexor carpi ulnaris m.  
w. Triceps brachii m.  
x. Tensor fasciae antebrachii m.  
y. Latissimus dorsi m.  
z. Teres major m.






Fig. X-60 - Horse - Rt. forearm  
- med. view




Fig. X-61 - Horse - Rt. forearm  
- lat. view



Fig. X-62 - Ox - Rt. shoulder & arm  
- lat. view





Fig. X-63 - Ox - Rt. shoulder & arm  
- med. view








Fig. X-64 - Ox - Rt. forearm  
- med. view




Fig. X-65 - Ox - Rt. forearm  
- lat. view

1. Radial n. (X-62)
2. Subscapular n. (X-63)
3. Suprascapular n.
4. Thoracodorsal n.
5. Axillary n.
6. Median n.
7. Ulnar n.
8. Musculocutaneous n.
9. Digital nn. (X-64)

- A. Cephalic v. (X-62)
- B. Median cubital v.
- C. Axillary a. & v. (X-63)
- D. Brachial a. & v.
- E. Median a. & v. (X-64)
- F. Subscapular a. & v. (X-63)
- G. Thoracodorsal a. & v.
- H. Collateral ulnar a. & v.
- I. Radial a. & v. (X-64)
- J. Accessory cephalic v.

- a. Cran. cutan. antebrachial n. (axillary n.) (X-62)
- b. Radial n., supf. br.
- c. Med. cutan. antebrachial n. (musculocutaneous n.) (X-63)
- d. Caud. cutan. antebrachial n. (ulnar n.) (X-64)
- e. Supf. br. of palmar br. (ulnar n.) (X-65)
- f. Palm. common digital nn. (lat. & med.) (X-64)
- g. Palm. abaxial digital nn.
- h. Palm. axial digital nn.
- i. Dors. common digital nn. (X-65)

- j. Deltoid m. (X-62)
- k. Brachiocephalicus m.
- l. Brachialis m.
- m. Triceps brachii m.
- n. Extensor carpi radialis m.
- o. Supraspinatus m.
- p. Subscapularis m. (X-63)
- q. Teres major m.
- r. Coracobrachialis m.
- s. Biceps brachii m.
- t. Lacertus fibrosus (X-64)
- u. Flexor carpi radialis m.
- v. Flexor carpi ulnaris m.






Fig. X-66 - Horse - Rt. forefoot - med. view

**NERVE SUPPLY TO THE MANUS:** differs between the species due to the difference in the number of digits. In the carnivores and pig, there is little clinical significance to the nervous distribution to the digits.

## HORSE - innervation to the forefoot:

**Median nerve:** divides just proximal to the carpus into lateral and medial branches.

**Ulnar nerve:** bifurcates into dorsal and palmar nerves above the carpus.

**Medial and lateral palmar nerves:** descend on either side of the digital flexor tendons to become the medial and lateral digital nerves.

- **Medial palmar nerve (c):** is the direct continuation of the median nerve.

- **Lateral palmar nerve (h):** is formed by the lateral branch of the median and the palmar branch of the ulnar nerve.

**3. Medial and lateral digital nerves (e,i):** the direct continuation of the medial and lateral palmar nerves past the level of






Fig. X-67 - Horse - Forefoot

the fetlock. They continue distally with the similarly-named arteries abaxial to the sesamoid bones and penetrate the hoof to innervate the heel region of the foot.

**Dorsal branches of the digital nerves (o):** arise near the fetlock and cross the abaxial surface of the proximal palmar sesamoid bones with the digital nerves. They then extend dorsally and distally to innervate the toe of the foot.

**Dorsal branch of the ulnar nerve (f):** continues down the lateral side of the limb to the fetlock.

**Deep branch of the lateral palmar nerve or deep branch of the ulnar nerve:** arises at the level of the carpus. It dives deep to the suspensory ligament and branches into lateral and medial metacarpal nerves.

**Lateral and medial metacarpal nerves (b,g):** travel along the metacarpal bone and emerge under the buttons of the splints to reach the fetlock.

#### CLINICAL

Nerve blocks: see the appendix






Fig. X-68 - Ox - Rt. forefoot - dorsomed. view

## OX - innervation to the forefoot:

1. Median nerve: supplies most of the palmar aspect of the foot. It divides above the fetlock into four palmar digital branches that descend on the four sides of the two digits.

2. Ulnar nerve: has palmar and dorsal branches. The palmar branch is joined by the most lateral of the median palmar digital nerves. It descends the abaxial surface of the lateral digit

(abaxial digital nerve IV). The dorsal branch (k) supplies the dorsal abaxial surface of the lateral digit.

3. Superficial branch of radial nerve: supplies most of the dorsum of the foot as common digital, and axial and abaxial dorsal digital nerves.






Fig. X-69 - Ox - Rt. forefoot  
- caud. view




Fig. X-70 - Ox - Rt. forefoot  
- lat. view

### CLINICAL:

#### Nerve blocks of the thoracic limb - ox:

- I. Superficial radial nerve: palpate the nerve at the mid-metacarpus and inject anesthetic medial to the common digital extensor tendon.
- II. Median nerve: inject between the interosseous muscle and the tendon of the deep digital flexor tendon.
- III. Palmar branch of ulnar nerve: redirect the needle used for

the dorsal ulnar nerve and inject between the interosseous muscle and deep digital flexor tendon.

- IV. Dorsal ulnar nerve: inject area between the metacarpal bone and the interosseous muscle.

**Ring block:** encircling the metacarpus with an anesthetic agent

**Intravenous technique:** use a tourniquet to raise the large veins (A) of the foot and then inject the anesthetic agent in them to anesthetize the lower limb in a retrograde fashion.






Fig. X-71 - Ox - Thorax  
- cross section

- a. Spinal cord
- b. Dorsal root
- c. Dorsal root ganglion
- d. Mixed ramus communicans
- e. Lumbar sympathetic trunk
- f. Med. br. of dors. br.
- g. Lat. br. of dors. br.
- h. Lat. br. of ventr. br.
- i. Med. br. of ventr. br.
- j. Costovertebral n. (T13) (X-72)
- k. Iliohypogastric n. (L1)
- l. Ilioinguinal n. (L2)
- m. Epaxial mm. (X-71)
- n. Hypaxial mm.
- o. Cutan. trunk mm.
- p. Ext. abdominal oblique m.
- q. Int. abdominal oblique m.
- r. Transversus abdominis m.
- s. Rectus abdominis m.
- t. Transverse fascia
- u. Parietal peritoneum
- v. 13th thoracic vertebra

**LUMBOSACRAL PLEXUS:** the ventral branches of the lumbar and sacral nerves. The first three or four lumbar ventral branches and the last thoracic branch supply the abdominal wall. The lumbosacral plexus to the pelvic limb is formed by the ventral branches of  $L_4$  to  $S_2$ . Nerves to the pelvic cavity and the genitalia arise from the ventral branches of the sacral nerves (pudendal, caudal rectal, perineal and dorsal nerve to the penis).

**Abdominal nerves:** The first three or four ventral lumbar branches are distributed to the abdominal wall (iliohypogastric, ilioinguinal, genitofemoral, and lateral cutaneous femoral nerves) along with the last thoracic (costovertebral) nerve. These are important in flank surgery in the ox and horse. These branches travel in a caudoventral direction. They pierce the transversus abdominis muscle at the transverse processes and travel caudoventrally between it and the internal abdominal oblique. They supply the

abdominal muscles and send lateral and ventral cutaneous branches to the skin.

**Costovertebral nerve (T13) (j):** not a part of the lumbosacral plexus, but, along with the first couple of lumbar nerves, innervates the abdominal wall.

**Iliohypogastric nerve ( $L_1$  or  $L1 \& 2$ ) (k):** in animals with six lumbar vertebrae (ox and horse), it is formed by the ventral branches of  $L_1$ . In animals with seven lumbar vertebrae (carnivores) there are cranial ( $L_1$ ) and caudal ( $L_2$ ) iliohypogastric nerves.

**Ilioinguinal nerve ( $L_2$  or  $L_3$ ) (l):** in animals with six lumbar vertebrae, formed by  $L_2$ ; with seven lumbar vertebrae,  $L_3$ .



Fig. X-72 - Ox - lat. view




Fig. X-73 - Ox - Lumbar vertebrae - dors. view




Fig. X-74 - Ox - Flank - lat. view





Fig. X-75 - Ox - 1st lumbar vertebra - cross section

1. Inverted "L" block
2. Paravertebral block
3. Magda block

**Genitofemoral nerve (L3 & 4):** divides into a genital branch supplying the external genital organs and the inguinal region (cranial part of the udder in the cow) and a femoral branch supplying the skin over the medial thigh.

## CLINICAL - (see Appendix for more)

**Standing flank surgery in the ox:** opening the paralumbar fossa to deal with such problems as "hardware disease", dystocia, displaced abomasum, etc. The first three or four ventral lumbar nerves and the last thoracic nerve are anesthetized in flank surgery of the ox and horse.

**Local anesthesia for a flank surgery:** concerned with  $T_{13}$ ,  $L_1$  and  $L_2$  nerves and can be done in a number of ways:

1. **Inverted "L" block:** injections are done in the abdominal wall, from the subcutaneous area to the peritoneum, in the pattern shown.
2. **Paravertebral block:** blocks all branches of the spinal nerves.
3. **Distal paralumbar analgesia or Magda block:** blocks only the ventral and lateral dorsal branches of the spinal nerves.



**NERVE SUPPLY to the PELVIC LIMB:** consists of the ventral branches of the fourth lumbar nerve to the second sacral nerve ( $L_4 - S_2$ ) of the lumbosacral plexus (caudal cutaneous femoral, femoral, cranial gluteal, caudal gluteal, caudal clunial, obturator, ischiatic, tibial, common (fibular) peroneal, and pudendal).

1. **Femoral nerve ( $L_4$ ):** innervation of the extensor muscles of the stifle (quadriceps femoris). It passes through the psoas muscles, out of the abdominal cavity and through the femoral canal to the quadriceps femoris muscle.

2. **Saphenous nerve:** the superficial branch of the femoral nerve, supplying cutaneous innervation to the medial side of the limb and motor innervation to the sartorius muscle.

3. **Obturator nerve ( $L_4$ ):** innervates most of the medial adductor muscles of the thigh. It extends from the lumbosacral plexus through the pelvic cavity on the body of the ilium and obturator foramen to the medial side of the thigh.

**Lumbosacral trunk: ( $L_5-S_1$ ):** leaves the pelvis over the greater ischiatic notch to continue as the ischiatic nerve. It gives three branches - cranial gluteal, caudal gluteal and caudal cutaneous femoral nerves.

7. **Cranial gluteal nerve:** supplies flexors and extensors of the hip (tensor fasciae latae, middle and deep gluteal muscles [also the superficial gluteal in some species]).

8. **Caudal gluteal nerve:** supplies the superficial gluteal muscles and the proximal part of the hamstring muscles, thus, the extensors of the hip.

**Caudal cutaneous femoral nerve:** supplies cutaneous innervation over the caudal aspect of the thigh.

4. **Ischiatic (sciatic) nerve ( $L_4-S_2$ ):** the largest nerve of the lumbosacral plexus, supplying the caudal thigh muscles and, by its terminal branches (tibial and common fibular [peroneal]), the muscles of the crus and pes. It continues the lumbosacral trunk caudal to the hip joint, to run distally caudal to the femur and deep to the biceps femoris muscle. It supplies the hamstring muscles and the pelvic association (internal obturator [except in ruminants and pigs], gemelli and quadratus femoris). It branches mid-thigh into tibial and common (fibular) peroneal nerves.

5. **Tibial nerve:** one of the two terminal branches of the ischiatic nerve. It runs between the two heads of the gastrocnemius muscle to reach and supply the caudal muscles of the crus. It splits at the level of the point of the hock into medial and lateral plantar nerves. The plantar nerves continue down the plantar aspect of the pes mainly supplying sensation.

**Caudal cutaneous sural nerve:** cutaneous branch of the tibial nerve arising above the stifle.

6. **Common peroneal (fibular\*) nerve:** the other terminal branch of the ischiatic nerve, coursing around the lateral side of the crus

(over fibula). It supplies the craniolateral muscles of the crus (deep peroneal branch) and the skin of the craniolateral crus and dorsal foot (superficial peroneal branch).

**Deep peroneal (fibular\*) nerve (n. peroneus profundus):** supplies motor innervation to the craniolateral muscles of the leg. It travels with the cranial tibial artery between the extensor muscles and the tibia.

**Superficial peroneal (fibular) nerve:** mainly a sensory nerve. It divides on the dorsal surface of the pes into the dorsal common digital nerves.

## CLINICAL

**Femoral nerve deficiency:** inability to extend the stifle results in the inability to bear weight on limb. There may also be a loss of sensation on the medial side of the limb (saphenous nerve).

**Obturator nerve paralysis:** can be caused by injury to the intrapelvic part of the nerve during parturition (birth). This results in inability to adduct the limb and is most noticeable on slippery floors where the limbs slip sideways. This is common in foaling and calving.

**"Downer cow":** a postpartum cow that cannot rise to stand. This syndrome, having many etiologies, can be caused by injury to the pelvic part of the obturator nerve due to trauma during parturition. The animal cannot adduct its limb to stand, but may recover.


**Tibial nerve damage:** affects the extensors of the tarsus and flexors of the digits. The tarsus drops and the animal cannot actively flex the digits.

**Common fibular\* (peroneal) nerve damage:** affects the digital extensors similar to low radial nerve paralysis in the front limb. This can result in "knuckling over".

\* Fibular nerve may be used instead of peroneal to avoid confusion with the perineal branches of the pudendal nerve of the pelvis. It also helps distinguish it from the tibia because it passes over the fibula (lateral side of limb. This option is allowed by the N. A. V.



Fig. X-76 - Horse - Lt. pelvic limb (schematic)  
- med. view



5. Tibial n.

6. fibular n.




Fig. X-78 - Horse - Lt. pes  
- plant. view




Fig. X-77 - Horse - Lt. pes  
- dors. view

- a. Caud. cutan. femoral n.
- b. Lat. cutan. femoral n.
- c. Caud. cutan. sural n.  
(tibial n.)
- d. Supf. fibular n.
- e. Deep fibular n.
- f. Lat. dors. metatarsal n.  
(br. of deep fibular n.)(X-77)
- g. Lat. plant. metatarsal n.  
(br. of deep fibular n.)

- h. Lat. plantar n. (X-78)  
(tibial n.)(X-76)
- i. Med. plantar n.  
(tibial n.)
- j. Communicating br.
- k. Lat. plant. digital n.
- l. Med. plant. digital n.
- m. Dors. brs.
- n. Deep br. of lat. plantar n.
- o. Plantar metatarsal nn.






Fig. X-79 - Dog - Lt. pelvic limb (schematic) - lat. view

## DOG - NERVES of the LEG and PES:


**Superficial peroneal (fibular) nerve:** supplies motor innervation to the peroneus brevis and lateral digital extensor, and then continues as a sensory nerve. It divides on the dorsal surface of the paw into the dorsal common digital nerves.

- Dorsal common digital nerves II, III, and IV: extend distally between the metatarsal bones to be joined by the dorsal metatarsal nerves.

**Deep fibular (peroneal) nerve:** supplies motor innervation to the craniolateral muscles of the leg. It passes between the muscles to reach the tibia and travel distally with the cranial tibial artery. At the tarsus it divides into medial and lateral branches that continue as the dorsal metatarsal nerves II, III, and IV.

- Dorsal proper digital nerves II, III and IV: formed by the joining of the dorsal common digital nerves and the dorsal metatarsal digital nerves at the level of the metatarsophalangeal joints. These branch into axial and abaxial digital nerves.





a. Caud. cutan. femoral n.  
b. Lat. cutan. femoral n.  
c. Lat. cutan. sural n.  
d. Caud. cutan. sural n.

e. Supf. fibular n.  
f. Deep fibular n.  
g. Dors. common digital nn. (X-80)  
h. Dors. metatarsal nn.

i. Med. plantar n. (tibial n.) (X-81)  
j. Lat. plantar n. (tibial n.)  
k. Plantar digital nn.  
l. Plantar metatarsal nn.

• Axial and abaxial proper digital nerves II, III, and IV: terminal branches of the dorsal proper digital nerves to the corresponding sides of the digits.

Axis: passes between the third and fourth digits.

Tibial nerve: supplies all the muscles of the caudal leg and sensory to the plantar aspect of the pes. Just proximal to the talocrural joint the tibial nerve divides into medial and lateral plantar nerves.

• Medial plantar nerve: the smaller branch of the tibial nerve that branches to form the plantar common digital nerves II, III and IV.

• Lateral plantar nerve: larger and deeper than the medial plantar nerve. It divides into plantar metatarsal nerves I, II, III and IV which join the plantar common digital nerves.

• Axial and abaxial proper digital nerves: arise from the joined common and metatarsal digital nerves and extend on the plantar sides of the digits.





# NERVES - PELVIC LIMB

Pelvic limb-505

NERVES	MOTOR	SENSORY
Lateral cutaneous femoral	motor - psoas major m.	sensory - skin of craniomed. thigh & cran. stifle
Femoral (L4-6)	motor - extensors of stifle (quadriceps femoris) & iliopsoas mm.	
Saphenous	motor - sartorius m.	sensory - med. aspect of limb from stifle to metatarsus
Obturator (L4-6)	motor - to adductors of thigh (ext. obturator, pectineus, adductor & gracilis mm.) (int. obturator m. in pig & ruminants)	
Cranial gluteal	motor - extensors & flexors of hip (supf., middle & deep gluteal mm., & tensor fascia lata m.) (some species - supf. gluteal m.)	
Caudal gluteal	motor - extensors of hip (supf. gluteal, biceps femoris & semitendinosus mm.)	
Caudal cutaneous femoral		sensory - caud. aspect of thigh
Caudal clunial nn.		sensory - skin of caudomed. & caudolat. face of thigh
Ischiatic	motor - deep gluteal, int. obturator, gemelli mm.	
Common fibular (peroneal)	motor - biceps femoris m.	
Lateral cutaneous sural		sensory - skin on lat. aspect of leg
Superficial fibular	motor - lat. digital extensor m.	sensory - skin on dors. aspect of crus & pes (horse just to fetlock)
Deep fibular	motor - dorsolat. flexors of hock & extensors of digits (cranial tibial, third fibular, long digital extensor, lat. digital extensor & short digital extensor mm.)	sensory - structures of foot
Tibial	motor - hamstring mm. (biceps femoris, semitendinosus & semimembranosus) to extensors of hock & flexors of digits (gastrocnemius, popliteal, supf. digital flexor & deep digital flexor mm.)	
Caudal cutaneous sural		sensory - to skin of caud. aspect of leg (crus).
Medial plantar		sensory - skin on medioplant. face of metatarsus
Digital nn.		sensory - med. digits or med. side of horse's digit
Lateral plantar	motor - interosseus m.	sensory - skin of lateroplant. surface of metatarsus
Digital nn.		sensory - lat. digits (horse, lat. side of digit)
Caudal rectal	motor - coccygeus, levator ani, ext. anal sphincter mm.	sensory - ischioanal fossa (not carnivores)
Cranial clunial		sensory - skin of craniolat. hip & lat. thigh.
Middle clunial		sensory - skin of dorsolat. hip & thigh.




**Fig. X-82 - Ox - lt. pes (schematic)  
- dors. view**



**Fig. X-83 - Ox - Lt. pes (schematic)  
(schematic) - plant. view**

**Fig. X-84 - Ox - Lt. pelvic limb (schematic)  
- med. view**



1. Femoral n. (X-84)
2. Saphenous n.
3. Obturator n.
4. Ischiatic n.
5. Tibial n.
6. Common fibular n.
7. Cran. gluteal n.
8. Caud. gluteal n.

- a. Cran. clunial nn. (X-84)
- b. Middle clunial nn.
- c. Lat. cutan. femoral n.
- d. Caud. cutan. femoral n.
- e. Caud. clunial nn.
- f. Muscular br.
- g. Caud. cutan. sural n. (tibial n.)

- h. Supf. fibular n.
- i. Deep fibular n.
- j. Dors. common digital n. (X-83)
- k. Dors. abaxial digital n.
- l. Dors. axial digital n.
- m. Communicating br. to deep fibular n.
- n. Dors. metatarsal n. III

- o. Communicating br. to plant. axial digital nn.
- p. Med. plant. (tibial) n. (X-82)
- q. Lat. plant. (tibial) n.
- r. Plantar common digital nn.
- s. Plantar abaxial digital nn.
- t. Plantar axial digital nn.







Fig. X-85 - Dog - Rt. hip & thigh  
- med. view

A. Aorta  
B. Caud. vena cava  
C. Ext. iliac a.  
D. Femoral a. & v.  
E. Int. iliac a.  
F. Int. pudendal a.  
G. Urogenital a.  
H. Pudendoepigastric trunk  
I. Saphenous a.  
J. Med. saphenous v.  
K. Caud. femoral a. & v. (X-87)  
L. Lat. saphenous v.  
M. Median sacral a. (X-85)  
N. Deep femoral a. & v.

a. Caud. cutan. sural n.  
(tibial n.) (X-87)  
b. Lat. cutan. sural n.  
(ischiatric n.)  
c. Deep fibular n.  
d. Supf. fibular n.  
e. Lat. plantar n. (X-86)  
f. Med. plantar n.  
g. Plant. common  
digital nn. (X-87)  
h. Dors. common digital n.  
i. Sartorius m. (X-85)  
j. Vastus medialis m.

k. Pectineus m.  
l. Adductor m.  
m. Gracilis m.  
n. Semitendinosus m.  
o. Gastrocnemius m.  
p. Deep digital flexor m. (X-86)  
q. Long fibular m. (X-87)  
r. Long digital extensor m. (X-85)  
s. Levator ani m.  
t. Coccygeus m.  
u. Sacrum










Fig. X-88 - Horse - Hip, deep layer  
- lat. view






FIG. X-89 - Horse - Lt. pelvic limb  
- lat. view






Fig. X-90 - Horse - Rt. pelvis  
& thigh - med. view






Fig. X-91 - Horse - Lt. leg  
- lat. view






Fig. X-92 - Ox - Lt. hip - lat. view



Fig. X-90 - Ox - Lt. leg  
- lat. view




Fig. X-93 - Ox - Lt. leg  
- lat. view

1. Sciatic n.
2. Cran. gluteal n.
3. Caud gluteal n.
4. Tibial n.
5. Common fibular n.
6. Digital nn. (X-93)

- A. Cran. gluteal a. & v.
- B. Caud. gluteal a. & v.
- C. Med. circumflex a. & v. (X-93)
- D. Caud. femoral a. & v. (X-92)
- E. Lat. saphenous v.
- F. Lat. plantar a. (X-93)
- G. Dors. pedal v.  
(continuation of E.)

- a. Caud. clunial n.
- b. Caud. cutan. femoral n.
- c. Muscular brs.
- d. Caud. cutan. sural n.
- e. Lat. cutan. sural n.  
(common fibular n.) (X-93)
- f. Supf. fibular n.
- g. Dors. common digital n.
- h. Dors. axial digital n.
- i. Dors. abaxial digital n.
- j. Lat. plantar (tibial) n.
- k. Plant. common digital nn.
- l. Plant. abaxial digital nn.
- m. Greater trochanter of humerus (X-92)
- n. Third fibular m. (X-93)
- o. Long fibular m.
- p. Lat. digital extensor m.
- q. Ischiatic ln. (X-92)
- r. Popliteal ln.
- s. Broad sacrotuberous lig.
- t. Greater ischiatic foramen
- u. Lesser ischiatic foramen






Fig. X-94 - Ox - Rt. thigh  
- med. view

1. Sciatic n.
2. Obturator n.
3. Femoral n.
4. Saphenous n.
5. Common fibular n. (X-95)
6. Tibial n.
7. Digital nn.

- A. Aorta
- B. Caud. vena cava
- C. Ext. iliac a.
- D. Pudendoepigastric trunk
- E. Femoral a. & v.
- F. Med. saphenous v.
- G. Saphenous a.
- H. Median sacral a.
- I. Int. iliac a.
- J. Genital a.
- K. Int. pudendal a.
- L. Med. plant. a.  
(supf. br.) (X-95)
- M. Dors. pedal a. (X-96)
- N. Digital a. (X-95)

- a. Prox. cutan. br.  
of pudendal n.
- b. Dist. cutan. br.  
of pudendal n.
- c. Deep perineal n.
- d. Supf. perineal n.
- e. Caud. rectal n.
- f. Lat. cutan. femoral n.
- g. Genitofemoral n.
- h. Med. plantar (tibial) n. (X-95)
- i. Lat. plantar (tibial) n.
- j. Plant. common digital nn.
- k. Plant. abaxial digital nn.
- l. Dors. common digital n.
- m. Dors. axial digital n.

- n. Deep fibular n.
- o. Supf. fibular n.
- p. Rectus femoris m.
- q. Vastus medialis m.
- r. Gastrocnemius m.
- s. Third fibular m.
- t. Long digital extensor m.



Fig. X-95 - Ox - Lt. leg  
- med. view





Fig. X-96 - Ox - Lt. leg  
- craniolat. view






Fig. X-97 - Horse - Rt. hindfoot - med. view

**NERVE SUPPLY TO THE PES:** proximal to the tarsus, the tibial nerve divides into lateral and medial plantar nerves. These nerves descend the pes on either side of the flexor tendons. In the horse, they continue on either side of the digit as the medial and lateral digital nerves. In the domestic species with more than one digit, the lateral and medial plantar nerves divide into digital nerves to supply the plantar sides of each digit. This distribution is similar to the medial and palmar branches of the median nerve of the forelimb. The superficial fibular and saphenous nerve also supply parts of the pes.

**HORSE:** has similar nerves in similar places of the forelimb. The plantar and metatarsal nerves correspond to the palmar and metacarpal nerves. The deep branch of the lateral plantar

corresponds to the deep branch of the lateral palmar (deep branch of the ulnar). The plantar digital nerves correspond to the palmar digital nerves and their dorsal branches. The caudal cutaneous sural and the saphenous nerve correspond to the median cutaneous antebrachial and dorsal branch of ulnar nerves respectively.

Medial and lateral dorsal metatarsal nerves, branches of the deep peroneal nerve have no counterpart in the thoracic limb. They pass between the dorsal surfaces of the splint bones and cannon bone to the fetlock and hoof. The superficial peroneal may send branches down to the fetlock. (For nerve blocks see Appendix, pg. 584-591)






Fig. X-98 - Horse - Rt. hindfoot - lat. view

A. Dors. common digital v. II  
(med. saphenous v.)  
B. Med. plantar a.  
C. Med. plant. digital a. & v.  
D. Coronary venous plexus  
E. Dors. metatarsal a. (X-98)  
F. Lat. plantar v.  
G. Med. plant. digital a. & v.

a. Med. dors. metatarsal n.  
(deep fibular n.) (X-97)  
b. Med. plantar n. (tibial n.)  
c. Med. plant. metatarsal n.  
(deep br. of lat. plantar  
n., tibial n.)  
d. Med. plantar digital n.  
e. Dorsal br.

f. Supf. peroneal n. (X-98)  
g. Lat. dors. metatarsal  
(deep fibular) n.  
h. Lat. plant. metatarsal n.  
(deep br. of lat. plant.  
n., tibial n.)  
i. Lat. plantar n. (tibial n.)  
j. Lat. plant. digital n.

k. Communicating  
branch  
l. Supf. digital  
flexor m.  
m. Suspensory lig.  
n. Lig. of ergot






Fig. X-99 - Ox - Lt. hindfoot  
- dorsolat. view

## NERVE BLOCKS - OX

I. Superficial peroneal nerve: inject on either side of the dorsal branch of the lateral saphenous vein at mid-metatarsus. The deep peroneal is blocked: through the same site by going deep to the extensor tendons.

II, III. Medial and lateral plantar nerves: inject next to the flexor tendons on both sides.

A. Lat. saphenous v. (cran. br.) (dors. pedal v.)  
B. Lat. plantar a. (supf. br.)  
C. Med. plantar a. (supf. br.) (X-100)  
D. Plant. common digital a.  
E. Plant. abaxial digital a.  
F. Plant. axial digital a.

a. Dors. common digital nn. (X-99)  
b. Dors. axial digital nn.  
c. Dors. abaxial digital nn.  
d. Lat. plantar n.  
e. Plant. common digital nn.  
f. Plant. abaxial digital nn.  
g. Plant. axial digital nn. (X-100)

h. Med. plantar n. (X-100)  
i. Tendon of long digital extensor m. (X-101)  
j. Interosseous m. (X-99)  
k. Suspensory br. of j.  
l. Tendon of supf. digital flexor m.

m. Tendon of deep digital flexor m.  
n. Accessory digit  
o. Distal phalanx

I-IV - Digital nerve blocks



Fig. X-100 - Ox - Lt. hindfoot  
- plant. view




Fig. X-101 - Ox - Lt. hindfoot  
- med. view






Fig. X-102 - Cow - Pelvis  
- lat. view




Fig. X-103 - Horse - Sacral plexus - lat. view

**1. PUDENDAL NERVE:** supplies the internal and external genitalia, rectum and perineal area. Arising from the ventral branches of the sacral nerves, it travels obliquely through the pelvic cavity. Its main branches are the superficial and deep perineal nerves and the dorsal nerve of the penis.

**2. PELVIC NERVES:** the parasympathetic (ANS) nerve supply to the pelvic area.

**3. CAUDAL RECTAL NERVES:** nerve supply to the anus.

#### CLINICAL

**Pudendal nerve block:** will block the anal and perineal region and in bulls will cause protrusion of the penis. Palpate the nerves rectally on the medial aspect of the broad sacrotuberous ligament. The nerve leaves the palpable lesser ischiatic foramen just dorsal to the palpable internal iliac artery. Insert a 5" needle medial to the sacrotuberous ligament and inject anesthetic. Continue to inject as you pull the needle out to anesthetize the caudal rectal nerves.

**Caudal rectal nerves:** can be damaged during anal sac removal resulting in paresis or paralysis of the external anal sphincter muscle.



Fig. X-105 - Ox - Needle placement (schematic) - dors. view





Fig. X-104 - Ox - Needle placement (schematic) - lat. view




Fig. X-106 - Ox - Needle placement (schematic) - med. view

1. Pudendal n. (S2-4)
2. Pelvic n.
3. Prox. cutan. br. of 1 (cut)
4. Dist. cutan. br. of 1 (cut)
5. Deep perineal n.
6. Supf. perineal n.
7. Dors. n. of penis
8. Scrotal br.
9. Caud. rectal n. (d1-5)
10. Aorta
11. Ext. iliac a. (cut)
12. Int. iliac a.
13. Int. pudendal a. (on med. aspect of broad sacrotuberal lig.)

- A. Needle in deepest part of ischiorectal fossa  
B. Gloved hand in rectum

The int. pudendal a. is palpated rectally an inch in front of the cran. dors. end of the lesser ischiatic foramen. The pudendal n. is dors. to this point.

- a. Broad sacrotuberal lig.
- b. Lesser ischiatic foramen
- c. Rectum (opened dorsally)
- d. Penis
- e. Sacrum
- f. First caud. vertebra
- g. ischium
- h. Pubic symphysis
- i. Coccygeus m.
- j. Levator ani m.
- k. Intrapelvic part of ext. obturator m.



# AUTONOMIC NERVOUS SYSTEM

451-General-523

**AUTONOMIC (aw'-toh-NOM-ik) NERVOUS SYSTEM (ANS):** that portion of the nervous system operating involuntarily or automatically to keep the animal's body stable. Without conscious effort, it regulates smooth muscle, cardiac muscle and glands (visceral structures) in the maintenance of normal internal stability (homeostasis) of the organism, and, when needed, deals with emergency situations. It regulates heart rate, intestinal motility, body temperature and blood pressure, among other visceral activities. The ANS, although said to be involuntary, is still controlled by higher centers in the brain, such as the cerebral cortex, hypothalamus and medulla oblongata. These centers interconnect and connect directly to the two divisions of the ANS.

**TWO DIVISIONS of the ANS:** the ANS is divided into two divisions, the sympathetic and parasympathetic. The visceral structures (smooth muscle, cardiac muscle and glands) usually have a dual innervation (sympathetic and parasympathetic). The action of the two divisions usually have opposite effects, as in the heart where the parasympathetic slows the rate and the sympathetic speeds it up. This allows a finer control of such activities.

**Reflex arcs:** Autonomic functions are mainly controlled by reflex arcs. Sensory (visceral afferent) fibers enter the spinal cord or brain stem via spinal or cranial nerves. These fibers carry sensory impulses from smooth muscle, cardiac muscle and glands (visceral effectors structures), as well as from specialized visceral receptors throughout the body. In the spinal cord or brain stem, they synapse with ANS motor neurons whose fibers (visceral efferent fibers) innervate the visceral structure (smooth or cardiac muscles or glands). In the somatic nervous system (dealing with voluntary skeletal muscles), there is usually only one motor (efferent) neuron; the autonomic nervous system has two. The first is the preganglionic motor neuron whose fiber leaves the spinal cord or brain stem to synapse with a postganglionic efferent neuron in ganglia. The postganglionic motor fiber innervates the visceral structure.

**Ganglion (pl.=ganglia):** collection of nerve cell bodies outside the central nervous system.

1. **Visceral [effector] structures:** the smooth muscle, cardiac muscle, and glands being controlled by the ANS.

2. **ANS sensory (afferent) neurons:** carry stimuli from a visceral effector or other receptor to the spinal cord via the dorsal root of the spinal nerve or to the brainstem via cranial nerves. ANS sensory (afferent) cell bodies are located in the dorsal root ganglia of spinal nerves or ganglia of the cranial nerves, located outside the brain.

**ANS motor (efferent) neurons:** carry motor impulses to a visceral effector by two motor (efferent) neurons. This is different from the somatic system, where reflex arcs have only one motor (efferent) neuron.

3. **Preganglionic (pree'-gang-lee-ON-ik) neuron:** an ANS motor neuron whose fiber extends from the CNS to synapse in an autonomic (motor) ganglion with a postganglionic neuron.

4. **Postganglionic neuron:** also an ANS motor (efferent) neuron whose fiber extends from a ganglion to the visceral structure (visceral effector) innervated.

The motor (efferent) outflow of the sympathetic division comes from the thoracolumbar segments of the spinal cord. Preganglionic motor (efferent) cell bodies are located in the lateral gray column (a) of the spinal cord. The motor fibers leave the spinal cord by the ventral root (D), pass through the spinal nerves and the white communicating branch (E) to reach the ganglia of the sympathetic trunk (G). In the ganglion the fiber has three possible pathways:

I. **Synapse with postganglionic neurons in the sympathetic trunk ganglion.** Postganglionic fibers then return to the spinal nerves by the communicating branch to be distributed to the periphery.

II. **Ascend or descend within the sympathetic trunk to other ganglia where they will have the same three choices.**

III. **Pass through the ganglion to a peripherally located collateral ganglion to synapse on postganglionic neurons (e.g., splanchnic nerves [I])(4).**

Ventral and dorsal branches of the spinal nerves: (not roots) carry visceral and somatic sensory (afferent) fibers.

A. **Spinal nerve:** the nerve carrying both somatic and autonomic sensory and motor fibers between the periphery and the spinal cord. These fibers include visceral sensory (afferent) fibers towards the spinal cord, and visceral motor (efferent) fibers back to effector organs.

B. **Dorsal root:** carries somatic and visceral sensory (afferent) fibers entering the spinal cord.

C. **Dorsal root ganglion:** the location of cell bodies of sensory neurons.

D. **Lateral gray column:** area where the preganglionic nerve cells are located.

E. **Ventral root:** carries somatic and visceral motor fibers leaving the spinal cord.

F-G. **Communicating branches\*:** connect the spinal nerves with the sympathetic trunk.

G. **Sympathetic trunk:** the series of connected ganglia (H) lying

\* There are two types of communicating branches, white and gray, which are indistinct from each other in most domestic animals. Thoracic and cranial lumbar nerves have both white and gray communicating branches. The other spinal nerves only have gray branches. White communicating branches are formed by myelinated preganglionic fibers, connecting thoracic and lumbar spinal nerves with the ganglia of the sympathetic trunk. The myelin of the fibers gives the branch its white color. Gray communicating branches connect the sympathetic trunk to all spinal nerves. They carry unmyelinated (thus, a gray color) postganglionic fibers from the chain ganglion to the spinal nerves to innervate vessels and skin glands.






Fig. X-107 - Sympathetic supply (schematic)

on either side of the vertebral column. It extends from the base of the skull to the sacral region of the vertebral column. The ganglion only receive preganglionic fibers from the sympathetic (thoracolumbar) division of the ANS. Preganglionic fibers that pass through the sympathetic trunk form the splanchnic nerves (I) that pass to collateral ganglia around the unpaired branches of the aorta.



# ANS - SYMPATHETIC DIVISION

General-525

**SYMPATHETIC DIVISION** (thoracolumbar [toh-ra-koh-LUM-bar] division) of the ANS: an energy-expending system that counterbalances the parasympathetic system to maintain homeostasis when the body is at rest. In an emergency, this division overrides the other and spends the body's energy reserves. Its activation dilates the pupils, increases the heart rate, opens the lung's airways, decreases gut motility, dilates the blood vessels in the skeletal muscles, increases glucose in the blood, and erects hair on the back. All these prepare the animal for "fight or flight".

**THORACOLUMBAR OUTFLOW:** The motor (efferent) outflow of the sympathetic division comes from the thoracolumbar segments of the spinal cord.

1. **Sympathetic trunk:** the series of connected ganglia lying on either side of the vertebral column. It extends from the base of the skull to the sacral region of the vertebral column. The ganglia only receive preganglionic fibers from the sympathetic (thoracolumbar) division of the ANS.
2. **Trunk ganglia (GANG-lee-a):** the ganglia located in the thoracolumbar region of the sympathetic trunk. They are connected by preganglionic fibers passing between the ganglia, thus forming the sympathetic trunk. Postganglionic fibers arising from these ganglia innervate the heart, bronchi, lungs and abdominal organs.
3. **Cervicothoracic (stellate) ganglion:** the largest autonomic ganglion in the body. It is located near the vertebral column medial to the first rib. Preganglionic fibers reaching this ganglion can synapse on postganglionic nerves to the heart and neck (blood vessels, sweat glands, etc.) or pass through it. If they pass through, they can synapse in the middle cervical ganglion or continue up the cervical part of the sympathetic trunk to synapse in the cranial cervical ganglion.
4. **Vertebral nerve:** postganglionic fibers arising from the cervicothoracic ganglion. It travels up the neck through the transverse canal and sends fibers (gray communicating branches) to the cervical spinal nerves to supply vessels and skin glands.
5. **Ansa subclavia:** two cord-like structures that connect the cervicothoracic ganglion and the middle cervical ganglion. They pass around the subclavian artery and are made of preganglionic fibers.
6. **Middle cervical ganglion:** a group of sympathetic postganglionic cell bodies located at the thoracic inlet.
7. **Sympathetic trunk (cervical portion):** the preganglionic fibers passing from the middle cervical ganglion up the neck to synapse in the cranial cervical ganglion. These fibers travel with the vagus nerve.
8. **Vagosympathetic trunk:** the combined vagus and sympathetic trunk in the neck. These are fused together. Fibers of the vagus pass down the trunk while sympathetic fibers pass up the trunk. The vagus leaves the sympathetic trunk at the thoracic inlet.
9. **Cranial cervical ganglion:** the terminal end of the sympathetic trunk near the base of the skull. It receives preganglionic fibers from the sympathetic thoracolumbar outflow and transmits postganglionic fibers to the head. These fibers pass through the middle ear.
10. **Splanchnic (SPLANK-nik) nerves:** the preganglionic fibers passing through the sympathetic trunk without synapsing. They leave the sympathetic trunk at the caudal thoracic and the lumbar regions to pass to collateral ganglia. They synapse in these ganglia with postganglionic neurons that innervate the abdominal and pelvic viscera.
11. **Collateral ganglia (prevertebral):** the large ganglia located away from the vertebral column around the unpaired branches of the aorta (celiomesenteric ganglion and caudal mesenteric ganglion). Collateral ganglia receive preganglionic fibers that pass through the sympathetic trunk without synapsing, and send postganglionic fibers to the viscera along vessels arising from the unpaired branches of the aorta.
12. **Hypogastric nerve:** the sympathetic innervation to the pelvic region. Postganglionic fibers extend from the caudal mesenteric collateral ganglion in the mesocolon to the pelvic plexus on the sides of the rectum.

## CLINICAL

**Horner's syndrome:** a group of signs due to loss of sympathetic innervation to the head. The problem can be anywhere from the hypothalamus down the spinal cord to the cranial thoracic limb segments to the orbit (thoracic roots avulsion, abscesses in neck, middle ear infections, orbital abscesses etc.) Signs of Horner's syndrome:

- Retraction of the eyeball (enophthalmos)
- Drooping of the upper eyelid (ptosis)
- Protrusion of the third eyelid
- Constriction of the pupil (miosis)






Fig. X-108 - Ox - Sympathetic division (schematic)

- a. Brain
- b. Otic ganglion
- c. Vertebral n.
- d. Cardiac ganglion
- e. Cran. mesenteric ganglion
- f. Celiac ganglia
- g. Caud. mesenteric ganglion
- h. Intermesenteric plexus



## ANS - PARASYMPATHETIC DIVISION

General-527

**PARASYMPATHETIC DIVISION** (craniosacral division) of the ANS: the energy-conserving system. It is mainly concerned with homeostasis ("day-to-day living"). It slows the heart rate and increases the motility of the GI tract so food can be absorbed and utilized or stored. It also brings the body back to rest after an emergency sympathetic stimulus is over.

**CRANIOSACRAL OUTFLOW:** the parasympathetic division has its outflow through certain cranial and sacral nerves. Thus, it has a "pair a" outflows.

**Terminal (intramural) ganglia:** the ganglia of the parasympathetic division located close to or in the wall of the organ they innervate. They receive long preganglionic fibers from the parasympathetic division of the ANS and send short postganglionic fibers to the effector organs.

**Cranial outflow:** the parasympathetic fibers carried by cranial nerves III, VII, IX and X (oculomotor, facial, glossopharyngeal and vagus). The brain stem contains motor nuclei of the cell bodies of the preganglionic parasympathetic fibers. The fibers leave the brain stem via the above cranial nerves to synapse with postganglionic fibers in terminal ganglia.

**Cranial nerves carrying ANS motor fibers:**

1. **Oculomotor nerve (Cn III):** carries preganglionic fibers to the ciliary ganglion to synapse on postganglionic fibers to the smooth muscles that constrict the pupil and "accommodate" (adjust the shape of) the lens of the eye.

2. **Facial nerve (Cn VII):** carries preganglionic fibers to the pterygopalatine (ter'i-goh-PAL-a-tin) (B) and the submandibular ganglia (C). Postganglionic fibers extend to the lacrimal gland, the glands of the nasal mucosa, palate, pharynx and the mandibular salivary gland.

3. **Glossopharyngeal nerve (Cn IX):** transmits preganglionic fibers to the otic ganglion (E). Postganglionic fibers extend to the parotid salivary gland and zygomatic salivary gland in carnivores.

4. **Vagus nerve (Cn X):** the majority of the cranial parasympathetic outflow. It carries long preganglionic fibers to synapse in the terminal ganglia of the organs of the thorax and abdomen. Short postganglionic fibers extend to the viscera, such as the heart, lungs, liver, stomach, pancreas, small intestine, kidneys and part of the colon.

**The sacral parasympathetic outflow:** has its motor cell bodies in the sacral spinal cord. The fibers leave the spinal canal by the ventral roots to unite as the pelvic nerve. The pelvic nerve branches into the pelvic plexus which contains terminal ganglia. From the ganglia, postganglionic neurons pass to the organs of the pelvic cavity.

5. **Pelvic nerves:** formed by parasympathetic preganglionic fibers from the sacral spinal cord. They branch into the pelvic plexus on

either side of the rectum. The pelvic plexus also receives the hypogastric (sympathetic) nerves. Postganglionic sympathetic and parasympathetic fibers extend to the terminal colon, rectum, ureters, urinary bladder and reproductive organs.

Acetylcholine (a-see-til-KOHL-leen) is the neurotransmitter of the parasympathetic division's nerve fibers. These cholinergic (koh'-lin-ER-jik) fibers result in more specific action than those of the sympathetic division, because their preganglionic fibers synapse on fewer ganglionic fibers, postganglionic parasympathetic fibers are less widespread in their distribution to effector organs, and acetylcholine is deactivated quickly.

The sympathetic division's preganglionic fibers also use acetylcholine, but the postganglionic fibers secrete norepinephrine (nor'-ep-ee-NEF-rin) (noradrenalin) and are called adrenergic (ad'-ren-ER-jik) fibers. The effects of the sympathetic division are more widespread and longer lasting because: a. its preganglionic fibers synapse on many postganglionic fibers; b. postganglionic fibers have widespread distribution to effector organs; c. norepinephrine is degraded slowly; and d. norepinephrine enters the blood. These effects help the parasympathetic division go about its day-to-day specific chores, while the sympathetic division, when called upon, can charge the entire body for "fight or flight".

### Clinical

**Oculomotor dysfunction:** will affect the pupils of the eye (see Appendix - pg. 574)

**Facial nerve paralysis:** due to ear infections can paralyze the lacrimal gland and the orbicularis oculi muscles causing the eye to dry severely.

**Vagal dysfunction:** is usually not a clinical problem except in the ruminant where it can cause vagal indigestion and bloat.



Fig. X-109 - Parasympathetic supply  
- head (schematic)





Fig. X-110 - Parasympathetic division (schematic)

- |                             |                                    |                              |               |
|-----------------------------|------------------------------------|------------------------------|---------------|
| A-F. Terminal ganglia       | a. Brain                           | h. Celiac plexus             | q. Liver      |
| A. Ciliary ganglion         | b. Brainstem                       | i. Ventr. vagal trunk        | r. Omasum     |
| B. Pterygopalatine ganglion | c. Ventr. root of sacral spinal n. | j. Eye                       | s. Abomasum   |
| C. Mandibular ganglion      | d. Parasympathetic nuclei          | k. Lacrimal gland            | t. Intestines |
| D. Sublingual ganglion      | e. Vagal cardiac n.                | l. Mandibular salivary gland | u. Kidney     |
| E. Otic ganglion            | f. Dors. vagal trunk               | m. Sublingual salivary gland | v. Rectum     |
| F. Terminal ganglion        | g. Br. to celiac plexus            | n. Parotid salivary gland    | w. Uterus     |
|                             |                                    | o. Larynx                    | x. Ovary      |
|                             |                                    | p. Heart                     |               |








## Chapter XI

# Common Integument

## Eye - Ear





# COMMON INTEGUMENT

527-General-531

**COMMON INTEGUMENT** (in'TEG-yoo-ment): consists of the skin, hair, skin glands (including the mammary glands), claws, hooves, and horns.

**Skin or cutis:** the thin organ covering the body, protecting underlying tissues from injury, drying, and bacterial invasion. It helps regulate body temperature, excretes water and salts through sweat glands, senses the environment and synthesizes vitamin D3.

**STRUCTURE of the SKIN:** consists of two layers - a superficial epithelium (ep'i-THEE-lee-um) (epidermis) upon a deeper, fibrous layer (dermis or corium), which lies on a layer of loose connective tissue (subcutis).

**1. Epidermis:** superficial layers of the skin, consisting of continually renewed stratified squamous epithelium. The epidermis is divided into five layers. Cells divide in the deepest layer, push out to form the more superficial layers. As they grow out they die, become keratinized, and are finally shed from the outermost layer. The basal layer (stratum basale) is the deepest layer and consists of a single sheet of cuboidal to columnar cells capable of cell division. These cells multiply, pushing out to form the more superficial layers. The layer above the stratum basale is the spiny layer (stratum spinosum), composed of polyhedral cells. When prepared for microscopic examination, the cells may take on a "prickly" or "spiny" appearance. This layer varies in thickness from one region of the body to another. Often the stratum spinosum and stratum basale are collectively called the **germinal layer (stratum germinativum)**. The granular layer (stratum granulosum), the third layer, is composed of squamous cells in different stages of degeneration, and contain keratohyalin granules involved in forming keratin. The clear layer (stratum lucidum), an inconsistently present fourth layer, is made of flat, dead squamous cells containing translucent droplets of eleidin, which give this layer its name (lucidum = clear). Eleidin comes from keratohyalin and becomes keratin. The outermost layer, the **horny layer (stratum corneum)**, consists of flat, dead, cornified cells completely filled with keratin, a waterproofing protein.

**2. Dermis (DER-mis) or corium:** the layer of skin directly below and separated from the epidermis by a basement membrane. It consists of collagenous and elastic connective tissue containing blood vessels, nerve fibers, glands and hair follicles. The papillary region or layer is the dermis immediately beneath the epidermis. Small finger-like projections, **dermal papillae**, project up into the epidermis greatly increasing the surface area between the two layers, thus holding them together. The deepest layer of the dermis, the reticular region or layer, is responsible for variations in skin thickness. It is named for the arrangement of collagenous fibers into a network (reticulum).

## CLINICAL

**Blister:** a fluid-filled separation between the epidermis and dermis.

**3. SUBCUTANEOUS LAYER or superficial fascia** (sub'kyoo-TAY-nee-us), hypodermis or subcutis: the layer of areolar connective tissue and interspersed fat connecting the skin to underlying structures, such as bones and muscles. This layer is often called subcutaneous tissue or **superficial fascia**.

**APPENDAGES OF THE SKIN:** the hair, hooves, claws, sebaceous glands, and sweat glands associated with the skin.

**4. Sweat glands or sudoriferous glands** (s'yoo'doh-RIF-er-us): simple, coiled, tubular glands of the skin that open independently of hair follicles. Merocrine (MER-oh'-krin) (eccrine) sweat glands, the predominant type of sweat gland in man, are restricted to the footpads of carnivores, the frog of the horse, the nasolabial region of ruminants and swine, and the pig carpus. Apocrine (AP-oh-krin) sweat glands predominate in the domestic species and are distributed throughout the skin. Sweat glands help maintain body temperature of the domestic species. The horse sweats the most ("lathering up") of the domestic species, the cat and dog the least.

**5. Sebaceous glands or oil glands** (se-BAY-shus): simple alveolar holocrine glands usually connected to hair follicles. The cells lining the glands disintegrate to form the secretion sebum (SEE-bum). Sebum is an oily substance consisting of a mixture of cholesterol, protein, and inorganic salts, which is released into the hair follicle to lubricate the skin and prevent excessive evaporation. Sebum of the fleece of sheep is called lanolin.

**HAIR:** the long, slender, filamentous appendage of the skin composed of keratinized (dead) epithelial cells. Each hair consists of a shaft and a root. The root is contained in a depression (hair follicle). Associated with hair follicles are sebaceous glands and a bundle of smooth muscle, the arrector pili muscle, connecting the side of the hair to the dermis. During stress, cold or fright the muscle pulls the hair into a vertical position, resulting in "goosebumps" in humans. In domestic species, this produces a trap for insulating air or making the animal appear more intimidating.

**Hair follicles:** horses and cattle have single hair follicles. Dog - has compound hair follicles with a single primary hair and a group of smaller secondary hairs. Pigs - have single follicles grouped in clusters. Cat - has a single follicle with a primary guard hair surrounded by clusters of compound follicles. The compound follicles have three primary hairs with many secondary hairs.

## Types of hair:

- **Bristles:** the hair coat of the pig; the cilia (eyelashes), vibrissae (hairs of the nostril), and "beard" (hair of the submandibular region) of the goat.

- **Guard hairs:** the outer coat ("topcoat") of the domestic species, except the sheep and pig.

- **Wool hair:** the wavy, fine, short, inner coat ("undercoat"). This is the hair type of the fleece of sheep.






Fig. XI-1 - Human skin - section

a. Sweat pores  
b. Pacinian corpuscle  
c. Papillary region  
d. Reticular region

e. Adipose tissue  
f. Sensory nerve (ANS)  
g. Vein  
h. Artery

i. Autonomic motor n. (ANS)  
j. Dermal papillae  
k. Duct of sweat gland

l. Secretory portion  
of sweat gland



# SKIN

• **Long (horse) hair:** the long hair of the horse - forelock, mane, tail, and "feathers" (behind fetlock).

• **Tactile hair:** stiff, sensory hair in some of the domestic species on the upper and lower lip, chin, cheek, around the eye and the carpus.

**Color of hair:** determined by complicated genetic factors governing the amount of pigment (melanin) in the hair. There are only three hair pigments: black, brown, and yellow. The great variation in color is due to combinations or absence of these three pigments. Gray hairs of aging result from loss of pigment; white hair is due to absence of pigment and presence of air in the hair shaft.

## SPECIALIZED GLANDS of the SKIN:

**Carpal glands:** in pigs just proximal to the carpus on the caudomedial side of the leg. They produce sexual pheromones to sexually stimulate the mating partner. They also mark the sow during mating as the boar's "property".

**Caudal (coccygeal) glands:** in carnivores on the dorsum of the root of the tail.

**Ceruminous glands:** in all domestic species, found in the wall of the external auditory canal. They produce "ear wax" which protects the tympanic membrane from foreign bodies (pg. 551).

**Circumanal glands:** in carnivores around the anus. They can become neoplastic (perianal adenoma).

**Circumoral or perioral glands:** only in cats, located in the skin around the mouth, especially the lower lip. Their functional significance, although called the "cleaning glands", is probably for marking.

**Glands of the anal sac:** in carnivores, in the walls of the anal sacs, they secrete into the anal sacs for storage.

**Glands of the inguinal sinus:** in sheep on either side of the udder or scrotum. The odor may help the lamb locate the udder.

**Glands of the infraorbital sinus:** in sheep found in the infraorbital sinus just rostral to the eye, used for marking.

**Glands of the interdigital sinus:** in sheep between the digits, used as "trail markers".

**Glands of the nasal skin:** in artiodactyls (even toed animals) in the skin of the nose.

**Horn glands:** in goats and some sheep just caudal to the base of the horn (similar location in hornless animals).

**Mental (chin) glands:** in pigs a wart-like skin eminence on the

## General-End

chin. It has both tactile and secretory (marking) functions.

**Preputial glands:** located in the prepuce, their secretions mix with degenerated cells to form a substance called smegma, which is significant in the horse.

**Subcaudal gland:** in goats, the two glands below the tail that are said to be responsible for the buck's characteristic smell.





Fig. XI-2 - Dog - Section of skin (schematic)





**MAMMARY GLAND:** a modified sweat gland that nourishes the young. It consists of the mamma and the teat. Undeveloped in both the male and female at birth, the female mammary gland begins to develop as a secondary sex characteristic at puberty. With the birth of the first young and the first lactation, the mammary gland attains its full size and function. When suckling by the young stops, milk production ceases and the gland regresses. Shortly before the next and subsequent parturitions, the gland is stimulated by hormonal changes to produce milk. With advanced age, the mammary glands regress, their tissue is replaced by connective tissue and loses its function.

**1. Mamma (pl. = mammae):** the glandular structure associated with a teat.

**Lobes:** the internal compartments of the mamma, separated by adipose tissue (fat). The lobes are divided into lobules. **Lobules** consist of connective tissue containing alveoli, the grape-like clusters of milk-secreting cells of the mammary gland.

**Milk (lactiferous) ducts:** large ducts conveying milk from the alveoli to the milk sinus.

**2. Milk (lactiferous) sinus:** the large milk storage cavity within the teat and the glandular body.

**3. Teat or papilla:** the projecting part of the mammary gland

containing part of the milk sinus. It is lined with a double layer of columnar epithelium.

**4. Teat canal, papillary duct or streak canal:** the duct leading from the milk (teat) sinus to the teat opening. It is lined with stratified squamous epithelium thrown into longitudinal folds. The cells produce a sebaceous plug in the teat canal.

**5. Teat openings:** the openings of the teat canal.

**Sphincter muscle:** the muscular fibers around the teat opening that prevent milk flow, except during sucking or milking.

**MAMMARY GLAND - COW:** the mammary gland of the cow takes on added significance due to the importance of milk as a human food source.

**Udder:** the term designating all the mammae in the ruminant and the horse (sometimes used for the sow also.)

**Quarters:** the four parts of the bovine udder, each associated with one teat. All four quarters are completely separated from each other. The intermammary groove (c) is the external indication of the separation of the two halves of the udder.






Fig. XI-4 - Cow - Suspensory apparatus of the udder (schematic)




Fig. XI-5 - Cow - Suspensory apparatus - lat. view

- a. Pelvic symphysis
- b. Symphyseal tendon
- c. Body wall
- d. Udder
- e. Intermammary groove

## Mammary gland - cow (cont.)

**Furstenberg's rosette:** fold of teat canal mucosa that extends into the teat sinus.

**Anular fold:** a constriction between glandular and teat parts of the milk sinus. It consists of muscular fibers, connective tissue and circular venous channels ("Furstenburg's venous ring"). This is variable in size and may occlude the connection between the two sinuses ("high spider"). Sometimes it has to be cut to allow milk into the teat sinus.

**"Furstenburg's venous ring":** venous circle surrounding the base of the teat.

**SUSPENSORY APPARATUS:** the specialized attachment of the udder to the symphyseal tendon (below the pelvic symphysis) and the ventral abdominal wall. It is best developed in the cow.

**Primary laminae:** four sheets of connective tissue applied to the lateral and medial side of each half of the udder and meeting at the teats to form the capsule of the udder.

**1. Medial laminae:** two elastic sheets arising from the ventral abdominal wall near the linea alba and extending ventrally between the two halves of the udder. Due to its elastic fibers, as the udder fills, it stretches more than the lateral laminae and the

teats angle laterally (helps prevent them from dragging on the ground).

**2. Lateral laminae:** two collagenous sheets arising from the pelvic symphysis.

**3. Secondary laminae:** seven to ten sheets arising from the primary laminae to enter the mammary gland and divide it into lobes.

**Blood supply:** the external pudendal arteries are the main blood supply to the cow's udder. They branch into cranial and caudal mammary branches which anastomose to form a ring around the base of the udder. The internal pudendal enters the caudal part of the ring. The cranial mammary artery (caudal deep epigastric artery) travels cranially on the ventral abdominal wall to anastomose with the caudal mammary artery (cranial superficial epigastric artery). The venous drainage travels with the arterial supply.

**MILK VEIN:** the large caudal superficial epigastric vein that runs along the ventral abdomen, draining the udder. In dorsal recumbency the milk veins disappear, thus, should be marked before any dorsal recumbent surgery.

**Nerve supply:** the iliohypogastric and ilioinguinal nerves to the skin of the cranial udder and by the genitofemoral nerve to the skin of the caudal udder.



1. Mamma
2. Milk sinus
3. Teat
4. Teat canal
5. Teat opening




Fig. XI-6 - Horse - Udder - parasagittal section

## SPECIES DIFFERENCES

### Mammary position:

- |                           |                          |
|---------------------------|--------------------------|
| • Thoracic                | man, monkeys & elephants |
| • Thoracoabdominal        | cat                      |
| • Thoracoabdominoinguinal | dog and pig              |
| • Inguinal                | horse and ruminants      |

**Bitch:** usually 10 mammae, 5 (4 - 6) mammary complexes on each side separated by an intermammary groove. Teats of animals that have been pregnant are always larger than those of animals which have never been pregnant.

**Queen:** 8 mammae, four on each side of the ventral abdominal wall.

**Sow:** 14 (10 - 18) mammae, seven on each side.

**Cow:** 4 mammae, two (quarters) on each side, all bound together to form an udder.

**Goat and sheep:** 2 mammae forming a pendulous udder.

**Mare:** 2 mammae forming a small udder.

**Male - teats:** usually have the same number as females.

**ACCESSORY TEATS or SUPERNUMERARY TEATS (polythelia):** extra teats that may or may not be connected to primary mammary gland tissue in both females and males. In the cow they are often found caudal to the other four but can be

between or cranial to them. These extra teats can be associated with extra glandular complexes (polymastia).

**Bulls, rams and bucks:** accessory teats, if found are usually cranial to the scrotum.

**Polymastia:** extra mammae.

Each mamma is usually separate from the other mammae.

**LYMPH DRAINAGE - DOG:** the cranial 2-3 pairs drain through the axillary lymph node and the caudal 2-3 drain through the superficial inguinal lymph nodes.

## CLINICAL

**Colostrum:** the mammary secretion in the first few days after parturition. It has a different composition from normal milk, with essential nutrients and immunoglobulins (antibodies). It also has a laxative effect to stimulate the expulsion of the neonate's first stool (meconium).

**Horse, ruminant and pig:** colostrum is especially important in these species because their placentae do not allow transfer of antibodies between the mother and fetus.

**Mastitis:** inflammation of the mammary gland. In the cow, each quarter is completely separated so an infection can be in only one quarter.

**"Milking out":** the complete emptying of a quarter. This is done before treating an infected quarter.







Fig. XI-7 - Horse - Hoof, lt. side untrimmed, rt. side trimmed - view of ground surface (for R.Kainer, Vet. Clinics of N. Amer.)

Fig. XI-8 - Horse - Hoof - lat. view



**FOOT of the HORSE:** the hoof and the structures within it. The foot skeleton consists of the middle and distal phalanges (pastern and coffin bones), the coffin joint, the navicular bone, and the lateral cartilages of the third phalanx. Many ligaments and tendons of the common/long digital extensor and deep digital flexor muscles insert on the bones of the foot.

**HOOF (ungula):** the horny epidermis covering the digit's distal end; divided into the wall, sole and frog.

**Wall:** the visible part of the standing horse's hoof.

1. "Toe": the dorsal part of the wall.

2. "Quarters": the medial and lateral wall parts.

3. "Heels" (or angles): the palmar or plantar aspect of the wall.


4. "Bars": the extension of the wall from the back (palmar/plantar side) of the foot towards the toe. They are seen on either side of the frog from the ground surface.

5. Sole: the concave surface facing the ground between the frog and walls. The medial and lateral angles of the sole are located between the bars and quarters.

7. Frog: the wedge-shaped structure between the sole, bars, and



Fig. XI-9 - Horse - Hoof & associated bones, dermis removed - sagittal section



- A. Middle phalanx
- B. Dist. phalanx
- C. Coffin joint
- D. Navicular bone

- a. Angle of sole
- b. "Collateral groove" (paracuneal sulcus)
- c. Water line
- d. Periople (XI-8)
- e. Crus of frog
- f. "Central groove of frog" (central cuneal sulcus)
- g. "Apex of frog" (cuneal apex)
- h. Wall
- i. Laminar surface of wall (XI-9)
- j. Coronary groove
- k. "Spine of frog"
- l. Solar foramen
- m. Digital cushion (XI-10)
- n. Perioplic groove (XI-9)
- o. Deep digital flexor tendon (XI-10)
- p. Extensor tendon




Fig. XI-10 - Horse - Digit - axial section (for R. Kainer, Vet. Clinics of N. Amer.)

bulbs. It points towards the toe. It is often called the "heart of the horse's foot" because its compression forces blood out of the foot back toward the body. The frog is homologous with other species' digital pads.

8. Bulbs: part of the hoof just proximal and palmar/plantar to the frog.

9. CORONET: the junction of the hoof and the skin.

10. WHITE LINE or white zone: the junction between the wall and sole on the ground surface of the foot. This is the external indication of the sensitive internal structures. The NAV uses white zone to avoid confusion with the linea alba of the abdomen. In practice, most horsemen wouldn't be confused because they've never heard of the linea alba, and couldn't translate it if they had.






Fig. XI-11- Horse - Hoof wall, coronary region - three dimensional dissection (modified from J. Daugherty's illustration in Adam's Lameness in Horses, Stachak for R.Kainer, Vet. Clinics of N. Amer.)

- a. Papilla:
- b. Tubular horn
- c. Non-tubular horn
- d. Primary lamina
- e. Secondary laminae

**STRUCTURE of the FOOT:** The covering of the foot is modified skin (integument) and like the skin, consists of an outer epidermis (the hoof) and an underlying dermis (corium). The subcutis connects the dermis to the internal structures of the foot.

**CORIUM or DERMIS** (KO-ree-um) (pl. = coria): the highly vascular part of the integument providing nourishment for the overlying epidermis (hoof). Nerves are located in the dermis, but not in the horny hoof (epidermis), making the dermis ("quick") the sensitive part of the foot. By attachments to the deep structures of the foot, the dermis holds the hoof in place. The corium (dermis) is divided into five parts: periople, coronary, laminar, sole and frog. Each corium (dermis), except the laminar, has pegs (papillae) extending into the horny epidermis. Around these pegs

(dermal papillae), the epidermis builds tubular and non-tubular horn. The tubular horn develops from the epidermis around the papillae as it grows away from the papillae. The nontubular horn develops from the germinal epithelium between the papillae. The vascular subcutis attaches the corium (dermis) to the periosteum of the distal phalanx.

**1. Periopic corium:** the dermis of the foot that is continuous with the dermis of the skin. It widens out over the bulb of the heel, and produces the thin, shiny, external layer (stratum externum) of the wall.

**2. Coronary corium:** the thick band of dermis just distal to the periopic corium, located in the coronary groove (Fig. XI-9,j) of



Fig. XI-12 - Horse - Dermis of foot, hoof removed - lat. view





Fig. XI-13 - Horse - Dermis of foot, hoof removed - dist. view

the hoof. The coronary corium's papillae provide the template for tubular and non-tubular horn of the wall's bulk. The corium's deep surface connects to the ligaments and cartilages of the distal phalanx by a very vascular connective tissue layer (subcutis).

**3. Laminar corium (sensitive laminae):** the dermis connecting the distal phalanx's lateral and dorsal sides (parietal surface) to the hoof wall. Its papillae are modified into elongated primary laminae (sheets) (Fig. XI-1 l,d) oriented perpendicular to the parietal surface of the distal phalanx. Secondary laminae extend off the primary laminae at acute angles. The laminae interdigitate with the laminae of the laminar epidermis of the hoof, tightly binding hoof (epidermis) to corium (dermis). The deep surface of the laminar dermis is attached by the subcutis to the periosteum of the distal phalanx.

**4. Corium of the sole:** the dermis underlying and nourishing the horny sole.

**5. Corium of the frog:** the dermis underlying and nourishing the horny frog. The deep surface of the dermis blends with the digital cushion (Fig. XI-10,m).

**Coronary band:** consists of the coronary and perioplic coria and the germinal layer of the epidermis overlying these coria. The coronary cushion is the modified, elastic subcutis under the coronary band.

**EPIDERMIS or hoof:** the part of the integument overlying the dermis (corium). The epidermal layer next to the corium is the germinal layer as would be expected in a skin structure. Here cells divide and push away from the dermis, hardening as they move

away to form the hard hoof.

**6. Perioplic epidermis:** the light band marking the junction between the hoof and skin (its dorsal edge is the coronet). It arises around the papillae of the perioplic corium. Growing down towards the ground as a shiny, thin, external layer of the hoof wall in young animals, it usually is worn away in older horses.

**7. Coronary epidermis:** the middle, highly keratinized hoof wall layer extending distally from the coronary corium that nourishes it. This layer forms the bulk of the wall of the hoof.

**8. Laminar epidermis:** the inside layer of the hoof that interdigitates with the laminae of the dermis, connecting the hoof to the parietal surface of the coffin bone (PIII). Overlying the dermis's primary and secondary laminae, the germinal layer of the epidermis multiplies, pushing the cells perpendicularly away from the laminar dermis to join the coronary epidermis. The arrangement of interdigitating laminar corium and epidermis greatly increases the surface area and strength of the bond. As the laminar dermis (sensitive) rounds the toe of the distal phalanx it becomes the sole dermis. The non-pigmented laminar epithelium (insensitive) continues from this turning point to the ground surface of the hoof, forming the white line.

**9. Sole epidermis:** similar to the coronary epidermis, consisting of pigmented tubular and non-tubular horn.

**10. Frog epidermis:** similar to the coronary epidermis, but more elastic and not fully keratinized. Its tubular horns are slightly wavy, thus, softer.






Fig. XI-14 - Horse - cross section of digit at level P III

- |                             |                     |
|-----------------------------|---------------------|
| a. Dist. phalanx            | d. Frog             |
| b. Space between frog & bar | e. Tubular horn     |
| c. Bar                      | f. Non-tubular horn |
|                             | g. Periople of heel |

**11. SUBCUTIS:** the layer of connective tissue joining the dermis to the coffin bone, cartilages of the hoof, and tendons.

**12. DIGITAL CUSHION:** the wedge-shaped mass of white elastic fibers and fat overlying the frog and attaching to the cartilages of the hoof.

**BULBS:** the two soft prominences behind and above the frog. With the frog they form the pad (torus ungula) of the horse.

## CLINICAL

**13. White line:** the junction between the wall and sole on the ground surface of the foot. It is formed by the insensitive laminae reaching the ground surface. It is an important landmark in horse shoeing. To insure the sensitive laminar corium is not invaded, a nail is driven into the hoof on the outside of this line. With experience a nail can be driven inside the line and angled across it without reaching where it interdigitates with the sensitive laminae.

## CONFORMATION OF THE HORSE'S FOOT

**Foot axis:** the angle of the foot in relation to the ground surface. When viewed from the front all legs should be perpendicular to the ground. When viewed from the side the dorsal foot surface should form an angle (foot angle) with the ground of roughly: 45-50° front foot, 50-55° - hindfoot.


**Pastern axis:** the angle of the proximal phalanx (long pastern) with relation to the ground. This axis should be in the same plane as the foot axis.

**Foot/pastern axis:** should be equal and form a continuous line. If the angles of the foot and pastern axes are not equal then the horse has a broken foot-pastern axis. This is more important than the foot axis. The foot axis can be manipulated by horseshoers to make a straight foot-pastern axis even if this deviates from the ideal foot angle.

**Level foot:** a foot with equal length to the medial and lateral quarters and heels.



10. Frog epidermis



9. Sole epidermis

Fig. XI-15 - Horse - Rear hoof, trimmed - dist. view

## ABNORMAL FOOT CONFORMATION

**Club foot, steep foot or upright foot:** a foot with a dorsal angle to the ground of 60° or greater.

**Low foot or sloping foot:** a foot with an angle of less than 45°.

**Broken foot:** when the foot and pastern axis are not the same from the lateral view. This increases stress on the distal limb and can lead to many problems. The foot-pastern axis should be corrected if possible by shoeing.

**Coon foot:** a broken foot-pastern axis in which the foot axis is steeper than the pastern axis.

**Buttress foot:** a foot with a swelling on the dorsal coronet. This may be tears of the extensor tendon's attachment to the extensor process of the distal phalanx or to low ringbone.

**Flat foot:** a foot with little concavity to the sole.

**Drooped foot:** a flat foot due to rotation of the distal phalanx pushing down on the sole.

**Off-level foot:** a foot with a lower quarter than the opposite quarter.

## DISEASES of the HORSE'S FOOT

**Laminitis or founder:** an inflammation of the laminae of the foot (feet) due to a number of causes. This can cause the laminar epidermis and laminar dermis to become uncoupled. When this happens, the pull of the deep digital flexor may rotate the toe of the distal phalanx downward to push on the sole causing a "dropped sole". Chronic laminitis can result in "seedy toe".

**"Seedy toe":** a separation of the "insensitive" (epidermal) and the "sensitive" (dermal) laminae, often occurring due to chronic laminitis. This is seen as a separation at the white line from the ground surface. This can develop into a gravel.

**"Gravel":** a drainage tract up the sensitive laminae and out the skin above the coronet, resulting from an infection of a crack in the white line.

**"Corn":** a bruise (contusion) of the medial angle of the sole.

**Thrush:** a degenerative condition of the frog or lateral angles of the hoof associated with filth, resulting in black necrotic material.

**Contracted heels:** a foot that is narrower than normal in its palmar/plantar aspect.

**Hoof bound:** a lameness due to chronic contracted heels.

**"Quittor":** a chronic inflammation of the lateral cartilages of the hoof characterized by draining tracts just proximal to the hoof.

**Brittle feet:** dry feet with cracks in the hoof wall.

**Toe crack, quarter crack and heel crack (sand cracks):** breaks in the hoof wall starting from the ground surface or the coronary border. Toe, quarter, or heel indicates the location of the crack on the hoof.



Fig. XI-16 - Ox - Foot - lat. view





Fig. XI-17 - Ox - ground surface of foot



a. Axial wall  
b. Abaxial wall

**FOOT of the OX and PIG:** the ox and pig have two weight bearing digits, the horse one. Otherwise, they are basically anatomically the same. The foot skeleton is formed by the middle and distal phalanges, the distal interphalangeal joints (coffin joints) and the distal sesamoid bones. Many ligaments and the tendons of the common/long digital extensor and deep digital flexor muscles attach to these two phalanges.

**Hooves:** the epidermis of the wall, sole and heels; similar to the horse, except they have no frog, bars or secondary laminae.

**Dermis or corium:** the sensitive vascular layer underlying the hoof consisting of perioplic, coronary, laminar, sole, and bulb dermis.

**1. Interdigital cleft:** the space between the two hooves.

**Hoof pads or bulbs (tori ungulae):** highly keratinized cushions on the palmar/plantar aspect of the foot.

## CLINICAL

**Foot rot:** inflammation of the ruminant's foot.

**Hoof cracks:** separations in the hoof wall, often following drying of the hoof.

**Interdigital dermatitis:** a wet inflammation of the interdigital cleft.

**Interdigital fibroma:** proliferation of tissue in the interdigital cleft. This is often associated with foot rot and interdigital dermatitis.

**Removal of a digit:** possible and often done in the ox because it has two. The ruminant can still stand if one is removed.






Fig. XI-18 - Ox - Foot, hoof removed showing dermis - lat. view




Fig. XI-19 - Ox - Hoof - dorsomed. view

Fig. XI-20 - Ox - Hoof - medioventr. view




Fig. XI-21 - Ox - Hoof - ventr. view





Fig. XI-22 - Ox - Hoof - lat. view



a. Periopic groove  
b. Toe  
c. Coronary groove  
d. Abaxial wall

e. Axial wall  
f. Parapedal groove  
(area of thinnest horn)



# CLAW - ERGOT - CHESTNUT

Thoracic limb-110




Fig. XI-23 - Dog - Dist. phalanx & claw - lat. view & palm. view





Fig. XI-24 - Cat - Phalanges - lat. view



a. Ungual crest  
b. Extensor process  
c. Flexor process

Fig. XI-25 - Dog - dist. forelimb

**1. CLAW:** a modification of the epidermis in the carnivores, conforming to and enclosing the ungual process (2) of the distal phalanx (P III). The claw consists of a wall and a sole growing away from the underlying dermis. The dermis nourishes the wall and connects it to the ungual process.

## CLINICAL

**Nail trimming:** The claws grow very fast and must be trimmed or worn down. If not they can curve around and enter the paw, especially the dew claw which normally gets little wear. If they are cut too short the dermis may be exposed, "quicked", causing pain and bleeding.

**Declaw (onychectomy):** removal of the claws of cats. To prevent regrowth, the dorsal aspect of the ungual crest must be removed. This is usually done by removing the whole distal phalanx by cutting through the distal phalangeal joint.

**PADS - CARNIVORES (tori):** the hairless, cushion-like pads on the palmar/plantar side of the limbs. The toughest skin on the dog, the epidermis is thick and highly keratinized with a rough surface due to many papillae. The underlying dermis contains sweat glands along with the fibroelastic tissue and fat.

**Carpal pad:** located palmar to the carpus. The carnivores lack tarsal pads.

**3. Metacarpal (metatarsal) pad:** the heart-shaped pad on the palmar/plantar surface at the level of the proximal metacarpophalangeal joints. These joints rest on the pad when the dog is standing.

**4. Digital pads:** the small pad over the distal end of each digit.

**Ruminant -** the hoof pads or bulbs are comparable to the digital pads of carnivores. The metacarpal, metatarsal, carpal and tarsal pads are missing in all the domestic species, except the carnivore and the horse (chestnuts and ergots).

## ERGOT and CHESTNUT of the HORSE

**Ergot:** a small mass of horny material on the palmar/plantar surface of the fetlock. They are buried in the "feathers" (long hair behind the fetlock).


**Chestnut or "night eyes":** a small horny mass on the forearm's medial surface above the carpus and on the medial surface of the tarsus. The tarsal chestnut is usually absent in donkeys and occasionally absent in horses.



# HORN - OX

317-Head-546

Fig. XI-26 - Ox - Horn  
- longitudinal section



**1. HORN (cornu):** the covering of the cornual process of the frontal bone (2) in all three domestic ruminants. They are present in both sexes. The cornual process starts from a horn bud and grows out as a solid structure that becomes hollowed out (pneumatized) by about 6 months of age. The horn is epidermal tissue formed similarly to the hoof wall. The underlying dermis has papillae providing the template for the germinal layer of the epidermis (horn) to form tubular and nontubular horn. The epikeras is the ring of soft horn marking the transition between skin and horn. Like the periople of the hoof, it grows out and covers the horn with a thin shiny layer. Horns are permanent and grow throughout life. The soft horn at the base is similar to the periople of the hoof.

## SPECIES DIFFERENCES

**Cattle:** the horns are located at the caudolateral end of the head.

**Sheep and goats:** the horns are located behind the orbits.

**Polled:** ruminants not having horns.

**Pregnancy grooves - cow:** the grooves (cornual rings) on the external surface of the horns, caused by slowing of growth near the end of gestation and during lactation. A rough estimate of a cow's age can be made by assuming an annual pregnancy; count the number of rings and add to the age of first pregnancy.

**Cornual rings - sheep and goats:** circumferential grooves on the horn. More distinct than in the cow, 9-12 are produced per year.

## CLINICAL

**Dehorning:** removal of horns. This is best done by removing

the horn bud when a calf or kid is between 5 to 10 days of age.

**Dehorning of calves:** can be done as soon as the horn bud is palpable, by chemical means, cauterization or surgical excision of the horn bud and surrounding skin.

**Dehorning young cattle:** after the horn has broken through the skin for at least one inch, the above methods for calves will not work. A Barnes dehorner or a small saw can be used.

**Dehorning adult cattle:** remove the horn close to the skull proximal to the epikeras so no horn can be produced later. This also insures that the branches of the cornual artery will be cut before they enter the horn or hemorrhage can't be controlled. Saws, horn shears and dehorning wires are all used.

**Dehorning of young goats:** may best done under general anesthesia because of hemorrhage, and the cranium under the horn buds is thin and easily opened to the brain.

**Cornual nerve block - cattle:** inject the cornual nerve (a branch of the trigeminal nerve) midway between the eye and the base of the horn just below the temporal line. This will anesthetize most cattle, if it doesn't, do a ring block around the base of the horn.

**Cornual and infratrochlear nerve blocks in goats:** inject the cornual nerve at the caudal ridge of the root of the zygomatic process of the frontal bone to a depth of 1/2 inch; inject the infratrochlear nerve dorsomedial to the eye close to the edge of the bony orbit.

**Sinusitis:** common sequel to dehorning because in animals over 7 months old the cornual sinus is opened.






Fig. XI-27 - Horse - Eye  
- vertical section

**EYE** (L. *oculus*, G. *ophthalmos*): the organ of sight, consisting of the eyeball and its accessory structures. Light passes through the transparent structures of the eye (cornea, aqueous humor, pupil, lens and vitreous humor) to reach the receptor organs (rods and cones) of the retina. The resulting nerve impulses are then conducted by the optic nerve to the visual center of the brain.

**Descriptive terms:** the eye is one of the few areas where the human nomenclature is used - anterior, posterior, superior and inferior.

**EYEBALL** (L. *bulbus oculi*): the eyeball can be divided into three layers - fibrous tunic, vascular tunic and nervous tunic (retina).

**Fibrous tunic:** the outer coat of the eyeball. It is divided into the sclera and the cornea.

- **1. Sclera** (SKLE-ra) (G. *scleros* hard) or "the white of the eye": the caudal part of the fibrous coat consisting of fibrous tissue. It gives shape and protects the inner structures of the eye.

- **2. Cornea** (KOR-nee-a): the transparent anterior part of the fibrous coat that lets light into the eyeball. Its collagenous fibers are organized in a series of layers that don't interfere with the passage of light - anterior epithelium, anterior limiting ("Bow-

man's") membrane, substantia propria, posterior limiting ("Descemet's) membrane, and posterior epithelium.

- **Limbus** (Fig. XI-29,e): the junction of the sclera and cornea.

**Vascular tunic or uvea** (YOO-vee-a): the middle layer of the eyeball (choroid, ciliary body and iris) consisting mainly of blood vessels and smooth muscle that supply nutrition to the eyeball, and control the shape of the lens and the size of the pupil.


- **3. Choroid** (KOH-royd): the posterior part of the vascular tunic. It is a thin, dark, highly vascular membrane inside the sclera. It supplies the retina and serves to absorb light not reflected out of the eyeball.

- **Tapetum lucidum:** specialized reflective area of the choroid. It is the reason animal's eyes glow when light is shined in them at night; not present in man and pigs.

- **4. Ciliary body** (SIL-ee-ar'ee): the thickest portion of the vascular tunic between the choroid and the iris. It consists of the ciliary muscle and the ciliary processes.

- **5. Ciliary muscles:** the smooth muscles that alter the shape of the lens (accommodation).





**Fig. XI-28 - Horse - Anterior part of eye - vertical section**

**-6. Ciliary processes:** folds on the inner surface of the ciliary body that anchor the zonular fibers.

**7. Suspensory ligaments or zonular fibers:** attach the lens to the ciliary body, hold the lens in position, and allow the shape of the lens to change due to actions of the ciliary muscles. Contraction of the muscles causes the ciliary ring to shrink towards the lens taking tension off the fibers. This allows the lens to take on a round appearance when focusing on close objects. Relaxing the muscles, as when gazing at the horizon, puts tension on the fibers which stretches the lens thin.

**8. Iris:** the colored, doughnut-shaped part of the eye surrounding the pupil. It has two layers of muscle reacting to light to increase or decrease the size of the pupil, regulating the amount of light entering the eyeball. The circular, smooth pupillary constrictor muscles constrict the pupil when stimulated by the parasympathetic fibers. The radiating, smooth pupillary dilator muscles dilate the pupil when stimulated by the sympathetic fibers. The color of the iris is determined by the number of pigment cells in it. A high number gives a brown color, a very low number a blue color.

**9. Pupil:** the central opening of the iris that lets light into the eye.

**10. Retina (RET-i-na) ("nervous" coat):** the inner coat of the eye, functioning in image formation. The retina contains three layers

of neurons: photoreceptors, bipolar neurons, and ganglion neurons.

• **Photoreceptors:** the light sensitive, first layer of the retina. Dendrites of photoreceptors are the cones and rods.

– **Rods:** dendrites sensitive to dim light (night vision) and shapes.

– **Cones:** dendrites sensitive to color and sharpness of vision.

• **Bipolar neurons:** the intermediate layer of the retina receives impulses from the rods and cones and passes them to the neuronal ganglia.

• **Ganglion neurons:** the inner layer of the retina which pass the impulse in their axons to the optic nerve.

• **11. Optic disc:** the area on the retina where the axons from the ganglion neurons leave the eye as the optic nerve. Having no rods or cones, this area is called the "blind spot".

**12. LENS:** the transparent, biconvex body of the eye suspended behind (posterior) the iris by the suspensory ligaments. It constitutes part of the refractive mechanism of the eye. The lens has a dense capsule and is arranged in layers of transparent dead cells, like an onion.






Fig. XI-29 - Horse - Rt. eye

**INTERIOR of the EYE:** the cavity of the eye, divided by the lens and iris into three chambers.

**13. Anterior chamber:** the space between the cornea and the iris.

**14. Posterior chamber:** the space between the iris and lens.

• **Aqueous humor:** watery fluid, similar to cerebrospinal fluid, filling the posterior and anterior chambers. Aqueous humor is secreted by the ciliary processes into the posterior chamber, flows through the pupil into the anterior chamber, and drains at the periphery into the scleral venous plexus which leads to the veins of the eye. It functions to maintain the intraocular pressure and as a nutrient and waste transport medium.

**15. Vitreous chamber:** the larger space lying between the lens and retina. It is filled with vitreous humor.


• **16. Vitreous body:** the jelly-like substance that fills the vitreous chamber, maintains the shape of the eye and holds the retina in place.

#### ACCESSORY STRUCTURES of the EYE

**17. Upper and lower eyelids or superior and inferior palpebrae:** the two movable folds protecting the rostral surface of the eyeball. The tarsus is a fibrous plate supporting the margin of the eyelid. Tarsal ("Meibomian") glands open in series onto the margin of the lid.



Fig. XI-30 - Ox - Anterior part of eye - vertical section



**Cilia or eyelashes:** hairs coming out of the eyelids. There are sebaceous and ciliary glands associated with the cilia.

**18. Lateral and medial commissures or canthi (sin. = canthus):** the point where eyelids meet. The lateral and medial angles are the areas near the canthi.

**19. Lacrimal caruncle:** a triangular prominence in the medial angle.

**20. Lacrimal puncta:** openings into lacrimal canals on upper and lower eyelids near the medial angles (pg. 558).

**Conjunctiva:** the special mucous membrane lining the eyelid and the eyeball.

• **21. Palpebral conjunctiva:** lines the inner surface of the eyelid.

• **22. Bulbar conjunctiva:** the reflection of the palpebral conjunctiva onto the eyeball.

**23. Third eyelid (palpebra tertia) or "nictitating membrane":** the fold of conjunctiva, reinforced by cartilage, located between the eyelid's medial angle and the eyeball. Retraction of the eyeball causes the third eyelid to move across and protect the eyeball. The gland of the third eyelid is a lacrimal gland.

#### SPECIES DIFFERENCES

**24. Corpora nigra (L. black body) or granula iridica:** several black masses at the upper and lower edges of the iris in the horse and ruminants.

#### CLINICAL

**Cataract:** the loss of lens transparency. The most common cause is aging.

**Glaucoma:** a group of eye diseases characterized by an increase in intraocular pressure which causes physiological changes in the optic disk and typical defects in the field of vision.

**Entropion:** the inversion of the margins of the eyelids.

**Ectropion:** the eversion of the margins of the eyelids.

**Stye or hordeolum:** inflammation of the glands associated with the cilia.

**Enucleation of the eyeball:** common in cattle as a treatment for cancer eye.






Fig. XI-31 - Horse - Eye  
- rostr. view




Fig. XI-32 - Horse - Extrinsic eye  
muscles - lat. view




Fig. XI-33 - Horse - Extrinsic eye muscles

- A. Dors. oblique m. (CN IV)
- B. Dors. rectus m. (CN III)
- C. Lat. rectus m. (CN VI)
- D. Ventr. rectus m. (CN III)
- E. Ventr. oblique m. (CN III)
- F. Med. rectus m. (CN III)
- G. Retractor bulbi m. (CN IV)

- a. Trochlea
- b. Corpora nigra

**MUSCLES of the EYE:** divided into intrinsic and extrinsic groups. Intrinsic muscles consist of the pupillary sphincter, pupillary dilator and ciliary muscles which deal with size of the pupil and lens shape (accommodation). Extrinsic muscles move the eyeball and are located behind it. They are the four rectus muscles (dorsal, ventral, medial, and lateral), two oblique muscles (dorsal and ventral) and the retractor bulbi muscles. Humans lack a retractor bulbi muscle. The muscles in the legend are followed by the nerves innervating them.

**Memory aid:** for the innervation of the extrinsic muscle of the eye: Do<sub>4</sub>(LrRb)<sub>6</sub>Rest<sub>3</sub>. The trochlear (CnIV) innervates the muscle that passes around the trochlea (a) - dorsal oblique. The abducens (CnVI) innervates the muscle that abducts the eye - lateral rectus, and the retractor bulbi. The oculomotor (CnIII) innervates all the rest.

**Levator palpebrae superioris muscle:** does not attach to the eye, but to the upper eyelid. It elevates the upper eyelid and is innervated by the oculomotor nerve (CNIII).

**Orbicularis oculi muscle:** surrounds the eye and functions to close it. It is innervated by the palpebral branch of the facial nerve (CNII).

## CLINICAL

**Facial nerve paralysis:** caused by damage to the facial nerve (CnVII). This distorts the face which may bother the owner, not the animal. A clinically significant problem is if the orbicularis oculi muscle is affected and the animal can't shut its eye. This can lead to serious drying of the eye.



## 1. Auricular cartilage




Fig. XI-34 - Dog - Auricular cartilage



Fig. XI-35 - Ox - Auricular cartilage & skull

- |                       |                      |
|-----------------------|----------------------|
| a. Helix              | f. Tragus            |
| b. Apex               | g. Intertragic notch |
| c. Med. crus of helix | h. Antitragus        |
| d. Lat. crus of helix | i. Annular cartilage |
| e. Pretragic notch    |                      |

**EAR** (L. *auris*; G. *ous*): the organ of hearing and balance. It is divided into three portions - the outer, middle, and inner.

**OUTER EAR:** the pinna and the external auditory meatus.

**Pinna** (L. a feather, wing, or fin) or **auricle**: the fleshy appendage attached to the side of the skull by muscles and ligaments, making it very mobile. It functions to catch and direct sound waves toward the middle ear (ear drum).

**1. Auricular cartilage:** the elastic framework of the pinna and


external auditory meatus, covered on both sides with skin.

**External auditory meatus:** the passageway from the pinna to the ear drum.

### CLINICAL

**Cerumen** (se-ROO-min)(L. *cera* wax) or **earwax**: brown, waxy material secreted by glands in the ext. auditory meatus.





**Fig. XI-36 - Middle ear & inner ear (schematic)**

**1. MIDDLE EAR or tympanic cavity:** the part of the ear inside of and including the tympanic membrane. It contains the auditory ossicles and the opening to the auditory tube.

**2. Tympanic membrane (tim-PAN-ik) or ear drum:** the thin, semitransparent partition between the external auditory meatus and the middle ear. The ear drum is vibrated by sound waves.

**Auditory ossicles (ear bones):** the three bones extending across the middle ear from the ear drum to the oval window of the cochlea. They transmit and amplify vibrations of the ear drum to the oval window, setting up vibrations in the fluid of the cochlea.

• **3. Malleus (the "hammer"):** the small bone connecting the inner surface of the tympanic membrane and the incus.

• **4. Incus ("anvil"):** the ossicle between the malleus and stapes.

• **5. Stapes ("stirrup"):** the smallest bone in the body. Its base fits into the oval window.

**6. Oval (vestibular) window:** one of two openings between the middle and inner ear. It is filled by the base of the stapes, which pushes inward.

**7. Round (cochlear) window:** the other opening between the middle and inner ear, located below the oval window and covered by a secondary tympanic membrane, which bulges outward with fluid movement.

**8. Auditory tube (eustachian tube):** the passageway between the middle ear and nasopharynx. It functions to equalize pressure on both sides of the ear drum, protecting it from rupture. Swallowing or yawning opens the auditory tube, allowing air into the middle ear.

## CLINICAL

**Auditory tube (8):** a potential path for spread of infection from the nasopharynx to the middle ear.






Fig. XI-37 - Horse - Head - cross section

2. Pharyngeal opening of the auditory tube

- |   |                                   |
|---|-----------------------------------|
| a. Lat. compartment of the guttural pouch | f. Epiglottis                     |
| b. Med. compartment of the guttural pouch | g. Nasopharynx                    |
| c. Stylohyoid bone                        | h. Larynx                         |
| d. Opposing medial walls                  | i. Basilar part of occipital bone |
| e. Rectus capitis & longus capitis mm.    | j. Atlas                          |
|   | k. Mandible                       |




Fig. XI-38 - Horse - Head - sagittal section

**GUTTURAL POUCH (GUT-ur-al):** large, ventral diverticula of the auditory tubes in the horse. Located between the cranium and the pharynx, a number of cranial nerves and the internal carotid artery pass next to the dorsal part of a pouch. The stylohyoid bone partially separates the pouch into lateral and medial compartments. The two guttural pouches are separated on the midline by a membranous wall (d).

**2. Pharyngeal opening of the auditory tube:** small slits in the lateral nasopharyngeal wall that open into the auditory tubes, thus, into the guttural pouches.

## CLINICAL

**Guttural pouch infections:** respiratory diseases can extend into the guttural pouches from the pharynx.

**Drainage of the guttural pouch:** performed by passing a catheter (long hollow tube) through the ventral nasal meatus into the pharyngeal opening of the auditory tube, thus, into the guttural pouch.

**Epistaxis:** bleeding from the nose. A mycotic (fungal) disease of the guttural pouch may erode the pouch and the internal carotid artery, causing a sudden and fatal epistaxis.



Fig. XI-39 - Bony labyrinth




Fig. XI-40 - Membranous labyrinth

**INNER EAR:** consists of the bony (osseous) and membranous labyrinth.

**Bony (osseous) labyrinth** (Fig. XI-39): a series of cavities in the temporal bone; lined with periosteum and divided into the vestibule, cochlea, and semicircular canals.


• **Perilymph:** fluid within the bony labyrinth, surrounding the membranous labyrinth.

**Membranous labyrinth** (Fig. XI-40): a series of tubes and sacs within the bony labyrinth.

• **Endolymph:** fluid within the membranous labyrinth.



Fig. XI-41 - Cochlea - cross section



**1. COCHLEA** (KOHK-lee-a) (L. snail shell): the snail shell-like part of the inner ear associated with hearing. The cochlea consists of an outer bony coil and an inner membranous cochlear duct.

**Bony labyrinth – cochlea** (Fig. XI-30): a bony, spiral canal making a number of turns around a central bony core, the modiolus (moh-DY-oh-lus). The membranous cochlear duct divides the bony spiral labyrinth into two channels – the scala vestibuli and the scala tympani.

• **2. Scala vestibuli**: the canal of the bony labyrinth communicating with the vestibule, the middle ear at the oval window, and the scala tympani at the apex of the cochlea.


• **3. Scala tympani**: the continuation of the scala vestibuli from the apex of the cochlea to the round window.

**Membranous labyrinth**: a membranous tube separating the two canals of the bony labyrinth and forming the cochlear duct.

• **4. Cochlear duct or scala media**: the spiral canal extending from the base to the apex of the cochlea, between the canals of the bony labyrinth. It is filled with endolymph and contains the spiral organ.

• **Spiral organ or organ of Corti** (Fig. XI-33): the organ of hearing consisting of a series of hair cells on the inner surface of the membranous labyrinth. Bending of the free ends of hair cells by vibrating endolymph generates a mechanical signal transmitted by the cochlear branch of the vestibulocochlear nerve (CN VIII) to the brain where it is perceived as sound.





**Fig. XI-42 - Ext. auditory meatus, middle & inner ear (schematic)**

## PHYSIOLOGY of HEARING

Sound waves reaching the ear are directed by the pinna to the external auditory meatus (1) and then to the tympanic membrane (2).

The tympanic membrane (2) is vibrated by the sound waves.

The malleus (4), connected to the tympanic membrane's inner surface, passes on and amplifies vibrations via the incus (5) and stapes (6) to the oval window (7).

Vibrations of the oval window by the stapes sets the perilymph (10) into a wave motion that travels through the scala vestibuli (8) and scala tympani (9) to the round window (16).

The round window (16) bulges into the middle ear and then back into the scala tympani, reversing the fluid wave movement.

Vibrations of the scala vestibuli and scala tympani generate wave motion of the endolymph (15) within the cochlear duct (11), displacing the hair cells of the spiral organ (12).

The movement of the hair cells (14) of the spiral organ develops a nerve impulse.

The nerve impulse passes through the cochlear branch of the vestibulocochlear nerve (CNVIII) to the hearing centers in the brain.






Fig. XI-44 - Macula

- a. Otolithic membrane
- b. Otoliths
- c. Hair cells
- d. "Hairs" (kinocilia)
- e. Cupula




Fig. XI-43 - Membranous labyrinth, utricle, saccule and one ampullae opened




Fig. XI-45 - Crista

**VESTIBULE** (Fig. XI-39): the central, expanded portion of the inner ear.

**Membranous labyrinth of the vestibule (1,2):** consists of two sacs called the utricle and the saccule.

1. **Saccule:** a sac of the membranous labyrinth.

2. **Utricle:** connected to the saccule by a small duct.

3. **Maculae** (MAK-yoo-lee) (sin. = macula): static equilibrium receptors located perpendicular to each other in the utricle and saccule.

**Hair (receptor) cells (c):** the receptor cells of maculae carrying impulses to the vestibular branch of the vestibulocochlear nerve (CNVIII). The otolithic (oh-toh-LITH-ik) membrane (a) is a gelatinous layer over the hair cells in which the "hairs" (kinocilia) (d) are embedded. The otoliths (b) are calcium carbonate crystals forming a layer over the otolithic membrane.

**PHYSIOLOGY of STATIC EQUILIBRIUM:** The otolithic membrane (a) is moved by the weight of the otoliths (b) under the pull of gravity. Thus, static equilibrium is concerned with "body (head) position" relative to gravity. This bends the hair cells (c) embedded in the otolithic membrane, generating a nerve action

potential. The impulse is carried by the vestibular branch of the vestibulocochlear nerve to the brain.

**SEMICIRCULAR CANALS:** the three bony canals arising from the vestibule, arranged at approximately right angles to each other.

**Ampulla:** an enlarged swelling at the end of each semicircular canal.

**Membranous labyrinth** (fig. XI-35): lines the bony labyrinth.

4. **Semicircular ducts:** the membranous labyrinth of the semicircular canals communicating with the utricle.

5. **Crista:** the receptor organ found in the ampulla of each semicircular duct. Composed of hair (receptor) cells and supporting cells, it senses motion of the head. The cupula (e) is a gelatinous mass covering the crista.

**PHYSIOLOGY of DYNAMIC EQUILIBRIUM:** When the head moves, endolymph pushes the cupula (e) bending the hair cells (c) which send impulses via the vestibular branch of the vestibulocochlear nerve (CNVIII) to the brain, thus, detecting angular (rotational) acceleration or deceleration of the head.




# LACRIMAL APPARATUS

Head-End



Fig. XI-46 - Ox - Position of lacrimal apparatus

1. Lacrimal gland



2. Lacrimal puncta

3. Lacrimal canaliculi

4. Lacrimal sac

5. Nasolacrimal duct

a. Med. angle of eye  
b. Bone  
c. Nasal mucosa  
d. Nostril

Fig. XI-47 - Ox - Lacrimal apparatus (schematic)

**LACRIMAL APPARATUS:** the group of structures that manufacture and drain away tears.

**1. Lacrimal gland:** the pink gland lying on the dorsolateral aspect of the eyeball. It releases its seromucous secretions via a number of ducts onto the surface of the eyeball.

**2. Lacrimal puncta:** the openings of the lacrimal canaliculi on the upper and lower eyelids near the medial angle (canthus).

**3. Lacrimal canaliculi:** the small canals from the lacrimal puncta to the lacrimal sac.

**Lacrimal sac:** located in a fossa in the lacrimal bone's orbital surface, it marks the beginning of the nasolacrimal duct.

**5. Nasolacrimal duct:** the duct extending from the lacrimal sac to the rostral part of the nasal cavity, first traveling in a bony canal in the lacrimal and maxillary bones and then deep to the nasal

mucosa before opening into the rostral nasal cavity.

**Innervation:** parasympathetic innervation by the facial nerve (CnVII). These fibers are in the area of the middle ear along with the sympathetic innervation.

## CLINICAL

**Middle ear infection:** can affect the parasympathetic fibers of the facial nerve to the lacrimal gland and cause decreased secretion of the lacrimal gland, resulting in keratoconjunctivitis sicca.

**Keratoconjunctivitis sicca:** drying of the cornea and conjunctiva due to malfunction of the lacrimal gland. This can be treated by transposing the parotid duct to the inside of the upper eyelid. When the dog sees food it will salivate ("spit") onto its cornea.



# Appendix



# TYPES OF NERVES

**SIMPLIFIED FUNCTIONAL CLASSIFICATION of NERVE FIBERS.** The functional classification of nerve fibers is confusing (complicated); with the words special, general, visceral, and somatic meaning different things for different neurons. Students have difficulty learning the complicated method and soon forget it if not constantly used. For learning purposes, this text simplifies this classification by dividing the nerves consisting of certain fibers into three groups: 1. Motor and sensory fibers, 2. ANS fibers, and 3. Special sensory fibers. The simplified and old "complicated" functional classifications are compared as a reference for books that use the complicated method.

1. **Motor and sensory fibers:** somatic motor fibers to skeletal muscle and somatic sensory fibers from skin and deeper somatic structures (skeletal muscle, skin, tendons, bones, etc.).

2. **ANS fibers (motor and sensory):** fibers to and from smooth muscle, cardiac muscle, and glands. These fibers, both motor and sensory fibers, are part of the autonomic nervous system (ANS). They are subdivided into fibers of the sympathetic and parasympathetic divisions. Sympathetic fibers are carried by branches of all spinal and most cranial nerves. Parasympathetic fibers are restricted to some sacral spinal roots (pelvic nerve) and only a few cranial nerves (Cnn III, VII, IX and X):

3. **Special sensory fibers:** fibers carrying taste, smell, vision, hearing & vestibular function over a few cranial nerves (Cnn I, II, VII, VIII, and IX).

**NERVE FIBERS:** nerves can have any combination of these fibers. Nerves that innervate skeletal muscle carry sensory information from the muscle. The sensory component is understood, but ignored in naming motor nerves. All spinal nerves and most cranial nerves possessing ANS sympathetic motor fibers are ignored in this classification. The initials indicate the complicated functional classification of fibers carried by each type of nerve.

• **Mixed nerve:** a nerve consisting of both somatic sensory and motor fibers (SVE, GSE, GSA). It also possesses ANS sympathetic motor fibers (GVE).

• **Motor nerve (SVE, GSE):** a somatic nerve consisting of motor fibers to (and sensory fibers from) voluntary (skeletal) muscles. It also possesses ANS sympathetic motor fibers (GVE).

• **Sensory nerve (GSA):** a somatic nerve consisting of only somatic sensory fibers. It also carries ANS sympathetic motor fibers (GVE).

• **Special sensory nerve (SVA, SSA):** a nerve possessing special sensory fibers dealing with smell, vision, hearing, or taste (special senses).

• **Autonomic (ANS) fibers (GVE, GVA):** a part of all spinal nerves and some cranial nerves.

Outlined below is the relationship of the "simplified" functional

classification to the actual "complicated" functional classification.

**MOTOR (SVE, GSE) and SENSORY FIBERS (GSA):** the somatic motor fibers (SVE and GSE) supply striated skeletal muscle. The difference between SVE and GSE is the type of embryonic tissue the muscles from which they innervate are derived. GSA fibers carry sensory information from SVE & GSE supplied muscles. GSA fibers also carry sensory information from skin and other deep structures other than muscles and are called sensory fibers. The simplified method groups all these (SVE, GSE & GSA) into motor and sensory fibers.

• **Special visceral efferent (SVE):** motor fibers supplying striated skeletal muscle derived from embryonic branchial arch mesoderm. These are found in only a few cranial nerves:

- viz. - Muscles of mastication (Cn V)
- Muscles of facial expression (Cn VII)
- Muscles of palate, pharynx, esophagus, & larynx (Cnn IX, X & XI)
- Trapezius muscle (Cn XI)

• **General somatic efferent (GSE):** motor fibers supplying striated skeletal muscle with the exception of those derived from branchial arch mesoderm. Such fibers are found in branches of all spinal and some cranial nerves:

- viz. - Extraocular muscles (Cnn III, IV, & VI);
- Muscles of the tongue (Cn XII)
- Striated muscles of the neck, trunk, tail, diaphragm, thoracic and pelvic limbs (spinal nerves)
- Striated sphincters of the urinary and gastrointestinal tracts

• **General somatic afferent (GSA):** sensory fibers supplying the body surface (skin and subcutaneous tissue) as well as deeper structures (bones, skeletal muscles, tendons, etc.) derived from embryonic somatic mesoderm. Fibers are found in branches of all spinal nerves, but only a few cranial nerves.

- viz. - Skin of head and face, and lining of the nasal and oral cavities (Cn V)
- Skin of the rest of body, tendons, ligaments, joint capsules and skeletal muscles throughout the body.

**ANS FIBERS, motor (GVE) and sensory (GVA):** carry motor (GVE) and sensory (GVA) fibers to and from smooth muscle, cardiac muscle, and glands, respectively.

• **General visceral efferents (GVE):** motor fibers supplying smooth muscle, cardiac muscle, and glands throughout the body. This fiber classification may be subdivided into sympathetic and parasympathetic components, which are part of all spinal nerves and most cranial nerves (sympathetic GVE). Some may be restricted to sacral spinal roots forming the pelvic nerve and a few cranial nerves (parasympathetic GVE):



# TYPES OF NERVES

viz. Parasympathetic GVE:

- Smooth muscle of the ciliary body and iris (Cn III)
- Salivary, nasal, and lacrimal glands (Cnn VII & IX)
- Smooth muscle of cervical, thoracic & abdominal viscera & cardiac muscle (heart)(Cn X)
- Smooth muscle of the pelvic viscera (pelvic nerve)

Sympathetic GVE (cranial nerves & spinal nerves):

- Smooth muscle, glands, and blood vessels of the skin of head, trunk & limbs
- Smooth muscle of cranial, cervical, thoracic & pelvic blood vessels and viscera
- Cardiac muscle of the heart

• General visceral afferent (GVA): sensory fibers supplying blood vessels and viscera throughout the head and body, and the endodermally-derived mucosa of the respiratory and gastrointestinal tracts caudal to the nasal and oral cavities. Such fibers are carried in branches of every spinal nerve and probably most cranial nerves:

- viz. - Chemoreceptors and baroreceptors associated with the internal carotid artery & aortic arch (Cnn IX & X)
- Mucosa of the nasopharynx, oropharynx & laryngopharynx (Cnn XI & X)

- Blood vessels, glands, & viscera of cranial cervical, thoracic, abdominal & pelvic regions
- Blood vessels & glands of the limbs

**SPECIAL SENSORY FIBERS (SVA & SSA):** carry special sensory information of taste, smell, vision, hearing & vestibular function.

• Special visceral afferents (SVA): sensory fibers responsible for carrying to the brain information related to taste and smell. All such fibers are associated with cranial nerves:

- viz. - Taste receptors ("taste buds") in the tongue, palate & epiglottis (Cnn VII, XI & X)
- Olfactory receptors on the nasal epithelium (Cn I)

• Special somatic afferent (SSA): sensory fibers responsible for carrying to the brain information related to vision, hearing and vestibular function (balance, body position, etc.). All such fibers are associated with cranial nerves:

- viz. - photoreceptors in the retina (Cn II)
- Auditory receptors of the cochlea in the inner ear (Cn VIII - cochlear part)
  - Receptors in the vestibular apparatus in the inner ear (Cn VIII - vestibular part)

Classification	Somatic		ANS	Special senses
Simplified functional fiber classification	Motor	Sensory	ANS (Motor & sensory)	Special sensory
Complicated functional fiber classification	(SVE)(GSE)	(GSA)	(GVE) (GVA)	(SVA) (SSA)



# NEUROANATOMY

Neuroanatomy and neurology, historically, have been portrayed as requiring an elite knowledge to master. This section attempts to simplify neuroanatomy for the future practicing veterinarian, not the future neurologist. A basic understanding of the "skeleton" of neuroanatomy will help the "country" veterinarian to localize neurological lesions without fancy equipment. This is an introduction to build on, thus, touches only on a limited number of structures. Once these are learned, the more advanced literature will hopefully be less daunting to the student. Localizing lesions in the nervous system requires a basic understanding of how the nervous system is organized, its structures, and connections. The nervous system can be divided into a central nervous system (CNS) which includes the brain and spinal cord; and a peripheral nervous system consisting of the cranial and spinal nerves and ganglia. The nervous system is also organized in a segmental fashion consisting of peripheral spinal and cranial nerves and the part of the central nervous system from which they arise.

**SPINAL CORD:** can be divided into segments.

1. **Spinal cord segment and its pair of spinal nerves:** A spinal cord segment is demarcated by the pair of spinal nerves that arise from it. Spinal nerves consist of sensory and motor fibers that pass over the dorsal (sensory) and ventral (motor) roots, respectively.

2. **Reflex arcs:** the functional units of the nervous system. They are programmed motor actions. A reflex arc consists of a receptor, a sensory neuron, usually one or more interneurons, a motor neuron, and an effector.

3. **Lower motor neuron (LMN):** the efferent neuron of a reflex arc that connects the spinal cord to the muscles and glands of the body. The lower motor neuron can be spontaneously active. Modification of the reflex arc by higher centers produces specific actions.

4. **Upper motor neurons (UMN):** pass in descending motor tracts that connect higher centers (the brain and brain stem) with the lower motor neurons of the reflex arcs. They usually act to inhibit the spontaneous activity of the lower motor neuron until an action is desired. They then stimulate the lower motor neuron to produce a programmed action.

5. **Ascending sensory tracts:** carry sensory (afferent) information up the spinal cord to higher centers in the spinal cord and brain. Sensory (afferent) neurons carry such information as pain, temperature, touch, and proprioception from the periphery up the spinal cord to the brain. The main information used clinically is superficial pain, deep pain, and proprioception.

• 6. **Proprioceptive fibers:** sense the position of different body parts in relationship to each other and to the environment. This sense is carried from receptors in the skin, fascia, muscles, and joints up peripheral nerves to the spinal cord. Proprioceptive fibers then travel up the spinal cord to pass through the brain stem to reach the cerebellum and cerebral cortex. The cerebral cortex interprets this information and sends motor information down descending tracts to reflex arcs to make adjustments in posture.

The cerebellum uses proprioceptive information to coordinate posture and movement. Loss of proprioception can indicate a lesion anywhere along this path: in a peripheral nerve, the spinal cord, brain stem, cerebrum, or cerebellum. Postural reactions are used to evaluate proprioception.

• 7. **Superficial and deep pain sensory fibers:** travel up the peripheral nerves, spinal cord, and brain stem to the cerebrum to be perceived.

**Myotome:** the muscles or muscle groups innervated by a spinal nerve (LMN).

**Dermatome:** the area of skin innervated by one spinal nerve (sensory). Knowing the spinal segments innervating myotomes and dermatomes can be used to localize lesions.

**BRAIN:** also organized into segments, although less distinct. Functionally, it can be divided into cerebrum, thalamus, brain stem, vestibular system, and cerebellum.

8. **Cerebrum:** includes the cerebral hemispheres and basal nuclei. It deals with voluntary motor control, behavior, and mental status. It interprets vision and audition, proprioception, and general sensations.

9. **Thalamus:** a part of the brain stem. Functionally, it is closely related to the cerebrum to which it relays information. It also controls the autonomic nervous system (ANS) and the endocrine system.

10. **Brainstem:** functionally includes the midbrain, pons, and medulla oblongata.

• **Walking motion reflex centers:** located caudal to the midbrain. Higher centers initiate and stop the motion through descending motor tracts that cross over in the midbrain. A cat with its cerebrum removed (decerebrate) can be made to walk/run by putting electrodes into the brainstem.

• **Reticular activating system:** Housed in the brain stem, it is concerned with the conscious level (alertness, depression, stupor, and coma).

• **Cranial nerves II to XII:** associated with the brainstem.

11. **Vestibular system:** controls posture and balance in relationship to gravity; and eye movements in relationship to head movements. It is divided into peripheral and central portions.

• **Peripheral vestibular centers:** located in the inner ear, they consist of the labyrinth, receptors, and the vestibular nerve.


• **Central vestibular portion:** includes the vestibular nuclei in the brain stem and centers in the cerebellum.

12. **Cerebellum:** concerned with coordinating movements, but does not initiate them. It also has connections to the vestibular



# NERVOUS SYSTEM

Fig. NS-1 -Nervous system (schematic)



system to help coordinate balance and posture.

**DEFINITIONS:** Once the organization and functions of the different parts of the central nervous system are understood, lesions affecting each part can be discerned. First, some terms need to be understood:

**Analgesia:** the absence of pain perception.

**Depression:** an awake animal that is relatively unresponsive to its environment.

**Stupor:** an animal that sleeps unless aroused by a strong stimulus.

**Coma:** an unconscious animal that can't be aroused. Complete disconnection of the reticular activation system from the cerebral cortex causes coma and is usually due to a severe brain stem lesion.

**Paralysis:** the complete loss of motor activity.

**Paresis (weakness):** the partial loss of voluntary motor activity. Paresis and paralysis are due to partial or complete loss, respectively, of voluntary motor stimulation due to damage of either UMNs or LMNs. The suffix -paresis and -plegia are used to describe paresis and paralysis, respectively:

- Monoparesis or monoplegia: one limb is involved.
- Hemiparesis or hemiplegia: both limbs on one side.
- Tetraparesis/quadraparesis or tetraplegia/quadriplegia: all four limbs are involved.

- Paraparesis or paraplegia: only the pelvic limbs.

**Flaccid paresis or paralysis:** decreased or no tone with paresis or paralysis due to lesions of LMNs.

**Spastic paresis or paralysis:** extra tone (hypertonicity) with paresis or paralysis due to lesions of UMNs.

**Hypertonicity:** excessive muscle tone (not tetany which is rigid, fixed muscle contraction).

**Ataxia:** a lack of coordinated movements with or without spasticity or paresis. Lesions of the entire nervous system neuroaxis may cause ataxia. Although not specific, it shows up frequently and is indicative of the nervous system.

**Tremor:** small, rapid, alternating movements at rest.

- Intention tremor: a tremor that becomes worse with initiation of a movement and disappears at rest. It indicates cerebellar disease.

**Myoclonus (flexor spasm):** coarse jerking moments of muscle groups at rest.

**Dysmetria (Gr. *dys*, abnormal + *metron*, measure):** improper measuring of distance in muscular activity, either too short or too long a range of motion (e.g., goose stepping). Cerebellar disease causes dysmetria (especially hypermetria).



## LMN / UMN

UMN or LMN: spinal cord and peripheral injuries will have characteristic signs. The concept of UMN and LMN helps differentiate peripheral from central lesions; and, if central, helps localize the level of the lesion. The central nervous system will not regenerate. If the cord is severed, function below the lesion will not be restored. Partial damage to the spinal cord may recover in time, but after a certain period it will not improve.

**LOWER MOTOR NEURON (LMN):** the final common pathway from the central nervous system (brain or spinal cord) to a muscle or gland. These are the motor parts of the reflex arcs. The somatic nervous system has one LMN per reflex arc, the autonomic nervous system has two LMNs (preganglionic and postganglionic). The cell bodies of a LMNs are located in the brain and spinal cord. They leave the CNS over the ventral roots, spinal nerves, and cranial nerves to reach the periphery.

**LMN damage:** can affect the nerve in the periphery or its cell body in the spinal cord segment or brain stem, causing loss of activity of the muscle or gland innervated, resulting in paresis or paralysis. This is a flaccid type ("limp as a dish rag") paresis or paralysis due to loss of the spontaneous stimulation of the LMN. Partial or complete damage to a lower motor neuron results in decreased (hypotonia) to no tone (atonia) and decreased reflexes (hyporeflexia) to absent reflexes (areflexia). LMN damage results in fast atrophy (neurogenic atrophy) within one week. These signs are very valuable in localizing lesions. (With lower motor neuron dysfunction point your thumb to the floor to indicate that everything decreases or disappears).

**UPPER MOTOR NEURON (UMN):** a central nervous system neuron that effects lower motor neurons. UMNs are responsible for initiating and maintaining conscious movements and for tone in the extensor muscles to maintain posture. Located totally in the central nervous system, they project down descending motor tracts onto lower motor neurons, either directly or through interneurons. The ultimate UMNs are in the cerebral cortex (voluntary center, the seat of true consciousness). There are two populations of UMNs - excitatory and inhibitory. The excitatory UMNs, under normal conditions, are kept inactive, thus, the descending tracts usually inhibit LMN activity. LMNs are spontaneously active without the input of UMN. If the UMNs are damaged, the LMNs increase their activity.

**UMN damage** causes loss of the ability to initiate voluntary motor activity, and possibly uncontrolled hyperactivity due to decrease of inhibition on LMNs. (Therefore, point your thumb up with UMN damage to indicate that activity goes up). In UMN diseases the tone will be normal to increased. Reflexes will tend to be normal or increased (normoreflexia or hyperreflexia). They will show a spastic paresis or paralysis. The atrophy is a disuse type (not neurogenic), because the LMNs are intact. These LMNs still stimulate the muscles through reflexes, thus, the atrophy will have a slow onset. An animal with a minimal UMN loss and the ability to walk may not develop significant atrophy. To compensate for posture, the extensors have more tone than the flexors. So with loss of upper motor neuron input on lower motor neurons the extensors are facilitated more than the flexors, resulting in an

extended limb with spastic paresis or paralysis.

Damage to the spinal cord will result in dysfunction to the area innervated (LMN damage), and hyperactivity to muscles innervated from segments caudal to the lesion (UMN damage). Damage to a spinal cord segment will show LMN, not UMN, signs to peripheral structures its reflex arc innervates. This is because UMN signs require intact LMNs.

### LMN disease signs (thumb down)

- Decreased or absent tone (hypotonia to atonia)
- Decreased to absent reflexes (hyporeflexia to areflexia)
- Flaccid paralysis
- Rapid atrophy (neurogenic atrophy) within 5-7 days

### UMN disease signs (thumb up)

- Normal to increased muscle tone (normotonia to hypertonia)
- Normal to increased reflexes (hyperreflexia)
- Spastic paresis to paralysis
- Slow (disuse) atrophy

**SHIFF-SHERRINGTON SYNDROME:** hyperextension of the forelimbs with lesions to the thoracic spinal cord. Neurons (border cells), located in the L<sub>1-4</sub> spinal cord, ascend to the forelimb centers to synapse on interneurons (Renshaw). These interneurons synapse on and inhibit extensor lower motor neurons in the cervical enlargement. This inhibition of the extensors coordinates walking movements between the limbs of quadrupeds. Lesions to this pathway remove inhibition, so the forelimbs are slightly hyperextended. Lower and upper motor neurons are still intact to the thoracic limb, therefore, this is neither an upper or lower motor neuron sign. This is the only time a spinal cord injury will show signs cranial to the point of the injury. It is usually a bad sign prognostically, indicating a serious lesion of the spinal cord. The hind limb would show UMN signs (activity goes up) when Shiff-Sherington signs are seen in the forelimb. This often causes confusion in localization.

**UMN/ LMN - localization of lesions:** Knowing the difference between LMN and UMN signs can be used to localize a spinal cord lesion. LMN signs always take preference to UMN signs clinically. If both are affected, the signs will be LMN because UMN signs require intact LMNs.

### Example 1:


Signs: flaccid paralysis, absent reflexes, decreased tone and rapid atrophy to the pelvic limbs with normal thoracic limb.

Indicates a L<sub>4</sub>-S<sub>1</sub> spinal cord lesion (Area 4) (LMN signs to pelvic limbs).

### Example 2:

Signs: spastic paresis, increased reflexes and tone to the left pelvic limb and flaccid paralysis, increased reflexes and tone to the left thoracic limb.





**Fig. NS - 2 - Localization - UMN/LMN**

Indicates a unilateral C<sub>6-T<sub>2</sub></sub> spinal cord lesion (Area 2) on the left (LMN signs to the left thoracic limb and UMN signs to left pelvic limb).

## Example 3:

Signs: spastic paresis, increased reflexes and increased tone to all limbs.

Indicates a C<sub>1-5</sub> spinal cord lesion (Area 1) (UMN signs to all limbs).

## Example 4:

Signs: spastic paresis, increased reflexes and increased tone to the pelvic limbs, and normal thoracic limbs.

Indicates a unilateral T<sub>3-L<sub>3</sub></sub> spinal cord lesion (Area 3) on the left (LMN signs to the left thoracic limb and UMN signs to left pelvic limb).

## Example 5

Signs: hyperextended thoracic limb and spastic paralysis, increased

reflexes and tone in the pelvic limbs.

Indicates: a T<sub>3-L<sub>3</sub></sub> spinal cord lesion (Area 3) (UMN signs in pelvic limbs and a Shiff-Sherington sign in the thoracic limbs).

**Table 1 LESSION - LMN/UMN - LOCALIZATION**

**Lesion 1 – transect spinal cord from C<sub>1-5</sub>:**

- No LMN signs to either limb
- UMN signs & proprioceptive deficits to all limbs

**Lesion 2 – in cervical enlargement, C<sub>6-T<sub>2</sub></sub>:**

- LMN to thoracic limb
- UMN signs & proprioceptive deficits to pelvic limbs

**Lesion 3 – damage in T<sub>3-L<sub>3</sub></sub>:**

- No effect on thoracic limb (+/- Shiff-Sherington)
- UMN signs & proprioceptive deficits to pelvic limb

**Lesion 4 – damage to L<sub>4-S<sub>1</sub></sub>**

- No effect on thoracic limb
- LMN to pelvic limb, even if UMN are also damaged



## SENSORY




Fig. NS- 3 - Cutaneous trunci reflex (schematic)

**OBSERVATION of PAIN:** may be diagnostic. Sensory loss to a dermatome (which would occur with damage to a peripheral nerve along with LMN damage) can be used to localize lesions. Assessment of pain is in three parts: (1) Presence or location of pain, (2) Perception of superficial pain, and (3) Perception of deep pain. History and palpation will help locate pain. Lesions to the nervous system will cause decrease in pain distal to the lesion. Therefore, palpate from distal to proximal. Palpate just strong enough to elicit pain. Palpate the limbs and the trunk in a systematic manner.

- Limbs - palpate from distal to proximal.
- Trunk - palpate.
- Vertebral pain - palpate.
  - Lumbosacral region - press over the lumbosacral junction, or extend the hip to stretch the ischiatic nerve.
- Neck - flex and extend the neck carefully.

**Ascending sensory tracts:** carry sensation up the spinal cord to higher centers. Clinically, the loss of these sensations (superficial pain, deep pain and proprioception) can help localize lesions in spinal cord compression and provide prognostic indicators.

**Superficial pain sensory fibers:** These are lost about the same time as motor functions. Superficial pain perception is evaluated by using a gentle pinch of a pair of hemostats to the skin. If superficial pain is perceived, deep pain will also be perceived. Perception causes a behavioral change such as looking toward the stimulus or attempts to bite. A withdrawal of the structure (limb) from the stimulus is a reflex, it DOES NOT require perception.

**Deep pain:** the first sensory fibers to show signs and the last to disappear (first to show, last to go). Loss of deep pain is a bad prognostic sign. Deep pain is evaluated when superficial pain is absent. Increase the pressure of the superficial pain pinch and watch for a behavioral change (attempt to bite).

**Proprioception damage:** loss of proprioception is usually the first sign in spinal cord compression. Therefore, testing proprioception will indicate problems before other signs (UMN and LMN) are present. Ataxia may be noticed which is different from cerebellar ataxia. The animal doesn't know the position of its limbs, thus, can't adjust them. The animal may stand with its distal limbs spread (base wide stance), may knuckle over, and may delay initiation of movement. For localization, losses of proprioception are interpreted the same as LMN/UMN signs (i.e., loss of proprioception in the thoracic limb indicates a lesion in the spinal cord segment C<sub>5</sub>-T<sub>1</sub> or cranial to C<sub>5</sub>).

**Cutaneous trunci reflex or panniculus reflex:** a normal reflex where a stimulus (e.g., a fly) to the lateral trunk causes the cutaneous trunci muscle to twitch. Sensory fibers extend from their dermatomes (bands of skin sensation) obliquely craniodorsally to synapse in the thoracolumbar spinal cord segments. Ascending sensory tracts extend up the spinal cord to the cell body of the lateral thoracic nerve in spinal cord segment C<sub>8</sub>. The lateral thoracic nerve supplies motor innervation to the cutaneous trunci muscle. The dermatomes are one or two vertebrae caudal to the point of origin of the sensory nerves. If a panniculus response is absent caudally and then appears cranial to a specific point (e.g., transverse plane through L<sub>1</sub>) the lesion is in the spinal cord up to two vertebrae cranially (at T<sub>12</sub>-T<sub>13</sub>). This response is not found over the sacral or cervical areas.

**Hyperesthesia:** abnormal increase in sensitivity. Lesions to a spinal cord segment will cause a focal hyperesthesia to the dermatome supplied.

**Diffuse or multifocal pain:** often due to inflammation.

**Focal pain:** often due to compression of the spinal cord or nerve root.



# PERIPHERAL NERVES

**PERIPHERAL NERVE LESIONS:** problems localized to only one limb (monoparesis) by LMN signs. The problem is in the specific nerve roots, nerve or group of nerves or muscles they innervate. These can be evaluated by knowing the motor and the cutaneous innervation of the limbs, then mapping the deficits. Damage to individual nerves will result in little gait abnormalities, except in the case of the radial, femoral, ischiatic, or peroneal nerves. All peripheral nerve damage will show loss of cutaneous sensation (analgesia) to the dermatomes they innervate.

## BRACHIAL PLEXUS

**Suprascapular nerve damage ( $C_{6,7}$ ):** causes marked atrophy to the supraspinatus and infraspinatus muscles. This is called "sweeney" in horses. Before atrophy, this will cause lateral slipping of the shoulder in the horse.

**Musculocutaneous nerve damage ( $C_{6,8}$ ):** analgesia to medial surface of the forelimb and inability to flex the elbow.

**Radial nerve damage ( $C_6-T_2$ ):** depending on the level of damage, will show different muscular deficits. If above the innervation of the triceps brachii muscle, the animal will not be able to bear weight on the limb because it can't extend the elbow, and the paw will knuckle over. Damage distal to the triceps brachii will result in knuckling over because the paw can't be extended. Analgesia will be to the dorsal surface of the paw and forelimb in the dog. In horses, the radial nerve only reaches the carpus.

**Median nerve damage ( $C_8-T_2$ ):** will have little gait abnormalities, maybe a little sinking of the carpus and metacarpophalangeal joints. There will be partial loss of analgesia to the palmar surface of the paw.

**Ulnar nerve damage ( $C_8-T_2$ ):** analgesia to the lateral digit (V) of the paw.

**Sympathetic nerve damage:** although not part of the brachial plexus, their preganglionic fibers travel over the roots of the brachial plexus and can be damaged with the brachial plexus nerves. Signs are miosis, ptosis, and enophthalmia (Homer's syndrome).

**Avulsions of the roots of the brachial plexus:** the pulling off of the spinal roots from the spinal cord due to trauma (hit by car). Signs exhibited will depend on the number of roots involved. If all roots of  $C_6-T_1$  are involved, the limb will be paralyzed and drag on the ground, along with loss of sensation distal to the elbow.

## LUMBOSACRAL PLEXUS:

**Obturator nerve damage ( $L_{4,6}$ ):** will cause lateral slipping on a slick surface due to loss of adductor muscle control.

**Femoral nerve damage ( $L_{3,6}$ ):** will result in severe gait deficits; the animal can't bear weight on the pelvic limb because it can't extend the stifle. Analgesia occurs on the medial surface of the limb.

**Ischiatic nerve damage ( $L_5-S_2$ ):** results in knuckling over (peroneal nerve), but has the ability to bear weight (intact femoral nerve). There will be loss of sensation below the stifle, except on the medial side (saphenous nerve).

**Peroneal damage ( $L_5-S_2$ ):** results in knuckling over due to inability to extend the digits. Cutaneous sensation is lost to the dorsal surface of the leg and pes.

**Tibial nerve damage ( $L_5-S_2$ ):** results in dropping of the hock and analgesia to the plantar side of the paw.

**SYSTEMIC or MULTIFOCAL NERVOUS SYSTEM DISEASE:** do not have signs consistent with a single focal lesion; have diffuse or multifocal signs (e.g., inflammation, nutritional, toxic, or metabolic diseases). Inflammation usually causes diffuse or multifocal pain.

Table 2 - Peripheral nerves - thoracic limb

Nerve & spinal cord segment		Clinical sign of damage
Suprascapular	$C_{6,7}$	Motor - atrophy of supraspinatus and infraspinatus muscles
Musculocutaneous	$C_{6,8}$	Sensory loss - med. side of limb Motor - inability to flex elbow
Radial	$C_6-T_2$	Motor - High - inability to bear weight Low - knuckling over Sensory loss - dors. forelimb (only to carpus in horse)
Median	$C_8-T_3$	Motor - little effect Sensory loss, partial - palmar paw
Ulnar	$C_8-T_3$	Motor - little affect Sensory - analgesia fifth digit
Sympathetic	$C_8-T_3$	Miosis, ptosis & enophthalmia

Table 3 - Peripheral nerves - pelvic limb

Nerve & spinal cord segment		Clinical sign of damage
Obturator	$L_{3,6}$	Motor - lateral slipping
Femoral	$L_{3,6}$	Motor - inability to bear weight Sensory loss - med. limb (saphenous)
Sciatic	$L_5-S_2$	Motor - nuckling over Sensory loss - all leg and pes, except med. surface
Peroneal	$L_5-S_2$	Motor - knuckling over Sensory loss - dorsal leg & pes
Tibial	$L_5-S_2$	Motor - little affect Sensory loss - plantar leg and pes



# BRAIN

**Lesions of the brain stem** (midbrain, pons and medulla oblongata): by affecting the reticular activation system, will decrease degrees of consciousness from depression to stupor to coma. Deficits in cranial nerves III to XII, arising from the brain stem may indicate brain stem lesions. Walking motion reflexes are generated in centers caudal to the midbrain. Higher centers initiate the motion through descending motor tracts that cross over in the midbrain. Therefore, the midbrain is a clinical localization point for most motor tract systems. Lesions rostral to the midbrain (cerebro-diencephalic disorders) affect the contralateral (opposite) side of the body with proprioceptive deficits, but a normal gait. Lesions caudal to the midbrain (brain stem and spinal cord) cause ipsilateral (same side) proprioceptive deficits with an abnormal gait. An animal with a normal gait and proprioceptive deficits on both sides has a lesion in the midbrain.

**Lesion to the vestibular system:** affects the ability to control posture in relationship to gravity; and eye movements in relationship to head movements. Head tilt, nystagmus, ataxia, possibly circling, and strabismus are all signs of vestibular disease. Central vestibular disease will also affect other motor and sensory centers in the brain

stem, resulting in postural deficits (proprioception) and paresis (UMN). Depression is also seen with central lesions. Peripheral vestibular disease will not produce UMN signs (paresis). Peripheral lesions also don't affect proprioceptive fibers, but the postural reactions appear abnormal (ataxic) because of loss of balance.

**Cerebellar lesions:** cause incoordination of movements (ataxia), intention tremors, and abnormal movements of the head and body. Lesions can also cause signs of vestibular disease, including head tilt and nystagmus.

**Cerebral lesions** to the cerebral hemispheres or basal nuclei: may produce alterations in behavior and seizures. A normal gait (the walking centers are caudal to the midbrain) with abnormal postural reactions may be seen because proprioceptive fibers pass to the cerebral cortex. Damage to the occipital (vision) lobe will result in loss of vision, with normal pupillary responses.

**Lesions to the thalamus:** functionally related to the cerebrum, showing similar signs. Autonomic and endocrine abnormalities (polyuria, polydipsia, altered sleep patterns) are also possible.

**Table 4 - Lesions of brain - signs**

<b>Brain stem:</b>	<p>Proprioceptive deficits with a normal gait indicate a lesion in or rostral to the midbrain</p> <p>Proprioceptive deficits with abnormal gait indicate a lesion caudal to the midbrain</p> <ul style="list-style-type: none"> <li>• Proprioceptive deficits (unilateral) and normal gait, a lesion rostral to midbrain on contralateral side</li> <li>• Proprioceptive deficits (bilateral) and normal gait, a lesion probably in the midbrain</li> <li>• Proprioceptive deficits (unilateral) and abnormal gait, a lesion caud. to the midbrain on ipsilateral side</li> </ul> <p>• Decreased levels of consciousness (depression, stupor, coma)</p> <p>• Deficits in cranial nerves III - XII</p>
<b>Vestibular system:</b>	<p>• Head tilt, nystagmus, asymmetric ataxia with possibly circling, and strabismus</p> <p>Central vestibular disease</p> <ul style="list-style-type: none"> <li>• Postural deficits (proprioception)</li> <li>• Paresis (UMN)</li> <li>• Depression</li> </ul> <p>Peripheral disease</p> <ul style="list-style-type: none"> <li>• No paresis</li> <li>• Postural deficits (balance)</li> <li>• No depression</li> </ul>
<b>Cerebellum:</b>	<ul style="list-style-type: none"> <li>• Incoordination of movements (ataxia), tremors, abnormal movements of the head</li> <li>• Vestibular disease signs, including head tilt and nystagmus</li> </ul>
<b>Cerebrum:</b>	<ul style="list-style-type: none"> <li>• Alterations in behavior</li> <li>• Seizures</li> <li>• Normal gait with abnormal postural reactions (proprioception loss)</li> <li>• Loss of vision (occipital lobe) with normal pupillary responses</li> </ul>
<b>Diencephalon:</b>	<ul style="list-style-type: none"> <li>• Cerebral signs</li> <li>• Autonomic and endocrine abnormalities (polyuria, polydipsia, altered sleep patterns)</li> </ul>



## NEUROLOGIC TESTS

We discussed the segmental organization of the nervous system, the general functions of each segment, and the signs that lesions produce at each segment. Now we will discuss ways to evaluate different clinical signs.

**POSTURAL REACTIONS:** although not very specific, they are very sensitive indicators of abnormalities. If an animal doesn't have a profound gait deficit or obvious paralysis or paresis, postural reactions can establish the presence of slight paresis (weakness) or a proprioceptive deficit. They do not localize the problem. All postural reactions should be done on carpet or grass to keep the animal from slipping. Some of these reactions don't belong together physiologically speaking, but are convenient to do at the same time.

**Screening postural reactions:** hopping and proprioceptive positioning are more sensitive than other postural reactions. If they are normal, all other postural reactions will be normal. If they are abnormal, checking other reactions may be helpful.

**Proprioceptive positioning:** tests proprioceptive (sensory) information passing up the spinal cord to the cerebral cortex. Place the foot knuckled over (the dorsal surface of the paw down) on the floor. The animal should immediately reposition the foot to the normal position. To avoid touching the limb of small animals, the animal's paw can be placed on a folded piece of paper. Hold the animal's head up so they can't see its foot, and slide the paper laterally. The animal should immediately replace the limb properly. Proprioception tests are extremely sensitive tests, especially to evaluate the integrity of CNS proprioceptive tracts. If there is a consistent deficit with this test, there is a nervous system problem.

- A normal gait and proprioceptive loss indicates a lesion rostral to the midbrain; it can be in the sensory cortex.
- Proprioception is the first thing lost in spinal cord compression.




Fig. NA- 4 - Proprioceptive positioning

**Hopping reaction:** evaluates motor function, proprioception (both conscious and unconscious), and cerebellar function. Thus, although very sensitive, it doesn't localize a lesion. Suspend the dog (arm under belly) and allow one limb to touch the ground. Force weight on the supporting limb to check for weakness, while supporting the chin. Hop the animal forward and laterally. Do this

to all four limbs, looking for asymmetry between any limb and the other three limbs. With a large animal, lift one limb and push so the animal has to hop on the other limb, or push it laterally while standing and walking so it has to step laterally. Pulling the tail laterally can also be used to test the rear limb. This provides information about motor, sensory or cerebellar circuitry.

- Weakness may result in collapse after just standing or after one or two hops.
- Proprioceptive lesion: results in extremely delayed initiation of the hop.
- Cerebellar lesion: results in an exaggerated step when they hop. This is because the main cerebellar output is inhibitory.




Fig. NA - 5 - Hopping reaction

If the animal has a normal gait and proprioceptive loss is indicated by the hopping reflex, the lesion is rostral to the midbrain. If there is an abnormal gait and proprioceptive loss, then the lesion is in or caudal to the midbrain. An animal that shows deficits in the right forelimb hopping reaction may have a lesion on the left side, rostral to the midbrain; or a lesion on the right side, caudal to the midbrain.

These two screening postural reactions, hopping and proprioceptions, are the most sensitive tests. If normal, the other postural reactions will be normal. If abnormal, then the following postural tests can be performed.

**Extensor postural thrust:** holding the animal up by its armpits, lower the hindlimbs to the floor. Normal animals will extend the rearlimbs and move them caudally. Pressing down may cause collapse in mild hindlimb paresis (paraparesis).

- Weakness, may result in collapse.
- Proprioceptive lesions - result in extremely delayed initiation of the caudal movement.



## NEUROLOGIC TESTS




Fig. NA - 6 - Wheelbarrowing

**Wheelbarrowing:** tests the integration of the forelimb walking mechanism. Suspend the animal on its forelimbs by elevating the abdomen. Push on each shoulder to evaluate strength. Walk the animal forward. The animal should have a normal, alternating gait. Wheelbarrowing tests motor, proprioception and cerebellar functions. Problems may be central or peripheral. Wheelbarrowing should be done with the animal sighted and unsighted (head elevated or blindfolded). Vision may compensate for placing a limb.

- Strength
- Incoordination with hypermetric steps seen in cerebellar disease.
- Abnormal or delayed limb placement is typical of proprioceptive problems.

- **Wobbler syndrome:** common in Thoroughbred horses, Great Danes, and Dobermans. It is a cervical vertebral column abnormality, which ultimately results in minimal to severe compression on the spinal cord. If minimal, there may be a partial loss of sensory and motor function. Severe deficits in the hindlimb, but nothing obvious in the forelimb, may be seen even though the white matter tracts to the forelimb are also effected. If a young Great Dane comes in with rear limb deficits, the first rule out is "wobbler" due to breed predilection. Wheelbarrowing an animal blindfolded will bring out subtle deficits (forelimb) that sighted wheelbarrowing doesn't. If a dog with hind limb deficits stumbles on its thoracic limbs when blind folded, it is tetraplegic, not paraplegic. To block vision, some people elevate the head, but never elevate the head if a neck lesion is suspected. Two human eye patches, a surgical mask, or even your hand will do nicely.

**Hemistanding - hemiwalking:** done if weakness on one side (hemiparesis) is found with other postural tests. Support one side of the body and both limbs on that side, while the animal stands and walks on the opposite limbs. Then alternate to test both sides of the body. A normal dog should be able to stand this way for 3 minutes (but they usually get bored in 20 seconds). Have an assistant press down on the hind limb and then the forelimb to assess strength. Then move it forward to see an alternating

hopping gait (the foreleg jumps forward and takes position and then the rear limb jumps forward and takes position).

- Delays or improper placement may indicate a proprioceptive lesions.
- Stumbling or collapse may indicate a motor lesion.
- A cerebellar lesion may be indicated by a hyperexaggerated gait.

**PLACING REACTIONS:** Placing reactions and postural reactions test for different things. They are placed together because they are convenient to perform together. Placing reactions are highly specific tests, unlike postural reactions. The two types of placing reactions are tactile and visual.

**Visual placing reactions:** sensitive evaluations of visual deficits, not proprioception. A sighted dog moved toward a table will anticipate it by reaching out. A dog held in a vulnerable position, not cuddled, will be more likely try to reach for the table. Do this on all four limbs.

- Tests the vision pathway

**Tactile placing:** belongs in spinal cord evaluation because it specifically tests for sensation. Hold the dog's head up so it can't




Fig. NA - 7 - Tactile placing

see the table, and touch the dorsal surface of its forepaw to a table edge. The animal should place its paw on the table. This tests the sensory branch of the radial nerve (specific test). Touching the lateral side of the fifth digit tests the ulnar nerve. It is harder to test on the hindlimbs, because when their dorsal surface touches, the animal will reach with its front limbs.

- Tests specific sensory nerves

**RIGHTING REFLEX:** tests the vestibular apparatus. Normal connections between the vestibular apparatus by way of the eighth cranial nerve (vestibulocochlear) to the spinal cord are required. An animal placed on its side will usually try to maintain at least sternal recumbency. This is a specific test for the eighth cranial nerve, not proprioception.

- Tests vestibular pathway



## NEUROLOGIC TESTS




Fig. NA - 8 - Myotatic (stretch) reflex

**SPINAL REFLEXES:** controlled by reflex arcs, consisting of a sensory neuron, usually at least one interneuron, and a motor neuron (LMN). They receive input from higher centers by way of UMNs and send sensory information up the spinal cord to higher centers. They do not require higher center input and will be present even if the spinal cord has been severed cranial to the reflex. The animal is put in lateral recumbency to evaluate the spinal reflexes.

### Myotatic or stretch reflex

• **Patellar, quadriceps or knee jerk reflex:** A stretch reflex that tests the femoral nerve, its nerve roots, and spinal cord segment L<sub>4-6</sub>. With the dog in lateral recumbency, the stifle is supported with the tarsus slightly flexed. The patellar ligament is struck with an instrument (plexor). There should be a brisk contraction of the quadriceps muscle, causing extension of the stifle. Taping the patellar ligament stretches the muscle spindle. The sensory nerve passes to the spinal cord and synapses directly on a motor nerve (without an interneuron) which causes the muscle to contract.

- Exaggerated with or without clonus - UMN disease cranial to L<sub>4</sub>
- Absent or depressed - LMN disease, can be due to disruption anywhere in the reflex arch, sensory fiber, motor fiber, spinal cord

segment or whole peripheral nerve.

- Normal - intact reflex arc, including its spinal cord segment. This doesn't say that the spinal cord (UMNs) is intact cranial to this segment.


• **Extensor carpi radialis reflex:** a stretch reflex that tests the radial nerve, its roots, and spinal cord segments C<sub>7</sub>-T<sub>2</sub>. With the animal in lateral recumbency, the elbow is supported with the elbow and carpus flexed. Tap the extensor muscles just distal to the elbow. This will result in extension of the carpus. Less reliable than the quadriceps reflex, it is the most reliable myotatic reflex of the frontlimb.

- Exaggerated - UMN disease cranial to C<sub>7</sub>
- Absent or depressed - LMN disease, can be due to disruption anywhere in the reflex arch, sensory fiber, motor fiber, spinal cord segment or whole peripheral nerve.
- Normal - intact reflex arc, including its spinal cord segment. There may still be UMN disease cranial to C<sub>7</sub>.

Other stretch reflexes are the cranial tibial, gastrocnemius, triceps and biceps reflexes. The books say these are harder to elicit and more difficult to assess. The withdrawal (flexor) reflexes that follow are easier to evaluate than these.



## NEUROLOGIC TESTS



**Fig. NA - 8 - Flexor and crossed extensor reflexes**

Modified from Kip Carter's illustration in *Veterinary Neurology*, Oliver, Horlein, Mayhew; W.B. Saunders Co., 1987

**Withdrawal (flexor, pedal) reflex and pain perception:** with the animal in lateral recumbency and the limb extended, pinch a toe of the hindlimb first and then the forelimb. A normal response is flexion of the joints, with withdrawal of the toe from the stimulus. This works by reflex arcs. The stimulus is cutaneous or deep pain, depending on the force of the pinch. Use the minimum amount of force to elicit the reflex. Sensory fibers synapse on interneurons in the spinal cord segments. These synapse on motor neurons to the flexor muscle to cause contraction, thus, flexion of the joints of the limb. Simultaneously assess if the pain reaches the cerebrum by noting behavioral changes (biting, looking towards stimulus). This assesses:

- Normal withdrawal - intact peripheral nerve and spinal cord segment
  - Hindlimb: L<sub>6</sub>-S<sub>2</sub>
  - Forelimb: C<sub>7</sub>-T<sub>2</sub>
- Depressed or absent - disruption of the reflex arc
  - Unilateral: peripheral nerve lesion
  - Bilateral: spinal cord lesion

• Normal with perception: normal spinal cord segments and spinal cord.

• Withdrawal reflexes don't require the animal to feel the stimulus, they will be elicited with UMN disease and may even be exaggerated. They are decreased in LMN disease or with a sensory nerve lesion.

**Crossed extensor reflex:** normal in the walking animals; but abnormal in the recumbent animal. During walking, when one limb is picked up (flexed) the other limb extends to bear the added weight. In the recumbent animal, this reflex is not needed and is inhibited by higher centers through UMNs. Pinch a paw to elicit a withdrawal (flexor) reflex. Extension of any other limb is abnormal and indicates blocking of descending, inhibitory pathways. A positive result:

- Indicates a chronic, potentially severe spinal cord injury
  - Unilateral crossed extensor reflex, lateralizing the lesion to the same side.



## CRANIAL NERVE EXAM

**Extensor thrust reflex:** gently spread the digits with your finger. Normally this will cause extension of the limb. This is hard to assess, but may be exaggerated in UMN disease.

**LMNs.** Pressing on the limb will slightly increase the tone in the limb due to the pad pressure reflex. After a moment of continual pressure, the limb collapses abruptly. This is a indication of upper motor neuron syndrome.




Fig. NA - 9 - Perineal reflex

**Perineal reflex:** pain stimulus to the perineal region will cause contraction of the anal sphincter and flexion of the tail. The perineal region and anal sphincter are innervated by the sacral spinal cord segments and the pudendal nerve, the same segments innervating the urinary bladder. The tail is innervated by the caudal nerves. Assesses:


- Sacral spinal cord and cauda equina. Good for bladder and sphincter problems.

**Extensor toe (Babinski) sign (pes sign):** an abnormal reflex of the pes (hindpaw). Scratch, with a blunt instrument, the plantar aspect of the pes from hock to toe. No reaction or withdrawal are normal reactions. Fanning the toes or extending the limb is abnormal. This reflex can also be obtained on the manus. Evaluation:

- Indicates a chronic and potentially severe spinal cord lesion.

**Cutaneous trunci reflex or panniculus reflex (see pg. 566):** is a normal reflex to twitch the skin. Sensory fibers extend from their dermatomes (bands of skin sensation) obliquely craniodorsally to synapse in spinal cord segments T<sub>8</sub>-L<sub>4</sub>. Ascending sensory tracts extend up the cord to the cell body of the lateral thoracic nerve in spinal cord segment C<sub>8</sub>. The thoracic nerve supplies motor innervation to the cutaneous trunci muscle. The dermatomes are one or two vertebrae caudal to the point of origin of the sensory nerves. If a panniculus response is present caudally and then disappears cranial to a specific point the lesion is in the spinal cord two vertebrae cranially.

**CLASP-KNIFE RESPONSE - UMN:** a delayed, abrupt collapse of a hyperextended limb. An animal with upper motor nerve (UMN) problems will have an extended limb due to release of the



Cutaneous trunci reflex - see pg. 566



## CRANIAL NERVE EXAM

**OLFACTORY NERVE, Cn I:** carries the special sense of smell. Olfactory receptors, located in the neuroepithelium of the nasal mucosa, pass through the cribriform plate to synapse in the olfactory bulb. Second order neurons then travel down the lateral olfactory stria to the pyriform lobe. Olfaction is tied into the limbic (emotional) system.

To evoke a response use a volatile non-irritating substance. Proper responses would be sniffing, licking, interest if pleasant smell; wincing, backing away from unpleasant ones. Irritating substances (e.g. alcohol) to the nasal cavity will evoke a response which may look like smelling. Food is excellent if not in a recognizable container or not presented with a recognizable approach. Bring food from a remote source on a tongue depressor. Destruction of any part of the pathway will cause a problem with smell. Nasal tumors may affect smell, but this is insignificant to the tumor. Clinically smell is not very significant, except in cats which depend heavily on smells and will show various bouts of anorexia if they can't smell.

**OPTIC NERVE, Cn II:** special sense of sight. It has no motor component. Light striking the retina passes over the optic nerves to the optic chiasm, then on to the optic tracts to synapse in the lateral geniculate nuclei. Neurons then pass over the optic radiations to the occipital lobe for visual interpretation.

Damage can affect any part of the pathway. Loss of vision can be due to ocular diseases, nervous system diseases, or both. Corneal diseases will affect vision by clouding the lens. Diseases of the lens, e.g., cataracts, affect vision. The retina can undergo atrophy. More than Cn II is necessary for proper vision (accommodation, pupil size (CN III), blinking the eye, tear film (CN VII), conjugation of eye movement (CN III, IV, VI). However, if an image can't be formed (CN II), the animal is blind.


In the dog, 75% of the optic fibers of one optic nerve cross over to the opposite (contralateral) optic tract and 25% stay in the ipsilateral optic tract. In cats there is a 65% cross over. Therefore, the optic tracts carry mainly vision from the opposite eye to the occipital lobe. Clinically, animals behave as if all fibers cross over. If the right occipital lobe is damaged, the animal will appear blind in the left eye.

**History:** animals can be fairly blind before many owners realize it. Stumbling on stair cases or poor night vision is often the first sign of visual degeneration. Visually observe, from a distance, the animal at rest and moving while taking the history. Obstacle courses: using objects from your clinic. A dimmer switch may be helpful to evaluate day and night visions.

**Visual placing reaction:** evaluate vision although it is placed with postural reactions for convenience (see placing reactions).

**Menace response (Cn II - Cn VII):** blinking in response to potentially harmful objects advancing toward the eye. Make a threatening gesture toward the eye without windpuffs or noise. A positive response is blinking. For unknown reasons, absence of connection from the cerebellum abolishes the response. Since the

visual pathway, facial nerve (Cn VII), and cerebellum are all involved, this response doesn't localize the lesion. It is another sign for visual dysfunction, facial nerve problems, or cerebellar dysfunction. If blind, there will be no menace response.



**OCULOMOTOR NERVE, Cn III:** constricts the pupil in response to elevated light levels by innervation to the constrictor pupillae muscle. It also innervates some of the extrinsic muscles of the eye.

Cn II and Cn III are tied together and can be evaluated together by checking the menace response, size of the resting pupil and the palpebral light reflexes. First check for vision in each eye by the menace response or visual placing reaction. Then look at the resting pupils (without shining a light in them). Finally, check the pupillary light reflex. Practice drawing quick schematics by incorporating the visual pathways and pupillary light reflex pathways as done on the following pages. Draw an X through the structure affected. Using the schematic and Chart 5 (pg. 576) will help to characterize the lesion.


• **Pupillary light reflex:** used to monitor patients with head trauma, to determine the degree of trauma, to localize the lesion, and to monitor degradation or improvement of an animal. A rapid change from one format to another may warn of deleterious changes that require immediate intervention to reverse. The pupillary light reflex involves the central visual light pathway before the thalamus. Therefore, cerebral diencephalic disease will not abolish the reflex, but may alter it.

Shine a light onto the retina. Impulses pass over the optic nerve, the optic chiasm and optic tracts. Collaterals of the optic tract peel off at the rostral end of the midbrain to synapse on midbrain nuclei (pretectal nucleus). These neurons synapse ipsilateral or contralateral in the accessory oculomotor nuclei (parasympathetic nucleus, Edinger-Westphal). Whichever cross at the chiasm recross in the midbrain to end up affecting the same eye in which the light was shone. Preganglionic fibers travel in the oculomotor nerve (Cn III) to synapse in the ciliary ganglion. Postganglionic neurons innervate the constrictor pupillary muscle, constricting the pupil.

Light shone in a dog's left eye will cause more constriction in the left pupil (direct side) than in the right pupil (indirect or consensual), because 75% of the optic fibers cross twice to affect the same eye



## PUPILLARY LIGHT REFLEX



and 25% end up in the other eye. Therefore, the left pupil should constrict quicker, more efficiently, and to a greater degree than the right (dynamic contraction anisocoria). This is normal in dogs and cats. Direct and indirect pupillary reflexes are named for the eye in which the light is shone, not for the eye that responds. The **direct pupillary light reflex** constricts the pupil in which a light is shown. The **indirect pupillary light reflex** constricts the pupil in the opposite eye in which the light is shone.

**Sympathetic innervation to the iris:** arises from the hypothalamus and travels down the cervical spinal cord. The preganglionic fibers arise from the first three thoracic spinal cord segments. They travel through the sympathetic trunk and then the vagosympathetic trunk up the neck to synapse in the cranial cervical ganglion. Postganglionic fibers pass through the middle ear and then into the orbit to reach the pupil. These innervate the pupillary dilator muscle to dilate the pupil. Injury anywhere along this pathway will cause the pupil to be more constricted.



## PUPILLARY LIGHT REFLEX

Complete lesion <b>LEFT</b> side	Menace response / vision		Resting pupil		Pupillary light reflexes	
	Lt. eye	Rt. eye	Lt. eye	Rt. eye	Light in lt. eye	Light in rt. eye
Retina or optic nerve	Blind	N	Slightly dilated	N	No response	N*
Oculomotor	N	N	Dilated	N	Constrict rt.	Constrict rt.
Orbit (both CnII & CnIII)	Blind	N	Dilated	N	No response	Constrict rt.
Optic chiasm	Blind	Blind	Dilated	Dilated	No response	No response
Optic tract	N	Blind	N	Nor Slightly dilated	N*	N*
Parasympathetic nucleus (bilateral)	N	N	Dilated	Dilated	No response	No response
Sympathetic nerves	N	N	Constricted	N	N*	N*
Optic pathway past optic tract	N	Blind	N	N	N*	N*

\* N (normal) for the pupillary light reflexes is constriction of both eyes when the light is shone in the eye.

Modified from Oliver JE Jr and Lorenz MD: *Veterinary Neurology*. Philadelphia, W. B. Saunders co., 1987

Damage to the left retina or left optic nerve (prechiasmatic damage): Clinically, although not the same diseases, they have the same effect to the visual and pupillary pathways. When light is shone in the left eye, neither pupil will constrict because its pathway is blocked. Light in the right eye will cause both to constrict because crossover at the optic chiasm is not blocked. The menace response will be absent in the blind, left eye. The right eye will have sight and show a menace response. At rest, the left pupil will only be partially dilated because it is still getting indirect tone from light coming into the right eye. If the right eye is covered the dilation will become total.




Fig. NA - 12 - Lt. retina or optic n. damage




Fig. NA - 13 - Left oculomotor nerve (Cn III) damage

Left oculomotor nerve (Cn III) damage: light can get to accessory parasympathetic (ANS) nuclei and cross over can occur. Thus, the right pupil will constrict with light shone in either eye (direct and indirect response). Parasympathetic innervation is lost to the left eye so it will be unresponsive to light shone in either eye. The resting pupil will be totally dilated due to the loss all parasympathetic innervation. Both eyes have normal vision, thus, menace responses.



## PUPILLARY LIGHT REFLEX




Fig. NA - 14 - Left postorbital problem (abscess)

**Left postorbital problem (abscess):** affects both the optic and oculomotor nerves on that side. The right eye will be normal, except it will have no indirect pupillary response (light in the left eye). The left eye is blind (no menace response) with no oculomotor innervation (no pupillary response), therefore totally dilated. The only response will be the direct pupillary (on the right-normal-side).




Fig. NA - 15 - Total chiasmatic lesions

**Total chiasmatic lesions:** less common in animals than in humans. Vision and crossover are blocked so the eyes will not see (no menace response) and there will be no parasympathetic innervation (both pupils totally dilated). With subtotal lesions there will be progressive degrees of these signs.





Fig. NA - 16 - Left optic tract (postchiasmatic) lesions

**Left optic tract (postchiasmatic) lesions:** 75% of the fibers in the optic tract originate from the opposite side, animals with lesions postchiasmatically tend to act contralaterally (opposite side) blind although precise and careful evaluation may show vision


intact in the contralateral nasal field (temporal retina). Pupils will still constrict with light shown in either eye because the minor pathways are still present. The resting right pupil will be partially dilated (still has minor crossover) and covering the eye will not have an effect. The menace response will be absent in the blind right eye.

**Midbrain lesion effecting the parasympathetic nucleus:** rarely unilateral. It will not effect the visual pathway, thus, the animal can see. It will eliminate all parasympathetic innervation to both eyes, thus, the pupils will be dilated and have no pupillary responses.

Fig. NA - 17 - Midbrain lesion effecting parasympathetic nucleus



Parasympathetic nucleus



Sympathetic fibers

Fig. NA - 18 - Lesions of left sympathetic pathway

**Lesions of the left sympathetic pathway:** result in constriction of the resting pupil on the side affected. They will have no affect on vision or the pupils. The lesion can be anywhere along the sympathetic pathway, from the hypothalamus down the cervical spinal cord to segment T<sub>2</sub>, over the sympathetic and vagosympathetic trunks from the thorax to the cranial neck, or in the sympathetic postganglionic fibers passing through the middle ear and orbit.





Fig. NA - 19 - Left lesion to the visual pathway past the optic tracts

**Left lesion to the visual pathway past the optic tracts (lateral geniculate nucleus, optic radiations and primary visual [occipital] cortex):** the animal acts contralaterally blind (blind in right eye). There will be no effect on the pupillary light reflexes because the lesion is past this pathway. It may cause some pupillary constriction because of loss of occipital inhibition (UMN) to the parasympathetic nucleus.



## CRANIAL NERVES



**Fig. Na - 19 - Strabismus due to lesions of Cn III, Cn IV, and Cn VI.**

Modified from L. Sadlers illustration in *Veterinary Neurology*, Oliver, Hoerlein, Mayhew, W.B. Saunders, 1987

**OCULOMOTOR, TROCHLEAR and ABDUCENT, Cn III, IV and VI:** evaluated together because they all function to move the eye. The parasympathetic innervation of the oculomotor nerve (Cn III) was considered previously. To evaluate, observe the resting position of the eyes, test the ability to move the eyes by following something (throw a cotton ball across the animal's field of vision). Vestibular eye movements are evaluated by moving the head up or down and from side to side.

The oculomotor (Cn III) and trochlear (Cn IV) nerves originate from the midbrain; the abducent nerve (Cn VI) from the pons. All three leave the orbital cavity through the orbital fissure. The vestibular nuclei in the medulla connect to the nuclei of these nerves and voluntary motor centers by the medial longitudinal fasciculus (MLF) located in the center of the brain stem. Movement of the head stimulates the vestibular receptors of the inner ear which pass to the vestibular nuclei and through the MLF to the cell bodies of these three eye muscle nerves. This causes a normal nystagmus with the fast phase in the direction of the head movement.

**Strabismus:** abnormal position of the eyeball. Lesions to Cn III, IV and VI will cause strabismus.

- Oculomotor lesion - ventrolateral strabismus
- Abducent lesion - medial strabismus
- Trochlear paralysis - not detectable in round pupils. Dorsal side of the eyeball is rotated laterally.

**Voluntary following:** determine if an animal can see or not, visual placing is a better test. Throw a cotton ball across the visual

field and note if the animal follows it with his eyes. A cotton ball is easy to see and doesn't make noise when it lands. An object which makes noise could cause an auditory following, thus, a false positive visual following.

Nystagmus at rest is always abnormal and is usually due to a vestibular system problem.

**TRIGEMINAL NERVE, Cn V:** three main divisions - the ophthalmic, maxillary, and mandibular - which are all sensory. The mandibular division is also motor to the muscles of mastication.

Pinching or touching the face with a hemostat will test for sensation. Look for a reaction. Use a tissue forceps if you can't get a reaction from a light touch. The last resort is scarification of the nasal mucosa (very painful). Test all three branches - ophthalmic, the medial canthus of the eye; maxillary, the lateral canthus, maxillary region or nasal mucosa; and mandibular, the chin.

Palpating the muscles of mastication (temporalis, masseter and digastricus muscles) for atrophy and manipulating the jaw for tone tests the motor division of the mandibular nerve. These muscles are massive and paralysis results in significant atrophy and loss of mass. Whereas, in facial nerve paralysis, there is no loss of mass in the thin muscles of facial expression, just facial deviation.


The sensory neurons are located in the trigeminal ganglion in the cranial cavity. Their fibers enter the pons. The motor nucleus of Cn V is located in the pons. Motor fibers project down to the spine




# CRANIAL NERVES

and up to the facial nucleus for the corneal and palpebral reflexes.

**Corneal and palpebral reflexes:** used clinically to evaluate the depth of anesthesia.



**Palpebral reflex:** a Cn V-VII reflex (trigeminal - facial nerves). Touching the eyelid sends sensory information over the trigeminal nerve (ophthalmic nerve of the maxillary division) to synapse with the facial nerve in the brain stem. Motor fibers of the facial (auriculopalpebral) nerve cause the obicularis oculi muscle to contract (blink). Blinking before the eyelids are touched is a menace response, therefore, repeat a number of times for a positive response. This reflex is used to evaluate depth of anesthesia; especially when an animal is becoming too light.




**Corneal reflex:** Cn V - VI reflex (trigeminal - abducent): touch only the cornea to stimulate the maxillary nerve (long ciliary nerve of the ophthalmic division). Retraction of the globe is due to connections to Cn VI (abducent) which innervates the retractor bulbi muscle. Blinking will also occur and is partly due to a menace response. Look for retraction of the globe. A corneal reflex is abolished at a deeper stage of anesthesia than the palpebral reflex. Therefore, it is a danger signal for an animal getting too deep in anesthesia.

**"Dropped jaw" (idiopathic trigeminal neuropathy):** a common, acute problem caused by bilateral disease of the mandibular

division. This happens without any other deficiencies and is usually self limiting; most animals return to normal in 21 days. The client usually thinks the animal has a broken jaw. The main concern is hydration since the animal has difficulty swallowing with its mouth open.

- Damage to one of the divisions past their separation into three branches will cause sensory loss to the area innervated.
- Damage proximal to the separation will cause loss of sensation to the face and loss of the palpebral and corneal reflexes.
- Unilateral disease of the mandibular division will initially result in deviation of the jaw to the side of the lesion. With atrophy (chronic) of the pterygoid muscle, it will deviate away from the side of the lesion.
- Brain stem nuclear damage can happen to either or both of the sensory or motor nuclei, resulting in sensory or motor loss or both. There should be signs of other brain stem damage.

**FACIAL NERVE, Cn VII:** has many different functions, motor to the muscles of facial expression, taste, lacrimal and salivary innervation. Taste has little clinical significance. Atrophy of the muscles of facial expression isn't noticeable, but results in deviations and deficits of facial reflexes.



The facial and vestibulocochlear nerves (Cnn VII & Cn VIII) travel from the brain together through the internal acoustic meatus. Then Cn VII leaves Cn VIII and crosses the middle ear cavity. Therefore, an ear infection can cause severe facial nerve problems. The facial nerve leaves the skull through the stylomastoid foramen. The branches of the facial nerve innervate the muscles of facial expression. The auriculopalpebral branch innervates the obicularis oculi muscle to close the eyelids. The ventral and dorsal buccal branches cross the masseter muscle superficially. Autonomic fibers leave the facial nerve internally and come out the orbital fissure to innervate the lacrimal gland.



## CRANIAL NERVES

• Peripheral lesions distal to the stylomastoid foramen result in paralysis to the area supplied. They do not affect lacrimation.

– Paralysis of the auriculopalpebral branch, thus, the obicularis oculi muscle, causes widening of the palpebral fissure in small animals and ptosis (bulging eye) in large animals and some dogs (Pekinese).

– Buccal branches: paralysis would result in deviations of the face (drooping lip or ear and pulling of the nose to the normal side. Chronically, it will result in deviation towards the lesion from fibrous atrophy).

• Inner ear infections can damage all the branches, resulting in facial deviations, loss of lacrimation and salivary function, and taste. This is often accompanied by vestibular signs (close proximity of Cn VIII) and Horner's syndrome (if the sympathetic nerves are affected).

• A lesion in the cranial cavity between the brain and the internal acoustic meatus will affect all branches of the facial nerve. This is usually accompanied by vestibular signs (Cn VIII), but not Horner's syndrome.

• Brain stem damage to the facial nerve affects all or some of the components, depending on the size of the lesion. It is accompanied by other brain stem signs (paresis, proprioceptive deficits, alteration of level of consciousness, and other cranial nerve deficits).

**Buccal nerve damage** (peripheral) is common in horses when the horse's head is left on an unpadded surface during surgery. (The buccal nerve in the horse is located under the buckle of the halter.)

**Palpebral nerve damage:** the animal can't close the eyelids, resulting in secondary exposure keratitis.

**Lacrimal deficiency:** very serious due to drying of the cornea.

**Salivation problems:** compensation from glands on the opposite side and by the glands on both side innervated by the glossopharyngeal nerve.

**Menace response:** gives you information on the facial and optic nerves. It is better for Cn II.

**Palpebral reflexes:** Cn V - VII reflex, response to palpebral touch, causing blinking.


**Trigeminal facial reflex:** facial movements when touching the face are mediated by the trigeminal nerve (sensory) and the facial nerve (motor).

**Shirmer tear test:** filter paper put in the corner of eye for a period of time to wick tears. The amount of wick is compared to a standard scale to measure relative amount of lacrimation.

**VESTIBULOCOCHLEAR NERVE:** has two divisions, the cochlear dealing with hearing (audition) and the vestibular dealing with movement of the head in relation to gravity and movement.

**Cochlear division:** deafness must be bilateral in an alert animal to evaluate completely without electrophysiologic instruments. Test by making a loud noise out of the animals vision and note

behavioral changes (looking towards noise). A central lesion usually doesn't cause extreme deficits in audition in a conscious animal. Therefore, look for the problem in a deaf dog's ears.



**Vestibular proprioception:** perceiving position of the head in relationship to gravity and motion. The vestibular apparatus has five components, the three semicircular canals, the utricle and the saccula. The saccula and utricle are responsible for static position and linear motion. The semicircular canals are responsible for angular motion. From the receptors in the semicircular canals, utricle and saccula of the inner ear, most of the nerve fibers pass to the four vestibular nuclei in the medulla oblongata and cerebellum. Fibers for these nuclei pass to many other structures:

- Down the spinal cord to facilitate extensor muscles on both sides and inhibit ipsilateral (same side) flexor muscles. This is important in maintaining posture against gravity.
- To the cerebellum (flocculonodular lobes)
- To motor nuclei of Cn III, IV, and VI to control vestibular eye movements (by medial longitudinal fasciculus (MLF)).
- Cerebral cortex through the thalamus
- Reticular formation to mediate motion sickness. Overall, animals seldom vomit in the face of vestibular disease.

### Signs

- Head tilt is a classic sign of vestibular disease. The tilt is usually toward the side of the problem.
- Leaning toward the affected side: due to loss of ipsilateral extensor tone in limbs and vertigo.
- Circling and falling to the affected side. Dogs and cats will lean and walk against a wall.
- Reluctance to lie on the good side because it worsens the vertigo and they do not like it.
- Ataxic gait due to cerebellar connections.
- Brain stem lesion - Altered proprioception and motor pathways



# CRANIAL NERVES

resulting in abnormal gait and abnormal postural reactions.

- Inability to right themselves, alter their posture.
- Nystagmus due to connections to the nerves of the extrinsic eye muscles.

**Nystagmus:** at rest is always abnormal and usually indicates vestibular dysfunction. It is repeated, involuntary, rapid movement of the eyeball, which may be horizontal, vertical, rotary or mixed, i.e., of two varieties. Both eyes are effected and usually move together (conjugate). The eyes will move to the same side as the lesion and snap back. Nystagmus is named for its fast (snap) component. If the animal's eyes move to the left and snap back to the right it is a right horizontal nystagmus, even though the lesion is on the left. In vertical nystagmus the eyes move up and down. Rotary nystagmus is deviation around the central axis.

**Peripheral vs central lesion:** differentiated by the type of nystagmus. A vertical nystagmus indicates a central lesion (99% of time). Horizontal and rotary nystagmus can be peripheral or central. Disconjugate nystagmus, different nystagmus in the eyes (e.g., horizontal in one and rotary in the other) is caused by a central lesion. Nystagmus that changes from one form to another (e.g., horizontal to rotary) with changing head position is due to a central lesion.

**Positional nystagmus:** inducing nystagmus in an animal without spontaneous nystagmus by changing head position. This can be due to a peripheral lesion as long as the nystagmus is not vertical, is conjugate and doesn't change to a different type with various head positional changes.

**Unilateral otitis (ear infection):** affecting the inner ear gives classical vestibular signs: head tilt, circling, leaning, falling, and possible nystagmus. These may be accompanied by Horner's syndrome (sympathetic nerves) and facial paralysis because these nerves also pass through the middle ear. Facial paralysis is critical because of lacrimal problems (dry eye) and inability to close the eye, not because of the distortion of facial features (dogs aren't vain). The loss of lacrimation requires constant artificial tears or surgical relocation of the parotid duct.

**Idiopathic vestibular disease:** an acute disease of unknown cause in animals. The presenting signs are severe unilateral vestibular signs indistinguishable from vestibular disease due to trauma or inner ear disease. The animal may not be able to stand, lies on the floor paddling its legs, with nystagmus and total disorientation. A self limiting disease, it resolves spontaneously without treatment in a few weeks with the only residual sign a possible slight head tilt. Many of these old dogs are probably needlessly put to sleep.

**GLOSSOPHARYNGEAL and VAGUS NERVES IX & X:** Cnn IX & X arise together from a motor nucleus in the medulla (nucleus ambiguus). They leave the skull together and do not diverge until they are some distance from the skull. It is almost impossible to have a lesion in one without the other. Therefore, when an animal has pharyngeal paralysis it indicates cranial nerve IX and X. With pharyngeal paralysis first think RABIES! The

glossopharyngeal nerve also innervates the parotid and zygomatic salivary glands, but salivation isn't a clinical problem because other salivary glands compensate and there is dual innervation on both sides. Taste to the root of the tongue also is not a clinical problem.

**Pathway:** IX, X & XI leave the cranial vault through the jugular foramen and exit the skull by the temporooccipital fissure.

**Gag reflex test:** stick a tongue depressor or a laryngeal scope paddle down the throat. Do not use a wooden swab or something the animal can bite in half.

**VAGUS, Cn X:** since it supplies innervation to the pharynx, larynx and esophagus, clinically look for pharyngeal, laryngeal and esophageal problems. Megaesophagus is a prime sign of CnX paralysis. This results in regurgitation of formed esophageal masses (tube of food).

**Left recurrent laryngeal nerve:** peels off from the vagus nerve in the thorax and passes around the arch of the aorta. It then travels up the neck to innervate most of the laryngeal muscles, most notably the cricoarytenoideus dorsalis. The cricoarytenoideus dorsalis is the only muscle that opens the glottic cleft. Paralysis of the recurrent laryngeal nerve results in "roarers", laryngeal hemiplegia in horses. The primary complaint is lack of exercise tolerance. (The roaring is sounds irritating but running out of gas near the finish line costs money.)

**Parasympathetic motor:** rarely do true cardiovascular or gastrointestinal signs point directly to vagal nerve lesions except in the ruminants. Vagal indigestion in ruminants causes eructation failure and bloat. Such animals are often culled for slaughter.

**SPINAL ACCESSORY, Cn XI:** arises from a nucleus (nucleus ambiguus) in spinal cord segments C<sub>1</sub> to C<sub>8</sub>. Its fibers leave the spinal cord and travels up to enter the cranial vault through the foramen magnum; and then join the vagus. Cervical roots from XI innervate neck muscles, omotransversarius, brachiocephalic, trapezius and sternocephalicus (muscles that move the head). With accessory nerve damage:

- Cervical muscle atrophy. If chronic, you may get fibrous atrophy and torticollis. Observe and palpate for symmetry of muscles on both sides of the neck.

**HYPOGLOSSAL NERVE, Cn XII:** motor to the muscles of the tongue. Prehension of food and water is done with the tongue. If the tongue is paralyzed the animal can't lap correctly.

- Unilateral paralysis will cause deviate to the side of the lesion at first and then over time away from the lesion as muscles atrophy.



CRANIAL NERVE EXAM	Test and poitive response (+)	Lesson localization
I Olfactory	• Odor stimulus	Usually nasal cavity
II Optic nerve	• Obstacle courses: vision • Placing reactions • Menace response • Fundascope	See chart 4
II & III	• Pupillary light reflex	See chart 4
III, IV and VI, oculomotor, trochlear & abducent nerves	Strabismus	Oculomotor lesion - ventrolateral strabismus Abducent lesion - medial strabismus Trochlear paralysis - not detected in round pupils, dorsal side rotated laterally
V Trigeminal	Muscles of mastication • Palpate the muscles of mastication • Open jaw, check tone Sensory • light touch • Palpebral reflex: V - VII reflex • Corneal reflex: V - VI reflex	• Past their separation sensory loss to area innervated. • Proximal to separation - loss of sensation to face & loss of the palpebral & corneal reflex. • Brain stem nuclear - sensory or motor loss or both and other brain stem signs.
VII Facial	• Schirmer tear test - lacrimation • Palpebral reflex: a Cnn V-VII reflex • Trigeminal facial reflex: V-VII reflex • Check symmetry of face • Menace response - Cn II-VII	• Peripheral- facial paralysis No effect on lacrimation. - Auriculopalpebral branch - widening of palpebral fissure, small animals & ptosis, large animals. - Buccal branches - deviations of face • Middle ear infections - all branches (eyelids, loss of lacrimation +/- vestibular signs & Horner's • Cranial cavity between brain & internal acoustic meatus - affect all branches, + vestibular signs, no Horner's • Brain stem - variable facial branch signs, accompanied by other brain stem signs.
VIII Vestibulochoclear		
Cochlear division -	• Deafness bilateral in alert animal	
Vestibular proprioception	• Observation of signs • Head tilt • Leaning towards the affected side • Circling & falling to affected side • Ataxic gait • Abnormal gait & posture • Look for nystagmus • Righting reflex	• Nystagmus - Vertical - central lesion (99% of time). - Horizontal and rotary - peripheral or central, - Disconjugate nystagmus - central lesions. Unilateral otitis Classical vestibular signs + Horner's syndrome & facial paralysis (in middle ear disease)
XI & X Glossopharyngeal & vagus	• Gag reflex test	- pharyngeal paralysis is seen - think Rabies
X Vagus	• Evaluate clinical signs • Laryngoscope • Esophgoscope	• Parasympathetic - ruminant vagal indigestion - eructation failure & bloat. • Recrrtent laryngeal nerve - laryngeal hemiplegia in horses and Bouvier de Flandres dogs.
XI - Spinal accessory	• Palpate cervical muscle atrophy, chronic - fibrous atrophy and torticollis.	
XII - Hypoglossal	• Pull on tongue • Observe tongue deviates toward lesion, chronic fibrosis away from lesion	



# Equine — Nerve and Joint Blocks



## NERVES - DISTAL LIMB - HORSE

**NERVE - EQUINE ANTEBRACHIUM:** Understanding the distribution of the nerves in the horse is very important in lameness diagnosis with nerve blocks. Draw a simple, line schematic of the nerves to the distal thoracic limb. Once this can be quickly done then placing the nerve blocks and what they block will be easier to understand.

1. **Radial nerve:** does not extend past the carpus as it does in the other domestic species.

**Median, ulnar and medial cutaneous antebrachial** (a branch of the musculocutaneous): the three nerves passing the carpus in the horse.

2. **Median nerve:** bifurcates into the medial and lateral branches proximal to the carpus.

3. **Ulnar nerve:** bifurcates just proximal to the carpus into dorsal and palmar branches.

4. **Dorsal branch of the ulnar nerve:** wraps around the cannon bone and descends on the dorsolateral side of the cannon region to the fetlock.

5. **Palmar branch of the ulnar nerve:** joins with the lateral branch of the median nerve to form the lateral palmar nerve.

6, 7. **Medial and lateral palmar nerves:** travel down either side of the flexor tendons. At the level of the fetlock, they give off a dorsal branch and continue as the palmar digital nerves. The median palmar nerve consists of only median fibers. The lateral palmar nerve is a combination of ulnar and median fibers.

8. **Communicating branch:** crosses over the palmar aspect of the flexor tendons about halfway down the metacarpus, where it is palpable. It carries fibers from the medial palmar nerve (median nerve fibers) to the lateral palmar nerve (ulnar and median nerve).

9, 10. **Medial and lateral digital nerves:** pass distally on the palmar aspect of the digit to innervate the heel region of the foot. They form a triad along with the digital vein and the digital artery on each side. These triads are arranged vein, artery and nerve (*memory aid:* VAN) from dorsal to palmar/plantar.

11. **Dorsal branches of the digital nerves:** pass distally for a short distance with the palmar/plantar digital nerves and then pass dorsally to innervate the toe region of the foot. The relationship between the digital nerves and their dorsal branches is important when blocking only one of the two.

12. **Deep branch of the lateral palmar nerve or deep branch of the ulnar nerve:** arises at the carpus from the lateral palmar nerve, dives deep and branches into the palmar metacarpal nerves. Some call this branch the deep branch of the ulnar nerve because they believe that even though it comes from the nerve formed from both the median and ulnar nerves, it carries only ulnar nerve fibers. This is academic and not of much clinical usefulness.

13. **Palmar metacarpal nerves:** continuations of the deep branch of the lateral palmar nerve. They course distally in the junctions between the splint bones and the cannon bone. They pass under the buttons of the splints to become superficial and continue to the fetlock.

14. **Medial cutaneous antebrachial nerve:** the cutaneous continuation of the musculocutaneous nerve. It extends distally to the fetlock.

**BLOCKS - LAMENESS DIAGNOSIS:** Pain causes lameness, the visual consequence of pain. Nerve blocks and intrasynovial anesthesia (see pg. 132) stop pain perception, thus, lameness (animal goes sound), therefore, help localize the problem.

The lame limb should first be identified by observing the animal at a rest and in motion. Once the limb has been identified, nerve blocks may be performed in a systematic order, starting distally (lower) and moving proximally (higher) to localize the problem. Block nerves above the area to be anesthetized because the nerve branches spread out as they move distally. Block bilaterally because pain doesn't know where the midline is. If a limb is blocked sound (no lameness) and the other limb is also affected, that limb will then appear lame. You are not necessarily looking for 100% soundness with a block, but for changes in the amount of lameness. If the animal does not "go sound" with a block, then block higher. If two or more blocks are needed for the animal to go sound, the problem is located between the last two blocks. Blocking to soundness localizes the source of lameness, but is not a definitive diagnosis, a thorough radiographic examination must follow.

**Procedure for nerve blocks:** The horse should be restrained, the handler and the veterinarian standing on the same side of the animal. Do not tranquilize as this will mask the effects of the blocks. Use a very small needle (25 gauge 5/8th inch) to minimize pain. Clean the injection area; a surgical prep is not necessary. Insert the needle quickly upward so if the horse moves, the needle won't be jabbed into the limb. Let the animal calm down, then attach the syringe using both hands. Inject a little anesthetic subcutaneously, then move the needle to the area of the nerve. Inject the anesthetic solution at a moderate rate. Lifting and flexing the leg gives control for most blocks.

**Types of nerve blocks:** point, line, and ring blocks. A point block (perineural anesthesia) is blocking a specific nerve directly at one site. This blocks the nerve and its branches past the site of injection. A line block is produced by infiltrating the anesthetic along a line. This numbs the nerve branches crossing the line. A ring block or field block is achieved by injecting anesthetic in a complete circle around the limb. Infuse anesthetic as closely as possible to the desired nerves in order to produce a limited field of anesthesia. Aspirate before injecting to avoid injecting into a vessel.

**Test the block:** 3 to 5 minutes after block, push a ball point pen (dull, not sharp, object) into the skin of the area that should be anesthetized. No response will be elicited with a successful block.



# NERVE BLOCKS

Fig. NB-1 - Nerves of thoracic limb, palmar view (schematic)





Fig. NB-2 - Nerves of thoracic limb, Dors. view (schematic)



- |                               |                                 |
|-------------------------------|---------------------------------|
| 1. Radial n.                  | 8. Communicating br.            |
| 2. Median n.                  | 9. Medial digital n.            |
| 3. Ulnar n.                   | 10. Lateral digital n.          |
| 4. Dorsal br. of the ulnar n. | 11. Dors. br. of digital n.     |
| 5. Palmar br. of ulnar n.     | 12. Deep br. of lat. palmar n.  |
| 6. Medial palmar n.           | 13. Palmar metacarpal nn.       |
| 7. Lat. palmar nerve          | 14. Med. cutan. antebrachial n. |

**Block success:** once the block has been performed and tested, exercise the horse in the same manner that showed the original lameness and look for any change.

Distal to the carpus and tarsus, nerve blocks are performed in the same manner since the neuroanatomy is roughly the same.




## SPECIFIC NERVE BLOCKS:

I. "Heel block" or palmar digital nerve block: anesthetizes the palmar/plantar digital nerves innervating the palmar/plantar aspect of the foot. The structures blocked are the navicular bone and its bursa, the frog, the digital cushion, the bulb of the heel, the flexor tendons, and the palmar portion of the coffin joint. The dorsal portion (toe) of the foot is unaffected.

Procedure: Flex the limb and lift the foot with your left hand. Search for the neurovascular bundle along the dorsal border of the flexor tendons. Palpate the ungual cartilages. Place the hoof between your knees. Insert the needle just proximal to the ungual cartilage at the level of the pastern joint. Aspirate and inject 1.5 to 2.0 ml of local anesthetic (5/8 inch 25 gauge needle) across the vascular bundle. (Make sure you aspirate first.) Use a small amount of anesthetic so it doesn't diffuse to the dorsal branch. An alternative is to push up the ergot and locate the tensed ligament of the ergot. Inject through the middle of this ligament to get the nerve passing under it. Three to five minutes after injecting, test the block by pushing a ball point pen into the skin over the bulbs of the heel. Also test the coronet over the toe to check that the dorsal branches have not been blocked. Hoof testers are also good for testing to see if deep structures (navicular bone) are anesthetized.

Boundaries Palmar/plantar - flexor tendons  
Distal - ungual cartilage  
Dorsal - Digital artery

Blocks: Heel




Area desensitized by a heel block

You may be able to predict the therapeutic success of a palmar digital neurectomy according to the animal's response to a heel block.

Palmar digital neurectomy or "Nerving a horse": transection of the palmar digital nerve in order to relieve pain in the palmar aspect of the foot. This will have the permanent effect of a heel block. This often relieves the pain associated with navicular disease. Do not cut the dorsal branches or there will be no feeling in the foot, resulting in a tendency to stumble (dangerous to the rider).

II. "Toe block" or dorsal branch of the palmar digital nerve block: blocks the toe area by blocking the dorsal branch of the palmar digital nerves. Many people bypass this block and move to the




Area desensitized by a toe block

abaxial sesamoid block. The structures blocked are most of the laminar corium, the dorsal and dorsolateral surfaces of the coffin bone, the extensor tendons, and the coffin bone. Inject 3 to 5 ml (5/8" 25 gauge needle) anesthetic subcutaneously in either a ring or line block at the level of the pastern, dorsal to the heel block injection site.

Injection: Dorsal to heel block

Blocks: Toe



Area desensitized by an abaxial sesamoid block

III. Abaxial sesamoidean block, high digital block or pastern block: blocks the pastern joint area and below by blocking the palmar digital nerves and their dorsal branches. Some people move to this block after the heel block. Anesthetized structures are the pastern joint and the structures associated with it. The toe and heel are also blocked, however, these structures were already ruled out with the appropriate heel and toe blocks, respectively.

Procedure: flex the limb and hold the foot between your knees. Palpate the palmar digital nerve and its dorsal branch over the sides of the proximal sesamoid bones ("pop" them under your fingers). Move distally and locate the base of the sesamoids. Inject 3 to 5 ml (5/8" 25 gauge needle) of local anesthetic in a short line at this level. Blocking distally from where the nerves can be palpated prevents the anesthetic from going too far proximally, possibly anesthetizing the fetlock area.

Injection: Abaxial sides at distal end of proximal sesamoids

Blocks: Pastern and below



# HEEL - TOE - ABAXIAL SESAMOID BLOCKS




Fig. NB-3 - Distal thoracic limb



## FETLOCK BLOCK

**IV. Fetlock joint block, low palmar (volar) block, or 4 point block:** blocks the fetlock joint area and below by blocking the six nerves innervating it. This block is performed at about a hand's width above the fetlock (where the epiphysis narrows down to the diaphysis). Nerves blocked include:

**1 & 2. Medial and lateral palmar nerves:** located on each side, between the flexor tendons and the suspensory ligament.

**3 & 4. Medial and lateral palmar metacarpal nerves:** found emerging beneath the buttons of the splint bones.

**5. Dorsal branch of the ulnar nerve:** crosses just dorsal to where the lateral metacarpal nerve emerges from beneath the button of the lateral splint.

**6. Musculocutaneous nerve branch (medial cutaneous antebrachial nerve):** travelling on the medial surface of the antebrachium near where the medial metacarpal nerve becomes subcutaneous near the button of the medial splint.

**Procedure:** Hold the limb up and flex the fetlock, taking tension off the flexor tendons.

- Medial and lateral palmar nerves: inject 3 ml (5/8" 25-gauge needle) of local anesthetic between the flexor tendons and the suspensory ligament on each side. It is critical to stay in the subcutis to avoid injecting into the tendon sheath.

- Medial and lateral metacarpal nerves: pass a needle (5/8" 25-gauge) under the buttons of the splints and infuse the area with 3 ml of anesthetic.

- Dorsal branch of the ulnar and the medial cutaneous antebrachial nerves: block by leaving a "bleb" subcutaneously as the needle is withdrawn after performing the metacarpal nerve blocks.

**Alternate procedure:** direct the needle (3" 22-gauge) from the palmar aspect of the limb dorsally to the palmar nerve between the flexor tendons and the suspensory ligament. Inject the palmar nerve (3 ml). Without removing the needle, push the flexor tendons to the side and direct the needle dorsally under the button of the splint (3 ml). Inject the metacarpal nerve. As you pull the needle from under the splint, leave a "bleb" of anesthetic under the skin to get the cutaneous nerve. Repeat this on the other side.

Check after 3 to 5 minutes, by poking a ball point pen into the skin around the fetlock.

**Inject:** Palmar nerves between the flexor tendon and suspensory ligament  
Metacarpal nerves under the buttons of the splints  
Cutaneous nerves as you withdraw from the buttons

**Blocks:** fetlock and below

**Low plantar block:** performed on the hind limb. It is similar to the low palmar block of the forelimb, with the exception of two

additional nerves that are blocked. It is done the same way, but the nerves have different names (these are followed in parentheses by the comparable nerve in the front limb):


- Medial and lateral plantar nerves (medial and lateral palmar)
- Medial and lateral plantar metatarsal nerves (medial and lateral metacarpal)
- Medial and lateral dorsal metatarsal nerves (no comparable nerves in the thoracic limb - from deep peroneal)
- Caudal cutaneous sural nerve (found laterally on the tibia) (dorsal branch of ulnar)
- Saphenous nerve (on medial side) (medial cutaneous antebrachial)

Medial and lateral dorsal metatarsal nerves (additional nerves in the pelvic limb): pass between the dorsal surfaces of the splint bones and cannon bone. Anesthetize with a line block to get the cutaneous branches (caudal cutaneous sural and saphenous). Many practitioners use half ring blocks to get the whole dorsal surface in the hind limb.

**Inject:** Plantar nerves between the flexor tendons and the suspensory ligament

Metatarsal nerves under the buttons of the splints  
Cutaneous nerves with a line or ring block of the dorsal surface of the cannon bone


**Blocks:** fetlock and below of the rear limb



Area desensitized by fetlock block



# FETLOCK BLOCK




**Fig. NB-4 - Dist. Hindlimb (med. or lat)**

Since 90% of all lameness is in the foot, most lamenesses will be isolated with these blocks ("heel", "toe", abaxial sesamoidean, and low palmar/plantar). If the horse is still lame, continue up the limb. The mid-cannon region is avoided because of the commu-

nicating branch between the medial and lateral palmar nerves. The communicating branches can be felt on the palmar surface of the superficial digital flexor tendon.



# HIGH PALMAR/ HIGH METACARPAL BLOCKS



V. High palmar blocks

VI. High metatarsal block

VI. High metatarsal block

Fig. NB-6 - Schematic of nerves

Fig. NB-5 - Thoracic limb, lat. view

**V. High palmar block:** used to anesthetize the superficial metacarpal structures, by blocking the medial and lateral palmar nerves at the middle of the metacarpus. Insert a needle (5/8" 25 gauge) below the carpus through the deep fascia to the palmar nerve located between the deep digital flexor and the suspensory ligament. Inject 5 ml of local anesthetic and repeat on the other side. This will not get all of the deep structures of the metacarpus.

**Injection:** palmar nerves on the sides of the flexor tendons.

**Blocks:** superficial metacarpal region.

**VI. High metacarpal block:** anesthetizes the metacarpal nerves, thus, most of the suspensory ligament and the interosseous ligaments of the metacarpal bones II and IV. Just distal to the

carpus, insert a needle (5/8" 25-gauge) between the splints (metacarpal II and IV) and the suspensory ligament down to the cannon bone (metacarpal III) on both sides. Inject 3 to 5 ml of local anesthetic.

**Inject:** the metacarpal nerves in the junction between the cannon bone and the splints, deep to the suspensory ligament.


**Blocks:** Deep structures of the metacarpus

**V - VI. Combination high palmar and metacarpal block:** blocks both superficial and deep structures of the metacarpus, except the origin of the suspensory ligament and the proximal ends of the splints.



# DEEP BRANCH OF LATERAL PALMAR NERVE


**Fig. NB-7 - Carpus, lat. view**



**VII. Deep br. of lat. palmar block**

- a. Tendons of digital flexor tendons
- b. Accessoriometatarsal lig.
- c. Accessory lig. of deep digital flexor tendon
- d. Suspensory lig.
- e. Accessory carpal bone

**Fig. NB-8 - Area Desensitized**



**VII. Deep br. of lat. palmar block**

**Metacarpal nn.**

**Fig. NB-9 - Schematic nerves, palmar view**



**VII. Deep branch of the lateral palmar nerve ("Deep ulnar" nerve) block:** The lateral palmar nerve passes in the carpal canal before it gives off its deep branch (deep ulnar branch) at the level of the heads of the splints. The deep branch bifurcates into the metacarpal nerves that pass against the palmar surface of the metacarpal bones. Structures anesthetized by this block are the origin of the suspensory ligament, the interosseous space, interosseous ligaments, and the proximal part of the splint bones. This block is useful for deep seated osseous lesions associated with the cannon and splint bones (e.g., splints, fracture, avulsion of the suspensory ligament, or exostoses, periostitis between the splints and the cannon bone).

**Procedure:** from the lateral side, insert a needle (1" 20 gauge) midway between the accessory carpal bone and the head of the fourth metacarpal bone. Pass medially to the ligament on the plantar aspect of the carpus, between the accessory carpal bone and metacarpus (accessoriometacarpal ligament), through the flexor retinaculum and lateral to the deep digital flexor down to

the carpal bones. Inject 5 ml of anesthetic.

**Inject:** lateral palmar nerve and its deep branch (deep branch of the ulnar nerve) in the carpal canal

**Blocks:** origin of the suspensory ligament, and proximal end of the splint bones

**V - VII. Combined high palmar and deep branch (of the ulnar nerve) lateral palmar nerve blocks:** anesthetizes all the structures of the metacarpus.

**Inject:** palmar nerves and the deep branch of the ulnar nerve

**Blocks:** all the structures of the metacarpus

**Blocking nerves above the level of the carpus is not very valuable.** It is difficult to isolate the nerves in this region and muscles can be paralyzed, leading to injury. To isolate joint pain proximally, intrasynovial injection is easier (see next page).



# JOINT BLOCKS

**Arthrocentesis (ar'thro-sen-TEE-sis):** the puncturing and aspiration of a joint.

**Reasons to inject a joint:**

- To remove a sample for visualization (e.g., viscosity of synovial fluid), or lab work.
- To administer therapeutic drugs (e.g., antibiotics).
- To administer a diagnostic substance (dye) for radiographic contrast studies.
- To administer an anesthetic.

Joints and bursae are blocked to localize pain to a specific joint or bursa. The higher risk in these injections over nerve blocks necessitates the observation of total surgical asepsis to prevent contamination. There is also the danger of damaging articular cartilage, thus, causing degenerative joint disease or acute arthritis. Nevertheless, they are very valuable diagnostic tools.

An injection of an anesthetic into a joint of a lame horse which then goes sound, localizes the problem to that joint. If the horse remains lame, that joint is not the problem; or it was not properly anesthetized.

**Surgical access to a joint:** arthroscopic surgery is becoming very popular and requires knowing where to access joints. More than one entrance may be necessary for surgery.

**Joint pouches:** focal points where the joint capsule protrudes between osseous and soft tissue structures. The pouches may or may not be swollen, thus, may or may not be palpable. The joint is accessible through pouches. Avoiding the articular cartilage is

desirable, but not always possible. Protrusion of the joint capsule (pouches) sometimes allows a needle to enter the joint cavity away from the articular cartilages. If it becomes necessary to enter between the articular cartilages, use a small needle and restrain the animal to minimize movement and possible scarification of the cartilage.


**To locate the injection site:**

1. Locate the level of the joint by palpating the regional structures.
2. Locate the injection sites by palpating their boundaries.
3. Insert the needle and aspirate synovial fluid. If you are injecting a large quantity of local anesthetic, remove the same amount of synovial fluid.

**VIII. Navicular (podotrochlear) bursa block:** anesthetizes the navicular bursa and, by diffusion, the navicular bone. This block is difficult. Make a subcutaneous injection under the skin on the midline, just above the bulbs of the heel. Direct a needle (2 inch, 20-gauge) through this point and direct it dorsally parallel to the ground until it hits bone (navicular bone). Back off slightly and inject 5 ml of anesthetic into the bursa.


**Boundaries:** Skin above the bulbs of the heel  
Direct needle parallel to the ground

**Blocks:** navicular bursa and navicular bone



**Fig. JB -1 - Saggital section - digit**

- |                             |                               |
|-----------------------------|-------------------------------|
| a. Extensor process of PIII | d. Deep digital flexor tendon |
| b. Navicular bone           | e. Interbulbar fossa          |
| c. Heel                     | f. Extensor tendon            |



**Fig. JB-2 -Digit, palmaromedial view**



# COFFIN, PASTER AND FETLOCK JOINTS




Fig. JB-3 - Digit, dorsolat. view




Fig. JB-5 - Saggital section - digit




Fig. JB-4 - Digit, med view

**IX, X, and XI. Dorsal approach to the fetlock, pastern and coffin joints:** injecting into the dorsal pouches of all three joints. Use the same procedure for all. Flex whichever joint you are injecting. Insert the needle (1 1/2" 20-gauge) proximal to the joint and under the common/long digital extensor tendon laterally, and pass it obliquely into the dorsal pouch. Inject 5 ml of anesthetic.

The coffin joint is within the hoof wall, therefore, it cannot be palpated, but mentally visualized. Insert the needle above the coronet, lateral to and under the extensor tendons into the dorsal pouch.

**Location:** Proximal to the joint  
Obliquely under the extensor tendon

**Block:** either the fetlock, pastern, or coffin joints.

**XII. Palmar approach to the fetlock:** an easier alternative to the dorsal approach. Flex the fetlock and palpate the boundaries of the palmar pouch. Insert the needle (1" 18-gauge) in the area between these boundaries. The needle must go dorsal to the suspensory ligament and palmar to the cannon bone in order to access this joint. Inject 5 ml of anesthetic.

**Boundaries:** Proximal - button of splint bone  
Dorsal - cannon bone  
Distal - proximal sesamoid bone  
Palmar - suspensory ligament

**Blocks:** fetlock joint



# CARPAL JOINT BLOCKS

**Fig. JB-6 - Carpus - dors. view**

Antebracheocarpal joint

Middle carpal joint

Carpometacarpal joint

- a. Lat. digital extensor
- b. Oblique carpal extensor
- c. Radius
- d. Metacarpal bone III

**XIII. Dorsal approaches - antebrachiocarpal**

**XIV. Dorsal approaches - middle carpal joints**

Extensor carpi radialis tendon

**Carpus anesthetic injections:** there are three joints in the carpus - antebrachiocarpal, middle carpal, and carpometacarpal joints.

- **Antebrachiocarpal or "Radiocarpal" joint:** doesn't communicate with the other carpal joints. Dorsally, it opens wide when the carpus is flexed.

- **Middle carpal joint (formerly intercarpal joint):** also opens dorsally on flexion, and communicates with the carpometacarpal joint.

- **Carpometacarpal joint:** too small to access with a needle. Fortunately it communicates with the middle carpal joint and is blocked when the middle carpal joint is anesthetized.

**XIII., XIV. Dorsal approaches to the antebrachiocarpal and middle carpal joints:** flex the carpus to open the joint. Palpate the depressions of both joints on either side of the tendon of the extensor carpi radialis muscle. Insert a needle (1" 20-gauge)

medially or laterally to the tendon and into the depressions. Put a syringe on the needle, aspirate 10 ml of synovial fluid, and inject 10 ml of anesthetic.

**Location:** Depression on either side of the extensor carpi radialis


**Blocked:** either the antebrachiocarpal joint or the middle and carpometacarpal joints.

**Palmarolateral pouch approach to the antebrachiocarpal joint:** an alternate technique that is safer for the articular cartilage, but is more difficult to perform. Locate the depression between the accessory carpal bone, the tendon of the ulnaris lateralis muscle as it inserts on the fourth metacarpal bone, and the caudal surface of the radius. Insert the needle (1" 20-gauge) obliquely and distomedially into the depression. Remove synovial fluid and inject 10 ml of anesthetic. This can be done with the animal standing, minimizing the danger of damaging the articular cartilage.




# ELBOW JOINT BLOCK

Fig. JB-7 - Lat. view of elbow



- a. Lat. epicondyle of humerus
- b. Lat. tuberosity of the radius

Fig. Lat. view of elbow



Elbow (cubital) joint: rather difficult to anesthetize. Fortunately, it is seldom needed as elbow problems are quite rare.

**XV. Lateral approach to the elbow:** Locate the lateral collateral ligament between the palpable lateral epicondyle proximally and the origin of the lateral digital extensor distally. Feel the space cranial to the lateral collateral ligament and slide the needle (2 1/2" 18-gauge) into this space. Aspirate and inject 10 ml. of local anesthetic.



# SHOULDER BLOCKS





Fig. JB-9 - Shoulder joint, lat. view



Area desensitized (schematic)

**XVI. Shoulder joint block:** Palpate the notch between the cranial and caudal prominences of the greater tubercle of the humerus. The greater tubercle extends proximally and cranially above the level of the joint, so insert the needle (3 1/2" 18-gauge spinal) through the notch at an angle caudal, distal, and medial in order to get into the joint space. Aspirate a liberal amount of


synovial fluid and inject 10 to 20 ml. of anesthetic.

Site: notch in greater tubercle

Blocks: shoulder joint.



# SHOULDER BLOCKS



- a. Shoulder joint
- b. Infraspinatus bursa
- c. Intertubercular bursa
- d. Tendon of origin of biceps brachii m.
- e. Infraspinatus bursa injection

Fig. JB-10 - Shoulder joint, lat. view

**XVII. Intertubercular (bicipital) bursa:** The shoulder joint and the intertubercular bursa in the horse are separate structures that do not communicate. Access to the bursa is blocked from the lateral side by the greater tubercle. Insert the needle (2 1/2" 18-gauge) at the level of the deltoid tuberosity and slide it up the cranial surface of the humerus, deep to the biceps brachii, and into the intertubercular groove and the bursa. If the needle goes past the bursa, resistance will be met as the needle enters the biceps

tendon. Back-off and aspirate synovial fluid, then inject 10 ml of anesthetic. (In a large horse this procedure may require a six inch needle.)

**Injection:** In at deltoid tuberosity  
Slide needle up cranial humerus

**Blocks:** intertubercular bursa.



## TARSUS

**TARSUS - HOCK:** has four joints – tarsocrural, proximal intertarsal, distal intertarsal and tarsometatarsal joints.

**Tarsocrural, talocrural or "tibiotarsal" joint:** the articulation between the tibia and the trochlea of the talus. It communicates with the proximal intertarsal joint. It has three pouches where the joint capsule protrudes subcutaneously: dorsal, medioplantar and lateroplantar. These are all connected, therefore, injection in any one anesthetizes all three and the proximal intertarsal joint.

**XVIII. Dorsomedial pouch:** easily palpated. Palpate the medial malleolus cranially to the calcaneal tuberosity. Palpate the tendon of the peroneus tertius cranially to the medial malleolus. Move distally until you feel a large, soft spot. Insert a needle (1" 20-gauge) into this soft spot, aspirate and inject 20 ml of anesthetic. Distally the cunean tendon crosses the tarsus. The medial saphenous vein crosses this pouch and must be avoided by inserting the needle behind (plantar to) it.

**Boundaries:** Proximal - medial malleolus  
Cranial - peroneus tertius muscle or medial saphenous vein

**Blocks:** tarsocrural and proximal intertarsal joint


**Lateral plantar pouch (a):** rarely injected. Inject into the soft spot in the "V" shaped area between the lateral malleolus and the body of the calcaneus.

**Medial plantar pouch (b):** harder to palpate, it also is rarely injected. Palpate the deep digital flexor tendon between the medial malleolus and the calcaneal tuberosity. Pass the needle between the caudal edge of the tibia and the tendon of the deep digital flexor muscle at the level of the medial malleolus. Avoid the synovial sheath of the deep digital flexor tendon by going dorsal to it.

**Proximal intertarsal joint:** between the talus and calcaneus proximally and the central and 4th tarsal bones distally. It is in direct communication with the tarsocrural joint, therefore never injected directly.

**Distal intertarsal and tarsometatarsal joints:** These are plane joints with little motion, thus, the joint spaces are very narrow and difficult to place a needle in. They are, however, most often affected by bone spavin and need to be injected for diagnosis more often than the easier to inject talocrural joint.

**XIX. Distal intertarsal joint, DIT:** located between the central and the 3rd and fused 1st and 2nd tarsal bones. It does not communicate with any other joint



so has to be injected specifically. It is extremely narrow and hard to consistently inject. Palpate the gap between the fused 1st and 2nd, 3rd, and central tarsal bone on the medial side of the hock with a finger nail. Inject a little anesthetic subcutaneously at this site. Insert a needle (1" 22-gauge) into this junction. This may require redirection of the needle. Inject 5 ml of anesthetic. If the gap can't be palpated, draw a straight line from the palpable distal tubercle of the talus to the palpable space between the heads of the 3rd and 4th metacarpal bone. Palpate the proximal border of the cunean tendon and inject where it crosses the line.

**Boundaries:** Junction of central, 3rd and fused 1st and 2nd tarsal bones (medial side)

**Blocks:** distal intertarsal joint

**Tarsometatarsal joint:** located between the distal row of tarsal bones (3rd, 4th, and fused 1st & 2nd, and the metatarsal bones).

**Medial approach to the tarsometatarsal joint (d):** injected distal to the site for the distal intertarsal joint where the 3rd, fused 1st and 2nd tarsal bones and the large metatarsal bone meet. This site is so small that it is difficult to hit. Put a bleb of anesthetic under the skin and repeatedly redirect the needle to find the site.







Fig. JB-12 - Tarsus, lat. view

Fig. JB-13 - Tarsus, med. view



XVI. Lat. plantar approach - tarsometatarsal joint

XIV. Dorsomedial pouch

XV. Distal intertarsal joint, DIT

1. Tarsocrural
2. Proximal intertarsal joint, PIT
3. Distal intertarsal joint, DIT
4. Tarsometatarsal joint

- a. Lat. plantar site (tarsocrural joint)
- b. Med. plantar site (tarsocrural joint)
- c. Med. approach to dist. intertarsal joint

- T. Tibia
- Tal. Talus
- Cal. Calcaneus
- I+II. fused first and second tarsal bone
- III. Third tarsal bone
- IV. Fourth tarsal bone

**XX. Lateral plantar approach to the tarsometatarsal joint:** Palpate the tubercle on the 4th tarsal bone and the head of the 4th metatarsal bone. Insert a needle (1" 20-gauge) in a sagittal plane between these two processes in a dorsodistal direction (obliquely towards the front and down). Inject 5 ml of anesthetic.

**Boundaries:** 4th tarsal bone  
4th metatarsal bone

**Blocks:** tarsometatarsal joint.

**Calcanean tendon:** the medial tendon of insertion of the cranial tibial muscle. It inserts onto the fused 1st & 2nd tarsal bone. It crosses the dorsomedial surface of the tarsus where bone spavin usually occurs.

**Cunean bursa injection:** slide a needle (1" 22-gauge) under the palpable distal border of the cunean tendon on the dorsomedial side of the hock. Inject 10 ml of anesthetic. This will differentiate cunean bursitis from bone spavin. If a lame horse improves within 20 minutes, it is a bursitis problem.



# STIFLE




Fig. JB-14 - Stifle, dors. view  
(Schematic)

## INJECTION OF STIFLE JOINT POUCHES

The stifle joint has three separate compartments – medial and lateral femorotibial and femoropatellar pouches. The medial femorotibial and femoropatellar pouches always communicate through a small slit. The lateral femorotibial pouch communicates with the femoropatellar pouch only 25 % of the time. The medial and lateral femorotibial pouches never communicate. Inflammation of the stifle may close all communications, therefore, each joint has to be individually assessed. First, identify the level of the stifle joint. (Students often mistake the medial trochlear ridge for the patella. Flex the limb and move the patella. It is usually more distal than the student first thinks.) Second, identify the specific boundaries of each pouch.

**XXI. Medial femorotibial pouch:** insert a needle (3" 18-gauge) between the medial collateral and the medial patellar ligaments at the level of the joint. Aspirate synovial fluid and inject 10 to 20 ml. of anesthetic.

Boundaries: Cranial - medial patellar ligament  
Caudal - medial collateral ligament

Blocked: medial femorotibial and femoropatellar pouches.

**XXII. Lateral femorotibial pouch:** protrudes between the lateral collateral ligament and the common tendon of origin of the long digital extensor and peroneus tertius muscles. Palpate the

two prominences of the extensor groove of the tibia to visualize where the two extensor muscles run. Palpate the lateral collateral ligament between the lateral epicondyle of the femur and the origin of the lateral digital extensor. Insert a needle (3" 18-gauge) caudal to the tendons, pointing proximally. Aspirate synovial fluid and inject 10 to 20 ml of anesthetic.

Boundaries: Cranial - combined tendon of peroneus tertius and long digital extensor  
Caudal - medial collateral ligament

Blocked: lateral femorotibial pouch and 25% of the time the other two pouches.

**XXIII. Femoropatellar pouch:** easy to access. Extend the stifle and grasping the patella pull it to widen the joint space. Insert a needle (2" 18-gauge) on either side of the intermediate (middle) patellar ligament. Advance the needle 2 inches between the patella and the patellar surface of the femur. Aspirate and inject 20 ml of anesthetic.

Boundaries: Intermediate patellar ligament  
Either medial or lateral patellar ligament

Blocks: femoropatellar and the medial femorotibial pouch and 25% of the time the lateral femoropatellar pouch.



Fig. JB-15 - Stifle, med. view




Fig. JB-16 - Stifle, lat. view

Combined tendon of long digital extensor & peroneus tertius muscle






Fig. JB-17 - Stifle, dors. view



# HIP JOINT BLOCK



**Fig. JB-18 - Hip joint, lat. view**

- a. Head of femur
- b. Summit of greater trochanter
- c. Convexity of the greater trochanter

**XXIV. HIP JOINT INJECTION:** very hard to achieve, especially on well muscled horses. Palpate the summit of the greater trochanter two thirds of the way from the tuber coxae to the ischiatic tuberosity. Palpate or estimate the location of the convexity. Then estimate the location of the notch between the two (not palpable). Insert a 6 inch needle (16-gauge) through the notch distally and slightly cranially. Walk the needle up the neck of the femur into the joint. Aspirate synovial fluid and inject 10 to 15 ml of anesthetic. This block is difficult and may require redirecting the needle.

**Boundaries:** Notch of greater trochanter

**Blocks:** hip joint

**XXVI. Trochanteric bursa injection:** The trochanteric bursa is

between the accessory gluteal muscle (of the middle gluteal) and the greater trochanter. Palpate the cranial part of the greater trochanter, the convexity. Insert a needle (3" 18-gauge) 2 inches distal to the convexity and direct it dorsomedially over the convexity into the bursa. Inject 10 ml. of local anesthetic.

**IM injections into the hip:** done in the gluteal muscles cranially, closer to the tuber coxae than to the midline. In a thin horse the ischiatic nerve can be paralyzed if the injection is too close to the midline.

**Hamstring injection:** should be made into the muscle, not into the intermuscular septum. Injections into the fascial planes greatly decrease the efficiency of the injections. Make injections into the caudal side of the semitendinosus muscle. Do not inject into the lateral thigh, thereby avoiding the ischiatic nerve.



# RADIOGRAPHY - INTRODUCTION

**Radiology:** the branch of medical science which deals with the use of radiant energy in the diagnosis and treatment of disease. This section is to help students start to understand radiology. It is not meant to be an in-depth presentation, but an introduction. Radiology, as a diagnostic modality, is selected when the history and physical exam suggests a possible benefit. Radiology seldom yields a final diagnosis, but contributes in the creation of an adequate differential diagnoses list.

**Radiography:** The study of the physics, photochemistry and electronic technologies used to form a high quality radiographic image.

**Radiograph:** a visible image formed by passage of ionizing radiation (energy) through the body, interaction of the escaped radiation with intensifying screens, the action of subsequent emitted light with film and the effect of developing chemicals.

**X-ray machine:** An X-ray beam is generated by passing an electron beam through a vacuum between a cathode and an anode. The positively charged anode attracts the electrons (opposite charges attract). A few percent of the electrons will pass close to the nuclei of the anode, interact with the electrostatic charge and convert their kinetic energy in to X-rays (photons) while the rest just create heat. The tube enclosure is shielded and a series of lead shutters allows the diagnostic beam to exit.


**Cassettes:** hold the radiograph film sandwiched between intensifying screens. They come in a number of sizes: 8"x10", 10"x12" 12"x14" and 14"x 17" (or metric equivalents). The object to be radiographed is placed on the cassette, between it and the tube head.

**Collimator (misnomer for Beam Limiting Device):** the part of the x-ray machine allowing restriction of the size of the beam leaving the machine.

**X-ray film:** a piece of plastic with a bilayer of silver halide emulsion. When exposed to light or x-rays, the silver halide is activated, which makes it reactive with the weak reducing solution of the developer. Silver halide which is reduced becomes microscopic crystals of silver metal, which appear black. The reduced silver metal is insoluble in the weak solvent of the fixer so it remains. The unreacted silver halide is soluble in fixer and will be removed (cleared). A film may be seen in several states:

- **Exposed; undeveloped; unfixed:** a film removed from the box in daylight (looks the same unexposed, but YOU cannot see it in the dark). It will be opaque with a greyish-green cast due to the emulsion (silver halide) covering it.
- **Exposed; developed; fixed:** film that has been subjected to light or x-rays and developed (i.e. a typical radiograph, exposed areas are black, unexposed regions clear).
- **Unexposed; developed; fixed:** a film removed from the box and developed in the dark room without being subjected to light or x-rays. All the inactivated silver halide is washed away in the

fixer, leaving only the transparent bluish piece of plastic. It is called "white" because films are looked at on a white viewer.



- **Exposed; undeveloped; fixed:** a film that had a virtual image from exposure to light or x-rays, but was not developed, no silver was precipitated so it all was removed by the fixer, resulting in a clear sheet.
- **Exposed; developed; unfixed:** a film with an image that was made visible by the developer, but because the unreacted silver halide was not removed by the fixer, the image is black and green instead of black and white.
- The radiograph is basically a negative, therefore, the whiter the film, the more underexposed it is. The darker a film, the more overexposed.

**Viewer:** a fluorescent light source for viewing radiographs.

**Spotlight or hot light:** a strong source of light placed behind the film to view over-exposed areas (darker than desired). A spotlight can make these areas still readable in some cases.

**FLASHLIGHT ANALOGY:** You can learn a lot about radiography using a flashlight. Radiant (x-rays) energy is a form of energy having many of the same properties as visible light. Both are generated from a source and transmitted as a primary beam. The primary beam is propagated until it strikes an object, where three things can happen: reflection (scatter), further transmission (penetration) or absorption.

- **Reflection or Compton scatter:** the redirection of a percentage of the primary beam striking an object's surface. Scatter radiation is a hazard to the operator as it is not limited to the region between the tube head and the cassette. In Compton Scatter the original photon interacts with an orbital electron which is accelerated and ejected from the atom. A secondary photon of x-ray is produced with less energy than the original and at a different direction of travel.
- **Penetration or transmittance:** the passing of part of the primary beam through the object. Light can be seen through a piece of paper. If more paper is added to the first, a smaller percentage will be transmitted. On the other hand the same thickness of tinfoil will transmit much less than paper (density). Therefore, transmittance is influenced by both thickness and density (atomic weight).
- **Absorption or Photoelectric effect:** the third possibility for the x-ray. This can be felt when the paper held in front of a light



# RADIOGRAPHY - INTRODUCTION

source gets warmer. The x-ray photon ceases to exist and its energy is converted to kinetic energy of an orbital electron which is ejected from the atom (i.e., heat).

**Inverse square law:** Intensity varies with the square of the distance. With visible light or x-rays, doubling the distance quarters the effective power. Therefore, any change of the distance between the x-ray emitter and the cassette film will greatly change the exposure. The use of standard distances for different techniques eliminates distance as a variable.

**Divergence:** the spreading of the primary beam as it moves away from the source. Scatter also diverges. Therefore, the closer the object is to the cassette, the less divergence, thus, the smaller and sharper its image. The farther from the cassette the larger (magnification effect) and fuzzier (geometric blurring) will be the image. Shine a light on your hand next to a wall. The closer to the wall, the smaller and sharper the shadow; the further from the wall the larger and fuzzier the shadow. Parts placed on the cassette will be sharp and almost actual size; parts away from the cassette will be abnormally enlarged and fuzzy. Always place the side of the animal you are interested in against the cassette so it will be sharp and close to actual size.

**Radiographic density:** the actual penetrative ability of x-rays to pass through an object and reach the film. Radiographic density of a part is determined by its thickness and its atomic weight. A piece of tin foil is denser (higher atomic weight) than a sheet of paper, thus, will stop more transmittance of light or x-rays. But paper can be stacked (thicker) sufficiently to stop as much transmittance as the piece of tin foil. Therefore, atomic weight and thickness go hand in hand. Although fat feels and looks more dense than water, it is not (fat floats). Air and fat have little reflection, little absorption, and a high degree of transmission to the film, thus, their images on the film will be black. Bone and metal have little transmission allowing less x-rays to reach the film, making their images white. Water densities fall between these in transmission, appearing as shades of gray. Water densities are the soft tissue densities of the body (viscera, muscles and fluids). Soft tissue radiographs are differences between very close densities, therefore, shades of grey. If a water density is thick enough (liver), it can appear as white or whiter than bone. Thickness plays a part

## BASIC SCHEME OF RADIOGRAPHIC DENSITIES

Commit this to memory!!

- AIR: Less radiodense than fat - black
- FAT: less radio-dense than water - black
- WATER: less radio-dense than bone - gray
- BONE: less radiodense than metal - white
- METAL: most dense - white

$A < F < W < B < M$  or  $M > B > W > F > A$

**Memory Aid** for radiographic densities mnemonic Bubbles, Blubber, Blood, Bones and Bullets, corresponding to the densities Gas; Fat; Water; Bones (Mineral); Metal.

in the appearance of overlapping densities also. Two bones that cross will appear whiter where they cross due to the greater thickness.

**Markers:** lead "R"s and "L"s placed on the cassette are used to tell which side of the animal has been placed on the film (down). These also designate which limb is radiographed if only one limb is shown. In addition to these markers, the film should have a label identifying the client, animal, date and facility performing the study, and if a time study, the time elapsed after the procedure was started.

**Patient preparation:** radiographs must be taken with a minimal amount of movement. For some animals this may be minimal restraint, whereas others will have to be sedated or anesthetized. For some procedures (e.g., radiographs of the spine) the animal must be anesthetized. Sand bags can be used to properly place the animal in relation to the beam direction. Some studies, such as abdominal radiographs, are compromised by food and fecal material in the GI tract. These patients are prepared by withholding food 12 hours prior to radiography and perhaps using an enema.

**Artifacts:** (definition: made by human hand) things seen on a radiograph that are not part of the animal. These can be due to a number of causes. Dirt, wet hair, ointments or iodine (radiopaque material) can cause artifacts on radiographs. Therefore, clean the animal first. Artifacts are also caused by static discharge, processing mistakes and physical damage to screens or films.

**SAFETY:** should be foremost in your mind whenever radiographing. Although invisible, X-rays are very dangerous and additive over time. Never place any part of your body or a helper's body in the primary beam. Wear lead aprons, gloves and stand behind a lead shield when ever possible to block secondary (scatter) radiation. A common misconception is that lead aprons and gloves protect you from the primary beam. This is not true. They only protect from scatter radiation. The beam should always be collimated to no larger than the size of the cassette or region being studied.

**ALARA:** As Low As Reasonably Achievable. The USNRC regulation concerning radiation exposure to human beings. Any use of ionizing radiation **MUST** be controlled by the operator to limit human exposure to be As Low As Reasonably Achievable.

**BEAM DIRECTION:** named for where the beam first passes into the body or part of body followed by where it exits the body or part to reach the film. Films shot from opposite direction are difficult to differentiate without markers on the film. A caudal/cranial and a cranial/caudal view will look identical in small animals because radiographs have no depth. Do not try to read or see depth in a radiograph.

- **Lateral medial (LM) view:** the beam enters the lateral side and leaves the medial side. Small animal extremities are usually



# RADIOGRAPHY - INTRODUCTION

exposed as Medial-Lateral projections.

- **Lateral projection of major body cavities (abdomen, thorax):** named by the exit surface or that surface closest to the cassette. An animal in left lateral recumbency (right side up, left side down) when radiographed produces a **LEFT LATERAL** projection.
- **DV or dorsoventral:** the beam enters the dorsal surface and exits the ventral surface. This is the standard position for small animal body cavity images with the patient in dorsal recumbency (back up, tummy on table).
- **VD or ventrodorsal:** the beam enters the ventral surface and exits the dorsal surface.
- **Craniocaudal or anterior/posterior (AP):** the beam enters the anterior (front) side of the limb above the carpus and exits the posterior surface (back) of the limb.
- **Caudocranial:** the beam enters the back of the limb and exits the front. Difficult (impossible) to differentiate from a craniocaudal view.
- **DP or dorsopalmar (dorsoplantar):** shot from the front to the back of the limb below the proximal extent of the carpus.
- **PD or palmar dorsal (plantar dorsal):** shot from the back to the front of the limb below the proximal end of the carpus.

**ANATOMICAL LANDMARKS:** certain organs or structures with specific locations are used to ascertain the side of the body or limbs in a film. Anatomical landmarks should always be used to check if the markers are correct. (Nature put on the landmarks, people put on the markers, who do you trust?) Use radiographic landmarks to get your bearings. A few of the common radiographic landmarks are:

## Anatomical Landmarks

- Apex of the heart - left
- Gas bubble in the fundus of the stomach - left
- Descending colon - left
- Cranial kidney - right; Caudal kidney - left
- Anticlinical vertebra - vertical vertebrae, usually T<sub>11</sub> in dogs.
- Head of humerus - caudal
- Radius - cranial
- Olecranon - caudal
- Distal end of ulna - lateral and caudal
- Accessory carpal bone - lateral and palmar
- Dew claw - medial
- Patella - cranial
- Fibula - lateral
- Calcaneus lateral and plantar


## READING FILMS:

**Survival Law!:** Read in a systematic manner. Extract maximum information from the entire film. Do not miss something impor-

tant by jumping at the most obvious. Determine what region is radiographed (shoulder or thorax etc.). Knowing the anatomy is necessary for reading films. Anatomical landmarks help you orient the views and indicate the direction of the beam. If lateral and medial structures are silhouetted (on the edges of structure), then the beam was directed craniocaudal, dorsopalmar or dorsoventral depending on what was radiographed (i.e., a view showing the outline of the radial [lateral structure] and ulnar carpal bone [medial structure] or the lateral edges of the ribs [lateral structures]). Silhouetted caudal and cranial structures indicate beam was directed lateromedial or mediolateral (i.e., accessory carpal bone silhouetted or chest with spines of vertebrae and sternum on the edges of the film).

**CHECKLIST:** Do not look at the lines, grays and shadows of a radiograph and try to identify what anatomic structure they represent. Instead work from a list of the structures that you expect to see and locate each in a specific order. The first approach will 'miss' agenesis (absence) of an organ, because there is nothing to see.

**Two-dimensional / three-dimensional:** A radiograph is a two dimensional representation of a three dimensional object. To extrapolate the third dimension at least two radiographs must be taken at 90° to each other. A dorsoventral view of the abdomen will have the medial to lateral and cranial to caudal dimensions, but will lack the dimension in the plane of the beam, dorsal to ventral. The lateral view will have the cranial to caudal and the dorsal to ventral dimensions, but lack the lateral to medial dimension. With both views (lateral and DV) all three dimensions are present and three dimensional information can be extrapolated. If, in the DV view, a buckshot shows up superimposed on the kidney, it could be anywhere in the plane of the beam (subcutaneous, below, in, or above the kidney). Another view is needed to place the buckshot in three dimensions. A lateral view showing the buckshot overlapping the kidney would now place it in the kidney.





## SKULL - FILMS




Fig. R-1- Dog  
Lat. view




Fig. R-2- Dog  
VD view

- |                  |                                    |   |
|------------------|------------------------------------|---|
| 1. Teeth         | 6. External occipital protuberance | • 11. Coronoid process                      |
| 2. Nasal cavity  | 7. Zygomatic arch                  | • 12. Articular condyle (condyloid process) |
| 3. Ethmoid area  | 8. Mandible                        | 13. Tympanic bulla                          |
| 4. Frontal sinus | • 9. Body (horizontal part)        | 14. TM (temporomandibular) joint            |
| 5. Cranium       | • 10. Ramus (vertical part)        |   |

**Skull radiographs** are difficult to read because of the confusing overlap of structures of different densities. Use a skull specimen to help read skull radiographs and position shots. All skull radiographs should be done under anesthesia because they need to be perfectly positioned. There are 3 types of skulls in dogs relative to the proportions of the facial bones and the cranial vault. This variation must be taken into account when viewing normal skull films - doliocephalic, larger facial component (i.e. long nosed breeds, such as the collie) - mesaticephalic: (i.e. beagle) - brachiocephalic: shorter facial component (i.e. Boston Terrier). Some indications for the skull radiographs are neurological problems (hydrocephalus), nasal or mandibular problems (fractures), maxilla (rhinitis, neoplasm), primary tumors of skull (soft tissue swelling), mass behind the eye, teeth diseases, and middle ear problems.

Many different positions are used in skull radiography to look at the different structures. The dorsoventral and lateral are standard views. Open mouth, lateral oblique of the mandible or upper jaw views are shot at 45° angle to separate the teeth of the opposite jaws. Occlusal views are shot by placing the cassette in the mouth and directing the beam in a DV or VD direction. This isolates the upper or lower jaw respectively from the other jaw. The lateral oblique (to see the TM joint), frontal or fronto-occipital (for the frontal sinuses), opened mouth VD or DV and foramen magnum are all different views to highlight specific structures.

Be able to identify the structures listed after the different views. Look for symmetry on the DV view by comparing one side to the

other.

**Cat differences:** The cat's skull is constructed differently than the dog and these differences need to be known. Cats have greater doming of the frontal and nasal bones, smaller frontal sinuses (may be absent in Persians), more complete bony orbits and wider skull because the zygomatic arches are wider




Fig. R-3 - Cat  
Lat. view




Fig. R-4 - Cat  
DV view view



## SKULL - FILMS



**Nasal cavity:** in the DV view, compare each side for opacity or lucency. Increased soft tissue caused by inflammation or a mass may increase the opacity. When there is a difference in the density of one half of the nasal cavity (heminasum) compared with the other, look for the fine detail of the nasal conchae. If conchal detail is present on both sides then the densest side is diseased (exudate, blood, tumor). If conchal detail is missing from one side then it is the diseased side regardless of whether it is dense (exudate, blood, tumor) or lucent (usually fungal rhinitis).



**Teeth:** locate the crown, root and pulp cavity. Note the presence or absence of the lamina dura. It is the side of the alveoli the beam passes through. This makes it appear as a white line separated by a space (periodontal space) from the tooth root. If this is eroded or missing, it indicates a problem with the tooth. The periodontal space is between the lamina dura and the tooth root and is occupied by the periodontal membrane.

**Pharynx:** Radiographically, its soft structures are contrasted against the air opacity. The pharynx is located ventral to vertebrae C<sub>1</sub>-C<sub>2</sub> and is best visualized on a lateral projection. Structures of the pharynx:

**A. Soft plate:** separates the oropharynx from the nasopharynx and can be seen radiographically.

**B. Nasopharynx:** air-filled area above the soft palate

**C. Oropharynx:** air-filled continuation of the oral cavity below the soft palate.

**D. Laryngopharynx:** the common part of the pharynx filled by

the larynx in the lateral projection.

**E. Hyoid bones:** suspend the larynx from the skull - stylohyoid, epihyoid, ceratohyoid, basihyoid, and thyrohyoid. As bones, they are visible radiographically. The most common clinical radiographic findings are fractures.

• **G. Basihyoid:** seen end on in the lateral projection; making it appear very white (dense).

**H. Laryngeal cartilages:** make up the skeleton of the larynx - epiglottis, thyroid, cricoid and arytenoid. With age the cartilages can mineralize, especially in large or chondrodystrophic breeds. The cricoid cartilage is the first to become calcified.

• **I. Cricoid cartilage:** the easiest to see.

• **J. Epiglottis:** also easy to see at the rostral end of the larynx. In the horse the normal position of the tip of the epiglottis is dorsal to the soft palate.

The pharynx is evaluated for decreased or increased contrast and displacement. Decreased contrast can be due to inflammation, masses, or a normal finding in brachiocephalic breeds. Increased contrast is due to air around the pharynx (retropharyngeal air) (e.g., penetrating wounds or rupture of the structures of the pharynx or esophagus). Ventral displacement can be due to retropharyngeal masses. Laryngeal, tonsillar or thyroid masses can displace the pharynx laterally. With fractures of the hyoid apparatus the pharynx can be displaced caudally. The pharynxes of brachiocephalic dogs are difficult to interpret because there is less air, therefore, less contrast in the pharyngeal region.




Fig. R-7 - Pharynx, lat. view



# LIMBS

**Endochondral ossification:** the formation of long bones by transforming a cartilaginous model into bone. Bone replacement takes place in three primary ossification centers - the diaphysis and the two epiphyses. This results in a bone capped with articular cartilage and two cartilage discs (metaphyseal growth plates or physes) between the diaphysis and the two epiphyses. Lengthening of bone occurs at the epiphyseal side of the metaphyseal plate. Lengthening stops when the epiphyseal plates are completely replaced by bone. During growth, radiographically, the epiphyseal cartilage appears as a radiolucent line (dark line), called the physis by radiologists, separating the diaphysis from the two epiphyses.




Fig. R-8 - Long bone

Accessory ossification centers of large processes of individual bones also display these dark lines in young animals. These (and sesamoid bones) should not be mistaken for fractures.

- Anconeal process of the ulna
- Sesamoid bone of the lateral collateral ligament of the elbow
- Accessory ossicle of the caudal scapula
- Sesamoid bones of the stifle
  - Patella
  - 2 Fabellae
  - Sesamoid of the popliteal muscle
- Sesamoid bones of the digits
- Os penis: sometimes has two ossification centers and can appear to be a broken penis.

**Evaluating radiographs of the limbs:** recognize different anatomical variations for the bones. A German Shepherd humerus looks different than that of a chondrodystrophic dog (Dachshund). Follow the cortex and see if it thins or thickens or if there

are breaks in it. Know the locations of the nutrient foramina so they are not mistake for lytic (dissolved) areas.

## Radiographing limbs:

- Long bones of the limbs: include the proximal and distal joints in the film.
- Joints of the limbs: center the joint in film.
- Comparison films: take the opposite limb if there is a question as to what you are seeing and compare the two.

**VIEWS OF THE LIMBS:** the most common are the lateral view and the craniocaudal or dorsopalmar/plantar. The different views silhouette different sides of the bones and can be identified by what is in silhouette.

**Lateral view of limb bones and joints:** place the affected limb on the cassette. Pull the affected limb forward and the unaffected limb backwards. The lateral view silhouettes the cranial and caudal surfaces of the bones.

**Craniocaudal or anterior-posterior (AP) or dorsopalmar view:** silhouettes the medial and lateral structures of the limb.

Structures silhouetted - thoracic limb	
Lat. view	Cranocaud or dorsopalm. view
<b>Cran. structures</b> <ul style="list-style-type: none"> <li>• Greater tubercle</li> <li>• Radius</li> </ul>	<b>Lat. structures:</b> <ul style="list-style-type: none"> <li>• Spine of scapula</li> <li>• Greater tubercle</li> <li>• Distal end of ulna</li> <li>• Accessory carpal bone</li> </ul>
<b>Caud. structures:</b> <ul style="list-style-type: none"> <li>• Head of humerus</li> <li>• Ulna</li> <li>• Accessory carpal bone</li> </ul>	<b>Med. structures:</b> <ul style="list-style-type: none"> <li>• Radial carpal bone</li> <li>• Dew claw</li> </ul>

**JOINTS** - synovial (diarthrodial): consist of the following components:

- 1. Joint space:** in a radiograph, is actually the joint space and the articular cartilage, since the cartilage is invisible in radiographs.
- 2. Articular cartilage:** caps the ends of the bones making up the joint. It can't be seen on the radiograph, only inferred.
- 3. Joint capsule:** surrounds the joint space and attaches at the edge of the articular cartilage. It can't be seen on radiographs unless calcified.

**Degenerative joint disease (DJD):** a disease affecting synovial joints due to mechanical problems and degrading changes in the articular cartilage. It can be caused by congenital or acquired deformities of the bones and joints, infection or trauma. Some important terms relating to DJD follow:



# SHOULDER JOINT

- Osteophyte (OS-tee-oh-fyt): an osseous (bony) outgrowth.
- Sclerosis (Slee-ROH-sis) (Gr. *sklerosis* hardness): hardening, in bone, referring to the increase in density of a bone.
- Ankylosis (ang'ki-LOH-sis): immobility and consolidation of a joint due to disease, injury or surgical procedure.
- Lysis (LY-sis) (Gr. *lysis* dissolution): destruction or decomposition, seen as reduced density in bones (blackier).

Radiographic possibilities in DJD (degenerative joint disease):

- Narrowing or disappearance of the joint space.
- Osteophyte formation, most often at the articular margins
- Subchondral bone sclerosis
- Joint deformities
- Lytic and proliferative changes where the joint capsule and ligaments attach around the joint.
- Ankylosis (complete or partial)

**SHOULDER JOINT** or scapulohumeral joint: the synovial joint between the head of the humerus and the glenoid cavity of the scapula. The lateral and craniocaudal views are standard for the shoulder. Take the lateral view by placing the dog in lateral recumbency with the affected leg down on the cassette. Push the affected limb dorsally and pull the unaffected limb ventrally and caudally to separate the limbs. To take a craniocaudal (AP) view of the shoulder, rotate the limb medially to pull the scapula away from the thorax.




Fig. R-9 - Shoulder joint radiograph (schematic)

When viewing shoulder films the joint space should be of equal width all around the head of the humerus. The head of the humerus should be smooth and round, with no flattening. Check for fractures of the spine of the scapula in the craniocaudal view. Do not confuse the accessory ossification center of the caudal aspect of the scapula with OCD (osteochondrosis dissecans) which occurs on the caudal aspect of the head of the humerus

(covered below). Remember to look at all the film, noticing structures other than the shoulder joint - neck, cervical vertebrae, air-filled trachea, ribs, and lung fields (air-filled).




Fig. R-10 - Osteochondritis of the shoulder

**Osteochondrosis:** a defect in endochondral ossification which causes the deeper layers of the articular cartilage to die. If something goes wrong in osteochondral ossification, the cartilage continues to grow and thicken. Beyond a certain thickness, diffusion from the synovial fluid can't reach the deeper layer, which dies. The etiology is unknown. Excessive nutrition and stress may have something to do with it. It tends to be bilateral. It is seen in 4 to 10 month old, rapidly growing, large breeds. It may occur as a subchondral bone cyst, which is a misnomer because it isn't a secreting membrane, rather a wad of necrotic cartilage with a sclerotic layer around it. Osteochondrosis tends to happen in predictable anatomical sites.

## Sites - osteochondrosis


- Shoulder - caudal aspect of the head of the humerus
- Medial humeral condyle - bears more weight
- Medial or lateral femoral condyle
- Trochlea of talus

The caudal aspect of the head of the humerus is the primary site for osteochondrosis. Radiographically, cartilage is not seen so the subchondral bone is checked to see if it indicates that the cartilage is damaged. This may appear as flattening or cratering of the caudal aspect of the head of the humerus with subchondral bone sclerosis (thickening). The lateral radiograph shows this best.

**Osteochondrosis dissecans:** a form of osteochondrosis that has a dissected flap of cartilage. The cartilage above the dead cartilage fractures and forms a flap. Dissecans means a dissecting flap. The fragment can calcify and/or break off and float around in the synovium and is then called a "joint mouse".



**ELBOW JOINT:** a complicated joint between the humerus, radius and ulna. Three important radiographic structures are listed below:



- **Anconeal process of the ulna:** the proximal projection of trochlear notch. It is an accessory ossification center in most dogs.

- **Coronoid processes of the ulna:** medial and lateral processes of the distal end of the trochlear notch. The **medial** coronoid process is larger and is not an accessory ossification center.


- **Sesamoid bone in the lateral collateral ligament of the elbow:** present in some dogs, do not mistake it for a fracture. Radiograph the other limb if there is doubt.

**Ununited anconeal process:** failure of the anconeal process to unite with the ulna. It should unite at about 5 to 6 months of age. It tends to occur in large breed dogs (German Shepherds) and tends to be bilateral. This disease is now felt to be related to OCD. If it has not united after 5 months of age it is considered ununited. You see a straight or ragged radiolucent line. The process may or may not be displaced. There may be degenerative changes in the elbow (DJD). The best view is the flexed lateral elbow which pulls the anconeal process out of the olecranon fossa of the humerus.

**Osteochondrosis of the elbow:** failure of endochondral ossification on the medial condyle of the humerus. The craniocaudal view is taken to try to see a subchondral lucency. This often accompanies ununited anconeal process.


**Fragmented medial coronoid process:** believed to be a syndrome of osteochondrosis. It is incorrectly called an ununited coronoid process because it is not a separate ossification center. The cartilaginous precursor undergoes improper development and fragments. It is cartilage so it can't be seen. Rounding off of the medial coronoid process may be seen. Rarely is the cartilage joint mouse seen, unless it calcifies. Most of the time you only see secondary degenerative joint disease (DJD). The earliest site of DJD is bone proliferation on the cranial aspect of the olecranon process. Bone build up (sclerosis) can also occur where the joint capsule attaches. Often it is a diagnosis of inference - a young dog with some kind of elbow dysplasia (developing DJD) with no evidence of other osteochondroses or ununited anconeal process. OFA will now certify elbows. A flexed lateral film is sent in for evaluation.

**Premature closure of the physis:** usually due to trauma. This is most common in the distal physis of the ulna or radius. Compare the opposite limb's physis on radiographs. Closure of either the physis of the ulna or the radius will cause deformities in the other bone and subluxation and/or degenerative joint disease of the joints on either end of these bones. Look for loss of the radiolucent physal line on radiographs.





## PELVIC LIMB - HIP JOINT



**HIP JOINT:** a ball-and-socket joint allowing great range of motion, but sacrificing stability.

**Acetabular rim:** the craniodorsal ridge is an accessory ossification area. This can be mistaken for a chip fracture.

**Physeal scar:** normal remnant of the closed physis.

**Fovea capitis:** an indentation on the head of the femur where the round ligament of the head of the femur attaches. This appears as a normal flattening of the femoral head on radiographs. Rotation of the limb medially will hide it in VD films.

**Hip dysplasia view:** Place the dog in dorsal recumbency with the limbs pulled caudally and rotated slightly medially to place the femurs parallel to each other, the patellas (or patellae) centered in the trochlea of the femur. Superimpose the femur and the ischiatic tuberosity similarly on both sides. The film should include views from below the stifle to just above the hip bones. The pelvis must be level (no rotation). Rotation will make one acetabulum look very deep and one very shallow, therefore, one joint will appear better. Rotation can be checked by looking at the symmetry of obturator foramen. Rotation will cause the "up" foramen to appear rounder and larger, and the "down" side smaller and more elliptical. Rotation also causes the width of the wings of the ilium to be different. The OFA will not certify a dog until it reaches two years of age.

50%-60% of the head of the femur should be inside the dorsal rim

of the acetabulum. Look for congruency (parallel lines) between the head of the femur and the acetabular cup, especially in the cranial third. A tangential line drawn from the edge of the cranial acetabular cup should be as close to perpendicular to the axis of the skeleton as possible. A non-perpendicular line would infer a shallow acetabular cup. Degenerative change (DJD, osteoarthritis, osteoarthritis) first shows up as osteophyte proliferation along the neck of the femur. This may look like a thickened neck of the femur. Osteophyte proliferation tends to occur where the joint capsule attaches. Lastly, you can see some spurring (proliferation along the edges of the cup of the acetabulum). Any signs of DJD indicates problems. There are a number of treatments for hip dysplasia, ranging from aspirin, cutting off the head of the femur, to hip replacement.

**Pelvic fracture:** "rule of thumb" - if one fracture is seen, look for two more (one may be a luxation of the hip). The pelvis is a box, if it breaks in one part, it has to break in two more locations in order to displace.

**Legg perthes:** avascular aseptic necrosis of the femoral head and neck. Loss of blood supply to the head or neck causes the head to become irregular (dissolve away). Over time it will collapse and become flattened and deformed. Treatment is to remove the head and neck, which small dogs tolerate very well. Etiology is unknown. It occurs from 3 to 11 months of age and is usually unilateral, but can be bilateral. This disease occurs in small breeds (Poodle).



## STIFLE




Fig. R-14 - Stifle, lat. view

**STIFLE:** a composite joint between the femur, patella, tibia and fibula.

**Sesamoid bones of the stifle:** the patella, two fabellae and the sesamoid bone in the popliteal tendon.

**Tibial tuberosity:** in young dogs, has a growth plate which looks like a fracture.

**Skyline view:** place the animal in sternal recumbency. Flex the stifle and place the animal on its knees. This view shows the depth of the trochlear groove, the patella and the femoropatellar joint space. The groove is shallow in dogs that have patellar luxation. This can be repaired by deepening the groove surgically.

**Subpatellar Fat Pad:** On the mediolateral projection of the stifle there is a radiolucent (fat) density seen in the triangle formed by the femur, tibia and distal patellar ligament. A small gray area is seen in the stifle joint apex, which represents the synovial fluid of the stifle. Intra-articular diseases, most common: Cruciate ligament rupture, will cause effusion of the joint and this is seen as the water density (gray) encroaching on the fat density (black).



Fig. R-15 - HOD, dist. ulna and radius

**HOD, hypertrophic osteodystrophy:** occurs in 3 to 7 month old dogs. It tends to occur in the distal end of long bones, especially the ulna, radius and tibia. The etiology is unknown, but felt to involve an excessive plane of nutrition. The animals present with swelling around the metaphyseal region of the long bones of the limbs, fever and lameness. The classical radiographic signs are bone cuffing around the metaphyseal region and double physes. This is a self limiting disease that resolves with time. The animal is treated for pain.

**HO, hypertrophic osteopathy:** lamellar periosteal proliferation on the long bones of the extremities, causing lameness and pain. The etiology is unknown, but it is associated with space occupying lesions of the thorax - tumor or chronic pneumonia. Radiographically there is periosteal proliferation around the diaphyses of affected bones. It usually starts in the metacarpal and metatarsal bones and then progresses to involve the long bones of all four limbs and the carpus and tarsus. Treatment of the associated thoracic lesion usually results in regression of the bony lesions.

**PANOSTEITIS:** occurs in 5 month to 2 year old dogs (German Shepherd). They present with shifting leg lameness. It tends to occur in more than one bone at more than one time. It can be almost anywhere, but it tends to occur in the humerus, ulna and femur. Classically what is seen are nodular opacities to complete opacification of the medullary cavities. With time there may be smooth periosteal and endosteal reactions. Reactions are most prominent near the nutrient foramen. When it goes away it tends to leave a vacant look to the medullary cavity (dark) with a coarse trabecular pattern. You may find any stage of this on different bones. The etiology is unknown. This is also a self limiting disease.

**Radiograph placement on viewing screen:** come up with a



# SPINAL RADIOGRAPHS

It is critical to have quality radiographs taken of an anesthetized animal to evaluate spinal problems. It is essential that the spine is aligned straight without rotation. Rotation of a VD/DV film is evaluated by seeing the sternum superimposed over the spine.

**TRIADS:** Look at general aspects and compare each vertebra with others. Look at them in triads (3's), comparing each vertebra to the one in front and to the one behind. Compare the size, shape and opacity of adjacent vertebrae. Check the alignment of the vertebrae by tracing the dorsal and ventral edges of the vertebral canal. It should be smooth and continuous. A step defect occurs when one of the vertebrae is out of alignment, causing a "step" in one of the edges of the spinal canal.

**INTERVERTEBRAL DISC SPACES:** evaluated to get an indication of the state of the intervertebral discs. The radiolucent intervertebral discs themselves cannot be visualized. Narrowing of the space may indicate a protruded disc. The intervertebral space between T<sub>10</sub> and T<sub>11</sub> is normally narrower than the other spaces. Cervical intervertebral spaces are normally wider than other spaces. A space further from the center of the film, due to divergence of the beam will be viewed obliquely, thus, appear narrower than it is. Thus, only the 6 to 8 vertebrae in the center of the film can be evaluated for joint space differences. Do not take long films of the entire spinal column to save time and money.

**INTERVERTEBRAL FORAMINA:** Called the "windows" to the spinal cord, (look like Snoopy's little bird buddy, Woodstock, in profile), should not abruptly change size from one to another. The radiolucent spinal cord can't be viewed. A calcified nuclei or disc is a major finding and is a radiopacity found in an intervertebral disc space or spinal canal seen through the intervertebral foramen.

Cats - lumbar vertebrae are relatively longer and narrower than in the dog.

**DENS:** the cranial projection of the axis that articulates with the ventral arch of the atlas. The dens may not develop (agenesis) or it may be fractured. It may be imaged with a lateral, a DV, or an open mouth radiograph.

"**SLEDS**" or transverse process of C<sub>7</sub>: in three parts, making it a landmark for cervical films.

**ANTICLINAL VERTEBRA:** the upright vertebra, usually T<sub>11</sub>, where the incline of the spinous processes change from caudal to cranial.

**MYELOGRAM:** the injection of a positive contrast medium into the spaces around the spinal cord (subarachnoid space). This will make the subarachnoid space visible as two white lines separated by a space (the invisible spinal cord). These contrast lines should be smooth, reflecting the smoothness of the spinal canal. Remember the spinal cord has a cervical and a lumbar enlargement that are normal. Look for any deviations in the contrast lines, therefore, in the cord. A break or thinning in the subarachnoid space that looks as if it is pushed outward indicates

a swelling of the spinal cord. A break appearing to be pushed inward could be due to a mass outside the meninges (herniation of a disc). A thinner dorsal column can be normal if balanced with a thicker ventral column. Contrast medium is heavier than CSF, so gravity can be used to move it up or down the subarachnoid space.





Fig. Mylogram contrast lines, A) normal; B) pushed outward; and C) pushed inward

**THORACOLUMBAR MYELOGRAM:** direct the needle between the spinous processes of L<sub>5</sub> and L<sub>6</sub>. The spine of vertebrae L<sub>6</sub> is palpated in front of the line drawn between the tuber coxae. Pass it through the ligamentum flavum into the spinal canal. Staying on the midline is critical. The needle is then advanced through the canal until it contacts the dorsal surface of the vertebral body. This usually goes through the conus medullaris, but causes few neurological problems. Withdraw the needle a little into the ventral subarachnoid space. Remove the stylette and hopefully CSF will flow out the needle. If unsure of the needle's position, inject a small amount and then take a film. The most common error is placement of the needle in the epidural space (epiduralgram).

**CERVICAL MYELOGRAM:** The cisterna magnum is entered to do a cervical myelogram. This is a relatively large space where a CSF sample can be taken and contrast medium can be placed. Flex the head and palpate the wings of the atlas, spine of the axis, and the occipital protuberance. Draw a line between the wings and a line from the occipital protuberance to the spine of the axis. Place the needle on the midline 1/2 inch in front of the line between the wings. Go roughly parallel to the caudal wall of the skull and feel for the "pop" of resistance as the needle passes through the dorsal atlantooccipital ligament. Stop when through the ligament. Do not pierce (needle through the brain stem) the dog. Pull out the stylette and look for CSF flow to tell if you are in the right place. Pull the stylette out any time resistance is felt or you are unsure if you are in or not, and look for CSF fluid. If you hit bone, either pull out and start again or walk the needle off the bone. Collect CSF for analysis and then inject the contrast medium. Never aspirate CSF so the spinal cord is not "sucked" into the needle or change pressure in the subarachnoid space resulting in herniation of the brain stem.



# THORACIC RADIOLOGY



placement system that works for you. Then always follow it for standard views to eliminate an unnecessary variable. The 1st rule of thoracic radiography is to have all of the thorax in the film, including part of the neck, part of the abdomen, the vertebral bodies and the sternum. Thoracic films are shot at the peak of full inspiration. The cavity is bigger during inspiration, resulting in less contact between the diaphragm and the heart. In expiratory films the lungs are deflated, thus, more opaque and easy to confuse with pathologic change. Among the problems requiring thoracic radiographs are a cough, heart problems, dyspnea, and abnormal lung sounds.

**VD and DV (as the beam sees it):** place the film so that the right side of the animal is to your left for both VD and DV views. (Minority opinion: Some radiologists place the images in the position they were taken so the VD has the patient's right to the viewer's left [face-to-face] and the DV has the patient's right to the viewer's right. This forces the viewer to remember the

gravitational and projection differences in the two views.)

**Lateral views:** place on the viewer so that the cranial side of the animal is to the left. (Minority opinion: Some radiologists prefer to place the images on the viewer in the manner they were obtained. A left lateral would be viewed with the head to the viewer's right, a right lateral, with the head to the viewer's left. This encourages the viewer to consider gravitational effects.)

**"R" or "L" marker:** on a lateral film of the trunk indicates the side the animal was lying on when the film was taken (right or left lateral recumbency). In VD/DV films, these markers orient the right and left sides of the animal. A quick check of the markers is the apex of the heart, located to the left in the VD or DV views.

**Cat thorax:** similar to the dog, but more triangular and more lucent than the dog's. The heart is also a bit more upright on the lateral view.



# THORACIC RADIOLOGY




Fig. R-17 - Cat - Lat. view of thorax




Fig. R-18 - Cat - DV or VD view of thorax

8. Mediastinum

a. Chest wall

9. Lungs

8. Mediastinum

d. Diaphragm

f. Caudal vena cava

Thoracic spine

g. Aorta

Fig. R-19 - Dog - VD view of thorax

**Evaluating and reading thoracic films:** can be done by an area, organ or a combination of the two. The area approach can be done diagonally from the upper caudal to lower cranial or starting at the center and moving outward, or from the outside to the inside. The organ approach looks at individual organs and organ systems systematically. A list of the organs looked at and a brief hint of for what follows:

## 1. Borders of thorax:

- a. Chest wall
- b. Thoracic spine
- c. Sternum
- d. Diaphragm
- e. Any of the thoracic limbs in the film.

## 2. Heart: shape, size, position and opacity.

## 3. Great vessels: shape, size, position and opacity.

- f. Caudal vena cava
- g. Aorta
- h. Cranial vena cava

## 4. Trachea: for position and diameter.

## 5. Tracheal carina

## 6. Bronchial tree

## 7. Pulmonary vessel: shape, size, position and opacity.

## 8. Mediastinum: for shifts, width and any abnormal density or masses.

## 9. Lungs: for increased or decreased opacities.

## 10. Pleural cavities: for fluid or air.



## DIAPHRAGM - MEDIASTINUM

**DIAPHRAGM:** divides the thoracic and abdominal cavities. The cranial surface of the diaphragm (water density) is easily visualized by its contrast to the adjacent air density of the lungs. The liver and stomach project cranially against the dome of the diaphragm. Being water dense, they are hard to distinguish from the diaphragm. The right and left crura are the dorsal muscular parts of the diaphragm attaching to the ribs and ventral bodies of the lumbar vertebrae.




Fig. R-20 - Diaphragm, lat. view, to different appearances of the crura

**Diaphragmatic hernia:** a severe problem with a 50% fatality rate. The hernia may allow the liver, stomach and/or small bowel to enter the thorax. The herniated organs often are strangulated and release a large volume of fluid.

**MEDIASTINUM:** the space (or imaginary wall) formed between the serosal layers of the two pleural cavities. The space is filled by all the organs of the thorax, except the lungs. The mediastinum divides the thoracic cavity into right and left halves. Unlike the pleural cavities, it is not a closed cavity, but is continuous with the fascial planes of the neck cranially and into the retroperitoneal space caudally. Therefore, air in the mediastinum can travel up the neck or into the retroperitoneal space. The dorsal mediastinum between the lungs is straight. The ventral mediastinum is very irregular in contour, due to the thymus, heart, and vena cavae. The mediastinum is divided into parts:

**1. Cranial part of the mediastinum:** the portion in front of the heart. It contains the esophagus, trachea, thymus (if present), vessels in front of the heart, etc.

• **Esophagus:** usually not visible on a radiograph unless it contains swallowed air (aerophagia), because it is surrounded by the similar water densities of the mediastinum. Air around it, as in pneumomediastinum, will make it visible. Chest survey films of the esophagus should include the cervical and thoracic portions, including the caudal pharynx and cranial abdomen.

– **Esophogram:** barium study of the esophagus and pharynx to evaluate anatomy or disease. Contrast medium is given by mouth and radiographs are immediately taken. The radiographs will delineate longitudinal folds of the mucous membrane in the dog. In the cat the proximal 3/4 of the esophagus has longitudinal folds and the last 1/4th has oblique mucosal folds, giving a “herring bone” pattern.




Fig. R-21 - Divisions of the mediastinum, lat. view

– **Esophageal and pharyngeal foreign bodies:** lodge in four common sites due to constriction of surrounding structures: 1. At the pharyngeal side of the esophageal opening, 2. Cranial to the thoracic inlet, 3. Cranial to the base of the heart, and 4. At cardia of the stomach.

– **Persistent right aortic arch:** congenital defect in the development of the aortic arches. This results in the esophagus passing to the left of the aorta instead of the right. The esophagus is thus ringed by the aorta, ligamentum arteriosum, pulmonary trunk and the base of the heart. This constriction stops food and causes the esophagus to balloon cranial to the base of the heart (or the ring).

– **Megaesophagus:** acquired or congenital dilatation of caudal cervical and thoracic esophagus. This results in ventral displacement of the trachea and heart.

– **Tracheal-esophageal stripe:** a line caused by the air in a megaesophagus and air in the trachea contrasting the adjacent walls of the two structures.

– **Esophageal cone:** the VD appearance of a megaesophagus as it passes caudally to the diaphragm.


• **Sail sign:** an oblique soft tissue opacity due to the thymus in the ventral part of the cranial mediastinum seen in VD or DV views.



# MEDIASTINUM

Cran. mediastinum

Fig. R-22 - Mediastinum, VD view (schematic)




Caud. vena cava

Caud. Mediastinum

Pretracheal lig.

Fig. R-23 - Mediastinum, lat. view (schematic)



Aorta

Tracheal carina

Trachea

Caud. vena cava

Heart

Pretracheal lig.

A sail sign is a normal finding in cats and young dogs.

• **Mediastinal lymph node:** located in the cranial mediastinum dorsal to sternbrae two. These are not seen unless enlarged (e.g., lymphosarcoma, common in cats).

2. **Middle part of the mediastinum:** the portion containing the heart and its pericardial sac, esophagus, bifurcation of the trachea, etc.

3. **Caudal part of the mediastinum:** the portion caudal to the heart; containing the aorta, esophagus, caudal vena cava, and vagal trunks.

• **Pretracheal ligament:** seen on the left side extending from the apex of the heart to the diaphragm. It forms the left side of the caudal mediastinum.

4, 5. **Dorsal and ventral portions of the mediastinum:** divided

by the trachea and the esophagus.

**Visible structures of the mediastinum:** most structures are not seen, except the air-filled trachea and tracheal bifurcation, the heart and the aorta.

**Pneumomediastinum:** air in the mediastinum. This causes an increased radiolucency of the mediastinum contrasting the water densities (esophagus and vessels), making them visible. This air can pass up the fascial planes of the neck or into the retroperitoneal space.

**Mediastinal shift:** moving of the mediastinum to the right or left. Know the normal position of the mediastinum in the VD or DV view so shifts can be detected (i.e. unilateral pneumothorax, pleural effusion, diaphragmatic hernia).

**Mediastinal masses:** change the shape and density of the mediastinum.



# TRACHEA - BRONCHI




Fig. R-24 - Trachea and bronchi, lat. view




Fig. R-25 - Trachea and bronchi, VD view

**Trachea:** an air filled tube within the cranial mediastinum, appearing as a dark line (air). It terminates over the base of the heart at the tracheal bifurcation. In a DV view the trachea should be superimposed over the thoracic spine. The tracheal angle normally is  $15^\circ$  to the vertebral column in the lateral view. Dorsal deviation of the trachea can be due to a cranial mediastinal mass, excess fat, right heart enlargement or an expiratory film (artifact).

**TB, Tracheal bifurcation or carina:** appears as a black, circular density above the base of the heart. It appears darker than the rest of the trachea because of its greater cross sectional area. (This is incorrectly referred to as the carina by radiologists. The carina is actually a ridge at the base of the tracheal bifurcation.)

**Mainstem bronchi or primary bronchi:** the two continuations of the trachea into the lungs. Only the air in the major bronchi normally show up. Due to the thickness of the caudal lobe (more tissue density), the air in the caudal bronchi shows better than the cranial ones. The right middle bronchus is the most ventral (dependent) of the bronchi, thus, the right middle lung lobe is the primary site for aspiration pneumonia. The second most common site is the cranial right lung lobe. A light, inhaled foreign body (grass awn), which moves by air flow and not gravity, will tend to take a straight shot to the right caudal lobe.

**"Cowboy legs":** bowing of the principal bronchi due to enlargement of the left atria or the tracheobronchial lymph nodes in a DV/VD view.

**Separation of principal bronchi in the lateral view:** due to an enlargement of the left atrium. This causes the left principal bronchus to be elevated and both bronchi to be seen as a "V" on its side, extending caudally from the tracheal bifurcation in a lateral view. Normally they are superimposed.

**Bronchogram:** air in bronchi showing up because of fluid in the lung tissue causing a contrast between the tissue and bronchi. They will appear as a black tubes (air) in white (water) surroundings.

**Pulmonary triad:** a lobar bronchus with its associated lobar pulmonary artery and vein. Radiographically, the vessels appear as a pair of water lines separated by an air line (bronchus). Normally the vessels will be about the same size. Pulmonary arteries come from the cranially located right ventricle. The artery to the cranial lung lobe is located dorsal (and cranial) to the vein in the lateral view. The pulmonary veins flow into the caudally-located left atrium, thus, are more ventral (lateral view) and central (VD view). These positions allow a straight shot to their respective heart compartments without crossing each other. In the DV or VD views the pulmonary arteries are at the 4 and 8 o'clock positions.

Fig. R-26 - Trachea and bronchi, VD view




Fig. R-27 - Trachea and bronchi, VD view

**Memory Aid:** Pulmonary veins are always ventral and central (medial).



# TRACHEA - BRONCHI




Fig. R-28 - Right lung lobes, VD view




Fig. R-29 - Left lung lobes, VD view

**LUNGS:** should not be seen on radiographs because they are air densities (black). The left lung anatomically has two lung lobes - cranial and caudal. The cranial lobe, divided into cranial and caudal parts, is considered one lobe by anatomists. Radiologists often speak of 3 left lung lobes (cranial, middle and caudal), the caudal part of the cranial lobe being the radiologist's middle lobe. The right lung has 4 lung lobes -cranial, middle, caudal and accessory both anatomically and radiographically. The cranial lobe of the right lung is seen in front of the cranial lobe of the left lung in a lateral view. This shows up as a separate, round, air filled structure that can be confusing. (Note: the Radiologist's scheme of 7 lung lobes holds in all species, where in the horse the anatomist's nomenclature must consider only 2 lobes to exist.)

**Lobular pattern of lungs and the lung fissures:** normally don't appear unless there is fluid or air in the pleural cavity (as opposed to fluid in the lungs), a collapsed lung or pleural thickenings.

**PLEURAL CAVITIES:** potential not real spaces, because serous tension holds the visceral pleura of the lungs to the parietal pleura of the thoracic wall. Thus, they are normally not visible radiographically. Fluid (pleural effusion) or air (pneumothorax) in the pleural space causes the lungs to separate from the chest wall.

**Cupula of pleural cavity:** the cranial extent of the pleural cavity, normally extending past the first rib.

**Pleural effusions:** fluid in the pleural space (i.e., water, [hydrothorax], air [pneumothorax], chyle [chylothorax] and pus [pyothorax]).

**Scalloped appearance or leafing:** to the lung borders due to pleural effusions pushing the lungs away from the body wall and filling the lung fissures. Fluid lines will be seen in the fissures between the lobes or pseudolobes of the lungs. There will be loss of detail, obscuring the heart and diaphragm

**Pneumothorax:** air in the pleural space.

**Skin folds:** may be mistaken for fluid lines. They usually can be traced past the boundaries of the thorax. Skin folds can also be mistaken for the borders of the lungs, causing a false diagnosis of pneumothorax.




Fig. R-30 - Ventral part of Lung lobes, and fissures, VD view,




Fig. R-31 - Dorsal part of lung lobes and lung fissures, VD view



## LUNG FIELDS

Basically, lungs are evaluated for fluid and air. Radiographically, air is black. A normal lung field has a black background with fluid (soft tissue) structures (vessels) passing through it. Evaluate lungs for an increase (more radiopaque) or decrease (more radiolucent) in density of their parenchyma. These changes can be generalized or localized, solitary or multiple. Compare the two sides of the thorax in the DV view. They should both be of equal opacity.

If an animal is dyspneic (difficult or labored breathing) do not compromise it by taking a VD view, instead take a DV.

**Interstitium or parenchyma:** the framework of the lungs, consisting of muscle tissue, cells making up the alveolar spaces, lymphatics, connective tissue, vessels and nerves. Normally this is a very dark air-filled network because the fine structures do not show up on the radiograph. Disease processes can cause them to enlarge and show up, making the interstitium more opaque.

**Hyperlucent chest:** increased radiolucency to the lung field which can be due to emphysema, hyperventilation, undercirculation or overexposure (artifact).

**Lung patterns with increased radio-opacities:** the different appearance of the lung field with different disease patterns. There are four basic lung patterns: interstitial, alveolar, bronchiolar and vascular. Usually more than one pattern and often all four will be present on the same radiograph. The goal is to determine which is the most predominant lung pattern or patterns. The distribution of the lung patterns can be lobar, isolated to one lobe; diffuse, over whole lung or hilar, around the hilus.

• **Interstitial pattern:** some disease processes cause the interstitial tissue to become more opaque due to the alveolar: interstitial ratio shifting toward the interstitial. As this continues the vessels become harder to see - "fuzzy". In the normal lung, the pulmonary vessels can be seen to the third order branches. Air can still be seen in the lung field because the alveoli are still filled with air. The number one cause of an interstitial pattern on a radiograph is an incorrectly taken film during expiration (expiratory film). This causes the alveoli to be compressed and thus, the interstitium is a larger component of the lung volume (artifact). Pathologic causes of this pattern are - interstitial fibrosis, interstitial (viral) pneumonia, atelectasis, allergic conditions, lung worms. A nodular interstitial pattern has masses differentiated by their size and dispersion and usually means neoplasia.

• **Alveolar pattern:** results from the alveoli filling with fluid. The vessels disappear because the soft tissue around them is filled with fluid. There is no air seen in the lung (alveoli) resulting in the air in the bronchi being highlighted, called an air bronchogram. Causes of alveolar pattern are - pneumonia, pulmonary edema, hemorrhage (contusion).

- **Air bronchogram:** the visualization of the air of the bronchi due to the lung being filled with fluid. The vessels disappear because the surrounding lung is filled with fluid.

• **Bronchiolar pattern:** enlarged or increased density of bronchiolar walls.

- **Peribronchiolar cuffing or infiltration:** thickening of the bronchiolar wall and space around it. End on, such bronchi look like "donuts". In sagittal section they look like "tram lines" (train or tram tracks). The normal arborization pattern to the normal bronchi appears like a tree with branches that taper. In a bronchiolar pattern the limbs may appear to be pruned.


• **Vascular pattern:** the fourth pattern; the vessels are either normal, increased or decreased. In a hypervascular pattern the vessels are larger than normal. They may become tortuous. Think of heartworm disease when large tortuous arteries are seen. When the veins are larger than the arteries, think of the left heart failing to deal with its preload.

**Pulmonary edema:** fluid in the lungs resulting in increased radiographic opacity of alveolar pattern.

### SUMMARY - LUNG PATTERNS

#### Interstitial pattern:


- slightly denser lung field (variable)
- Air evident in lung
- Vessels fuzzy, but evident



#### Alveolar pattern:


- Opaque lung field
- No air in the lung
- No vasculature
- Air bronchogram (black worm holes in white apple)

Air bronchogram



#### Bronchiolar pattern:

- Peribronchiolar cuffing
- Donuts
- Tram lines



#### Vascular pattern

- Enlarged vessels (hypervascularity)
- Smaller vessels (hypovascular)
- Normal vessels
- Loss of symmetry in size of arteries versus veins





# HEART




Fig. R-32 - Lat. view - clock faced analogy




Fig. R-33 - VD view - clock faced analogy

**Heart:** fills about 75% of the thorax in a lateral view and two thirds in a VD/DV view. Minimal heart enlargement will be hard to determine. The heart appears as a solid disk because it is muscle filled with blood (both water densities). Therefore, you will evaluate the borders or silhouette of the heart, not its cavities. (The heart should be less than 1/2 the width of the VD thorax at the level of the 9th rib.)

## CHAMBERS OF THE HEART

**Chambers of the heart:** can be imagined on a lateral view by drawing two crossing perpendicular lines. The first one follows the axis of the heart and passes through the apex. This gives a rough estimate of the location of the chambers. Another learning aid is the clock-faced analogy. "Be very careful of this approach", it is not good when trying to figure out the chambers in heart enlargement. This is because the right ventricle wraps almost completely around the left ventricle, except for the caudal side. In right heart enlargement it can even project caudal to the left ventricle. In spite of this, the analogy can still aid the student in a three dimensional interpretation of the radiographs of a normal heart. Of special value is the location of the pulmonary trunk, aortic arch, apex and left auricle.

## Heart - clock face analogy:

### VD view:

- 11-1: Aortic arch
- 1-2 o'clock: pulmonary trunk (MPA)
- 2-3 o'clock: left atria appendage (auricle)
- 2-6 o'clock: left ventricle
- 5 o'clock: apex
- 6-9 o'clock: right ventricle
- 9-11 o'clock: right atria

### Lateral view:

- 1-2 and 9 o'clock: waist of heart
- 11-12 o'clock: aortic arch
- 1-2 o'clock: left atrium
- 2-6 o'clock: left ventricle
- 5 o'clock: apex
- 6-9 o'clock: Right ventricle
- 9-11 o'clock: right atrium



# HEART

## LATERAL VIEW

1. **Cranial vena cava:** located cranial to the heart, usually its ventral edge is all that can be seen.

2. **Caudal vena cava:** seen caudally between the heart and the diaphragm.

**Right side heart:** cranial part of the heart.

3. **Right atria:** upper part of the cranial heart.

3'. **Right auricular appendage:** wraps around the front of the outflow tract.

4. **Right ventricle:** lower part of the cranial heart.

5. **Pulmonary trunk or main pulmonary artery (MPA):** can't be seen on a lateral projection because it is superimposed.

**LEFT HEART:** makes up the caudal aspect of the heart.

6. **Left atrium:** located on the upper part of the caudal aspect of the heart.

6'. **Left auricle:** superimposed over the middle of the heart so it is not visualized in the lateral or VD views.

7. **Left ventricle:** makes up the ventral part of the caudal aspect of the heart and the apex.

8. **Aortic arch:** comes out of the base of the heart.

9. **Brachiocephalic trunk and left subclavian artery:** come off the arch of the aorta and travel cranially. These can't be seen, unless there is air in the mediastinum (pneumomediastinum).

10. **Descending aorta:** travels caudally high in the thorax against the vertebral bodies to the abdomen. It is easily seen.

11. **Cranial waist:** located at the junction between the cranial vena cava and the right atrium. In this area there is the arch of the aorta, right auricular appendage and pulmonary trunk. Enlargement of any of these structures could cause a bulge and loss of the cranial cardiac waist.

12. **Caudal waist:** the coronary (atrioventricular) groove between the left atrium and left ventricle.

13. **Sternopericardiac ligament:** connects the ventral pericardium to the sternal floor of the thorax.

## DV/VD VIEW:

1. **Cranial vena cava:** doesn't show up because of all the other structures in the cranial mediastinum.

2. **Caudal vena cava:** extends between the right side of the heart

and the diaphragm on the right side.

3. **Right atria:** on the cranial side of the heart.

4. **Right ventricle:** makes up the cardiac silhouette from the apex along the right side.

5. **Pulmonary trunk** (called the main pulmonary artery [MPA] by radiologists): arises on the left cranial side of the heart at the 1 - 2 o'clock position.

6. **Left atrium:** summated over the caudal heart directly above the left ventricle. It is located just caudal to the tracheal bifurcation.

6'. **Left auricle:** superimposed over the middle of the heart so it is not visualized unless it is enlarged, and then it projects out at 2 to 3 o'clock position.

7. **Left ventricle:** makes up the caudal half of the left silhouette of the heart.

7'. **Apex:** part of the left ventricle at the 5 o'clock position. It points to the left in the DV/VD view.

8. **Aortic arch:** not visible in the DV view because it is summated over the cranial mediastinum. It is located at the 11 - 1 o'clock position.

10. **Descending aorta:** a line representing the left edge of the aorta is all that is seen due to overlapping densities. This edge should be seen in a good radiograph.

11. **Phrenicopericardiac ligament:** makes up the left margin of the mediastinum.

**Contrast studies of the heart (angiocardiography):** radiographs of the heart taken while a radiopaque contrast medium circulates through it. Insert a canula into the external jugular vein and into the right atrium with the aid of a fluoroscope. Inject the contrast medium quickly as a bolus and take a film. This lights up the right side of the heart. The right ventricle covers the cranial part of the cardiac silhouette. It actually covers most of the silhouette, except the caudal part. The pulmonic valve shows up as little black indentations in the beginning of the pulmonary trunk (MPA). The pulmonary arteries are seen extending away into the lung fields.

**Left side of the heart:** cannulate the common carotid in the dog. Thread the catheter into the aorta and into the left ventricle.

6. **Aortic sinus:** (Sinus of Val Salva) the pockets in the base of the aorta behind the aortic semilunar valve leaflets. The coronary arteries arise from the aortic sinuses as the first branches of the ascending aorta. The brachiocephalic trunk is the first branch of the aortic arch. The left subclavian artery is the second branch of the aortic arch.



Fig. R- 34 - Heart, lat. view





Fig. R- 35 - Heart, VD view



# EVALUATING HEART RADIOGRAPHS

**2/5-3/5 rule:** Draw a line from the "carina" of the trachea to the apex of the heart in a lateral view. Approximately 2/5th of the bulk of the heart should be in back of the line and 3/5th should be in front of the line. More than 2/5th behind the line infers left heart enlargement. More than 3/5th in front of the line infers right heart enlargement.

**Sternal contact:** there should be three sternabrae contacted by the cardiac silhouette. More than this infers right heart enlargement. This is not as reliable as the 2/5th-3/5th rule.

**Signs of enlargement of the different chambers of the heart:** the left ventricle is likened to a cylindrical pump and the right to a bellows. The right ventricle responds by dilatation quite readily. The left ventricle usually responds initially with concentric hypertrophy which may not be noticed without contrast studies. The thin-walled atria respond readily by dilatation.

**Right atrial enlargement - Lateral view:** elevation of the trachea and loss of the cranial waist. DV projection: enlargement of the 9 to 11 o'clock silhouette of the heart.

**Right ventricular enlargement:** seen as a cranial bulging on the lateral view with more sternal contact. In a VD view, it will bulge cranially and to the right (backwards or reverse "D"). Right ventricular enlargement causes fluid to back up into the abdomen and extremities. Pulmonic stenosis or heartworm disease can cause right ventricular enlargement.

- Lateral projection
  - increased sternal contact
  - elevation of the trachea
  - elevation of the caudal vena cava
  - elevation of the apex off the sternum
- DV projection:
  - rounded right cardiac border
  - inverted "D" sign with marked enlargement
  - apex more to the left

• **Heart worms:** located in the pulmonary arteries and right ventricle. This will cause enlargement of the right ventricle and enlarged, tortuous pulmonary arteries in reactions to heart worms.

**Left atrial enlargement:** will cause tracheal and left mainstem bronchi elevation in the lateral view. These are not very noticeable in the cat. In the DV view the auricle will project beyond the normal cardiac border between the 2-3 o'clock position. Enlargement can cause the mainstem bronchi to spread out ("cowboy legs") (VD).

- Lateral projection:
  - elevated trachea and carina
  - separation of mainstem bronchi (left dorsal to right)
  - enlarged atrium and straight border
- DV projection:
  - auricle projects at 2-3 o'clock position
  - increased density of the left atrium
  - "cowboy legs" (mainstem bronchi)

**Left ventricular enlargement:** seen as a caudal bulging on the

lateral view which eliminates the caudal waist. The caudal border of the heart is normally straighter and more vertical. The apex will also enlarge, elevating the heart, which in turn will elevate the trachea. On a VD view, it will bulge caudally and to the left, moving the apex to the right. This is common in mitral valve insufficiency.

- Lateral projection:
  - loss of caudal waist
  - Caudal bulging to the caudal border of the heart
- DV projection:
  - rounding of left ventricle border (3 - 5 o'clock)
  - apex shifted to right

• **Mitral valve insufficiency:** will result in left ventricle enlargement.

## Signs of heart chamber enlargement - indicate:

### Lateral view

- Apex off the sternum: right ventricle
- Elevation of the trachea: right or left atria, left or right ventricle
- Separation of the main stem bronchi: left atrial
- Loss of caudal cardiac waist: left atria
- Bowing out of caudal border - left ventricle

### DV view

- Backwards "D" - right ventricle
- "Cowboy legs" - left atria

**VESSEL EVALUATION of CARDIAC DISEASE:** Cardiac disease is basically a pump failure. To avoid overinterpretation of the cardiac bulges, look for signs of hydrolic failure. If the right heart fails, the preload (systemic venous return) will overload. Signs are enlarged caudal vena (post) cava (should be the same size as the aorta), effusion in the peritoneal and/or pleural spaces. Left heart failure will result in back up of blood into the preload - pulmonary venous drainage. Therefore, you should see the pulmonary veins larger than the corresponding arteries, enlargement of the left atria and eventually pulmonary edema. If you see none of these signs, then there may be cardiac lesions, but the heart is still in compensation.

## VESSELS - CARDIAC DISEASE

Right heart failure -	Enlarged caudal vena cava Pleural or peritoneal effusions
Left heart failure -	Enlarged pulmonary veins Enlarged left atria Eventually pulmonary edema



## ABDOMINAL RADIOGRAPHS

**Abdominal radiographs:** taken during the pause after expiration. Positioning is very important and there should be no motion. Use the right or left lateral projection consistently to eliminate this as a variable. High latitude films are taken to see subtle shades of gray for the different water densities. This also burns through the distracting ribs in the cranial abdomen. Standard views of the abdomen are the lateral and VD/DV views. Standing lateral views use a horizontal beam direction through a standing animal to detect fluid levels in bowel or abdomen. Special lateral recumbency views direct the beam horizontally through a laterally recumbent animal in the VD direction. These are used to detect small amounts of air in the abdomen. Oblique views are shot through the animal placed in DV or VD position and rotated 15 to 30°. These are used to get a more complete examination of the esophagus, stomach, colon and urinary bladder by moving them away from the spinal column.

**Peritoneal detail:** depends on serosal fat surrounding the surface of the organs. Fat is radiographically less dense than water (appears darker), thus, contrasts the water densities. Fat is deposited in the omentum, the falciform ligament and in the retroperitoneal space.

- **Loss of serosal detail:** happens when fat is absent from the abdomen in neonatal or emaciated animals and when there is fluid in the abdomen. This causes the abdomen to have an overall gray appearance like "ground glass". The difference between absence of fat and extra fluid is assessed by the shape of the abdomen. A thin dog will be gaunt or "tucked up". A dog with a lot of peritoneal fluid will have a full, rotund or pendulous abdomen. Young dogs have poor serosal detail because they don't have the right type of fat. This is normal in dogs under 4 months of age.

- **Ground glass appearance:** classical description of an overall gray abdomen due to loss of serosal detail. This can be overcome by adding contrast material in the abdomen.

- **Focal loss of detail:** small areas where serosal detail is poor while the rest of the abdomen has good detail. An example would be pancreatitis with focal peritonitis. This causes loss of detail in the right cranial quadrant of the abdomen where the pancreas resides.


**Gas:** within the organs allows differentiation between the inside of the organs and helps to identify them (e.g., stomach).

**Hydroabdomen(ascites):** fluid in the abdomen due to hypoproteinemia, liver failure, heart failure, renal failure, portal hypertension.

**Kidneys** can become invisible if there is surrounding fluid in the retroperitoneal space (ruptured ureter, abscesses).

**Air in the abdomen:** will go to the independent site. Air first appears against the diaphragm. Usually only the lung side of the diaphragm is seen because the abdominal side is summated with the liver tissue. If both sides can be seen there is air in the abdomen. Horizontal views are used to detect a small amount of

air in the abdomen. The animal is placed in left lateral recumbency (right side up). A small amount of gas present will be detected between the right lobes of the liver and the diaphragm.



**POSITIONING:** The right lateral view (left lateral recumbency) is preferred to the left lateral view (right side up) to avoid gas in the fundus, which confuses what is seen. This view puts the fundus down so that gas will collect in the smaller pylorus (located on the right, thus, independent in this view).

**Positioning of film:**

- Center the umbilicus in the center of the film
- Include the entire abdomen from the pelvic inlet to the diaphragm
- Put the thickest end towards the cathode because of the heel effect

**CONTRAST STUDIES:** use of opaque media (positive contrast agents) or gas (negative contrast agent) to delineate portions of the GI tract. Survey radiographs must always precede any contrast studies.

**Negative contrast agents:** usually CO<sub>2</sub> or air, are used to see where organs are, such as the stomach. Blow air into the stomach or give the animal a carbonated beverage.

**Positive contrast agents:** mineral densities that appear very white on radiographs. They are used to detect or confirm gastric or small bowel disease and to outline size, shape, and position of segments of the GI tract. Barium Sulfate is a positive contrast agent. It is inert in the lungs but causes granulomatous responses in the peritoneal cavity. Avoid it if there is a possibility of perforation of the GI tract. Use barium in the stomach in case of aspiration into the lungs. Iodine is also a second positive contrast substance that is extremely hyperosmotic and can cause pulmonary edema but has little effect on the peritoneum. Because of its hyperosmolarity it dilutes itself decreasing its radio-opacity. It gives poor mucosal detail compared to barium. It is indicated if there is suspected perforation of the stomach.

**COMPRESSION STUDIES:** squeeze the contents of the abdomen with a wooden spoon or piece of Plexiglass to separate different structures, while taking radiographs.



# ABDOMENAL RADIOGRAPHS




Fig. R-36 - Lat. view of abdomen

**Viewing abdominal films:** just as in the thorax, viewing needs to be systematic and consistent (done the same way ever time). Frame of the picture first, look at the diaphragm, spine, musculature of sublumbar soft tissue, part of the pelvis in film, ventral body wall, falciform fat area and the caudal thorax. Look at the location of organs normally not seen on radiographs. If seen, something is amiss. Therefore, it is important to know anatomically where organs are located. Mobile structures of the abdomen, such as the small and large intestines, can be displaced. A displaced organ may be normal with an invisible, abnormal structure displacing it (indirect evidence).

## BOUNDARIES OF ABDOMEN:

- Cranial - diaphragm
- Caudal - pelvic inlet
- Dorsal - spinal column
- Lateral and ventral - abdominal muscles
- Ventral - rectus abdominis muscle

**QUADRANTS:** draw two imaginary lines on the DV abdominal view. The first, down the midline and one perpendicular to it through the umbilicus. This divides the abdomen into four quadrants. Knowing what is in each quadrant helps viewing radiographs. The greatest number of individual structures are located in the cranial quadrants.

## Lateral view of abdomen:

1. Liver abuts the diaphragm cranially.
2. Stomach is caudal to the liver.
3. Spleen: its distal part is seen on end as a triangle in the ventral abdominal wall just caudal to the liver.
4. Right kidney: seen high in the abdominal cavity. Its cranial pole is embedded in the caudate process of the liver, thus, not visualized.
5. Left kidney: 1/2 kidney length caudal to the right kidney and usually can be completely visualized. It is also usually somewhat ventral to the right kidney.
7. Transverse colon: crosses the abdomen caudal to the stomach and is seen end on if it contains any gas.
8. Descending colon: continues from the transverse colon caudally to the pelvis where it becomes the rectum.
9. Spleen: in ventral abdomen caudal to the liver.
10. Urinary bladder: caudoventral abdomen.

**Abnormal mass:** may be caused by enlargement of any structure present in the area.



# ABDOMINAL RADIOGRAPHS




Fig. R-37 - VD/DV view of abdomen

## DV/VD view:

- A. Diaphragm
- B. Liver: between stomach and diaphragm
- C. Fundus of stomach: located on the left side of the abdomen.
- D. Body of the stomach: crosses the midline.
- E. Pylorus: located on right side of the abdomen in dogs; on midline in cats.
- F. Duodenum: passes down the right side of the abdomen.
- G. Small intestines: hard to follow.
- H. Cecum: located on the right side.
- I. Ascending colon: located on the right side.
- J. Transverse colon: crosses midline from right to left.
- K. Descending colon: travels down the left side.
- L. Spleen: located caudal to the stomach on the left side.

## Quadrants - organs

### Right cranial quadrant

Pylorus  
Pancreas  
Duodenum  
Right lobes of liver  
Gall bladder  
Ascending colon  
Right kidney

### Left cranial quadrant

Fundus of stomach  
Spleen  
Left kidney

### Right caudal quadrant

Cecum  
Small intestine  
Right ovary  
Right uterine horn

### Left caudal quadrant

Descending colon,  
Left ovary  
Left uterine horn



## ABDOMEN - RADIOGRAPH

**Stomach:** its radiographic appearance varies with the position of the patient and amount of filling. Air will move upward, while fluid is gravity dependent. Do not confuse fluid in the stomach with a mass (ball). The unfilled stomach is normally within the rib cage (doesn't project past the last rib). A foreign body can act as a ball valve in the pylorus and cause projectile vomiting. The cat's stomach is J-shaped. The cat's pyloric antrum is to the left of midline. The peristaltic rate of the stomach is 2 to 4 a minute. During fluoroscopy, look for emptying, contraction and function. A thumb print pattern is depressions in the wall of the stomach indicating an infiltrative process. Stomach rugae are visible with contrast studies. Gastric distention can be extremely large, causing great pain and possibly a rupture of the stomach.

- Right lateral recumbency (left side up) - air in fundic region located in the dorsal abdomen on the left side.
- Left lateral recumbency (right side up): air in pyloric region located in the ventral, right side of the abdomen.
- DV projection (dorsal side up): gas in fundic region.
- VD (ventral side up): gas will be in pyloric antrum and body, which are in the ventral part of the abdomen.

**Stomach axis:** can be seen if there is gas in the stomach. Clinically the axis of the stomach is used to evaluate the size of the liver. In the lateral projection the normal position of the stomach axis is between a line drawn vertical to the spine and a line parallel to the ribs. The pylorus is superimposed over the body or slightly cranial to it (10-11th ribs). In the VD or DV view the axis of the stomach is perpendicular to the spine.

**Double contrast studies:** use of air and contrast material in an organ. Barium is a good coating material providing good mucosal detail. The rugae of the stomach should be about the size of the valleys between them.

**DESCENDING DUODENUM:** located on the right side of the abdomen. It is classically larger than the rest of the small intestines. Multiple views must be seen on contrast studies to make a diagnosis of duodenal problems.

- Lymphatic craters: normal depressions in the wall of the duodenum that are seen in contrast studies. They are often mistaken for ulcers, and have been called pseudo-ulcers

**SMALL INTESTINE:** train yourself to routinely look for individual loops. The serosal surface of small intestines is smooth. The thickness of the bowel wall is 1/9 to 1/8th the width of the distended lumen. Mucosal detail can only be evaluated with contrast material or in air-filled segments.

- Rule of thumb for intestinal size: equals the height of a lumbar vertebral body or two rib widths. Small intestines wider than 2 1/2 rib widths may be abnormal.

- Sentinel loops: large distended loops of bowel named because

they indicate trouble.

- Intraluminal foreign bodies: in the small intestine will be noticed by finding a gas filled loop that ends abruptly.

- Linear foreign bodies in the small intestine: items, such as string, will cause the bowel to bunch up on the string due to peristalsis. This is very apparent with a contrast study. Do not pull on a string sticking out of the mouth or anus or it can saw through the bunched up bowel (peritonitis). Remove surgically.

- Ileus: multiple loops of gas-distended bowel.

**LARGE INTESTINE:** usually contains more gas than the small intestine. Food and gas make the large intestine much easier to see and follow.

**Cecum:** in the dog appears as a corkscrew shape on the right side of the abdomen at the level of L<sub>3</sub>. It can be seen on survey films if it contains some intraluminal gas. In the cat the cecum is a small cone-shaped structure. It is not visible on survey films.

**Ascending colon:** extends for a short distance from the cecum up the right side of the abdomen to be continued as the transverse colon.

- Right colic or hepatic flexure: the point at which the ascending colon becomes the transverse colon.

**Transverse colon:** crosses the abdomen from right to left and continues as the descending colon.

- Left colic or splenic flexure: where the transverse colon becomes the descending colon.

**Descending colon:** on the left side. Fecal material can usually be seen in it.

**Rectum:** in the pelvic cavity.

The colon often provides clues to what is going on around it. It is filled with either radiopaque fecal material or gas, making it generally quite visible. The colon is relatively mobile because of its relatively long mesentery. If it is focally displaced, look for what is displacing it. An enlarged left kidney may displace the left colic flexure. The pancreas and right kidney may displace the right colic flexure.

**Medial iliac lymph nodes:** located at the termination of the abdominal aorta and usually not seen radiographically.

**LIVER:** The largest organ in the abdomen, it is located in the cranial quadrants behind the diaphragm and in front of the stomach. Normally the edges are sharp. In adult dogs the liver doesn't extend past the last rib. It is relatively larger in the young animal. The liver is contrasted cranially by air filled lungs and caudally by gas in the stomach.



## ABDOMEN - RADIOGRAPH

**Gall bladder:** a pear-shaped structure lying between the quadrate lobe and the right medial lobe. It is normally not visible unless it contains stones or gas.

**Renal impression:** cups the cranial pole of the right kidney. It is part of the caudate process of the caudate lobe.

Clinically the axis of the stomach is used to evaluate the size of the liver. Assess stomach fullness. A full stomach can fool you.

- **Enlarged liver:** indicated if the stomach extends back and exceeds the angle parallel to the ribs.

- **Small liver:** indicated if the axis of the stomach inclines cranially in front of the line perpendicular to the spine. Small liver size can be due to chronic liver disease or a portal-caval shunt.

- Try to 3-dimensionally visualize the size of the liver from the lateral and the VD view, using the stomach axis.

A crisp, triangular caudal margin of the liver in a left projection indicates normal liver. A blunt and rounded caudal liver margin infers liver enlargement.

**Paradoxical liver:** when the stomach slants cranially, indicating a small liver, but the caudal end of the liver extends past the costal arch indicating a large liver. It has a crisp triangular caudal margin inferring a normal liver. This is a normal occurrence in older dogs due to gravity causing slumping of the liver (splachnoptosis). The liver is of normal size.


**Liver enlargement:** can be diffuse or focal. Enlargement of the right liver lobe will extend past the costal arch in the lateral projection. It will appear as a large area opacification in the right cranial quadrant. This can be confused with splenic enlargement. Masses in the center of the liver can distort the shape of the stomach.

**PANCREAS:** a soft tissue density normally not visible radiographically because of its small size and its similar density to the surrounding structures. Cranial displacement of the duodenum or pylorus may indicate pancreatitis. Pancreatic masses of the body and right limb of the pancreas will be in the right cranial quadrant. The mass may not be seen due to focal loss of serosal detail because of surrounding inflammation and a small amount of fluid. Contrast studies may show displacement of the pylorus and the descending duodenum by a pancreatic mass. Left limb pancreatic disease is also possible and is located in the left side of the abdomen.

**SPLEEN:** a tongue-shaped organ loosely attached to the greater curvature of the stomach in the left cranial abdomen. The tail of the spleen extends caudally; ventral and medial to the stomach. The head of the normal spleen is attached loosely to the stomach by the gastrosplenic ligament. The head is normally tucked over in the left cranial quadrant of the abdomen with the kidney right behind it in the DV view. Splenic enlargement assessment is completely subjective, and depends on experience. The spleen's

size is variable depending on the amount of engorgement. Barbiturates cause normal physiological enlargement of the spleen. Disease processes can cause the spleen to be enlarged normal-shaped spleen. Splenic tumors can be found in many places in the abdomen because the spleen is very mobile.

- **Lateral projection of the spleen:** appears as a soft tissue triangle in the middle of the ventral abdomen just behind the liver.



- **VD projection:** the head of the spleen appears as a triangular shape adjacent and caudal to the stomach. Occasionally it may be seen superimposed over the caudal portion of the right kidney.

**MESENTERIC LYMPH NODES:** enlarged lymph nodes located in the root of the mesentery. Enlarged mesenteric lymph nodes can give a radiographic enlargement in the middle of the abdomen.

- Root of the mesentery is at about the level of L<sub>2</sub>.

**KIDNEYS:** located in the dorsal cranial part of the abdomen. Normally both are smooth and of equal size and shape. Visualization of the renal borders is dependent on the amount of perirenal fat present. Cat's and obese dog's kidneys are easier to see than young and emaciated dogs. Compare the kidneys for size. Check that there are two, especially if you are removing one.

### LOCATION

- Left kidney

Dog: L<sub>2</sub> - L<sub>4</sub>  
Cat: L<sub>2</sub> - L<sub>3</sub>

- Right kidney

Dog: T<sub>13</sub> - L<sub>3</sub>  
Cat: L<sub>1</sub> - L<sub>4</sub>

### SIZE

Dog: 2.5 - 3.5 times the length of lumbar vertebrae L<sub>2</sub> on VD view.

Cat: 2.5 - 3 times the length of L<sub>2</sub>.



## GENITALIA - RADIOGRAPH

**URETERS:** not visible on survey films because of their density and small size.

**ADRENAL GLANDS:** not visible on survey films.

**URINARY BLADDER:** has a vertex, body and neck. Normally it is an oval shape in the dog and elliptical in the cat. It is located in the caudal ventral abdomen, just cranial to the pubis and ventral to the rectum and colon.

**URETHRA:** not seen on normal survey radiographs.

### FEMAL GENITAL TRACT:

- **Ovaries:** small, thus, not usually seen on radiographs. If enlarged a mass may be apparent caudal to the kidney on the DV view or in the center of the abdomen on the lateral projection. If they become very enlarged, they may stretch their ligamentous attachment and migrate more ventrally.

- **Uterus:** if nongravid, can't be seen on survey films. In obese dogs and cats the uterine body can be seen between the rectum and the bladder. The uterus is often radiographed to determine pregnancy and number of fetuses by visualizing and counting fetal skulls.

**MALE GENITAL TRACT:** the internal genitalia are not seen on survey films. The penis and testicles can be seen on the abdominal wall, but they are best assessed by physical examination.

- **Os penis:** in close association with the penile urethra.

- **Scrotum:** contains the testicles, the epididymis, and ductus deferens.

- **Prostate gland:** normally located in the pelvic cavity, around the neck of the bladder, ventral to the rectum and dorsal to the pubis. It is spherical to oval. Its position is influenced by age. It should not extend past the pelvic inlet. A prostate can be mistaken for a bladder. It is hard to see prostatic enlargement on a VD view because it is summated with the rectum, which is often filled with feces. The lateral view is better. Dorsal displacement of the colon can indicate prostatic enlargement. The bladder will not displace the colon.

**SUBLUMBAR LYMPH NODE:** located at the termination of the aorta in the caudodorsal abdomen. Enlargement of these lymph nodes will result in ventral displacement of the colon.

**ORGANOMEGALY:** there are three organs in the abdomen that normally enlarge.

- **Stomach:** can distend a tremendous amount due to the amount of food in it. It can take up 1/3 to 1/2 of the abdomen making it hard to interpret the other structures. This causes displacement of the GI tract and the spleen caudally. Gastric dilatation due to a


disease process will also look like this. Prior to radiography the patient should have nothing per os from 12 to 24 hours and be given cleansing enemas to remove material from the descending colon. Food, relatively radiopaque, will mask anything that is in the same plane.

- **Urinary bladder:** can fill up to one third of the abdomen pushing everything cranially. Walk the dog and allow it to urinate before radiography.

- **Uterus:** A gravid uterus can occupy up to half the abdomen.



# EQUINE LIMB RADIOGRAPHS



## Rules for reading equine limb radiographs:

1. **Distance:** view radiographs first from a distance to get the overall picture. Then move closer.
2. **A minimum of two views:** required to make three dimensional sense of a two dimensional image (radiograph).
3. **Silhouette:** when radiographing a lesion try to silhouette the lesion (place it on an edge) where there is greater contrast between the lesion and the surrounding structures.
4. **Shoot enough films** when you travel in the field to avoid second trip.
5. **Bone preps:** when reading films use articulated bone preparations to line up the different views correctly.

**Bone preps:** radiologists use articulated bone preparations to line up different views exactly. This allows them to check the exact part of each bone in question. This is especially true of the hock and the carpus. Radiographs of the carpus and tarsus have a lot of confusing lines. Use an articulated specimen to determine if they are normal. The different overlapping lines are caused by the bones not being level, so the same joint may have different representative lines on the radiographs. The complicated configurations of the hock and carpus and possible subtle lesions make

referring to bone preps essential.

**Carpal radiograph views:** Localizing a lesion in the carpus or tarsus requires four standard views because the carpus and tarsus are so large. Some problems require even more views from different angles. The four standard views are - DP, LM, DLPMO and DMPLO. The different views (projections) are named for the entrance and exit points of the beam. Although the DMPLO is actually shot from the lateral side, and logically should be called a PLDMO, it is not. The obliques usually aren't all 45° off of 0° or 90° because different problems require different angles to silhouette them.

- **DP (dorsopalmar view) or AP (anterior/posterior):** 0° - 180° degrees, the beam passes through the dorsal side and out the palmar side.
- **Lateral or LM (lateral-medial view):** 90° - 270°, the beam passes through the lateral side and out the medial side.
- **DLPMO (dorsolateral-palmaromedial oblique) or medial oblique:** 45° angle (45° - 235°); shot from the dorsolateral to the palmaromedial side.
- **DMPLO (Dorsomedial palmarolateral oblique) or lateral oblique:** 135° - 314°; shot from the palmarolateral to the dorsomedial side.



# EQUINE LIMB RADIOGRAPHS


## Supplemental views:

- **Flexed lateral view:** usually added to the four standard views.

**Skyline or tangential view:** dorsoproximal views of which there may be at least three.

It is common to deal with at least ten films of the carpus or tarsus.

To learn the different views of the carpus, draw a schematic of the carpus as two ellipses, as shown below. The smaller ellipse represents the accessory carpal bone, which is on the lateral and palmar side of the carpus. Using the accessory carpal bone, label the sides of the joint and the degree they correspond to as follows: dorsal surface corresponds to 0°, palmar - 180°, lateral - 90° and the medial - 270°.



The configuration of the accessory carpal bone and the amount it overlaps the other carpal bones differs in each view. These facts can be used to identify the different views.

**DP (Dorsopalmar) view:** the accessory carpal is narrow and completely overlapped by the rest of the carpus.


**LM (lateromedial) view:** the accessory carpal is as large as possible and slightly overlapped.

**DLPMO:** the accessory carpal is completely silhouetted.


**DMPLO:** the accessory carpal is completely overlapped

Identifying the DP and LM views is easy with a little practice. Students have the most problem with the oblique views. From the configuration and amount of overlap, draw the direction of the beam through your drawing (do both entering the dorsal surface). Then read the labelled surface on either side of your entrance and exit points to name the oblique views.


If the accessory carpal bone is completely overlapped, your drawing should look like this and is a DMPLO.



If the accessory carpal is completely silhouetted then your drawing should look like the one below and is a DLPMO.



To understand which sides of the carpus are silhouetted, draw the beam passing through the carpus and then box the sides of the carpus parallel to the beam. Read the sides of the carpus on either end of your box for the obliques and the side your box is on for the DP and lateral. These will be the sides silhouetted for each view. Another way to remember which side each oblique view silhouettes is to take the name of the view and switch the combination of the entrance and exit points, the DLPMO, dorsolateral-palmaromedial oblique silhouettes the dorsomedial and palmarolateral sides. The dorsomedial-palmarolateral oblique silhouettes the dorsolateral and palmaromedial sides.



DMPLO - Silhouettes DM & PL sides



# CARPUS

1st carpal bone: may or may not appear, the 5th is rarely (never say never) seen.

Use the laterally-located accessory carpal bone to identify the other carpal bones. A carpal bone on the same side as the accessory carpal bone is on the lateral side; if it is on the opposite side it is medial.

Carpal chips: running causes hyperextension of the carpus and may lead to chip fractures. The most common sites, in order of occurrence, are in the areas where the following bones come together:

- the radius and the radial carpal bone
- the radial carpal bone and the third carpal bone
- the intermediate carpal bone and the radius

Chip fractures are seen when the beam passes through the fracture line, thus, the need for multiple views. They usually are not seen on DP view. The lateral view may show them and the flexed lateral even better. The oblique views show them best. Skyline views may also show them to advantage.

Evaluating joints of the carpus: look at the edges and see if they are sharp (clean). Exostosis is bone growth that makes the edges fuzzy. Lipping is buildup of exostosis on the contours of bones.

DP view: silhouettes structures on the lateral and medial sides of the carpus. The accessory carpal bone is shot on end so it appears flat and very dense. This is a good view for evaluating whether the joint spaces have narrowed. Each one of the carpal bones is clearly seen in this view.

- Radial and second (first if present) - medial side.
- Ulnar, accessory & fourth - lateral side.
- Intermediate - center (between the radial and ulnar)

Third carpal bone: has a palmar projection that can appear like a different bone in the DP view.

Lateral view: the accessory carpal bone located on the palmar side is very round and not very dense. It has very little overlap with the other bones. Surfaces on the dorsal and palmar sides are silhouetted.

Flexed lateral view: opens up the joints. The antebrachial carpal joint opens wide, the middle carpal joint about 50% as much, and the carpometacarpal joint very little. This view removes the contacts between the rows of carpal bones, thus, places them in silhouette. The intermediate carpal rises and the radial drops in a flexed view. This will help decide which bone has the chip seen in a normal lateral view.

Oblique views: somewhere between the DP and the lateral views.

DLPMO (dorsolateral-palmaromedial oblique) or medial oblique: 45° - 225°, the accessory carpal bone is maximally silhou-

etted. The palmarolateral and the dorsomedial edges of the carpus are silhouetted. The commonly fractured radius, radial and 3rd carpal bones are silhouetted on the dorsomedial surface, making this the best view to evaluate them.

DMPLO (palmarolateral-dorsomedial oblique) or lateral oblique: the accessory carpal bone is completely overlapped. The dorsolateral and palmaromedial surfaces are silhouetted. The second carpal bone on the 2nd splint bone are not overlapped. This is the common site of splints, thus, the best view to visualize splints in the forelimb. In the hindlimb a DLPMO is the view for splints between the 3rd and 4th metatarsal bones.


Skyline view: The carpus is flexed maximally and shot across the dorsal surface of the bones. These highlight slab fractures so you can see straight through their radiolucent line. There are three different skyline views: distal radial skyline, proximal carpal skyline, and distal carpal skyline. These highlight structures of the same name. These will highlight very small chip fractures or slab fractures. To interpret skyline views the exact angle used when taking the film must be known.




# TARSUS

Draw a schematic view of the dorsal surface of the tarsus to learn the bones. Label the bones and the joint spaces.

- Calcaneus is lateral
- Talus is medial
- 4th tarsal bone is a two story bone on lateral side.
- Central is on medial side
- The distal intertarsal joint doesn't span the tarsus because of the 4th tarsal bone.



To learn the different views of the tarsus, as you did for the carpus, draw a schematic of the tarsus as two ellipses. Mark one ellipse "C" for the calcaneus. The calcaneus is located on the lateral and plantar side of the tarsus. Label the sides of the joint and the corresponding degrees. The dorsal surface of the tarsus corresponds to 0°, the plantar to 180°, the lateral to 90° and the medial to 270°.



The configuration of the calcaneal tuberosity and the amount of its overlap with the other tarsal bones differs in each view.

DP (Dorsoplantar) view: the calcaneal tuberosity is narrow and overlapped by the rest of the carpus.


LM (lateromedial) view: the calcaneal tuberosity is as large as possible.

DLPMO: the calcaneal tuberosity is completely silhouetted.


DMPLO: the calcaneal tuberosity is overlapped.

Identifying the DP and LM are obvious. As in the carpus the oblique views give the student the most problems. From the configuration and amount of overlap of the calcaneal tuberosity draw the direction of the beam through your drawing (do both entering the dorsal surface). Then read the labelled surface on either side of your entrance point and exit point to name the oblique view.

If the calcaneal tuberosity is completely silhouetted, your drawing should look like this and is a DLPLO.



If the calcaneal tuberosity is completely overlapped then your drawing should look like the one below and is a DLPMO.



To understand which sides of the tarsus are silhouetted in each view, draw the beam passing through the carpus and then box the sides of the tarsus parallel to the beam. Then read the sides of the tarsus on either end of your box for the obliques and the side your box is on for the straight views, and you have the sides silhouetted.

Lateral view, LM: the beam is shot from lateral to medial, 90° to 270°. The dorsal and plantar sides of the tarsus are silhouetted.



## FOOT FILMS

The calcaneus is as large as possible and the front of the 3rd tarsal bone is flat.

**Dorsoplantar, DP:** shot 90° off the lateral view, from 0° to 180°. It is actually shot from plantar to dorsal. It silhouettes the medial and lateral surfaces of the tarsus. The calcaneus is completely overlapped by the rest of the hock. The ridges of the talus are as far apart as possible.

With only two views, the dorsal, plantar, lateral and medial edges of the tarsus will be in silhouette. This eliminates about 50% of the joint. To silhouette the rest, two more views are needed, the oblique views.

**Dorsolateral-plantaromedial oblique, DLPMO:** shot between the lateral and dorsal views (in theory 45°). In cases of spavin the area to be silhouetted is more dorsal, so it is usually shot between 60° to 70° (D70L-PM). The lateroplantar and dorsomedial surfaces are silhouetted. The dorsal surface of the 3rd tarsal bone has a bump on it. The vascular canal is large. The distal end of the calcaneus is in silhouette. This is the view for spavin problems (dorsomedial surface). It also shows the 4th tarsal on the 4th metatarsal so is also the view for splints in the hindlimb.

**Dorsomedial-plantarolateral oblique, DMPLO:** shot at about 115° (D115°M-PL). It is named as if the beam entered the dorsomedial surface even though it is usually taken through the plantarolateral side. It silhouettes the dorsolateral and medioplantar surfaces. The vascular canal is not seen. There is more overlap of the calcaneus.

These four views silhouette most of the hock. Most of the time the lateral, DP and DLPMO are evaluate. This is because the most common initial place for osteoarthritis of the hock occurs between the central and 3rd tarsal bone, or the 3rd tarsal bone and the 3rd metatarsal bone on the dorsomedial aspect of the hock. The DLPMO silhouettes this aspect of the hock.

## FOOT FILMS:

To take foot films it is desirable to remove the shoes. This won't be possible (e.g., horse is jumping that afternoon). Clean the foot to remove rocks and gravel from the commissures and frog to eliminate artifacts. Pack the ground surface with play dough to eliminate air artifacts.

**Lateral view:** you need to get all of the phalanges including the hoof, so the foot must be elevated off the ground. A 2 by 6 with a groove that holds the cassette works nicely. The foot is placed on the board.

A lateral view may show bone cysts, chips, avulsion fractures, fractured sesamoids, articular lesions, chronic degenerative joint disease, osselets, high ring bone, low ring bone, pyramidal disease, and pedal osteitis. Radiolucent nail lines are seen in shod horses. Also seen is the relative position of the navicular bone, the deep palmar processes of the coffin bone, sidebones, foreign

bodies (nails and wires), etc. With a soft tissue technique, you may even see wood splinters. Contrast medium can be placed into gravel tracts to highlight them.

**DP view:** do not place the foot directly on the cassette. Mount two sides of a 1 inch thick piece of plexiglass on two wood blocks. Stand the horse on the plexiglass stand and slide the cassette under the plexiglass.

Things seen on a DP view are the parietal notch, solar groove and solar foramina, parietal sulcus, areas for attachment of the superficial digital flexor on the distal end of P1 and the proximal end of P2, the navicular ("boat") bone, and the extensor process of P3.

**Rotational Laminitis:** the dorsal surface of the hoof wall and the dorsal surface of the distal phalanx should be parallel. In laminitis, P3 separates from the hoof wall to varying degrees. This is due to uncoupling of the laminar epidermis and laminar corium. The angle between the dorsal surfaces has prognostic value. Less than 5°, the prognosis of returning to soundness and former athletic performance is good. 11° - a good chance of returning to soundness, but not to former athletic performance. Greater than 11° has a poor prognosis of returning to soundness. Gas may be pulled out of the blood due to the pressure caused by separation (negative pressure) of the lamina in the closed state.

**Navicular films:** Five views for navicular films:

- Standard DP
- Standard lateral
- Shallow DP
- Steep DP
- Skyline view

**Skyline view:** silhouettes navicular disease. This is a tough view to achieve. Stand the horse on the cassette, walk it over a little (make it plant its foot and move its shoulder forward) then shoot from behind. This view allows analyzing the vascular channels and sets off osteophytes.

**Navicular bone:** Situated behind the coffin joint it has articular surfaces articulating with the middle and distal phalanges. The navicular bone normally has tiny little triangular shaped radiolucent areas along its borders. These are the vascular channels coming into the navicular bone. Avascular necrosis erodes the channels around the vessels, causing what radiologists call "lollipops". The erosion can erode centrally and result in large cystic radiolucent lesions. If the disease is severe, exostoses will appear on the edges of the bone or the vascular channels will appear in abnormal areas. A significant percentage of affected horses don't show any signs at all. Therefore, negative signs on radiographs do not rule out navicular disease.

Lollipops on the distal border of the navicular bone are one indication of navicular disease.



## OX - EXPLORATORY RIGHT PARALUMBAR LAPAROTOMY

**Right flank (paralumbar) laparotomy:** a good approach for exploring the abdomen of ruminants. Standing flank laparotomy is possible for simple exploration and many surgical procedures (repositioning, untwisting, or deflating a structure). A lateral recumbency flank laparotomy is indicated if the animal may fall or for extended surgeries (e.g. intestinal resection). Calves, because of their small size, are best done in lateral recumbency. Exploratory surgery should be systematic. Try to develop a mental picture of how the viscera are positioned in the abdomen. A right paralumbar incision is placed in different positions within the paralumbar fossa depending on what structure you want to reach: small intestines, in the center of the paralumbar fossa; the cecum and proximal colon – in the cranial part of the fossa caudal and parallel to the last rib. The following is a systematic palpation of the abdomen:

### STRUCTURES SEEN through a RIGHT PARALUMBAR INCISION:

1. **Descending duodenum:** crosses the dorsal end of the incision.
- 2, 3. **"Omental curtain":** the superficial and deep leaves of the greater omentum attached to the duodenum and extending ventrally along the abdominal wall to reach the rumen.

4. **Mesoduodenum:** attaches the duodenum to the dorsal abdominal wall.

The bulk of the viscera is behind the curtain formed by the greater omentum, duodenum, and mesoduodenum.

**STRUCTURES PALPATED BETWEEN the OMENTAL CURTAIN and the RIGHT ABDOMINAL WALL:** Run your hand cranially between the wall and the greater omentum. Identify the following structures:

5. **Liver:** located on the right side due to the rumen. Its edges should be sharp. Feel for abscesses, enlargement or irregularities. The right lobe is dorsal and the left lobe is ventral.

6. **Gall bladder:** hangs down from the center of the caudoventral edge of the liver.

**Diaphragm:** palpate it lateral to the liver and cranial to the reticulum.

**Reticulum:** against the diaphragm. Feel for adhesions, internal foreign bodies or magnet.

7. **Omasum:** felt as a firm (but not hard), round structure through the lesser omentum.

8. **Lesser omentum:** extends between the lesser curvature of the abomasum and the liver. It covers the omasum.

9. **Abomasum:** felt ventral to the omasum as it lies on the floor of the abdomen. The fundus and body are filled with fluid digesta.

10. **Pylorus:** can be found by following the descending duodenum cranially. It normally contains dry firm digesta. Exteriorize the pylorus for examination if the abomasum is not too full.

**Cranial duodenum:** feel the direct continuation of the pylorus as an S-shaped loop next to the liver.

1. **Descending duodenum:** travels down the right side of body attached to the mesoduodenum and the greater omentum.

11. **Right kidney:** located dorsal to the descending duodenum, between the mesoduodenum and the abdominal wall.

**Right ureters:** extend caudally from the kidney, retroperitoneally.

**STRUCTURES BEHIND the OMENTAL CURTAIN** (in the supraomental recess): Grasp the caudal edge of the omental curtain and move it cranially like a shower curtain. This exposes the supraomental recess and the viscera within it.

12. **Left kidney:** located high in the supraomental recess on the left side of the root of the mesentery and to the right of the rumen. Palpate its ureter.

13. **Cecum:** the blind-ended viscus located in the supraomental recess. It may extend out the caudal end of the recess. To identify the other intestinal structures, first find the easily identified cecum.

14. **Ileum:** located by following the cecum cranially to where the smaller ilium enters the junction between the cecum and the ascending colon.

15. **"Flange":** the section of the intestine with the longest mesentery. It consists of the distal part of the jejunum and the proximal part of the ileum. It is found by exteriorizing the intestine and following the ileum proximally.

16. **Jejunum:** located running proximally (orad) from the end of the "flange". Replace the flange and palpate the jejunum to the duodenojejunal flexure.

17. **Great mesentery:** suspends the ilium and jejunum from the dorsal abdominal wall.

18. **Root of the mesentery:** follow the great mesentery to the dorsal abdomen.


Return to the cecum and follow it cranially to the ileoceocolic junction:

19. **Ileoceocolic junction:** where the ileum joins the cecum and proximal loop of the ascending colon. Move the omental curtain as far cranially as possible to see this junction.

20. **Proximal loop of ascending colon:** located as the continuation of the cecum cranial to the ileoceocolic junction. Exteriorize



## OX - EXPLORATORY RIGHT PARALUMBAR LAPAROTOMY



**Fig. Ox-1 - Intestines, right lat view**

(Add your own labels)

the cecum and the proximal loop. Note the proximal loop turns caudally on itself on the right side of the mesentery. Follow it until it again turns, this time cranially, on the other side (left) of the root of the mesentery.

**21. "Conjoined mesenteries":** the short, fused mesenteries of the third part of the proximal loop, transverse colon, ascending duodenum, distal loop and first part of the descending colon. This makes a mass of the structures in the dorsal abdomen. It is impossible to distinguish each of these by palpation.

**22. Spiral loop:** reflect the "flange" of the intestine cranially to locate the disc-like spiral loop attached to its mesentery's left side. Note the inward spiraling centripetal coils, the outward spiraling centrifugal coils and the central flexure between the two. In the sheep and goat, follow the last centrifugal coil as it swings wide to pass just inside the jejunum. In the ox, the last coil does not stray.

**23. Distal loop:** can't be readily found because of the "conjoined mesenteries". It has a descending part on the left of the mesentery and an ascending part on the right side.

**24. Transverse colon:** can't be located because of the "conjoined mesenteries". It is situated cranial to the root of the mesentery.

**25. Descending colon:** its proximal part can't be palpated because of the "conjoined mesenteries". Its distal part runs in the dorsal abdomen on the left side of the mesentery and to the right of the rumen and can be palpated.

### STRUCTURES LOCATED in the CAUDAL ABDOMEN:

**Uterus and ovaries:** note that the ovaries are located near the pelvic inlet. In the pregnant state the uterus will usually expand into the supraomental recess and make exploration difficult.

**Urinary bladder:** located over the brim of the pelvis below the uterus.

### STRUCTURES LOCATED in the LEFT SIDE of the ABDOMEN

**26. Rumen:** fills the left half of the abdomen. Palpate it. Pass your hand caudally and dorsally around the caudal end of the rumen to palpate the left side of the rumen.

**Spleen:** palpated cranially on the left side of the rumen.

**Left displaced abomasum:** would be located between the rumen and the left body wall.



A circular diagram representing a cell. The outer boundary is a thick black line. Inside, there are several smaller circles and irregular shapes. Some are labeled with letters: 'A' (a small circle near the top left), 'B' (a small circle near the top right), 'C' (a small circle near the bottom left), 'D' (a small circle near the bottom right), 'E' (a small circle near the center), 'F' (a small circle near the center), 'G' (a small circle near the center), 'H' (a small circle near the center), 'I' (a small circle near the center), 'J' (a small circle near the center), 'K' (a small circle near the center), 'L' (a small circle near the center), 'M' (a small circle near the center), 'N' (a small circle near the center), 'O' (a small circle near the center), 'P' (a small circle near the center), 'Q' (a small circle near the center), 'R' (a small circle near the center), 'S' (a small circle near the center), 'T' (a small circle near the center), 'U' (a small circle near the center), 'V' (a small circle near the center), 'W' (a small circle near the center), 'X' (a small circle near the center), 'Y' (a small circle near the center), 'Z' (a small circle near the center). The diagram is a simplified representation of a cell with various organelles.



3. Deep leaf of greater omentum

- 6. Gall bladder

- 14. Ileum (Fig. Ox-1)


- 14. Ileum (Fig. Ox-1)

23". Ascending part

- Spleen



# OX - EXPLORATORY RIGHT PARALUMBAR LAPAROTOMY



**Fig. Ox-3 - Abdominal contents, right caudolateral view**

## STRUCTURES - EXTERIORIZED - PALPABLE or IMPALPABLE:

Exteriorization of structures is limited by the length of their mesenteries and their attachments. Many of those that can't be exteriorized can still be palpated.

Rumen, reticulum, omasum, and fundus and body of the abomasum: can't be exteriorized because of their attachment to each other and their position. They can be palpated.

**PYLORUS:** usually can be exteriorized if the abomasum is not too full of digesta.

S-loop of cranial duodenum, liver, gall bladder, and pancreas: can't be exteriorized, but can be palpated.

**DESCENDING DUODENUM:** easily exteriorized with attached mesoduodenum and greater omentum.

**Ascending duodenum:** can't be exteriorized or palpated because of its close association with the descending colon and the "conjoined mesenteries" in the dorsal abdomen.

**JEJUNUM, ILEUM and "FLANGE":** can be easily exteriorized, except the proximal 3-4 m of the jejunum.

**CECUM:** easily exteriorized.

**Proximal loop of the ascending colon:** easily exteriorized.

**Distal loop:** can't be exteriorized or palpated because of the "conjoined mesentery" of the structures in the dorsal abdomen.

**Transverse colon and proximal part of the descending colon:** can't be palpated or exteriorized because of the "conjoined mesenteries" in the dorsal abdomen.

**SIGMOID LOOP of the DESCENDING COLON:** Just caudal to the duodenocolic ligament, it has a long mesentery and may be pulled to the incision site.

**Remaining caudal part of the descending colon and intraperitoneal part of the rectum:** can be palpated, but not exteriorized.

Adapted from *Bovine Intestinal Surgery*, D. F. Smith, DVM, Food Animal, Nov. 1984



# FLANK ANESTHESIA

Standing flank surgery in the ox: opening the paralumbar fossa to perform surgery on such problems as "hardware disease", dystocia, displaced abomasum, etc. The first three or four ventral lumbar nerves and the last thoracic nerve are anesthetized in flank surgery of the ox and horse.

**Local anesthesia for a flank surgery:** concerned with T<sub>13</sub>, L<sub>1</sub> and L<sub>2</sub> nerves and can be done in a number of ways.

- **Line block:** infiltration of the intended incision line.
- **Inverted "L" block:** injections are done in the abdominal wall, from the subcutaneous area to the peritoneum, in the pattern shown.
- **Paravertebral block:** blocks all branches of the spinal nerves.
- **Distal paralumbar analgesia or Magda block:** blocks only the ventral and lateral dorsal branches of the spinal nerves.

**Line block:** infiltration of the intended incision line. This is probably the most commonly used technique. Multiple subcutaneous injections (1" 20-gauge needle) are made in the skin. Then a needle (3" 18 gauge) is inserted through the desensitized skin to infiltrate the muscles and peritoneum (10 - 100 ml). Allow 10 to 15 minutes for the anesthetic to take effect.

- **Advantages:** easy.
- **Disadvantages:** edema in the incision site and possible interference with healing.

**Inverted "L" or "7" block:** the line infiltration of anesthetic cranial and dorsal to the intended incision site, taking advantage of the caudoventral course of the nerves of the region. Two lines are laid down, one caudal to the last rib and one ventral to the transverse processes of the lumbar vertebrae. Up to 100 ml of anesthetic is injected. Allow 10 to 15 minutes for analgesic to take effect.

- **Advantages:** easy and is away from incision site.
- **Disadvantages:** amount of anesthetic required.

**Proximal paravertebral analgesia, Farquharson technique:** desensitizing the dorsal and ventral nerve branches T<sub>13</sub>, L<sub>1</sub> and L<sub>2</sub> spinal nerves as they emerge from the intervertebral foramina. The injection sites are from 1 to 2 inches lateral to the dorsal midline over the cranial edge of transverse process of L<sub>1</sub> and the caudal edge of the transverse processes of L<sub>1</sub> and L<sub>2</sub>. Prep and desensitize the skin over these areas with 3 ml of anesthetic subcutaneously. Push a 1/2 inch 14-gauge needle through the skin as a cannula. Pass a 2 to 6", 18-gauge spinal needle through the 14 gauge needle. To desensitize T<sub>13</sub>, pass the needle ventrally to contact the transverse process of L<sub>1</sub>. Walk the needle off the cranial edge of the transverse process and through the intertransverse fascia 1/2 inch (1 cm) below the transverse process. Inject 5 to 10 ml of anesthetic to desensitize the ventral branch of T<sub>13</sub>. Withdraw the needle 1/2 to 1 inch above the transverse process and inject 5 ml of anesthetic to block the dorsal branch of T<sub>13</sub>. Desensitization of L<sub>1</sub> and L<sub>2</sub> are done at similar levels with the same amounts of anesthetic as for T<sub>13</sub>. The only difference is the transverse process and direction you walk off it. Walk the needle off the caudal border of the transverse process of L<sub>1</sub>, for L<sub>1</sub>;

off the caudal border of L<sub>2</sub> for L<sub>2</sub>. Locating the transverse process of T<sub>13</sub> can be difficult because it is in the angle between the last rib and the spinal column. Locate the easily palpated transverse processes of L<sub>2</sub> and L<sub>3</sub>. Measure the distance between them and use this distance to estimate how far in front of L<sub>2</sub>, T<sub>13</sub> is. Signs of successful block are analgesia to the skin of the area and scoliosis toward the blocked side because of paralysis of the epaxial muscles. Analgesia usually begins in 10 minutes and last 90 minutes.

- **Advantages:** small amount of anesthetic needed, good analgesia and no anesthetic near wound site.
- **Disadvantages:** difficulty of technique, possibility of hitting large abdominal vessels, paresis of hind limb.

**Distal paravertebral analgesia, Magda technique:** desensitizes (blocks) the dorsal and ventral branches of spinal nerves T<sub>13</sub>, L<sub>1</sub> and L<sub>2</sub> at the distal end of the transverse processes (L<sub>1</sub>, L<sub>2</sub> and L<sub>4</sub>). Insert a needle (3" 18-gauge) under the ventral tip of the respective transverse processes (L<sub>1</sub>, L<sub>2</sub> and L<sub>4</sub>). Inject 10 to 20 ml of anesthetic in a fan-shaped pattern. Withdraw the needle and reinsert it dorsal to the transverse process in a slightly caudal direction. Inject 5 ml of anesthetic around the dorsal branches of T<sub>13</sub>, L<sub>1</sub> and L<sub>2</sub>.

- **Advantages over the proximal paravertebral analgesia:** no scoliosis because not all branches of the dorsal branches are blocked. There is also minimum pelvic limb paresis, no danger of hitting abdominal vessels and uses standard needle sizes.
- **Disadvantages:** more anesthetic needed, effectiveness can vary, especially if the nerves vary.


**Segmental dorsolumbar epidural analgesia, Arthur block:** desensitization of the nerve roots as they leave the spinal cord by injecting into the epidural space through the dorsal space, between first and second lumbar vertebrae. Thorough restraint is necessary. Locate the space between the spinous process of L<sub>1</sub> and L<sub>2</sub> by palpating the transverse processes of L<sub>2</sub>. Inject 2 to 4 ml subcutaneous at this site. Insert a 1/2" 14 gauge needle through the skin as a cannula. Insert a 4 1/2" 18-gauge needle through the cannula. The needle is directed ventrally at an angle of 10 to 15° to the vertical for 3 to 4 inches. Direct the needle through the interarcuate ligament into the epidural space. Inject anesthetic into the epidural space. The amount of anesthetic depends on the size of the animal and the nerves that you want to block. To block T<sub>13</sub>, L<sub>1</sub> and L<sub>2</sub> of a 1100 pound cow, 8 ml of anesthetic is injected. Resistance will be felt as the needle passes through the interspinous ligament and the interarcuate ligament. If the needle hits the arch of a vertebrae then withdraw it and redirect it. Once the interarcuate ligament is penetrated you are in the epidural space. Do not go any further and remove the needle immediately after injection. Aspiration of CSF indicates the needle has crossed the epidural space, through the dura mater and arachnoid and into the subarachnoid space.

- **Advantages over proximal and distal paravertebral analgesia:** only one injection, small amount of anesthetic, and uniform analgesia.
- **Disadvantages:** difficult technique, motor loss to hind limbs, possibility of damage to spinal cord and venous sinuses.



# FLANK ANESTHESIA

Ox - Lumbar vertebrae  
dors. view



Ox - lat. view







Fig. X-74 - Ox - Flank  
- lat. view



Ox - 1st lumbar  
vertebra - cross section

- 1. Inverted "L" block
- 2. Paravertebral block
- 3. Magda block





# Anatomy of the Domestic Animals

Chris Pasquini , DVM  
Tom Spurgeon , PhD


*The Anatomy of Domestic Animals* makes learning anatomy more pleasant and longer lasting for animal science majors, wildlife majors, zoology majors, veterinary technician students and veterinary students.

This systems-oriented book is a heavily illustrated summary of essential anatomical facts in a comparative format, making the information readily accessible.

Over 700 clear, concise drawings lend excellent visual representation to the text. Most figures are conveniently grouped with the supporting text, which gives the essentials of each structure in outline form. Differences between species follow in the text. Clinical applications relating to each group of structures are also presented to stimulate interest.

The essential structures on each illustration are labeled by numbers and names. Less important structures are labeled with letters. This keeps the illustrations uncluttered without compromising completeness. Some of the common views of the different species are numbered for self testing.

Though written for the student, veterinarians and other animal professionals will find this text a valuable reference.





## ARTERY

infraorbital a., 411, 412u  
int. carotid a., 411, 413  
int. iliac a., 428  
int. pudendal a., 428  
int. thoracic a., 408p, 410i,  
414  
interlobar a., 335  
interlobular a., 335  
interosseous aa., 416l,m  
interspinous br., 415s  
jejunal a., 427b  
labial aa., 412g,h  
laryngeal a., 411  
lat. plantar a., 433h  
lingual a., 411, 412c  
linguofacial a., 412d  
malar a., 412s  
maxillary a., 411, 413  
med. circumflex femoral a.,  
433c  
med. plantar a., 433i  
median a., 416  
mental a., 411, 412p  
mesenteric a., 422, 426  
metacarpal aa., 417  
metatarsal aa., 433k  
middle cerebral a., 413G  
middle colic a., 427d  
middle meningeal a., 412b  
middle sacral a., 437a  
musculophrenic a., 415j  
nasal a., 412j  
occipital a., 411, 412a  
of abdomen, 423  
of body, 382  
of fetus, 386, 387  
of head, 412, 413  
of neck, 411  
of pelvic limb  
dog, 432-433, 436-437  
horse, 434  
ox, 435  
of pelvis, 428  
of rumen, 425  
of simple stomach, 424, 425  
of thoracic limb  
dog, 416, 417  
horse, 418, 420, 421  
ox, 419  
of thorax, 414, 415  
ophthalmic a., 411, 412r  
ovarian a., 350G  
palatine a., 411, 412w  
palm. common digital  
aa., 417  
palm. metacarpal a., 416r

## ARTERY

palm. proper digital aa.,  
416t  
palmar arches, 416  
palpebral a., 412n  
pancreaticoduodenal a.,  
425d  
paraconal interventricular  
br., 406  
parotid a., 411  
perforating br., 415  
phrenic br., 415w  
plantar aa., 433h,i  
plantar arch, 433j  
popliteal a., 432  
proper digital a., 417  
proper hepatic aa., 296  
prostatic a., 428  
pudendocpigastic  
trunk, 428  
pulmonary a., 384  
pulmonary trunk, 384  
radial a., 416,o  
rectal a., 427j  
renal a., 329c, 422  
reticular a., 425j  
rostr. cerebellar a., 413C  
rostr. cerebral a., 413F  
ruminal a., 425i,k  
sacral a., 437a  
saphenous a., 432  
sphenopalatine a., 412v  
spinal a., 411c, 413A  
splenic a., 425f  
sternal br., 415i  
subclavian a., 408, 410  
sublingual a., 412f  
subscapular a., 416c  
subsinosal interventricular  
br. 406  
supf. brachial aa., 416w  
supf. caud. epigastric a., 428  
supf. cervical a., 408c, 410j,  
411h  
supf. palm. arch, 416p  
supf. temporal a., 411, 412l  
supreme intercostal a., 410h  
testicular a., 362  
thoracic aorta, 409, 411  
thoracic vertebral a., 410h  
thoracodorsal a., 416c  
thyroid a., 411  
tibial a., 432  
transverse cubital a., 416j  
transverse facial a., 412m  
umbilical a. 386  
uterine a., 428

## ARTERY

vaginal a., 428  
ventr. intercostal a., 414  
ventr. spinal a., 476c  
vertebral a., 410d  
Articular process, 36g  
Articular process, 106  
Articular surface, 22  
of ilium, 69a  
of lumbar vertebrae, 67b,c  
of patella, 96f  
Articulation (see joint)  
Atrial septum defect, 392  
Arthrocentesis, 124  
Arthroidal joint, 108  
Atlanto-axial joint, 128  
Atlanto-axial joint, 128  
Atlas, 62  
Atrium, 384, 394  
lt. atrium, 401  
rt. atrium, 398  
Auditory ossicle, 552  
Auditory tube, 552  
Auricle, 401  
Auricular cartilage, 106  
Auscultation, 404  
Autonomic nervous system,  
(ANS), 445, 522  
Autonomic reflex arc, 522  
Axial skeleton, 26  
Axis, 63  
Axon, 446  
Axon collateral br., 447e  
Axon hillock, 447d

## B B B B B B B B B

Ball & socket joint, 108  
"Balling up", 369  
Bands, 276, 278  
Bars, 536  
Base  
of heart, 394  
of cecum, 278  
of patella, 96f  
"Bean", 372  
Biceps brachii m., 152  
Biceps femoris m., 176  
Bicipital a., 416h  
Bile, 296  
Bile canaliculi, 296  
Bishoping, 247  
Blind spavin, 124  
Blood spavin, 125  
Blood vascular system, 383  
Body  
of femur, 96b



## BODY

of fibula, 99g  
of humerus, 78  
of ilium, 95d  
of radius, 80h  
of tibia, 99h  
of ulna, 80i  
Bog spavin, 124  
Bone, 21-102  
  anticlinal vertebra, 64  
  articular surface, 22  
  atlas, 62  
  auditory ossicles, 552  
  axis, 63  
  basihyoid b., 58f  
  calcaneus (fibular  
    tarsal b.), 100  
  cannon b., 85  
  carpal b., 82  
  centroquartel b., 101  
  ceratohyoid b., 58d  
  conchae, 32  
  clavicle, 76  
  coffin b., 87, 88  
  coxal b., 94  
  diaphysis, 22  
  dist. phalanx, 86  
  dist. sesamoid b., 88  
  dors. sesamoid b., 86, 87g  
  endosteum, 22  
  epihyoid b., 58c  
  epiphysis, 22  
  ethmoid b., 32, 42  
  fabellae, 97  
  femur, 96  
  fibula, 98  
  fibular tarsal b., 100  
  flat b., 22  
  frontal b., 32  
  humerus, 78  
  hyoid b., 58  
  ilium, 94  
  incisive b., 32  
  incus, 48h, 52  
  interparietal b., 32, 34a  
  irregular b., 22  
  ischium, 95  
  lacrimal b., 32  
  large metatarsal b., 85  
  long b., 22  
  long pastern b., 87, 88  
  malar b., 32  
  malleus b., 48f, 552  
  manubrium, 71  
  mandible, 32, 44, 45  
  maxillary b. (maxilla), 32  
  medullary cavity, 22

## BONE

metacarpal b., 84, 85  
metaphysis, 22  
metatarsal b., 102  
middle phalanx, 86  
nasal b., 32  
navicular b., 88  
occipital b., 32  
of body, 26  
of head (see skull), 32-44  
of cranium, 32  
of face, 32  
of pelvic limb, 90-102  
of skull  
  cat, 53  
  dog, 32  
  goat, 54  
  horse, 34  
  pig, 52  
  ox, 35  
  sheep, 55  
of thoracic limb, 72-89  
  dog, 72  
  horse, 73  
  ox, 74  
  pig, 75  
of vertebral column, 60-69  
occipital b. 32  
palatine b., 32  
palm. sesamoid b., 86  
parietal b., 32  
pastern, 87  
patella, 96  
pelvis, 94  
periosteum, 22  
prox. phalanx, 86  
pterygoid b., 32  
  hamulus of, 41f  
pubis, 95  
radius, 80  
rostral b., 52  
sacrum, 68  
scapula, 76  
sesamoid bb., 86, 22  
short b., 22  
short pastern, 87  
small metacarpal b., 85  
sphenoid b., 32  
splint b., 85  
stapes, 48g, 552  
stylohyoid b., 58b  
talus (tibial tarsal b.), 100  
tarsal b., 100  
temporal b., 32  
thyrohyoid b., 58e  
tibia, 98  
tibial tarsal b., 100

## BONE

tympanohyoid b., 58  
ulna, 80  
ventr. nasal concha, 32  
vertebrae, 60  
vomer, 32  
zygomatic b., 32  
Bone spavin, 124  
Bony labyrinth, 554, 555  
Bots, 269  
Bowed tendon, 164  
Bowman's capsule, 336  
Brachial a., 416  
Brachialis m., 150  
Brachiocephalic trunk, 408, 410  
Brachiocephalicus m., 146  
Brachium, 26  
Brachydont, 238  
Brachygnathia, 239  
Brain, 452  
Breastbone, 71  
Bristles, 531  
Brittle feet, 541  
Broad lig., 348  
Broken foot, 541  
Broken penis, 368  
Bronchi, 321  
Bronchial vessels, 325  
Bronchioles, 321  
Bronchus, 321  
Buccal n., 463v  
Buccal vestibule, 234b  
Buccinator m. 204j  
Bucked shin, 85  
Bulb, 537  
Bulbourethral gland, 364  
Bulbospongiosus m., 374  
Bulla, tympanic, 40  
Bursa, 106  
  intertubercular, 110e  
  infraspinatus, 110f  
  olecranon, 111f  
  omental, 286  
  ovarian, 348  
  synovial, 106  
Burstis, 106  
Buttress foot, 88, 54  
  
C C C C C C C C C C  
Calcaneus, 100  
Calyx, 331, 332f  
Canal, 24  
  cervical, 342  
  femoral, 225  
  for transverse sinus, 46h  
  for trigeminal n., 46g



## CANAL

hyoglossal, 41a, 42b, 46  
infraorbital, 56d  
inguinal, 225  
lacrimal, 36, 558  
metacarpal, 85h,i  
metatarsal, 102c,d  
optic, 40, 46(2), 48  
pterygoid, 41e  
semicircular, 557  
streak, 533  
teat, 533  
transverse, 42b  
vertebral, 60  
Canines, 240  
Cap, 247  
Capillary, 383  
Capped elbow, 81  
Capped hock, 100  
Capitulum, 78e  
Cardia, 268  
Cardiac loop, 390  
Cardiogenic tissue, 388  
Cardiogenic tubes, 388  
Carotid sheath, 212f  
Carnassial teeth, 240  
Carnassial tooth abscess, 241  
Carpal joint, 72,75  
Carpal pad, 544  
Carpus, 26, 82  
Cartilage  
  alar, 303h  
  accessory nasal, 303f,g  
  anular, 551i  
  arytenoid, 308  
  auricular, 551  
  costal, 71  
  cricoid, 308  
  epiglottic, 308  
  interarytenoid, 309k  
  of larynx, 308  
  of third eyelid, 549  
  nasal, 303  
  scapular, 77  
  scutiform, 206a,208c  
  sesamoid, 309l  
  thyroid, 308  
  tracheal, 321  
  tympanohyoid, 58a  
  ungual, 88  
  xiphoid, 71  
Cartilaginous joint, 104  
Caruncles, 343, 353  
Castration, 358-360  
  closed, 358  
  opened, 358  
Cataract, 548

## CAUDA EQUINA

Cauda equina, 470  
Caudal (caud.), 16  
  nares, 40  
Cavernous body, 370  
Cavity  
  abdominal, 224  
  amniotic, 352  
  cotyloid, 24  
  cranial, 42  
  glenoid, 25, 76  
  nasal, 42,304  
  oral, 234  
  pelvic, 225  
  pericardial, 318,383  
  peritoneal, 282  
  pleural, 318  
  pulp, 239  
  thoracic, 224,318  
  tympanic, 552  
Cecocolic orifice, 276, 278  
Cecum, 276  
  horse, 278  
  ox, 280  
  pig, 281  
Cementum, 238  
Central nervous system (CSN), 445  
Centrifugal turns, 280a, 281a  
Centripetal turns, 280b, 281b  
Cerebellar cortex, 457  
Cerebellar peduncles, 457  
Cerebellum, 456  
Cerebral aqueduct, 456, 473  
Cerebral cortex, 452  
Cerebral hemispheres, 452  
Cerebrospinal fluid, 473  
Cerebrum, 452  
Cerumen, 551  
Cervix, 342  
Cesarean section, 345  
Cisterna magna, 475  
Cheeks, 235  
Cheek teeth, 240  
Chestnut, 544  
Choanae, 40, 48, 263  
Choncha, 42  
  dors. nasal, 42  
  ventr. nasal, 42  
Cholinergic fibers, 522  
Chordae tendinae, 401  
Chorioallantois, 352  
Chorion, 352  
Choroid, 546  
Choroid plexus, 473  
Ciliary body, 462, 546  
Ciliary process, 546

## CIRCULATION

Circulation  
  adult, 384  
  fetal, 386  
  pulmonic, 384  
  systemic, 384  
Circulatory system, 382  
Circumduction, 108  
Cisterna chyli, 440  
Clavicular intersection, 146, 147b  
Claw, 544  
Clavicle, 76  
Clinical  
  anal sacs, 276  
  arthrocentesis, 124  
  auditory tubes, 552  
  auscultation - heart, 404  
  "balling-up", 369  
  "bean", 372  
  bishopsing, 245  
  blind spavin, 123,124  
  blood spavin, 125  
  blister, 530  
  bog spavin, 123  
  bone spavin, 123  
  bots, 269   brittle feet, 541  
  broken foot, 541  
  broken penis, 368  
  bucked shins, 85  
  bursitis, 106  
  butterfoot, 88,541  
  capped elbow, 81  
  capped hock, 100  
  carnassial tooth abscess, 241  
  castration, 358-360  
  cataract, 548  
  cerumen, 551  
  cesarian section, 345  
  clostrum, 535  
  club foot, 541  
  common fibular n. damage, 500  
  contracted heels, 541  
  contracted tendons, 164  
  coon foot, 541  
  corn, 541  
  "cow-hocked", 125  
  cryptorchidism, 360, 361  
  cuncan tenotomy, 125  
  curb, 124  
  dislocation, 106  
  displaced abomasum, 271  
  "downer cow", 500  
  drawer sign, 121  
  drooped foot, 541  
  epistaxis, 553



## CLINICAL

ext. hydrocephalus, 475  
false joint, 106  
femoral canal, 225  
femoral n. deficiency, 500  
fibrotic myopathies, 182  
fibular n. damage, 500  
flank surgery, 464, 465  
flat foot, 541  
"floating", 241  
foot rot, 542  
founder, 541  
"fractured splint", 85  
glaucoma, 548  
gravel, 541  
guttural pouch, 553  
    drainage, 553  
    infections, 553  
hardware disease, 271  
heart auscultation, 369, 370  
heart murmur, 369, 370  
heart worms, 370  
heel crack, 541, 542  
hepatitis, 295  
"high flanker", 360  
"high spavin", 124  
hoof bound, 541  
hydrocephalus, 575  
hydrops pericardii, 318  
impaction, 278  
inguinal hernias, 358  
int. hydrocephalus, 475  
interdigital dermatitis, 542  
interdigital fibroma, 542  
intervenous technique, 497  
intubation, 313  
intussusception, 275  
inverted "L" block, 499  
"jack spavin", 124  
"L" block, 499  
laminitis, 541  
luxation, 106  
Magda block, 499  
mastitis, 535  
medial n. damage, 480  
"milking out", 535  
mucocoele, 261  
murmurs, 369, 370  
navicular disease, 88  
"needle teeth", 241  
nephritis, 328  
neuritis, 446  
"nerve", 495  
nerve block, 495, 497  
occult spavin, 124  
omentum, 291  
palpation of ovaries, 341

## CLINICAL

paralysis of penis, 369  
paravertebral block, 499  
patellar luxation, 121  
PDA, 404  
pedal osteitis, 88  
pericardial tamponade, 318  
peritonitis, 282  
PMI, 404  
pregnancy diagnosis, 345  
pregnancy grooves, 545  
quarter crack, 541  
quittor, 88, 541  
radial paralysis, 480  
rectal prolapse, 276  
ring block, 497  
"ridglings", 360  
"rigs", 360  
ringbone, 8  
"roarer", 313  
rotation of coffin b., 88  
rumen palpation, 271  
rupture of intervertebral  
    disc, 131  
seedy toe, 541  
"siklc-hocked", 125  
"sidebone", 88  
spavin, 124  
spavin test, 125  
splenectomies,  
    "splints", 85  
standing flank surgery, 499  
stomach tube, 271, 305  
"stringhalt", 182  
strongylus vulgaris, 426  
supf. lymph nodes, 441  
"sweeney", 480  
tarsal conformation, 125  
"teaser" bull, 369  
temperature regulation, 455  
tibial n. damage, 500  
thrush, 541  
toe crack, 541  
torsion of intestine, 275  
tracheostomy, 321  
trephination, 57  
trocharization, 271  
"tubing", 263  
upward fixation of patella,  
    121  
urethral calculi, 368  
uterine prolapse, 345  
vaginal smears, 347  
volvulus, 275  
white line, 540  
whorlbone disease, 176  
"windsuckers", 347

## CLITORIS

Clitoris, 346  
Clostrum, 535  
Club foot, 541  
Cochlea, 555  
Cochlear duct, 555  
Cochlear window, 48e, 552  
Coffin b., 87, 88  
Collecting duct, 336  
Colliculum seminalis, 378a  
Colliculus, 456n,o  
Colon, 276  
    ascending, 276  
    descending, 276  
    horse, 278  
    ox, 280  
    pig, 281  
    transverse, 276  
Commissure  
    habenular, 456c  
    ventral, 343c, 344c  
Common digital extensor m.,  
    158  
Common fibular n. damage,  
    500  
Common integument, 530  
Compound joint., 104  
Concha  
    dors. nasal, 304a  
    ethmoid, 304  
    nasal, 304  
    ventr. nasal, 304  
Condyle, 24  
    occipital, 36  
    of femur, 96  
    of humerus, 78  
    of metacarpal bb., 84  
    of metatarsal bb., 102f  
    of tibia, 98  
Cones, 547  
Conjunctiva, 549  
    bulbar, 549  
    palpebral, 549  
Contact surface, 240c  
Contracted heels, 541  
Contracted tendons, 164  
Conus, 394  
Conus medullaris, 470  
Convolutions, 452  
Coon foot, 541  
Corium, 530, 538  
Corn, 541  
Cornea, 546  
Corniculate process, 38  
Cornu, 309c,e  
Cornual process, 38  
Cornual rings, 545



## CORONARY BORDER

Coronary border, 89c  
Coronary sinus, 394  
Coronet, 537  
Corpus cavernosum, 370  
Corpus hemorrhagicum, 354  
Corpus luteum, 354  
Corpus spongiosum, 370  
Corpuscle, renal, 336  
Cortex  
    of kidney, 330  
    of uterus, 340  
Costal fovea, 64  
Costochondral junction, 70c, 131  
Cotyledon, 353  
Cotyledonary placenta, 353  
Cotyloid cavity, 24  
"Cow-hocked", 125  
Coxal jt., 118  
Coxofemoral jt., 118  
Cranial (cran.), 16  
Cranial cavity, 42  
Cran. drawer sign, 121  
Cran. dura mater, 474  
Cran. mesenteric a. 422, 426  
Cranial nn., 460, 560  
Cranial outflow, 526  
Cran. tibial m., 188  
Cranium, 32  
Crena, 89k  
Crest, 24  
    epicondylar, 78c  
    facial, 38d  
    intertrochanteric, 96i  
    median, cricoid cart., 309h  
    median sacral, 68  
    nuchal, 38  
    of ilium, 95a  
    petrosal, 46f  
    renal, 330  
    sacral, 68, 69b  
    sagittal, 38b  
    ungual, 544a  
    urethral, 379f  
Cribriform plate, 42, 46(1)  
Cribriform foramina, 50  
Cricoid cartilage, 308  
Crista, 557  
Crown, 238  
Crura of penis, 370  
Crus, 26, 98  
Cryptorchid, 360  
Cryptorchidism, 360-361  
Cubital jt., 111  
Cunean tenotomy, 125  
Cuneate nucleus, 456g

## CUNEIFORM PROCESS

Cuneiform process, 309j, 310j  
Cup, 246  
Cup gone, 250  
Curb, 124  
Cusps, 239  
Cysterna chyli, 440

## DDDDDDDDDD

Dartos, 376  
Deciduate placenta, 353  
Deciduous dentition, 240  
Deferent duct, 357  
Deep, 17  
Deep digital flexor m., 21, 190  
Deep fasciae, 221  
Deep inguinal ring, 202  
Deep leaf (of omentum), 290  
Deltoid m., 150  
Dendrites, 446  
Dens, 63  
Dental aging  
    dog, 245  
    horse, 246-253  
    ox, 254-257  
Dental formula, 242, 243  
Dental pad, 235, 254  
Dental star, 246, 250  
Denticulate lig., 476  
Dentin, 238  
Dentition  
    cat, 245  
    dog, 240, 242  
    horse, 241, 243  
    ox, 241, 243  
    pig, 52, 244  
Dermatome, 477  
Dermis, 530, 538  
    coronary, 539  
    laminar, 539  
    of the frog, 539  
    of the sole, 539  
    periople, 538  
Descending aorta, 409  
Descent of testicles, 358  
Development of heart, 388  
Dew claw, 84, 86, 87i, 544 c  
Diaphragm, 224  
Diaphragmatic flexure, 278  
Diaphysis, 22  
Diarthrosis, 104, 106  
Diastole, 404  
Diencephalon, 454  
Diffuse placenta, 353  
Digital cushion, 537m, 540  
Digital pad, 544

## DISC

Disc, intervertebral, 60  
Dislocation, 106  
Displaced abomasum, 271  
Distal (dist.), 17  
Diverticulum  
    cornual, 57  
    nasal, 305  
    pharyngeal, 264  
    preputial, 367  
    suburethral, 347  
Dorsal (dors.), 17  
Dorsal root, 523  
Dorsal root ganglion, 523  
Dorsum sellae, 46e  
Downer cow, 500  
Drawer sign, 121  
Duct  
    accessory pancreatic d., 299  
    arterial d., 386  
    bile, 296  
    collecting d., 336  
    cystic d., 296  
    deferent d., 357  
    epididymal d., 356  
    hepatic d., 296  
    interlobular d., 296  
    milk d., 533  
    nasolacrimal d., 558  
    pancreatic d., 299  
    papillary d., 336  
    parotid d., 256  
    salivary d., 256  
    semicircular d., 557  
    sublingual d., 256  
    thoracic d., 408h, 440  
    venous d., 386  
Ductus arteriosus, 386  
Ductus deferens, 357  
Ductus venosus, 386  
Duodenojejunal flexure, 274d  
Duodenum, 274  
Dura mater, 474

## EEEEEEEEEE

Ear, 551  
Ear drum, 552  
Ectopic cordis, 392  
Efferent ductules, 356  
Elbow jt., 72, 75, 111  
Ellipsoid jt., 108  
Eminence  
    ileopubic, 95f  
    intercondylar, 99a  
Enamel, 238  
Enamel spot, 246, 250



## ENDOCARDAL CUSHIONS

Endocardial cushions, 341  
Endocardium, 383  
Endolymph, 554  
Endoneurium, 472  
Endosteum, 22  
Endotheliochorial placenta, 333  
Endothelium, 352, 353  
Epicardium, 383  
Epicondylar crest, 78c  
Epicondyle, 24 79, 96d,e  
Epidermis, 539, 539  
    coronary, 539  
    frog, 540  
    laminar, 540  
    perioplic, 539  
    sole, 540  
Epididymal duct, 356  
Epididymis, 356  
    body, 357b  
    head, 357a  
    tail, 357c  
Epidural space, 474  
Epiglottic cartilage, 308  
Epiglottis, 300  
Epineurium, 472  
Epiphysis, 22  
Epiploic foramen, 288, 290  
Epistaxis, 553  
Epitheliochorial placenta, 353  
Epithelium, chorionic, 353  
Ergot, 544  
Eruption time, 250  
    horse, 250  
    ox, 254  
    sheep & goat, 254  
Esophageal hiatus, 225  
Esophagus, 263  
Eustachian auditory tube, 552  
Extraembryonic membrane, 352  
Ext. ear, 551  
Ext. abdominal oblique m., 200  
Ext. acoustic meatus, 36  
Ext. occipital  
    protruberance, 36k  
Ext. iliac a., 428  
Ext. intercostal m., 216  
Ext. pudendal a., 428  
Extension, 108, 140  
Extensor carpi radialis m., 158  
Extensor carpi ulnaris m., 158  
Extensor fossa, 96e  
Extensor process, 87e, 89f  
Eye, 546  
Eyelid, 549

## F F F F F F F F F

Fabella, 97  
Facet, 24  
Facial crest, 38d  
Fallopian tube, 340  
False jt., 106  
Falx cerebri, 475  
Fascia, 221  
    deep, 221  
    spermatic, 362  
    subserous, 221  
    supf., 221  
    visceral, 221  
Fascicle, 472  
Fasciculus cuneatus, 456h  
Femoral a., 432  
Femoral canal, 225  
Femoral n. deficiency, 500  
Femur, 96, 97  
Fetlock jt., 114  
Fibrocartilagenous jt., 104  
Fibroelastic penis, 366  
Fibrous capsule, kidney, 328  
Fibrous capsule, synovial jt., 106  
Fibrous pericardium, 383  
Fibrotic myopathies, 182  
Fibula, 98  
Fibular tarsal b., 100  
Filiform papillae, 236j  
Filum terminale, 470, 476  
Fimbriae, 340  
Fissure, 24, 452  
    median, 470  
    lateral, 453h  
    longitudinal, 452  
    orbital, 41i, 46(3), 48 (8), 50  
    palatine, 46a  
    transverse, 452  
    tympano-occipital fissure, 50  
Flank surgery, 499  
Flat foot, 541  
Flexion, 108, 140  
Flexure  
    diaphragmatic, 278  
    duodenojejunal, 274d  
    pelvic, 278  
    sigmoid, 280  
    sternal, 278  
"Floating", 24i  
Fold  
    alar, 304f  
    basal, 304g  
    straight, 304e  
Follicle, 354  
Foot, 536  
Foot axis, 540

## FOOT

Foot rot, 542  
Foramen, 24  
    alar, 48a, 62a  
    caval, 225  
    epiploic for., 288, 290  
    foramen I, 391  
    foramen II, 391  
    foramen magnum, 40, 46, 48  
    greater sciatic (ischatic) for., 118  
    infraorbital for., 36, 50  
    interventricular for., 391  
    intervertebral for., 60  
    jugular for., 42d, 46(8), 48, 50  
    lacerum, 41d, 46(6), 48, 50  
    lat. vertebral for., 62d, 65b  
    lesser sciatic (ischiatric) for., 118  
    major palatine for., 41g, 48b  
    mandibular for., 42i, 50  
    maxillary for., 50  
    mental for., 44, 50  
    nutrient for., of scapula, 77h  
    obturator for., 95  
    omental for., 286, 290  
    optic for., 462  
    ovale, 48, 50, 386  
    round for., 46(4), 50  
    sacral for., 68  
    solar for., 89h, 537i  
    stylomastoid for., 41, 48, 50  
    supracondylar for., 79  
    supratrochlear for., 79  
    supraorbital for., 38e  
    transverse for., 62  
    ventr. sacral for., 68  
    vertebral for., 60  
Fornix, vaginal, 344p, 347  
Fossa, 24  
    acetabular, 95  
    clitoridis, 343d, 344d  
    condyloid, 41n  
    extensor, 96e  
    for lacrimal sac, 50  
    hypophyseal, 42  
    infrapinnous, 76  
    intercondyloid, 96m  
    mandibular, 40  
    masseteric, 44i  
    pararectal, 282  
    ovulation, 341  
    of glans penis, 372  
    olecranon, 79  
    radial, 79



## FOSSA

subscapular, 76  
 supracondyloid, 96, o  
 supraspinous, 76  
 temporal, 38  
 tonsillar, 236  
 trochanteric, 96j  
 Founder, 541  
 Fovea, 25  
   costal, 64  
   of femoral head, 96h  
 Fractured splint, 85  
 Freely movable jt., 104  
 Frontal bone, 32  
 Frontal plane, 18  
 Frontal sinus, 42, 56  
 Frontomaxillary opening, 56  
 Frog, 537  
 Functional blood, 296  
 Functional classification of  
   jts., 104  
 Funicular part of nuchal lig.,  
   129a

## G G G G G G G G G

Gallbladder, 297  
 Galvayne's groove, 248a  
 Ganglia (-on), 450, 461, l-v  
   cardiac, 525d  
   caud. mesenteric, 525g  
   celiac, 525f  
   cervicothoracic, 524  
   ciliary, 527A  
   collateral, 524  
   cran. cervical, 524  
   cran. mesenteric, 525c  
   dorsal root, 523  
   mandibular, 527C  
   pterygopalatine, 527B  
   stellate, 524  
   sublingual, 527D  
   trunk, 524  
 Gastric groove, 268, 273  
 Geniculate body, 456c, f  
 Genital fold, 364a  
 Ginglymus, 108  
 Girdle  
   pelvic, 26  
   thoracic, 26  
 Gland  
   accessory sex, 364  
   adrenal gl., 328  
   anal (sacs), 276, 532  
   buccal gl., 261f  
   bulbourethral gl., 364  
   cardiac gl. region, 268e

## GLAND

carpal gl., 532  
 ceruminous gl., 532  
 chin gl., 532  
 circumanal gl., 532  
 circumoral gl., 532  
 Cowper's gl., 364  
 fundic gl. region, 268f  
 horn gl., 532  
 lacrimal gl., 558  
 mammary gl., 533  
 mandibular gl., 258, 259  
 mental gl., 532  
 monostomatic part, 259  
 of infraorbital sinus, 532  
 of inguinal sinus, 532  
 of interdigital sinus, 532  
 of nasal skin, 532  
 parotid gl., 258  
 perioral gl., 258  
 polystomatic part, 259, 258c  
 preputial gl., 532  
 prostate gl., 364  
 pyloric gl. region, 268g  
 salivary gl., 258  
 sebaceous gl., 530  
 subcaudal gl., 259  
 sublingual gl., 259  
 sweat gl., 530  
 vesicular gl., 364  
 zygomatic gl., 259  
 Glans, 366  
 Glaucoma, 548  
 Glenohumeral jt., 110  
 Glenoid cavity, 25, 76  
 Glottic cleft, 312, 316  
 Glottis, 317b  
 Gomphosis, 104  
 Granula iridica, 549, 550b  
 Gravel, 541  
 Gray matter, 450, 470  
 Greater curvature of stomach,  
   268  
 Greater omentum, 286, 288, 290  
 Groove, 25, 452  
   abomasal, 273c  
   bicipital (interventricular),  
     394  
   brachial, 78  
   coronary, 394, 537j, 543c  
   extensor, 80, 81, 98  
   Galvayne's, 248a  
   gastric, 268, 273  
   intermammary, 534c  
   intertubercular (bicipital),  
     78

## GROOVE

interventricular, 394  
 longitudinal groove  
   of metacarpal bone, 85  
   of metatarsal bone, 102  
 "milk", 273  
 muscular (extensor sulcus),  
   99d  
 omasal, 272l  
 of lat. malleolus, 99i  
 on radius, 81  
 paraconal interventricular,  
   394  
 parapedal, 543f  
 perioplic, 543a  
 reticular, 272j  
 solar, 89y  
 subsinuosal gr., 394  
 Glenoid cavity, 76  
 Glomerular capsule, 336  
 Glomerulus, 337  
 Gluteal surface, 95h  
 Guard hair, 532  
 Gums, 235  
 Guttural pouch, 553  
 Gyri, 452

## H H H H H H H H H

Hair, 530  
 Hair cells, 557  
 Hard palate, 40  
 Hardware disease, 271  
 Head, 25  
   of humerus, 78  
   of metacarpal b., 84  
   of radius, 80  
   of rib, 70  
 Heart, 384-403  
   auscultation, 404  
   murmurs, 404  
   worms, 404  
   sounds, 404  
 Heel, 536  
 Heel crack, 541  
 Helix, 551a  
 Hepatic cells, 296  
 Hepatic vv., 296  
 Hepatitis, 295  
 "High flanker", 360  
 High-crowned teeth, 238  
 Hilus, renal, 331  
 Hinge jt., 108  
 Hip jt., 118  
 Histology of liver, 296  
 Hock, 100  
 Hoof, 536



## HOOF

horse, 536-541  
ox, 542  
Hoof-bound, 541  
Hoof-cracks, 541-542  
Horn, 545  
Horny claw, 86, 87h  
Humeral condyle, 78  
Humerus, 78  
Hydrocephalus, 475  
Hymen, 344g  
Hyoid apparatus, 26  
Hypodermis, 530  
Hypophyseal fossa, 42  
Hypophysis, 455  
Hypothalamus, 454  
Hypsodont teeth, 238

|||||||

Ileocecal fold, 276, 285  
Ileocolic orifice, 276  
Ileum, 274  
Ilium, 94  
Iliopubic eminence, 95f  
Immovable jt., 104  
Impaction, 278  
In wear, 246, 250  
Incisors, 240  
Incus, 48, 552  
Infraglenoid tubercle, 77f  
Infraorbital foramen, 36, 50  
Infundibulum, 246, 340, 455  
Inguinal canal, 202  
Inguinal hernia, 358  
Inguinal lig., 302  
Inguinal ring, 202  
Insufficiency of heart valves, 404  
Integument, 530  
Interatrial septum, 398  
Intercondylar area, 99b  
Intercondylar eminence, 99a  
Intercostal space, 70  
Interdental space, 234  
Interdigital dermatitis, 542  
Interdigital fibroma, 542  
Intermammary groove, 534e  
Intermediate tubercle, 79  
Internal hydrocephalus, 475  
Internal iliac a., 428  
Interparietal b., 32  
Interstitial fluid, 383  
Interthalamic adhesion, 454, 455c  
Intertrochanteric crest, 96i

## INTERTROCHLEAR

Intertrochlear incisure, 85k, 102f  
Intertubercular groove, 78  
Intervenous techniques, 497  
Interventricular foramina, 473  
Interventricular septal defect, 392  
Interventricular septum, 391, 401  
Intervertebral disc, 60  
Intracapsular lig., 106  
Intubation, 313  
Intussusception, 275  
Inverted "L" block, 499  
Iris, 547  
Ischiatic  
arch, 95m  
table, 95l  
spine, 95j  
Ischium, 95  
Isthmus faucium, 263

## J J J J J J J J J

Jack spavin, 124  
Jejunum, 274  
Joint  
amphiarthrosis, 104  
arthroidal jt., 108  
atlanto-axial jt., 128  
atlanto-occipital jt., 128  
ball-and-socket jt., 108  
capsule, 106  
carpal jt., 72-75, 112  
carpometa carpal jt., 112  
cartilaginous jt., 104  
cavity, 106  
coffin jt., 114  
compound jt., 104  
condyloid jt., 108  
costochondral jt., 131  
costovertebral jt., 131  
coxal jt., 118  
coxofemoral jt., 118  
cubital (elbow) jt., 111  
diarthrosis, 104, 106  
dist. interphalangeal jt., 114  
elbow jt., 72-75, 111  
ellipsoid jt., 108  
false jt., 106  
femoropatellar jt., 120  
femorotibial jt., 120  
fetlock jt., 114  
fibrocartilagenous jt., 104  
fibrous jt., 104  
freely movable jt., 104

## JOINT

functional classification, 104  
genua jt., 120  
ginglymus jt., 108  
glenohumeral jt., 110  
gomphosis, 104  
hinge jt., 108  
hip jt., 118  
humero radioulnar jt., 72-75  
immovable jt., 104  
intercarpal jt., 112  
interphalangeal jt., 114  
intertarsal jt., 123  
distal, 123  
proximal, 123  
"knee", 112  
metacarpophalangeal jt., 114  
metatarsophalangeal jt., 125  
of auditory ossicles, 127  
of hyoid apparatus, 127  
of pelvic limb, 118-126  
of thoracic limb, 72-75, 110-118  
of vertebral column, 128-131  
pastern jt., 114  
pelvic symphysis, 118  
phalangeal jt., 114  
pivot, 108  
plane, 108  
prox. interphalangeal jt., 72-75, 114  
radiocarpal jt., 112  
sacroiliac jt., 118  
saddle jt., 108  
scapulohumeral jt., 110  
shoulder jt., 72-75, 110  
simple jt., 104  
slightly movable jt., 104  
spheroidal jt., 108  
sternocostal jt., 131  
stifle jt., 120  
suture, 104, 127  
symphysis, 104  
symphysis of mandible, 127  
synarthrosis jt., 104  
synchondrosis, 104  
syndesmosis, 104  
synovial jt., 106  
tarsal jt., 123  
tarsometatarsal jt., 123  
temporomandibular jt., 127  
tibiofibular jt., 123  
tibiotarsal jt., 123  
Jugular foramen, 42b, 48



## JUGULAR PROCESS

Jugular process, 36

**K K K K K K K K K**

Kidney, 328

lobated, 331

smooth, 331

"Knec", 112

**L L L L L L L L L**

"L" block, 499

Labia, 346

Lacertus fibrosus, 493t

Lacrimal apparatus, 558

Lacrimal b., 32

Lacrimal canal (canaliculi), 36, 558

Lacrimal caruncle, 549

Lacrimal gland, 558

Lacrimal puncta, 549, 558

Lacrimal sac, 558

Lamellar part of nuchal lig., 129b

Laminae,

of udder, 534

of vertebra, 60d

primary, 534, 538d

secondary, 534, 538e

Laminitis, 541

Lanolin, 540

Large colon (great), 276

Large intestine, 276-281

Laryngeal hemiplegia, 313

Laryngeal opening, 263

Larynx, 300

Laryngopharynx, 262

Lateral (lat.), 17

Lat. masses, 457

Lens, 547

Leptomeninges, 474

Level, teeth, 246

Lesser curvature of stomach, 268

Lesser omentum, 286, 290

Ligament, 106, 282

accessory lig. of deep

digital flexor mm., 196

accessory lig. of femur, 119

accessory lig. of supf.

digital flexor mm., 196

acetabular lig. 119n

arterial lig., 386

broad lig. of uterus, 338, 348

## LIGAMENT

broad sacrotuberous  
lig., 119

caud. cruciate lig., 120

check lig.

of pelvic limb, 198

of thoracic limb, 196

collateral lig. (see involved  
joints)

collateral sesamoid lig., 115c

coronary lig. of liver, 294

costotransverse lig., 131a

cran. cruciate lig., 120

cran. pubic lig., 119

denticulate ligg., 476

digital annular ligg., 115b,c

dist. digital annular lig.,  
115c

dors. elastic lg., 114g

dors. longitudinal lig., 130

dist. sesamoidean ligg.,  
115g-i

duodenocolic lig., 284

extracapsular lig., 106

extensor br., 115k

falciform lig., 282, 286H,  
294

funicular part of nuchal  
lig., 129

impar lig., 115o

inguinal lig., 202, 361,o

intercarpal lig., 112i

intercapitate lig., 131c

intercornual lig. 344, 350(8)

interdigital cruate ligg.,  
115r,s

intersesamoidean lig., 114

interspinous lig., 129

intertarsal ligg. 125a

intertransverse lig., 131k

intracapsular ligg., 114

lat. patellar lig., 120j

ligamentum arteriosum, 394

longitudinal lig. 129

long plantar lig., 124

medial patellar lig., 120h

median lig., 338, 282

meniscal ligg., 120

meniscofemoral lig., 120

middle patellar lig., 120i

navicular lig., 115o

nuchal lig., 128, 129

oblique sesmoidean lig.,  
115h

of femoral head, 118

of liver, 282

## LIGAMENT

of tail of epididymis, 357

of urinary bladder, 282

ovarian lig., 348

palm. annular lig., 115a

patellar lig., 182

patellar ligg., 120, 182

proper lig. of ovary, 348

proper lig. of testicle, 357

prox. digital annular lig.,  
114

pubic lig., 119d

pulmonary lig., 318

radiate lig., 130b

rt. triangular lig., 294

round lig. of femur, 118

round lig. of liver, 294

round lig. of uterus, 348

sacroiliac lig., 119a,o

sacrotuberous lig., 118

scrotal lig., 357

sesamoidean ligg., 114, 196

splenophrenic lig., 295j

straight sesmoidean lig.,  
115g

supraspinous lig., 128

suspensory lig., 164, 190,  
196

of eye, 547

of ovary, 349

navicular lig., 115p

transverse lig., 120e

transverse acetabular lig.,  
119n

triangular ligg., 294

ventr. longitudinal lig., 130

Ligamentum arteriosum, 386

Limb

pelvic, 26, 90-102

thoracic, 26, 72-89

Limbic system, 459

Line, 25

Lingual process, 58

Lingual surface, 240a

Lips, 234, 235

Liver, 292-297

Liver attachments, 294

Liver sinusoids, 296

Lobe

kidney, 330

liver, 293

lung, 323

of brain, 452

frontal, 452

occipital, 452

parietal, 452



## LOBE

temporal, 452  
pancreas, 298  
Long pastern, 87, 88  
Longitudinal fissure, 452  
Longitudinal section, 19  
Loop of Henle, 336  
Low-crowned teeth, 238  
Lumbar cistern, 476c  
Lumbosacral plexus, 477, 498  
Lung, 322  
Luxation, 106  
Lymph node, 259, 440  
Lymphatic system, 440  
Lymphatic vessels, 440  
Lymphocenter, 440  
Lymph vascular system, 440  
Lyssa, 237

## M M M M M M M

Maculae, 557  
Magda block, 499  
Malar bone, 32  
Malleolus, 98  
Malleus, 48f, 552  
Mamma, 533  
Mammary gland, 533-535  
Mammary suspensory apparatus, 534  
Mammillary body, 455b  
Manus, 26, 82  
Mandibular In., 249  
Mandibular salivary gl., 258  
Mandibular symphysis, 440  
Masticatory surface, 240  
Mastitis, 535  
Maxillary b., 32  
Maxillary recess, 42f  
Maxillary sinus, 56, 57  
Meatus, 25  
    acoustic, 36, 50  
    common nasal, 304d  
    dors. nasal, 304b  
    ext. auditory, 551  
    internal, 42e  
    middle nasal, 304c  
    nasal, 36, 304  
    nasopharyngeal, 305  
    ventr. nasal, 305  
Medial (med.), 17  
Median a., 416  
Median plane, 18  
Medial sacral crest, 68  
Mediastinum, 318  
Mediastinum testis, 356  
Medulla

## MEDULLA

of brain, 458  
of kidney, 330  
of uterus, 340  
Medulla oblongata, 458  
Medullary cavity, 22  
Medullary rays, 332c  
Membranous labyrinth, 554, 555, 557  
Meninges, 474  
    cranial, 474  
    spinal, 476  
Menisci (genual joint), 106  
Mental foramen, 44, 50  
Mesentery, 284  
Mesencephalon, 456  
Mesial surface, 240  
Mesocolon, 285  
Mesoduodenum, 284  
Mesoileum, 285  
Mesojejenum, 285  
Mesorchium, 362,, 357e, 361f  
Mesometrium, 348  
Mesorectum, 285  
Mesosalpinx, 348, 349  
Mesovarium, 348  
Mesothelium, 282  
Metacarpal b., 84, 85  
Metacarpal pad, 544  
Metacarpus, 26, 84  
Metaphysis, 22  
Metatarsal b., 102  
Metatarsus, 26, 102  
Midbrain, 456  
Middle ear, 552  
"Milk vein", 534  
Mouth, 234  
Murmur, 404  
Muscle  
    abductor pollicis longus, 160  
    arytenoideus transversus m., 313h  
    adductor m., 182  
    ascending pectoral m., 148  
    auricular m., 206  
    biceps brachii m., 152  
    biceps femoris m., 176  
    brachialis m., 150  
    brachiocephalicus m., 146  
    buccinator m., 204j  
    bulbospongiosus m., 374  
    caninus m., 205a  
    capitis mm., 215  
    caud. crural abductor m., 178  
    ceratohyoideus m., 315x

## MUSCLE

cervicoauricularis m., 206(16)  
ciliary m., 547  
cleidobrachialis m., 146  
cleidocephalicus m., 146  
coccygeus m., 220, 222  
common digital extensor m., 158  
constrictor vulvae m., 343f, 344e  
constrictor vestibuli m., 343e, 344f  
coracobrachialis m., 152, 153  
cran. tibial m., 188  
cremaster m., 359d  
cricoarytenoideus dorsalis m., 312  
cricoarytenoideus lateralis m., 313e, 315t  
cricoesophageus m., 315p  
cricopharyngeus m., 205j, 315o  
cricothyroideus m., 313  
cutaneous mm., 221  
deep digital flexor m., 164, 190  
deep gluteal m., 176  
deep pectoral m., 148  
deltoid m., 150  
descending pectoral m., 148  
digastricus m., 205g  
dors. cricoarytenoideus m., 312  
epaxial mm., 218  
extensor carpi radialis m., 158  
extensor carpi ulnaris m., 158  
ext. abdominal oblique m., 200  
ext. anal sphincter, 220  
ext. intercostal m., 216  
ext. obturator m., 174  
extrinsic mm., 146  
facial mm., 204  
fibularis longus (long fibular) m., 188  
fibularis tertius m., 188  
flexor carpi radialis m., 162  
flexor carpi ulnaris m., 162  
frontalis m., 205f  
gastrocnemius m., 190  
genioglossal m. 205ml, 236h  
geniohyoid m., 205nl



glutei mm., 176  
 gluteobiceps m., 176  
 gracilis m., 180  
 hyoepiglottic m., 313  
 hyoglossal m., 205m3, 236g  
 hyopharyngeus m., 205j5  
 iliacus, 172  
 iliocostalis m., 218  
 iliopsoas m., 172  
 infraspinalis m., 150  
 int. abdominal oblique m., 200  
 int. intercostal m., 216  
 int. obturator m., 174  
 interosseous m., 164, 190, 196  
 interscutularis m., 206(12)  
 intertransversarii mm., 211g, 218  
 ischiocavernosus m., 374  
 lat. digital extensor m., 158  
 lat. digital flexor m., 158, 188  
 lat. ulnar m., 158  
 latissimus dorsi m., 146  
 levator ani m., 220  
 levator anguli oculi medialis, 204e  
 levator costarum m., 218k  
 levator labii superioris, 205b  
 levator nasolabialis, 205c  
 levator veli palatini, 205k  
 long digit I abductor m., 160  
 long digital extensor, 188  
 long fibular, 188  
 long peroneal, 188  
 longissimus m., 218  
 longissimus atlantis, 211j  
 longissimus capitis, 211i  
 longus capitis, 206(25), 211d  
 malaris m., 206(8)  
 masseter m., 204  
 middle gluteal m., 176  
 multifidus m., 212i, 218  
 mylohyoideus m., 205n4  
 oblique capitis m., 213(5)  
 oblique carpal extensor 160  
 of crus, 188  
 of ear, 204  
 of eye, 550  
 of head, 204-209  
 of hyoid apparatus, 205n1-5  
 of neck, 210  
 of pelvic limb, 167-195

of pharynx, 262  
 of thorax, 216  
 of tongue, 205m1-3  
 of trunk, 216  
 omotransversarius m., 146  
 orbicularis oris, 205e  
 orbicularis oculi, 204d  
 palatopharyngeus m., 205j2  
 papillary mm., 401  
 pectinate mm., 398  
 pectineus m., 180  
 pectoral mm., 148  
 peroneus longus (long fibular), 188  
 peroneus tertius m., 188  
 popliteus m., 190  
 pronator teres m., 162  
 psoas major, 172, 173  
 psoas minor, 172, 173  
 pterygoid mm., 205h,i  
 pterygopharyngeus m., 205j1  
 quadratus femoris m., 182  
 radial carpal extensor, 158  
 radial carpal flexor, 162  
 rectus abdominis m., 201  
 rectus capitis mm., 215(13-16)  
 rectus femoris m., 182  
 rectus thoracis, 216f  
 retractor penis m., 374  
 rhomboideus m., 148  
 sartorius m., 180  
 scalenius m., 211e  
 scutuloauricularis m., 206(15-16)  
 semimembranosus m., 182  
 semispinalis capitis m., 211h, 218a  
 semitendinosus m., 178  
 serratus dorsalis mm., 216b,d  
 serratus ventralis m., 148, 196  
 soleus m., 190, 192g, 195g  
 sphincter m., 533  
 splenius m., 206(17), 211c  
 sternocephalicus m., 210  
 sternohyoideus m., 204  
 sternomandibularis m., 210  
 sternomastoideus m., 210  
 sternooccipitalis m., 210  
 styloglossal m., 205m2, 236f  
 stylohyoid, 205n3  
 stylopharyngeus mm., 205j3-4

subclavius m., 154  
 sublumbar mm., 167, 172, 173  
 subscapularis m., 152  
 supf. pectoral m., 148  
 supf. digital flexor m., 164, 190  
 supf. gluteal m., 176  
 supinator m., 160  
 supraspinatus m., 150  
 temporalis m., 205f  
 tensor fasciae antebrachii m., 152, 153  
 tensor fasciae latae m., 178  
 tensor veli palatini, 205l  
 teres major m., 152  
 teres minor m., 150, 151  
 third fibular, 188  
 thyroarytenoideus, 315q  
 thyropharyngeus m., 205j6  
 trachealis m., 315w, 321  
 transversus abdominis m., 200  
 trapezius m., 146  
 triceps brachii m., 152  
 ulnar carpal flexor, 162  
 ulnaris lateralis m., 158  
 urethral m., 346  
 vastus intermedius m., 182  
 vastus lateralis m., 182  
 vastus medialis m., 182  
 ventricularis m., 313f  
 vocal m., 313  
 zygomaticoauricularis m., 20b, 13  
 zygomaticus m. 204f  
 Muscular process, 308  
 Musculocavernous penis, 367  
 Myelin, 449

## N N N N N N N N N

Nares, caud., 40, 263, 305  
 Nares, rostr., 303  
 Nasal aperture, 38, 302  
 Nasal bone, 32  
 Nasal cavity, 42, 304  
 Nasal conchae, 304  
 Nasal diverticulum, 303c 305  
 Nasal meatus, 304  
 Nasal plane, 303a  
 Nasolabial plane, 303b  
 Nasolacrimal duct, 558  
 Nasopharyngeal meatus, 305  
 Nasopharynx, 262  
 Navicular bone, 88



## NAVICULAR DISEASE

Navicular disease, 88

### Neck

of humerus, 78f

of scapula, 77b

of radius, 80b

of femur, 96a

Needle teeth, 241

Nephric loop, 336

Nephritis, 328

Nephron, 336

### Nerve, 450

abaxial digital nn., 487n,q,  
518e,f

abducens n., 463

accessory n., 465, 478A

auricular n., 464g,j, 469h

auriculopalpebral br., 464n,  
469a

auriculotemporal br., 463s,  
469d

axial nn., 487,o,r, 517b,g

axillary n., 480, 482d, 486

buccal n., 463v, 464l,m,  
467c,d, 469b,c,g

caud. cutan. antebrachial n.,  
482h, 488s

caud. cutan. femoral n.,  
501a, 504

caud. cutan. sural n., 501c,  
504

caud. nasal n., 463m

caud. rectal n., 520

clunial n., 504, 505a,b,c

common digital n., 487n,p

common fibular n., 500, 504

communicating br., 484n,  
487l, 496c

cornual br., 463j, 469f

costoabdominal n., 479m,  
498

cranial n., 459, 460

deep temporal n., 463q

digastric br., 464k

digital nn., 494, 501k,l,n  
504, 505r,s,t

dors. digital n., 482i

esophageal br., 465e

ethmoidal n., 463e

facial n., 464, 526

femoral n., 500, 504

fibular n., 504, 501d,e

frontal n., 462b

genitofemoral n., 498

glossopharyngeal n., 465,  
526

gluteal n., 500, 504

## NERVE

hypogastric n., 524

hypoglossal n., 465, 478C

iliohypogastric n., 498

ilioinguinal n., 498

inferior alveolar n., 463x,  
469l

infraorbital n., 463n, 469n

infratrochlear n., 463f

intercostal n., 477

intercostobrachial n., 479l

ischiatric n., 500, 504

lacrimal n., 463a

laryngeal br., 465f

lat. cutan. brachial n., 482d

lat. cutan. femoral n., 501b

lat. cutan. sural n., 504

lat. thoracic n., 479k, 480

lingual n., 463w, 465c, 469m

long ciliary n., 463d

long thoracic n., 479i, 480

mandibular division (V3),  
463

masseteric br., 468p

maxillary division (V3), 463

med. cutan. antebrachial n.,  
481e, 482e, 488b

median n., 480, 486, 494,  
496

mental n., 463z

metacarpal n., 495b,g

metatarsal n., 501f,g, 517a,c  
f,g

mixed n., 460

musculocutaneous n., 480,  
482e, 487d

myohyoid n., 463y, 469k

nasal br., 468,o

nasociliary n., 463c

obturator n., 500, 504

oculomotor n., 462, 526

of bovine pelvic limb, 505,  
512, 518

of bovine thoracic limb,  
487, 492, 496

of canine pelvic limb, 502,  
506

of canine thoracic limb,  
481, 482, 488

of equine pelvic limb, 501,  
508, 516

of equine thoracic limb,  
484, 490, 494

of pelvic limb, 500-519

of penis, 521

of thoracic limb, 480-497

olfactory n., 460

## NERVE

ophthalmic division (V3),  
463

optic n., 462

palatine nn., 463l

palmar br., 482m,n

palpebral br., 464i, 469

parotid br. 463t

pectoral n. 482b, 486

pelvic n., 520, 526

perineal n., 521

peroneal n., 500

pharyngeal br. 465b,d

phrenic n., 477, 481A

plantar n., 501h,i, 504,  
517b,d,i

pterygoid n., 463r

pterygopalatine n., 463k

pudendal n., 520

radial n., 480, 482f,g, 486

rectal n., 504, 520

saphenous n., 500, 504

sciatic n., 500, 502

scrotal n., 521

sensory n., 460

special sensory n., 460

spinal nn., 472

dors. branch, 472

organization, 472

ventr. branch, 470

spinal plexuses, 477

splanchnic nn., 524

subscapular n., 480, 481C,  
482a, 486, 489(1)

suprascapular n., 486

supf. radial n., 481D, 488c,e

sympathetic trunk, 524

tibial n., 500, 504

thoracic n., 477, 482c

thoracodorsal n., 479j, 480,  
486

transverse fasial n., 463u

trigeminal n., 463

trochlear n., 462

ulnar n., 480, 482h,j,k,  
484, 486, 488f,g, 495

vagal cardiac n., 527e

vagosympathetic trunk,  
465a

vagus n., 465-6, 526

vertebral n., 525c

vestibulocochlear n., 464

zygomatic n., 463g, 464h,  
469

zygomaticofacial n., 463h

zygomaticotemporal n.,  
463i, 469e



## "NERVE"

"Nerve", 495  
Nerve block, 494, 497  
Nerve tracts of fasciculi, 450  
Nervous system, 445  
    autonomic, 445  
    central, 445  
    peripheral, 445  
    somatic, 445  
Neurofibril, 447b  
Neuroglia, 449  
Neuromuscular junction, 448  
Neurons, 446, 450  
    association, 446, 450  
    motor (efferent), 446, 450  
        460, 522, 560  
    postganglionic, 522  
    preganglionic, 522  
    sensory (afferent), 446, 450  
        460, 522, 560  
Nissl body, 447a  
Nodes of Ranvier, 447h, 449  
Nodule, 403a  
Non-tubular horn, 538c  
Norepinephrine, 522  
Nose, 292  
Notch, 25, 60a,b  
    alar, 62a  
    intertragic, 551g  
    ischiatric, 95i, k  
    pretragic, 551e  
    popliteal, 99i  
    radial, 80g  
    scapular, 77a  
    trochlear (semilunar), 80  
Nuchal crest, 38  
Nucleus, 450  
Nutrient blood, 296

OOOOOOOO

Obturator foramen, 95  
Occipital bone, 32  
Occipital condyles, 36  
Occlusal surface, 240  
Occult spavin, 124  
Olecranon, 80  
Olecranon tuberosity, 80j  
Omasal laminae, 272  
Omasum, 270, 272  
Omental bursa, 286  
Omental foramen, 286, 290  
Omental vestibule, 288  
Omentum, 286, 288, 290, 291  
Opening  
    aortic, 401  
    atrioventricular, 400

## OPENING

cardiac, 272  
coronary sinus, 403b  
frontal maxillary, 56  
nasomaxillary, 56e,  
pulmonary, 400  
Optic canal, 40  
Optic chiasm, 455a, 462  
Optic disc, 537  
Optic tract, 456, 462  
Oral cavity, 234  
Orbit, 36  
Orbital fissure, 46, 48, 50  
Orifice  
    ejaculatory, 379h  
    urethral, 346  
    uterine, 343a,b  
"Originals", 360  
Oropharynx, 262  
Os penis, 367  
Ossa cordis, 403j  
Osteology  
    of hyoid apparatus, 58  
    of pelvic limb, 90  
    of skull, 32  
    of thoracic limb, 72  
    of thorax, 70  
    of vertebral column, 60  
Otolithic membrane, 557a  
Otoliths, 557b  
Oval foramen, 411, 46(5), 48,  
    50, 386  
Oval window, 552  
Ovarian a., 350G  
Ovarian bursa, 348  
Ovarian lig., 348  
Ovary, 340  
Overshot, 239  
Oviduct, 340  
Ovulation depression, 354  
Ovulation fossa, 341

PPPPPPPP

Pachymeninx, 474  
Pacemaker phenomena,  
    389  
Pad, 544  
    cutaneous, 544  
    dental, 235  
Palate, 235  
    hard, 40, 235  
    soft, 235  
Palatine bone, 32  
Palatine ridges, 234d  
Palatine tonsil, 234i, 263  
Palatopharyngeal

## PALATOPHARYNGEAL

    arch, 234f  
Palmar (palm.), 16  
Palpation of ovaries, 354  
Palpebra conjunctiva, 549  
Pampiniform plexus, 362  
Pancreas, 298, 299  
Papilla  
    conical, 236k  
    filiform, 236j  
    foliate, 236m  
    fungiform, 236l  
    lenticular, 236,o  
    renal, 330  
    vallate, 236n  
Papillary duct, 336  
Papillary mm., 401  
Paraconal interventricular  
Paraventricular  
    groove, 394  
Paralysis of penis, 369  
Paranasal sinuses, 56, 57  
Parasympathetic division, 526  
Parasympathetic nuclei, 527d  
Paravertebral block, 499  
Parietal bone, 32  
Parietal sulcus, 89d  
Parietal surface of coffin  
    bone, 89a  
Parietal surface of stomach,  
    268  
Parotid duct opening, 234e,  
    259  
Parotid ln., 249  
Parotid salivary gl., 258  
Parrot mouth, 247  
Pastern, 114  
Patella, 96  
Patellar ligg., 120, 182  
Patellar lock mechanism, 198  
Patellar luxation, 121  
Patellar surface, 96  
PDA, 404  
Pectinate mm., 398  
Pedal ostetis, 88  
Pedicle, 60c  
Pelvic cavity, 225  
Pelvic diaphragm, 220  
Pelvic flexure, 278  
Pelvic girdle, 26  
Pelvic limb, 26  
Pelvic symphysis, 118  
Pelvis, 94  
    renal, 330  
Penis, 366  
    fibroelastic, 366  
    glans, 366, 372



## PENIS

- musculocavernous, 367
- os, 367
- Pericardial cavity, 383
- Pericardial tympanade, 318, 383
- Pericardium, 383
- Peripheral, 17
- Perilymph, 554
- Perineal body, 220
- Perineal hernia, 220
- Perineal laceration, 220
- Perineum, 220
- Perineurium, 472
- Periodontal membrane, 239
- Periople, 537d
- Periosteum, 22
- Peripheral, 17
- Peripheral nervous system, 445
- Perirenal fat, 328
- Peritoneal cavity, 282
  - pouches of, 282
- Peritoneum
  - connecting, 282
  - parietal, 282
  - visceral, 282
- Peritonitis, 282
- Permanent dentition, 240
- Pes, 26, 102
- Petiolus, 309a, 310a
- Peyer's patches, 440
- Phalangeal jt., 114
- Phalanx, 86
- Pharyngeal diverticulum, 264
- Pharyngeal opening, 263
- Pharynx, 262
- Physiology
  - of dynamic equilibrium, 557
  - of static equilibrium, 557
- Pia mater, 474
- Pineal body, 456d
- Pinna, 517
- Piriform recess, 262
- Pituitary gland, 455
- Pivot jt., 108
- Placenta, 352
  - adeciduate, 353
  - cotyledonary, 353
  - deciduate, 353
  - diffuse, 353
  - endotheliochorial, 353
  - epitheliochorial, 353
  - partially deciduate, 353
  - zonary, 353
- Placentome, 353

## PLANE JOINT

- Plane jt., 108
- Planes, 18, 19
  - dorsal, 18
  - frontal, 18
  - median, 18
  - midsagittal, 18
  - paramedian, 18
  - parasagittal, 18
  - sagittal, 18
  - transverse, 18
- Plantar (plant.), 17
- Pleura, 318
  - costal, 318
  - diaphragmatic, 318
  - parietal, 318
  - pericardial, 318
  - pulmonary, 318
  - visceral, 318
- Pleural cavity, 318
- Plural sacs, 318
- Plexus
  - autonomic, 524
  - brachial, 477
  - celiac, 527h
  - cervical, 477
  - coronary venous, 495m, 517D
  - intermesenteric, 525h
  - int. vertebral venous, 476d
  - lumbosacral, 477, 498
  - spinal, 477
- PMI, 404
- Point of maximum intensity, 404
- Polled, 545
- Pons, 456
- Popliteal notch, 99j
- Popliteal sesamoid b., 99k
- Porta of the liver, 292
- Portal v., 296
- Pouches of peritoneal cavity, 282
- Premolars, 240
- Prepuce, 367
  - ext. fold of, 378b
  - int. fold of, 378c
- Preputial diverticulum, 367
- Preputial orifice, 378d
- Preputial ring, 378e
- Process, 25
  - anconeal, 81
  - angular, 36i, 44g
  - articular, 36g, 44, 60
  - caudate, 293

## PROCESS

- ciliary, 546
- clinoid, 46c,d
- condyle, 24
- condyloid process of mandible, 44
- coronoid, 36L, 44b
- corniculate, 309
- cornual, 38
- crest, 24
- cuneiform, 309j, 310j
- epicondyle, 24, 96d,e, 179
- extensor, 86, 87c, 89f
- facet, 24
- flexor, 86, 87f
- frontal, 36b
- head, 24
- jugular, 36
- line, 24
- lingual, 58
- mammillary, 65a, 67a
- mastoid, 36h
- muscular, 308
- myelinated, 449
- papillary, 293
- retroarticular, 41m
- spinous, 60
- styloid
  - ulnar, 81
  - radial, 80d
- spine, 24
- spinous, sacrum, 68
- transverse, 60, 66
- trochanter, 24
- trochlea, 24
- tubercle, 24
- tuberosity, 24
- ungual, 86
- unmyelinated, 449
- urethral, 372
- vaginal, 349
- vocal, 308
- xiphoid, 71
- zygomatic, 36a, 38a
- Prognathia, 239
- Promontory, 48c, 69c
- Prostate, 364
- Prostatic a., 428
- Proximal (prox.), 17
- Prox. loop, 280
- Pseudopapillae, 332d, 335a
- Pterygoid bone, 32
- Pubis, 95
- Pudendoepigastric trunk, 428
- Pulmonary a., 384
- Pulmonary lig., 318



## PULMONARY

- Pulmonary opening, 400
- Pulmonary trunk, 384
- Pulp, 239
- Pulp cavity, 239
- Pulvini, 344
- Pupil, 547
- Pyloric opening, 268b
- Pylorus, 273
- Pyramids, 458

## Q Q Q Q Q Q Q Q Q

- Quarter crack, 541-542
- Quarters
  - of mammary gl., 534
  - of horse hoof, 536
- Quittor, 88, 541

## R R R R R R R R R

- Radial carpal b., 82
- Radial n., 480
- Radial paralysis, 480
- Radius, 80
- Ramus of mandible, 44
- Ranula, 261
- Receptor, 450
- Recess, 43f
  - maxillary, 57
  - pelvic, 332e, 335b
  - terminal, 331
  - vaginal, 347
- Rectangular (teeth), 251
- Rectogenital pouch, 282
- Rectum, 276
  - horse, 278
  - ox, 280
  - pig, 281
- Reflex arc, 450, 522
- Reflex centers, 458
- Renal crest, 330
- Renal hilus, 331
- Renal impression, 292
- Renal papilla, 330
- Renal pelvis, 330
- Renal sinus, 331
- Reproductive system, 339-380
  - female, 339-355
  - male, 356-380
- Respiratory bronchioles, 321
- Respiratory system, 301-325
- Rete testis, 356
- Reticular formation, 459
- Reticulum, 270, 272
- Retina, 547

## RETROPERITONEAL

- Retroperitoneal, 282
- Rib, 70
  - angle of, 70f
  - false rib, 70b
  - floating rib, 70c
  - true rib, 70a
- "Ridglings", 360
- "Rigs", 360
- Rima glottidis, 312
- Ring block, 497
- Ringbone, 88
- "Roarer", 313
- Rods, 547
- Root of mesentery, 284
- Rostral (rostr.), 16
- Rostral bone, 52
- Rotation, 108, 141
- Rotation of coffin bone, 88
- Round (teeth), 250
- Round window, 552
- Ruggae, 268c
- Rumen, 270, 272
- Rumen palpation, 271
- Ruminant stomach, 270
- Rupture of intervertebral disc, 131

## S S S S S S S S S

- Sacculations, 278
- Saccule, 527
- Sacral crest, 68
- Sacral foramina, 68
- Sacral parasympathetic outflow, 526
- Sacrum, 68
- Saddle jt., 108
- Sagittal plane, 18
- Sagittal ridge, 84f, 102c
- Salivary glands, 258
- Sphenous a., 432
- Scala tympani, 555
- Scala vestibuli, 555
- Scapula, 76, 77
  - angle, 77i,j
  - dorsal border, 77d
  - neck, 77b
- Scapular cartilage, 77(7)
- Schwann cell, 447g, 449
- Scissor mouth, 247
- Sclera, 546
- Scrotum, 376
- Scutiform cartilage, 208c
- Sebaceous gl., 530
- Sebum, 530
- Sections, 19

## SECTIONS

- cross, 19
- longitudinal, 19
- transverse, 19
- Seedy toe, 241
- Semilunar line, 89i
- Seminiferous tubules, 356
- Septum
  - interventricular, 392, 401
  - membranous part, 392
  - septum 1, 390
  - septum 2, 391
  - spiral, 392
- Serosa, 318
- Serous membranes, 282
- Serous pericardium, 383
- Sesamoid bone, 22
- Sesamoidean lig., 114, 196
- Seven-year-hook, 248
- Shear mouth, 247
- "Sickle-hocked", 125
- "Sidebone", 88
- Sigmoid flexure, 368, 280
- Simple stomach, 268
- Sinus
  - aortic, 406
  - coronary, 394
  - dors. conchal, 56,a
  - dural, 475
  - rontal, 42, 56
  - milk, 533
  - maxillary, 56, 57
  - palatine, 42g, 56f
  - paranasal, 56, 57
  - renal, 331
  - sphenoid, 42j, 56
  - sphenopalatine, 42h, 56c
  - venous, 389
- Sinusitis, 57
- Skeleton
  - appendicular, 26
  - axial, 26
  - cat, 30
  - dog, 27
  - horse, 28
  - llama, 31
  - of heart, 403
  - ox, 29
  - pelvic limb
    - of dog, 90
    - of horse, 91
    - of ox, 92
    - of pig, 93
  - pig, 30
  - sheep, 31
  - thoracic limb, 72
  - of dog, 72



## SKELETON

- of horse, 73
- of ox, 74
- Skin, 530
- Skull, 32-57
  - cat, 53
  - dog, 33-48
  - goat, 54
  - horse, 34-51
  - pig, 52
  - ox, 35-51
  - sheep, 55
- Slightly movable jt., 104
- Small colon, 278
- Small intestine, 274
- Soft palate, 262
- Solar foramen, 89n
- Solar groove, 89g
- Solar surface of
  - coffin bone, 89b
- Sole, 537
- Somatic nervous system, 445
- Sow mouth, 247
- Space
  - intercostal, 71
  - interosseous, 81n, 98
- Spavin, 124
- Spermatic cord, 362
- Spermatic fascia, 362, 376
- Sphenoid bone, 32
- Spinal cord, 470
- Spinal meninges, 476
- Spinal nerves, 472, 523
- Spine, 25
  - ischiatric, 94
  - of cat penis, 373b
  - of frog, 537k
  - of scapula, 76
  - of vertebrae, 60
- Spiral loop, 280, 281
- Spiral septum, 392
- Spleen, 442
- Splenectomy, 442
- Splint bone, 85
- Splints, 85
- Stapes, 48g, 518
- Stay apparatus
  - pelvic limb, 198
  - thoracic limb, 196
- Stenosis (heart valves), 404
- Step mouth, 247
- Sternal flexure, 278
- Sternum, 71
- Stifle, 120
- Stomach
  - ruminant, 270
  - simple, 268

## STOMACH TUBE

- Stomach tube, 271
- Stratum
  - basale, 530
  - coreum, 530
  - granulosum, 530
  - lucidum, 530
  - spinosum, 530
- Stria habenularis thalami, 456b
- "Stringhalt", 182
- Strongylus vulgaris, 426
- Styloid b., 58
- Subarachnoid space, 474
- Subcutis, 530, 540
- Subdural space, 474
- Sublingual caruncle, 258h
- Sublingual salivary gl., 259
- Subsinuosal interventricular groove, 394
- Suburethral diverticulum, 347
- Sulci, 452
- Sulcus
  - chiasmatic, 46b
  - coronal, 453d
  - collateral, 537b
  - cruciate, 453a
  - ectosylvian, 453c
  - lat. rhinal, 453b
  - of frog, 537f
- Superficial (supf.), 17
- Supf. leaf (of omentum), 290
- Supf. lymph nodes, 441
- Supraglenoid tubercle, 77c
- Supraomental recess, 290
- Suspensory lig. of ovary, 349
- Sustentaculum tali, 101a
- Suture, 104, 127
  - frontonasal, 38f
  - internasal, 38g
  - nasomaxillary, 38h
- Sweeny, 480
- Sympathetic division, 522
- Sympathetic trunk, 524
- Symphysis, 104
  - mandibular, 44c, 127
  - pelvic, 95, 118
- Synapse, 448
- Syndesmosis, 104
- Synovial fluid, 106
- Synovial membrane, 106
- Synovial sac
  - carpometacarpal, 112f
  - intertarsal, 125f, g
  - middle carpal, 112g
  - radiocarpal, 112f
  - tarsometatarsal, 125h

## SYNOVIAL SAC

- tibiotarsal, 125c
- Synovial sheath, 106, 113, 115, 124
- Systole, 404

## T T T T T T T T T

- Tactile hair, 532
- Tarsal bones, 100
- Tarsal jt., 123
- Tarsus, 26, 100
- "Teaser bull", 369
- Teat, 533
- Teat canal, 533
- Teeth, 238-257
  - carnassial, 240
  - canine, 240
  - cheek, 240
  - deciduous, 240
  - formula, 242
  - horse teeth, 246-253
  - molars, 240
  - ox teeth, 254-257
  - premolars, 240
  - sectorial, 240
  - surfaces, 240
  - "wolf", 241
- Telodendrite, 447f
- Temperature regulation, 455
- Temporal b., 32
- Tendon
  - accessory digit, 496r
  - bowed tendon, 164
  - calcanean tendon, 190
  - contracted tendon, 164
  - cunean tendon, 188
  - patellar tendon, 182
  - prepubic tendon, 201
  - symphyseal tendon, 182
- Tendinous cords, 401
- Tentorium cerebelli, 475
- Tentorium osseum, 42a
- Terminal recess, 331
- Testis, 356
  - descent, 358
- Testicle, 356
- Thalamus, 454
- Third eyelid, 549
- Third ventricle, 454
- Thoracic aorta, 409
- Thoracic cavity, 224, 318
- Thoracic duct, 405C, 408h, 440
- Thoracic girdle, 26
- Thoracic limb, 26
- Thoracic opening, cran., 224j
- Thorax, 70



## THRUSH

- Thrush, 541
- Thyroid cartilage, 308
- Toe, 536
- Toe crack, 541
- Tongue, 236
- Tonsillar fossa, 236i
- Tonsils, 263, 440
- Torsion, 275
- Torus linguac, 237
- Torus pyloricus, 263, 267
- Trabeculae, 371, 494
- Trachea, 321
- Tracheal bronchus, 321
- Tracheostomy, 321
- Tragus, 551f
- Transposition of great vessels, 392
- Transverse fissure, 452
- Transverse plane, 18
- Transverse process, 60, 66
- Transverse section, 19
- Trephinement, 57
- Triangular (teeth), 250
- Tricipital line, 78a
- Trigone, 379d
- Trochanter 25
  - greater (major), 96
  - lesser (minor), 96
  - third, 96
- Trocharization, 271
- Trochlea, 25
  - of digits, 87
  - of eye, 550
  - of femur, 96
  - of humerus, 78d
  - of tibial tarsal b., 101
- Trochlear notch, 81
- Trochlear tubercle, 97
- Truncal ridges, 392
- Truncus arteriosus, 389
- Trunk ganglia, 524
- Tuber, 25
  - calcanei, 100
  - coxae, 95
  - facial, 38c
  - olecrani, 81
  - sacrale, 95b
  - spinal, 77
- Tubercle, 25
  - greater (major lat.), 78
  - infraglenoid, 77f
  - intermediate, 79
  - lesser (minor med.), 78
  - of rib, 70
  - major, 78
  - pubic, 95g

## TUBERCLE

- supraglenoid, 77c
  - trochlear, 97
  - ventr., of atlas, 62c
  - Tuberosity, 25
    - calcanean, 100
    - deltoid, 78
    - ischiatric, 95
    - metacarpal, 84, 85
    - of scapula, 77
    - olecranon, 81
    - radial, 80c
    - supracondylar, 96k
    - tibial, 98
  - "Tubing", 263
  - Tubular horn, 538b
  - Tubule
    - dist. convoluted, 336
    - prox. convoluted, 336
    - seminiferous, 356
  - Tunic
    - vaginal, 362, 367
    - vascular, 546
    - visceral, 362
    - white, 340, 356, 371
  - Tunica albuginea, 340, 356, 371
  - Tusk, 52, 241
  - Tympanic bulla, 40
  - Tympanic cavity, 552
  - Tympanic membrane, 552
  - Tympano-occipital fissure, 50
- UUUUUUUUUU
- Udder, 534
  - Ulna, 80
  - Ulnar carpal bone, 82
  - Ulnar n., 480, 486
  - Undershot, 239
  - Ungual cartilage, 88
  - Ungual crest, 87
  - Ungual process, 86
  - Ureter, 338
  - Urethra
    - female, 346
    - male, 365
  - Urethral calculi, 368
  - Urethral process, 372
  - Urinary bladder, 338
  - Urinary space, 336
  - Urinary system, 327-338
  - Uterine a., 428
  - Uterine horns, 342
  - Uterine orifice, 343a,b
  - Uterine prolapse, 345
  - Uterine tube, 340

## UTERUS

- Uterus, 342, 354
  - Utricle, 557
  - Uvea, 546
- VVVVVVVVVV
- Vagina, 346
  - Vaginal a., 328
  - Vaginal cavity, 362
  - Vaginal process, 349
  - Vaginal ring, 362
  - Vaginal smear, 347
  - Vaginal tunic, 362, 376
    - parietal, 362
    - visceral, 362
  - Valve
    - of foramen ovale, 386
    - of heart, 403
  - Vein, 383
    - brachiocephalic v., 438, 439
    - capsular v., 328
    - cardiac v., 399
    - caud. mesenteric v., 423g
    - caud. vena cava, 384, 423.
    - cephalic v., 438
    - coronary, great, 369
    - cran. mesenteric v., 423j
    - cran. vena cava, 384, 386, 438
    - digital vv., 517A,C,G
    - ext. iliac v., 423c
    - ext. jugular v., 438, 439
    - gastric v., 423i
    - gonadal v., 423d
    - great (cardiac) coronary v., 396
    - hepatic vv., 423b
    - iliac vv., 423c,f
    - liver sinusoids, 423a
    - mesenteric vv., 423g,j
    - "milk" v., 528C
    - of pelvic limb, 438
    - of thoracic limb, 438
    - plantar v., 517F
    - portal v., 423, 438
    - renal v., 423c
    - saphenous v., 438
    - splenic v., 438h
    - subclavian v., 438, 439
    - umbilical v., 386
  - Ventral (ventr.), 16
  - Ventr. aortae, 390
  - Ventral root, 524
  - Ventricle, 384, 394, 400, 452, 454, 473
    - fourth, 458, 473



## VENTRICLE

- left, 401
- right, 400
- third, 454, 473
- Vermis, 457
- Vertebra, 60-69
  - caudal, 68
  - cervical, 62
  - coccygeal, 68
  - lumbar, 66
  - sacral, 68
  - thoracic, 64, 65
- Vertebral canal, 60
- Vertebral column, 26
- Vertebral formula, 60
- Vesicogenital pouch, 282, 286m
- Vesicopubic pouch, 282, 286n
- Vesicular gl., 264
- Vestibular bulb, 347
- Vestibular fold, 313a
- Vestibular lig., 313a
- Vestibular surface, 240b
- Vestibular window, 552
- Vestibule, 346, 557
  - of female reproductive tract, 346, 557
  - of larynx, 313k
  - of omentum, 288
- Visceral effectors, 522
- Visceral surface of stomach, 268
- Visceral vaginal tunic, 357d, 362
- Vitreous humor, 548
- Vocal lig., 312b
- Vocal process, 308
- Volvulus, 275
- Vulva, 346

## W W W W W W W

- Wall (of hoof), 536
- Water line, 537c
- Wave mouth, 247
- White line, 540
- White matter, 450, 470
- Whorlbone disease, 176
- Windsucker, 347
- Wing
  - of atlas, 62
  - of sacrum, 68
- Wolf teeth, 240

## X X X X X X X X

- Xiphoid process, 71

## Y Y Y Y Y Y Y Y

## Z Z Z Z Z Z Z Z

- Zygomatic arch, 36
- Zygomatic gland, 259
- Zygomatic process, 36a